
GOVERNMENT OF INDIA DEPARTMENT OF ARCHAEOLOGY CENTRAL ARCHAEOLOGICAL LIBRARY Acr. 21558 CALL No. D160 XII

D.G.A. 79.







ARCHÆOLOGICAL SURVEY OF INDIA.

THE MO MENTAL ANTIQUITIES

AND

INSCRIPTIONS,

IN THE

NORTH-WESTERN PROVINCES AND OUDH,

DESCRIBED AND ARRANGED

BY

A. FÜHRER, Ph.D.,

ARCH-EOLOGICAL SURVEY, NORTH-WESTERN PROVINCES AND OUDH.

21558

R 913.012 I. D. A./ Füh




D160

ALLAHABAD:

PRINTED AND PUBLISHED BY THE SUPERINTENDENT, GOVERNMENT PRESS, N.-W. P. AND OUDH. CALCUTTA: THACKER, SPINK & Co. BOMBAY: THACKER & Co., LD. MADRAS: HIGGINBOTHAM & Co. LONDON: TRÜBNER & Co., AND W. H. ALLEN & Co. LEIPZIG: OTTO HARRASSOWITZ.

1891.





PREFACE.

THE Classified Lists of the Monumental Antiquities and Inscriptions in the North-Western Provinces and Oudh contained in this volume have been prepared in compliance with the orders of the Government of India, Home Department (Archæology), Resolution No. $\frac{5}{170-82}$ of the 22nd August, 1885. The information here given regarding these monuments is based partly on personal knowledge and partly on accounts given in the oriental scientific journals published since A.D. 1785 which bear on the subject. These include the numerous volumes of the Asiatic Researches, of the Journals of the Asiatic Society of Bengal, and of the Bombay Branch of the Royal Asiatic Society, as well as the whole of General Cunningham's Archæological Reports, the Corpus Inscriptionum Indicarum, the Indian Antiquary, and the Epigraphia Indica; in the foot-notes the volumes and pages of the works consulted have always been referred to, so that the reader who wishes further information may know where to find it. Some additions doubtless will still have to be made to these Lists; but it is believed they include nearly all that is at present known as deserving of special notice. Of only a small proportion of these monuments is conservation or restoration desirable and possible; of very many of them a detailed archeological survey and delineation is desirable, but even of these only a selection can be made.

All the monuments here mentioned have been classified, on the margin, in accordance with the requirements of the Government of India Resolution, Home Department (Archæology), No. 3 of the 26th November, 1883, as follows:—

- Ia.—Monuments which, 'from their present condition and historical or archæological value, ought to be maintained in permanent good repair, and which are in possession or charge of Government, or in respect of which Government must undertake the cost of all measures of conservation.
- Ib.—Monuments of the same class, which are in possession or charge of private bodies or individuals.
- IIa.—Monuments which it is now only possible or desirable to save from further decay by such minor measures as the eradication of vegetation, the exclusion of water from the walls, and the like, such being in possession or charge of Government, or in respect of which Government must undertake the cost of such measures.
- IIb .- Monuments of the same class in possession of private bodies or individuals.
- III.—Monuments which, from their advanced stage of decay or comparative unimportance, it is impossible or unnecessary to preserve.

fi Preface.

The lists given of all the *Inscriptions* known in each district are based on the same sources as the antiquities, but supplemented by the information obtained from the Returns of the "*Inscription* Forms," prepared by Dr. J. Burgess, C.I.E., the Director-General of the Archæological Survey, and issued to a large number of officials and private gentlemen, both European and Native, in these Provinces, under the orders of the Government of India, Home Department (Archæology), No. $\frac{9}{269}$ of the 13th October, 1886. The statements made in these returns are doubtless in many cases inaccurate and unreliable; and the Lists must, therefore, be considered as only provisional and tentative, not final. By corrections, additions, and alterations, these *Inscription* Lists may, however, in the course of time be rendered perfect: at present they must in many instances be considered merely as forming a basis for investigation. Additional information will be gratefully received by the Department.

The object of this volume is not only to produce complete lists so far as known of the antiquities and epigraphs in each district for the use of the Archæological Survey, but to furnish general information for the guidance of the many residents in these Provinces, with the view of enabling them, if their tastes so incline, to interest themselves in the character and history of the remains in their vicinity.

In conclusion, I have to thank Babu P. C. Ghosh, the Assistant in Charge, Camp Branch, Government Press, North-Western Provinces and Oudh, for the unremitting care and attention he has bestowed on the proof-sheets, and for the correctness and elegance of style with which this volume has been carried through the Press under his intelligent direction, which reflects great credit on Indian book printing.

A. FÜHRER, Ph.D.,

Archæological Survey, N.-W. P. and Oudh.

PROVINCIAL MUSEUM, LUCKNOW:

The 1st June, 1891.



CONTENTS.

NORTH-WESTERN PROVINCES.

					4
					PAGES.
I MÎRAȚH DIVISION :-		***	***	***	1-19
I.—Aligarh District		1245	12001	19447	1-3
II.—Bulandshahr District	***	***	***	***	3-7
III.—Dêrah Dûn District	***	***	144		7-8
IV.—Mirath District	***	488	122	1999	8-12
VMuzaffarnagar District	***		***	***	12-14
VI.—Sahâranpûr District	***		***		14-19
II.—ROHILKHAND DIVISION :-	274	***	***	11000	20-43
I.—Badaon District	***	22	222	144	20-24
II.—Barell District		***	222	277	24-30
III.—Bîjnôr District /	***	***	***	***	30-34
IV.—Murâdâbâd District	100	200	222	22	34-38
V.—Pilibhît District	****	***		***	38-41
VI.—Shâhjahânpûr District	***	***	***	***	41-43
III.—KUMAON DIVISION:-	***	2.2	550	***	44-52
L.—Garhwâl District	***	200		144	44-46
II.—Kumaon District					46-50
III.—Tarâî District	***	***	***	135	50-52
The state of the s					
IV.—ÂGRĂ DIVISION:—	***	20.0		144	53—111
I.—Âgrâ District✓	452			-	53-77
II.—Farrukhâbâd District	444	***		***	77-84
III.—Îtâh District	***	100	***	***	84-89
IV.—Itawah District	444	100	766	(944)	89-92
V.—Maînpurî District	***	445		***	92-97
VI.—Mathurâ District	***	***	****	555	97—111
V.—JHANSI DIVISION :-	444	244	***		112—126
I.—Jalaun District	***	200	+++)	***	112—114
II.—Jhansi District	***	200	227		114—119
III.—Lalitpûr District	***	***			119—126
					wer wer
VL-ALLAHÂBÂD DIVISION:-	***	262	***		127—186
I.—Allahâbâd District	***	***	446		127—145
II.—Bândâ District	***	***	247		145—157
III.—Fathpûr District	***	***	525		157—165
IV.—Kanhpar District	200	***	141	1	165—170
V.—Hamîrpûr District	***	***			170—178
VI.—Jaunpûr District	*** *	***	***	****	178—186

CONTENTS.

				L'AGES.
VIL-BANARAS DIVISION:			244	187—262
I.—Âzamgarh District	***	252	***	187—190
II.—Bâliyâ District	***	***	***	190—195
III.—Banâras District	494		***	195—216
IV.—Bastî District	***	255	200	216—227
V.—Ghâzîpûr District	***	222	94+	227—237
VI.—Gôrakhpûr District	(999	(0.00	200	237—251
VII.—Mîrzâpûr District	001	***	334	251—262
AND THE PARTY OF				
AUDH	(AWA	DH).		
VIII.—LAKHNÂÛ DIVISION:—	***	are.	444	263—276
I.—Bâra Bankî District	122	222	999	263-264
II.—Lakhnâû District	****	***		264-268
III.—Unão District	1440	200	***	268-276
IX.—SÎTÂPÛR DIVISION :—	754	411	300	277—291
L.—Hardôî District	22.5	29993	100	277—283
II.—Kherî District	***	225	944	283—287
III.—Sîtâpûr District	16967	***	(888)	287—291
				000 919
X.—FAIZÂBÂD DIVISION:—	***	7.7	120	292—313
I.—Bahraich District	22.2	220	1999	292—295
II.—Faizābād District	888	55.55	- 222	295—302
III.—Gonda District	940	***	***	302—313
XI.—RÂÎ BARELÎ DIVISION:—		461		314—330
	""	***		314-319
I.—Pratapgarh District	***	***		319—325
II.—Raî Barelî District	***	19.5	125	325—330
III.—Sulţânpûr District	***	***	***	II SANSTONIA TURA
XII.—ADDENDA ET CORRIGENDA	****	54	44	331—334
				335—359
XIII.—APPENDIX	***	***	725	
XIV.—INDICES	244	100	***	361—425

I.-MÎRAȚH DIVISION.

I.—Aligarh District.

Akrābād, in tahsil Sikandrā Râo, 12 miles S.-E. from Aligarh. Four miles to the west are two small villages known under the name Kherā Bajerā, the deserted site of an ancient town. The mound is full of broken bricks and old pottery; the bricks are of a large size, 1' 6" × 9".1

Six miles to the north-east from Akrâbâd is Sâhêgarh (or Sâîgarh) / Kherâ, a very ancient and extensive deserted site. Old coins, especially Indo-

Scythian, are found in great numbers during the rains.

III.

III.

Ш

IIb.

A mile to the west of Sâhêgarh there is another ancient site, called Nagariâ Kherâ.²

2. Hâthras Khâs, tahsîl station, lat. 27°-35′-31″ N., long. 78°-6′-9″ E., 21 miles to the S.-W. of Alîgarh. To the east of the town are the remains of Daya Râma's fort, consisting of a broken mound of earth-work and four corner bastions of great size, surrounded by a ditch fully 40 yards wide on the town side. Inside the fort there are the ruins of an old Hindû temple.

III. there are the ruins of an old Hindu temple.
3. Jalalt, in tabsil Kôl, 11 miles south-east from Alîgarh, is said to have been founded about 700 years ago by the Pathâns near the ruins of an ancient Hindû town called Nilautî. There are three masjids in the town, besides numerous ruined tombs, and the ruins of some small masjids. There are several inscriptions, dated A.H. 965, in the Jâmi Masjid, and one in the Karbalâ, dated A.H. 1137. Of the old III. Hindû site nothing now remains except a bare kherû about a quarter of a mile to the

west of the town.

About a mile and a half to the north-west is another ancient Hindû site, called Kitkharî Kherâ.³

4. Kôl (or Kôîl), lat. 27°-55′-44″ N., long. 78°-6′-45″ E., tahsîl and headquarters of the district, so called after the neighbouring fort of that name. Local tradition identifies it with Kauśāmbî, to which Nichakra removed his capital after Hastināpura had been swept away by the Ganges. But Kauśāmbî has been identified with Kosām on the Jamnā, in the Allāhābād district. The present name was given to the city by Balarāma, who slew here the great asura Kola, and with the assistance of the Ahîrs subdued this part of the Doāb. Kôl is undoubtedly a town of great antiquity, as statues of Buddha and other Buddhist as well as Hindū remains⁵ have been found in excavations made on an eminence in the centre of the city known as the Bâla Qila. Close by stands the Jāmi Masjid of Nawāb Sābit Khān commenced A.H. 1137 (1724 A.D.), and finished A.H. 1141 (A.D. 1728), as recorded in an inscription⁵ over the entrance door. The architecture is the debased style of the last century; the building has five cupolas, three in the middle and one on each side. The materials are block kankar, brick in the domes, and here and there

¹ Canningham, Archaeological Reports, Vol. XII, pages 7 to 9.

⁵ Conningham, L. c., pages 9 to 12.

² Cunningham, L. c., pages 12 to 15.

North-Western Provinces' Gazetteer, Vol. II, pages 484-490, 514-519.

Deposited in the Aligarh Institute.

a Proceedings of Asiatic Society of Bengal for 1872, page 167.

Ia.

IIb.

red sandstone. In the south-east corner of the Jami Masjid there is a well, built Tb. by Hafiz Muhammad Afzal in A.H. 930, as recorded in an inscription on a white sandstone slab.

Near the ruins of the old fort of Bala Qila and south-east of the Jami Masjid TTb. is a smaller and somewhat more ornate masjid, attributed also to Sâbit Khân, and

known as the Moti Masjid.

Close to the Moti Masjid stands the dargah of Shah Ilah Bakhsh; from the inscription it appears to have been built by Sabit Khan, alias Jafar Beg, in

A.H. 1129 (A.D. 1717).

The Masjid in mahallâh Banî Isrâîl was built by Ibrâhîm Sikandar Shâh IIb. in A.H. 930, as stated in an inscription over the entrance of the bath-room adjoining the Masjid.

About a quarter of a mile to the west of the Jami Masjid there is a group of tombs to the south of the Khair road; the central one is called the dargah of Shah IIb. Jamal, Shams-al-Arifin, built in A.H. 949, as stated in an inscription on the wall of the inner compound, opposite the entrance door. The building itself is insignificant, but the surrounding graveyard contains a number of slab tombs and head-stones of considerable antiquity, the inscriptions on a good many being in Arabic.

Although the tomb of Shah Jamal is held in much reverence by the pious, the tomb of Muhammad Gêsû Khân is undoubtedly the most beautiful of the Ia. mortuary buildings around the town. Close behind it is an Îdgâh, bearing a Persian inscription, showing that it was built by Muhammad Gêsû Khân, A.H. 970, (A.D. 1563). On the high ground of the Bâla Qila stood formerly the great mînâr of Vazir Ghias-ad-din Balban on the site of the principal Hindu temple to commemorate the reduction of the town in the reign of Sultan Nasir-addîn Mahmûd; it was pulled down with the sanction of Mr. G. Edmonstone, Lieutenant-Governor, in 1862, to make room for improvements round the Jâmi Masjid. According to its inscription in Tughrâ characters,1 preserved in the Aligarh Institute, it was erected in A.H. 652, or A.D. 1254. It consisted of a round tower on a square base, apparently divided by external cornices into stages. At the time of demolition, the first stage and part of the second remained. The base was of block kankar, with a few pieces of red sandstone; the first stage was entirely of block kankar and the second of burnt bricks. To the north, a doorway opened on a spiral staircase made of block kankar, which originally led to the top of the column. The staircase was lighted by several apertures, and opened on the balcony at the top of the first stage. The lower stage was 54 feet high, and what remained of the second stage was 20 feet. The external circumference at the base was 80 feet, and the walls here were six feet, diminishing at the top of the first stage to 41 feet. Immediately where the kankar staircase terminated, there was an ornamental Hindû pillar laid across the stairway, and above this several beams of wood.

The present fort of Kol was originally known as Ramgarh, from the village Ha. of that name close by. An inscription2 records its construction during the reign of

^{*} Thomas, Pathan Kings of Dehli, page 129. Cunningham, Archaeological Reports, Vol. I, page 191.

Proceedings of Asiatic Society of Bengal for 1872, page 167.

Ibrâhîm Lodi by the Shikkdar Muhammad, son of Umar, in A.H. 931, or A.D. 1524, who called it Muhammadgarh, after his own name. This name was changed to Sabitgarh by Sabit Khan, who repaired it about A.D. 1717, and to Râmgarh by the Jâts about 1757. Najaf Khân took the fort, and changed the name to Aligarh, which it has since retained.

5. LAKHANÛ (or Lûkhnô), six miles S.-E. from Hâthras, is a very ancient place. Several ancient Buddhist sculptures and other remains were found in a tild or mound about a quarter of a mile to the west of the town. There is another mound about one-third of a mile to the south-west from the town.1

6. PILKHÂNA, small village in pargaṇa Akrâbâd of tahsîl Sikandrâ Râo, 13 miles E. of Aligarh, between the Khâsganj road and the Great Trunk Road, possesses a small masjid which has a very beautifully carved doorway, well deserving of a careful drawing.

7. Sânkâra, in tahsîl Atraulî, 36 miles east from Alîgarh, is an extensive ancient site, which consists of the remains of an ancient fort and of an extensive khera.2

8. Såsni, in tahsîl Hâthras, 14 miles S. from Alîgarh, possesses a very large mud fort, in a ruinous state, constructed by the Jats. A short distance to the east is situated a large and conspicuous mound, called Gohana Khera, an old Buddhist establishment. The traces of an ancient temple are still to be seen. Fragments of Buddhist statues were found by Mr. Carlleyle during the exploration of the mound.3

9. TAPPAL, in tahsîl Khâîr, situated near the Jamnâ, 32 miles N.-W. from Aligarh, and 18 miles from Khâir, was in former days a place of some note. Towards the edge of the high land separating it from the khadir of the Jamna are the remains of a very large old fort said to have been built some eight hundred years ago.

10. Tuksan, about five miles N.-W. from Hathras, consists of an ancient khera and a mud fort built by the Jats.4

II.—BULANDSHAHR DISTRICT.

 Aπâr,⁵ in tahsîl Anûpshahr, situated upon the right bank of the Ganges, 21 miles to the N.-W. of the town of Bulandshahr, is no doubt a place of great antiquity. The name Ahar is locally derived from ahi and hara- killing of the serpent,' and the present town is said to be the place where Janamejaya performed the great snake sacrifice and rewarded the Nagara Brahmanas and others who assisted him with grants of lands in the vicinity. Ahar also lays claim to be the Kausambi to which the Pandava rulers transferred the seat of government after Hastinapura had been swept away by the Ganges, a pretension unsupported by probability or evidence. The people of Ahar also claim for it the honor of being the residence of Rukmini, wife of Krishna and daughter of Bhishmaka, Raja of

III.

IIb.

III.

III.

III.

III.

Cunningham, Archaelogical Reports, Vol. XII, pages 1 and 2.

² Cunningham, L c., pages 15 to 24.

^{*} Cunningham, L. c., pages 3 to 7.

⁴ Cunningham 1 - page 2.

North-Western vinces' Gazetteer, Vol. III, page 105. Cunningham, Archaeological Reports, Vol. XII, pages 27-36.

III.

III.

III.

III. Vidarbha. The temple of Ambikâ from which Krishna decoyed Rukminî away is still pointed out by the Brâhmanas of Ahâr as situated on the Ganges about two miles below the present town. This claim must also be negatived, as Kundinapura, the capital of Bhîshmaka, has been identified with Kondavir, the old chief town of Berâr. Connected with Ahâr is a mutilated Kuţila inscription of Mahipâla III. Dêva of Dehlî and Kanauj, dated Samvat 1173. There are several large tumuli (kherâs) in and about Ahâr, which testify to the great antiquity of the place, and there is little reason to doubt that it was the seat of a Hindû principality for some centuries previous to the Musalmân occupation. Heaps of brick and other traces of ruin still extend over a large area. Mr. Growse found several fragments of stone sculpture of early date lying in the streets. He dug up on the very verge of the high cliff overhanging the Ganges a mutilated round pillar having its base

encircled with a coil of serpents, which would seem to corroborate the connection of the local name with the word ahi—snake.\(^1\) The J\(^2\) mi Masjid bears an Arabic inscription.

2. Anûpshahr, tahsîl, lat. 28°-21′ N., long. 78°-18′-55″ E., is situated on the right bank of the Ganges, 25 miles to the E. of Bulandshahr. The town was built by Badgûjar Râjâ Anûp Râî in the reign of Jahângîr on an old kherâ or mound known as Bhadôr. The remains of a brick fort and temple built by Ani Râî still exist below the remains of the old manufactory of the East India Company.

3. Aurangābād Chandok, an old village in pargaņa Shikārpūr, of the Bulandshahr tahsīl, 15 miles E. from Bulandshahr, was in ancient days the capital and residence of the famous Hindū Rājā Chand, the hero of many popular songs and legends. The ruins of the ancient fort and town are still visible, and the ruins of an old temple are pointed out under the name of Chandrāṇī-kā-Mandir.

4. Bulandshahr, 2 called also Baran, lat. 28°-24'-16" N., long. 70°-54'-13" E., is situated on the right bank of the Kâlîndi. It is a place of great antiquity, as even to the present day coins of Alexander the Great and the Indo-Baktrian Kings of Upper India as well as of the Gupta dynasty are found in and around the town. It was founded by a Tômâr, or Pândava chief of Ahâr, Parmâl, and called Banchhati or 'land reclaimed from the forest.' The site of this original settlement is the large mound to the west of the modern town. Subsequently it received the name of Ahibaran (Ahivarana), "snake-fort," from its being the stronghold of the Naga tribe. Baran might with much plausibility be identified with Varanavata mentioned in Mahabharata, I, 143. Later it received from its high position the name of Unchanagar, which has been Persianized into the form of Bulandshahr or "high town." That Baran was occupied by Buddhists from about 400-800 A.D. is proved by several discoveries made by Mr. Growse³ of many specimens of plain stone stools as found only at Buddhist sites, of scores of earthenware flasks used as finials for miniature Buddhist stupas, of an enormous number of large and well-burnt bricks measuring a cubit in length by half a cubit in breadth and three inches in thickness, of a statue of Buddha of black trap with the Buddhist

¹ F. S. Growse, Bulandshahr, Benares, 1884, page 35.

¹ F. S. Growse, l. c., 28—50; Journal, Asiatic Society of Bengal, Vol. XLVIII, page 270 sqq., Vol. LII, page 270 sqq.; Cunningham, Archaeological Reports, Vol. XIV, page 147.

³ F. S. Growse, l. c., page 30.

creed-formula, inscribed in letters of the ninth century, and of a terra-cotta seal, inscribed in characters of the fifth century.1 According to the Manpur inscription Haradatta, a leader of the Dor Rajpûts, took possession of Baran and built a III. fort. The ruins known as the Balaî Kôt, or upper fort at Bulandshahr, are pointed out as the remains of the buildings erected by Haradatta, who ruled at the time of Mahmûd of Ghaznî's invasion of India, A.D. 1018. All the fragments of Brâhmanical stone sculpture that have been discovered at Bulandshahr belong to his time, viz., an unusually lofty column dug up at some low ground at the entrance of the town from the Cholâ Railway Station. Though long since brought under cultivation, the field is still called the sarovar, and is the traditional site of a large masonry tank which Haradatta is said to have constructed. Six short pillars of the same period were found buried under the steps of a small masjid on the highest part of the old town. In digging the foundation of a house on the opposite side of the same street a stone was recovered sculptured with a representation of three miniature temples as well as a mediæval door-jamb and a block carved with rows of temple facades of the Nasik cave pattern.2 From the well adjoining the tomb of Khwaja Lal Barani, about half a mile due east of Bulandshahr, Mr. Growse brought an oblong block of stone measuring 29" by 10," inscribed on two sides in characters of the twelfth century. Both are records of land for religious purposes, but for the most part illegible. They have been deposited in the Indian Museum.3

Among the principal ancient remains near the town is the dargah, bearing an Arabic inscription, dated A.H. 1030, of Khwaja Lal Ali, one of the principal Ia. officers of the invading army of Qutb-ad-din Aibak, Shahab-ad-din Muhammad Ghori's General, killed A.D. 1193 by the Raja of Baran, Chandrasena of the Dor tribe. In the pavement of the same building there is a Sanskrit inscription, partly defaced. Near the town is an Idgah: though not itself an old building, was Hb. evidently constructed from the debris of a still more ancient masjid, as there are in the walls several slabs of stone bearing detached portions of an Arabic inscription in Kufic characters. One of the stones contains a complete Persian inscription, dated A.H. 943, or A.D. 1536, recording the construction of a masjid by Nek-bakht Khân.

The Magbara of Miyan Bahlol, Khan Bahadur, a leading officer under Ia.Akbar, stands in the suburbs with an inscription, dated A.H. 1006, or A.D. 1597.

The Jâmi Masjid is situated on the Balai Kôt; it was commenced in A.D. 1730 at the instance of Sâbit Khân of Kôl, who died before its completion, and was finished in 1830 by Qâzî Fyâz Alî of Bulandshahr, as stated in an Arabic inscription; but an earlier structure probably preceded it on the same site.

Other buildings of some interest are the Masjid of the Moghals, bearing an inscription, A.H. 965; the Dar gah of Makhdûm Shah, with an Arabic inscription said to be of the time of Shahab-ad-din Ghori; the Masjid above the Kôt, with two inscriptions of the time of Muhammad Shah and Alamgir, the latter dated A.H. 1055; and the Gumbaz-i-Qâziân, built during the reign of Akbar.

Ib.

IIb.

¹ Proceedings of Asiatic Society of Bengal for 1881, pages 112, 113, 120,

^{*} F. S. Growse, Le., page 41.

³ Journal of Asiatic Society of Bengal, Vol. XLVIII, page 270.

Ha.

III.

IIb.

III.

III.

III.

IIb.

5. Dankaur, in tahsil Sikandrabad, 20 miles to the S.-W. of Bulandshahr, was, according to the ancient tradition, either founded by or named after Drona, the tutor of the royal youths of Hastinapura. The correct name of the town is said to be Dronakaar, and a masonry tank and an ancient temple still exist which are called Donachar (Dronacharya).

The ruins of a large fort built by Qayâm-ad-dîn Khân in the time of Akbar are still to be seen, and among them stands a masjid of comparatively recent construction.

- 6. Dibhat, an old town in tahsil Anûpshahr, 26 miles S.-E. from Bulandshahr, is the ancient Darbhavatî. Dibhaî is said to have been built upon the ruins of Dundhgarh about the time of Sa'id Salar Masa'ûd Ghâzî, A.H. 420, or A.D. 1029, who expelled the Dhâkra Rajpûts from Dundhgarh, and razed the town. The site of an ancient fort is still to be traced.
- 7. Index (the ancient Indrapura), a kherà or artificial mound of great elevation and extent, about 10 miles from Anapshahr, was the site of an ancient temple of the Sun as proved by a copperplate inscription, measuring 7"×5", in 12 lines, dated Gupta Samvat 146, or A.D. 464, during the reign of Skandagupta, excavated here by Mr. Carlleyle.² This important document shows that in the neighbourhood of the Ganges there were numerous communities, and amongst them Gaura Brâhmanas, as early as the latter part of the fifth century of our era. Besides the inscription a large number of coins, some supposed to be older than the Asoka period, together with beads, fragments of terra-cotta, brass ornaments, and toys were found by Mr. Carlleyle during his exploration of the mound. They were presented to the Indian Museum.³ The ruins of an ancient fort can still be traced.

To the west of Indôr Kherâ lay two large mounds known under the traditional names Kundanpûr and Ahîrpûr. Mr. Carlleyle excavated here an extensive block of temple buildings, and at Vaidyapûr, another extensive mound, the base of an ancient temple.4

- S. Karanbas, in tahsil Anapshahr, is situated upon the right bank of the Ganges, 30 miles S.-E. of Bulandshahr. It is said to have been founded by Raja Karana, a contemporary of Vikramaditya of Ujjayini. There is here a very old temple sacred to Sitaladevi, the goddess of small-pox, which is visited by numbers of women every Monday.
- Kâsnâ, in tahsîl Sikandarâbâd, is situated on the left bank of the Hindân,
 19 miles east of Bulandshahr. The ruins of a large brick fort and other forts close by testify to its former greatness.

IIIb. The tomb of Ikrâm Khân, one of the officers entrusted with the building of the fort at Dehlî by Shâh Jahân, constructed of red sandstone, still exists in a fair state of preservation.

IIb. 10. Khûrjâ, tahsîl, 10 miles south of Bulandshahr, has a modern Jain temple, and the tomb of Makhdûm Sâhib near the Great Trunk Road is the only remains of IIb. any age near the town, and this is only about 400 years old.

¹ This name is also applied to Dabhoi in Gujarat in an inscription of Vira Dhavala.

¹ Journal of Asiatic Society of Bengal, Vol. XLIII, page 363; Cunningham, Archeological Reports, Vol. XII, pages 36—67.

² F. S. Growse, L. c., page 36.

⁴ Cunningham, Archaeological Reports, Vol. XII, pages 67-82,

- 11. Mânpûr, a village about eight miles to the north of Bulandshahr. Here was dug up in 1869 a copperplate grant, dated Samvat 1133, of the Dôr Râjâ Ananga, granting to a Gaura Brâhmana the village of Gandavâ. It has been published in Journal of Asiatic Society of Bengal, Vol. XXXVIII, page 21; but the plate has since disappeared from the Asiatic Society's Rooms at Calcutta, and cannot be traced.
- 12. Shikarpur, in tahsil Baran, 13 miles S.-E. of Bulandshahr; there is a khera or mound near the city called Talpat Nagari or Anyai Khera, "the tyrant's abode."

About 500 yards to the north of the town there is a very remarkable building commonly known by the name of Bârakhambhâor "the twelve pillars." These pillars are of red sandstone and so enormously massive that popular report attributes their preparation and erection to the agency of demons. The building is in reality an unfinished tomb begun by Sa'id Fazl-ullâ, son-in-law of the Emperor Farokh Sir, about A.H. 1131, or A.D. 1718, but never completed; there is besides another inscription, dated A.H. 1076, which was apparently removed from elsewhere and built into the dargâh.

In the town itself the ruins of an old fort are still traceable.

IIb. The masjid of I mâm Sa'dât Khân was founded in A.H. 1057, according to an inscription over the entrance door.

Ha. 13. Tilbēgampûr, in tahsîl Sikandarâbâd, 14 miles N.-E. of Bulandshahr. There is an old bathing well or bâoli near the town, having a Persian³ and Sanskrit inscription, dated A.H. 945 and Sansvat 1595, or A.D. 1538, in the time of Humâyûn, when Faqîr Alî Beg was Governor.

III.—DERAH DUN DISTRICT.

IIb. 1. Dêrah, 3 lat. 30°-19′ N., long. 78°-5′ E., chief town and tahsil of the Dêrah Dûn district. The Sikh temple or Gurudvâra of the Udâsis, the sect of the religious ascetics founded by Râm Râl, their guru, was built in Samvat 1756, or A.D. 1699, and is the only object of historical interest. The central block in which the guru's bed is preserved is a handsome structure, designed in the style of the Emperor Jahângîr's tomb; at the corners it has smaller monuments in memory of the guru's four wives. The model adopted has naturally given a Musalmân appearance to the whole; brick, plastered over and pointed in imitation of mosaic, IIa. forms the material of the building. Three reservoirs, the largest of them being 230 feet long by 184 feet wide, are attached to the temple.

2. Kâlsi, 4 tahsîl, lat. 30°-32′-20″ N., long. 770°-53′-25″ E., is the chief village in pargaṇa Jaunsâr Bâwar. One mile and a half to the south of Kâlsi, close to the little villages of Byâs and Haripûr is the celebrated stone containing the 14 dedicts of Aśoka. The stone is a huge quartz boulder scarcely 10 feet high by 11 feet wide and seven feet thick at the base, the breadth diminishing towards the top. It faces S.-S.-E., and this side has been partly smoothed from three feet

III.

Ib.

III.

Ia.

¹ F. S. Growse, I. c., page 37.

² Proceedings of Asiatic Society of Bengal for 1875, page 14.

³ North-Western Provinces' Gazetteer, Vol. XII, page 197.

Cunningham, Archaelogical Reports, Vol. I, page 244. Corpus Inscriptionum Indicarum, Vol. I, pages 12, 117.
Proceedings of Asiatic Society of Bengal for 1865, page 199. North-Western Provinces' Gazetteer, Vol. XII, page 388.

above the ground for a height of 5½ feet, and bears the greater part of the inscription; but a portion of the record has been inscribed on the left hand side of the rock, the prepared surface having been evidently found insufficient for the whole. On the right hand side an elephant is traced in outline with the word gajatame between the legs. The natives call it Chitrasila, "inscribed or pictured stone," not as General Cunningham states Chhattrasila, "canopied stone." When first discovered by Mr. Forrest early in 1860, the letters of the inscription were hardly visible, the whole surface being incrusted with the moss of ages; but on removing the black film the surface became a greyish white. On comparison with the other edicts that at Kâlsi was found to be in a more perfect state than any other, and more especially so in that part of the thirteenth edict which contains the names of five Greek Kings.

3. Марна, 25 miles N.-E. from Kalsi on the Jamna, in the Bhaundar IIb. Khat of pargana Jaunsar Bawar, possesses some old temples and many interesting remains. Many old and quaintly carved figures are lying about, and some of the IIb. temples pretend to considerable antiquity. The chief temple, called Lakkha Mandir, is apparently constructed from the wrecks of several earlier ones, and

Mandir, is apparently constructed from the wrecks of several earlier ones, and contains two inscriptions, which, though undated, probably belong to about 600 A.D. The most perfect one records the building of a temple by the princess Îsvarâ, the wife of Chandragupta, the son of a king of Jâlandhara (who did not reign). Îsvarâ was the daughter of Kapilavardhanâ, the wife of king Bhâskara of Simghapura, visited by the Buddhist pilgrim Hiuen Tsiang. It gives the following vamsavalî of eleven generations of the Simghapura family:—Sênavarman, Dattavarman, Pradîptavarman, Îsvaravarman, Vriddhivarman, Simghavarman, Jala (varman), Yajnâvarman, and Achalavarman, whose two sons were Divâkaravarman and Bhâskara. This inscription was discovered in 1849 by Major Dawes of the Bengal Artillery. An abstract translation by Bâbû Siva Prasâd was published in the Simla Akhbâr in the same year, and an account of the contents of the record was prepared by H. H. Wilson, and was published in 1858 by Mr. Thomas in his edition of Princep's Essays, Vol. II, Useful Tables, p. 245, note.

Not far from Madha at the village of Bankauli there is an old temple of Mahasu or Mahadeva; the shrine is built on a Tibetan model.

IIb. About 15 miles N.-E. from Madhâ there is a famous temple, sacred to Mahâsu, at the village of Hanôl or Onôl.

IIb. 4. RIKHIKÊS, 25 miles E. from Dêrah, on the Ganges, has an old Hindû temple said to have been built by Sańkarâchârya, about A.D. 675.

IV.—Mîrațh District.

AJRÂRA, in tahsîl Hâpûr, 11 miles S.-E. from Mîrațh, is said to have been the seat of a Hindû monarchy previous to the irruptions of the Musalmâns. Ajipâl, a yogi, built a temple, Thâkuradvâra, and called the place Ajipâra, now corrupted to Ajrâra. In the time of Muhammad Shâh, Khwâja Basant Khân built

Williams, Memoirs of the Dêrah Dûn District, 1874, paragraph 346.

³ S. Beal, Buddhist Records of the Western World, Vol. I, page 143.

- III. a fort which was razed by the Marâthas in 1202 fasli, A.D. 1794, on the rebellion of Fath Alî Khân, brother of Khwâja Basant Khân.
 - 2. BAGPAT, or Bâghpat, tahsil, 30 miles to the west of Mîrațh, on the left bank of the Jamnâ, is said to have been one of the five pâts mentioned in the Mahâbhârata. Its original name appears to have been Vyâghraprastha, or "place of tigers;" another derivation of the name is Vâkyaprastha, or "place of speech." There are a fine Saraugî (Jain) temple, a good-looking Vaishnava temple, and three masjids in the town.
 - 3. Balênî, 15½ miles to the S. of Mîrațh in pargaņa Bâgpat of tahsîl Ghâziâbâd, is a village of great antiquity. The name is said to be derived from Vâlmîkî, whose âsthâna was in this place when a jungle. A modern temple stands on this fabled spot.
- 4. Barnawa, 19 miles N.-W. from Mîrațh in tahsîl Sardhana, is said to have been an outlying fortress of Hastinapura. Some say that the little mound to the III. south of the town, called the Lakha mandap, was the real scene of the attempt to burn the Pandavas in the house made of wax which the Mahabharata places at Varanavata, which identification General Cunningham approves of.
- IIb. On the top of this kherâ there are the dargâhs of Badr-ad-dîn Shâh IIb. and Shâh Alâ-ad-dîn, alias Makhdûm Shâh, built in A.H. 1082, as recorded in two inscriptions. An old Sanskrit inscription, unfortunately much defaced, is built into the walls of Makhdûm Shâh's dargâh; it belonged, no doubt, originally to the old Hindû temple destroyed by the Musalmâns. Over the door of the maqbara of Pîr Sarwâr there is a long Persian inscription, dated A.H. 948, engraved on nine marble slabs, which have been removed from the tomb of Badr-ad-din Shâh.
- III. At Sirsâr is a fort in ruins, said to have been built by one Jalâl-ad-dîn about 700 years ago.
 - 5. BEGAMÂBÂD, 14 miles S.-W. from Mîrath, in tahsîl Ghâziâbâd. There is a modern temple built by Râṇi Bâla Bâî of Gwâlior, 70 years ago, and the ruins of a fine masjid built by Nawâb Zafar Alî, outside the town.
- 6. GARHMUKTÈSAR, lat. 28°-47′-10″ N., long. 78°-8′-30″ E., in tahsîl Hâpûr, 26 miles S.-E. from Mîrath, is frequently mentioned in the *Bhâgavatapurâna* and the *Ib. Mahâbhârata*. There was a very ancient fort here, which was repaired by Mîr IIb. Bhâwan, a Marâtha leader. The name of the town is derived from the great temple of Muktesvara Mahâdêva, dedicated to the goddess Gaṅgâ.
 - There are four principal temples, two placed high on the cliffs and two lower down, in all of which Gangâ, formed of white marble and clothed with brocade, is worshipped. Near these temples there are no less than 80 satî pillars. On the tomb of Ganj Baksh, alias Dargâh Sharîf, near the Jâmi Masjid, there is a Persian inscription of Ghiâs-ad-din Balban, dated A.H. 682 or A.D. 1283.2
- 7. Ghàziàbàn, or Ghàzî-ad-dìnnagar, lat. 28°-40" N., long. 77°-28' E., Hb. tahsil, 25 miles S.-W. from Mirath, possesses six masjids and a good temple, called Mandar Dudhesvaranâtha, built some 200 years ago.

IIb.

Hb.

Ib.

Hb.

 Πb .

Archaeological Reports, Vol. XIV, page 148.

I Thomas, Puthan Kings of Dehil, page 136.

III

- 8. Hàpûr, tahsîl, 18 miles south from Mîrath, is said to have been founded by Haradatta, the Dôr chieftain, about 983 A.D., and called after him Harapûr. Others say that Ghiâs-ad-din Tughlak on visiting the place found the people going about naked, and called it Hayapûr, or "town of shame," and hence the name Hâpûr; but the most probable derivation is from Hâpûr, which signifies "an orchard" or grove, such as abound in the town. The Jâmi Masjid is the only building of any pretension, it was built during the reign of Aurangzîb in A.H. 1081.
- Ib. At the village of Jasrûpnagar Asharpûr there is a celebrated bioli constructed of Agra sandstone, some 500 years ago by Ashar Khân, a Commander in the Army of Ghiâs-ad-din.
 - 9. Hastinapûr, an old town in tahsîl Mawâna, 22 miles to the north-east of Mirath, is said to mark a portion of the site of the ancient Paṇḍava city. There are no ancient remains of any value.
- 10. Кнеката (Khekora or Kakhra), a town in tahsil Bagpat, 26 miles иеst from Mirath, possesses a fine Jain temple.
- 11. Lonî, in tahsîl Ghâzîâbâd, 29 miles S.-W. from Mîraţh; the name is derived from its being the centre of a salt-tract, in Sanskrit lavana, and in Hindî lôn. The remains of a fort of Prithvîrâj, the Chauhân ruler of Dehlî, are still visible. Up to the time of Muhammad Shâh, Emperor of Dehlî, there was another old broken-down fortress of the Hindû period, called Sabkaran Râjâ-kî-Garhî. Muhammad Shâh razed this fort, and used the bricks to build a grove and tank, about 1789 A.D.
- IIb. { At Behtâ Hâjipûr, three miles to the west of Loni, is the dargâh of Abdullâh Shâh and a masjid, built by Aurangzib.
- 12. Mawana, tahsil, 16 miles S.-E. from Mirath, is an old town, and was called Mumana; the original site of the village was on a hill close by. On the banks of the ruined Ini tank is a fine old temple, built some 300 years ago.
- Bâisumâ, a small town eight miles N. of tahsili, possesses a dargâh of Sa'id Abdullâh Shâh, and a dargâh of Sa'id Muhammad Râza Shâh, both erected in Akbar's time, according to two Arabic inscriptions.
 - 13. Мі́патн, lat, 29°-0′-41″ N., long. 77°-43′-3″ E., is the chief city of the district and division of Mı́rath. The people give four derivations for the name Mı́rath:— Yudhishthira on becoming king of Indraprastha (Dehlı̂) is said to have given his village of Mı́rath to Mahi (called also Dâra), a distinguished architect, in exchange for a palace and grounds belonging to him at Indraprastha. Mahi called his new possession Mahirâshṭra, and built the Andar-Kôṭ, a high brick fortress now existing. The Jâṭs allege that Mı́rath was founded by a colony of their contents.
- existing. The Jats allege that Mirath was founded by a colony of their caste belonging to the Maharashtra gotra; others say that Mirath received its name from forming part of the dominions of Mahipala, King of Indraprastha. Others again say Mirath was in very ancient time called Mahidanta-kâ-Kherâ.
- Ia. Undoubtedly the earliest monument connected with Mîrațh is an Asoka pillar, now on the ridge at Dehlî, which runs from the Dehlî monument to Hindû Râo's house to

¹ North-Western Provinces' Gazetteer, Vol. III, pages 318 sqq., 413 sqq.

the north-west of Shah Jahanabad. Shams-i-Siraj1 relates that this pillar once stood in the vicinity of Mîrath, and was conveyed to Dehli by Firûz Shâh, by whom it was erected in the Kushak-shikar, or "hunting palace." The Mirath pillar, as noted by the Persian chronicles, is smaller than the minara-i-zarin, or the "golden pillar," brought from the Sahâranpûr district by Firûz Shâh. General Cunningham makes the upper diameter of the smooth portion 29.5" and the lower diameter 38". giving a diminution of thickness of 0.2" per foot. The pillar lay in fragments until 1867-having been thrown down by an accidental explosion of a gunpowder magazine in the time of Farokh Sîr-when they were again collected together and re-erected on the spot, which has been identified with the Kushak-shikar of Firaz Shah. The inscription on this pillar is very imperfect owing to the mutilated and worn surface of the stone. Such portions as remain have been examined and published by James Prinsep in the Journal of Asiatic Society of Bengal, Vol VI, page 794 sqq. The existence of this pillar and the discovery of Buddhist remains within the city leaves little room to doubt that Mîrath was an important place of the Buddhists in the time of Asoka. No mention, however, of the place is made by the Chinese Buddhist travellers, and this may possibly point to its decay during the early centuries of the Christian era. In the eleventh century Haradatta, the Dor leader, conquered Mîrath and built a fort "which is one of the celebrated forts of the country of Hind, for the strength of its foundation and superstructure and its ditch, which is as broad as the ocean and fathomless."2 The fort was captured by Qutb-ad-dîn in A.D. 1191, and all the Hindû temples were converted into masjids.3 A masjid built by the conqueror bears his name to the present

Amongst the remains of former times in and around Mîrațh may be noticed the Sîtâkund constructed by Jawâhîr Mâl, a wealthy merchant of Sâvâr, in 1714. There are numerous small temples, dharmsâlas, and satî pillars on its banks, but none of any note. The largest of the temples is dedicated to Manoharanâtha, and is said to have been built in the reign of Shâh Jahân. The Balesvaranâtha temple is the oldest in the district, and dates from before the Musalmân invasion. The Mahesvara temple is also an old one, and its construction is popularly attributed to some of the direct descendants of the Pândavas.

The tank called Tâlâb Mâtavâla was built in 1714 by Lâla Dayâl Dâs, a Kâyath merchant; it has now silted up, and only the walls remain. The dargâh in the Nauchandî mahallâh is said to have been built from the remains of an old temple pulled down by Qutb-ad-dîn.

IIb. The dargâh of Shâh Pîr is a fine structure of red sandstone, erected about 1620 A.D. by Nûr Jahân, the wife of the Emperor Jahângîr, in memory of a pious faqîr named Shâh Pîr. The Jâmi Masjid is said to have been built in A.H. 410 or A.D. 1019 by Hasan Mahdî, Vazîr of Mahmûd Ghâznavî, and was repaired by Humâyûn. The remains of a Buddhist temple were discovered near this spot in 1875.

III.

IIb.

Hb.

IIb.

IIb.

Hb.

III.

IIb.

¹ Elliott, Indian Historians, Vol. III, page 353, Cunningham, Archaeological Reports, Vol. I, page 168. Corpus Inscriptionum Indicarum, Vol. I, page 37.

^{*} Elliott, Indian Historians, Vol. 11, page 219.

³ Elliott, I. c., Vol. II, pages 297, 300,

III.

III.

IIb. The dargâh of Makhdâm Shâh Wilâyat was built by Shahâb-ad-dîn IIb. Ghorî; the maqbara or mausoleum of Abâ Muhammad Kambôh was built by his family in A.D. 1658.

IIb. The maqbara of Salar Masa' û d Ghâzî is attributed to Qutb-ad-din Aibak, in 1194 A.D. The maqbara of Abû Yar Muhammad Khân was erected in A.H. 1039, as recorded in an Arabic and Persian inscription on the northern arch of the doorway.

IIb. The Karbalâ was built about 1600 A.D. There is a masjid by Nawâb Khâirandesh Khân in Sarâîganj, and besides these already mentioned there are IIb. 66 masjids and 60 Hindû temples in the city, none of which, however, deserve any particular notice.

14. Muzaffarnagar Sàfnî, in tahsil Mawâna, lat. 29°-2′-21″ N., long. 77°-49′-50″ E., six miles N.-E. from Mirațh, was by common report the great gate of Hastinâpura, and the base of the mound on which it is built is clearly masonry above which the layers of brick are still visible.

15. Parichhatgarh, in tahsil Mawana, 14 miles E. from Mìrath. On the lighest point in the centre of the town is the brick fort of the former Raja Naîn Singh, and adjoining it is his family residence, both of which are still in good repair. The fort claims a hoary antiquity. Tradition ascribes the building to Parikshit, the grandson of the Pandava Arjuna, who was also the founder of the town. The fort remained untenanted until the rise of the Güjar power in the last century, when Raja Naîn Singh repaired and strengthened it. The fort was dismantled in 1857.

16. Pêth, a small village in tahsil Hâpûr, 34 miles S.-E. from Mîrath, is said to have contained the favourite garden of the Hastinâpura Râjâs, by whom it was called *Pushpavatî*. The Musalmâns have the credit of changing the name to Pûth.

17. Råjå Karan-κå-Kherå, 32 miles S.-E. from Mirath, in pargaņa Pāth of III. tahsil Hāpūr, near the village of Mustafābād, is said to mark the site of a village founded by the Karņa mentioned in the Mahābhārata.

18. Sarâwâ, in tahsîl Hâpûr, 13 miles S. from Mîrațh. The Jâmi Masjid bears a Persian inscription of A.H. 1112. Near the village site are two kherâs named Khôr Kâlî and Jalâlpûr. There is also an old kherâ near the village of Atrâra, called Kithaulî, and another at Badnaulî.

IIb. 19. Sardhana, tahsîl, 12 miles N.-W. from Mîrath, has four temples, two of which, known as Lâljî Râm kê and the Chakravâla, are fine buildings.

V.—MUZAFFARNAGAR DISTRICT.1

- BHAINSWÂL, a large village in tahsîl Shâmlî, 27 miles N.-W. from Muzaffarnagar, possesses in its centre a mound of earth about 30 feethigh, now the scene of a melâ, and said to contain the grave of Pîr Ghâib, the founder, who used to house his cattle there when all around was covered with water.
- 2. Bhukarherî, a large village in tahsil Jânsath, 15 miles E. from Muzaffarla. nagar, has a very old tomb, slightly decorated, of a Hindû Yogî. It is a place of worship both of Hindûs and Musalmâns, as the former consider it to be the tomb of Bala Garîb Nâth, and the latter that of Bala Garîb Shâh.

¹ North-Western Provinces' Gazetteer, Vol. III, pages 636-740, passim.

3. Hasanpûr, in tahsîl Jânsath, 28 miles S.-E. from head-quarters, has the III. remains of brick-built houses and of an old masjid now out of repair.

III.

III.

IIa.

Ia.

IIb.

III.

4. Jalâlâbâd, in tahsîl Shâmli, 21 miles N.-W. from Muzaffarnagar. Within a short distance lies the celebrated fort of Ghâusgarh built by Najîb Khân Rohilla. Inside the fort stands a masjid with a well, built in the time of Nawâb Zâbita Khân. The structure is broken in several places, but the outline is quite preserved. The well is of extraordinarily large diameter, being centrally situated between Jalâlâbâd, Thâna Bhâwan and Lohâri.

5. Jhanjhana, in tahsîl Shâmli, 30 miles W. from Muzaffarnagar, possesses a masjid and tomb of Shâh Abdul Razâk and his four sons, built during the reign of Jahângîr in A.H. 1033, A.D. 1623. The domes of both masjid and tomb are decorated with blue coloured flowers, of excellent workmanship. The oldest monument is, however, the dargâh of Imâm Sâhab, built in A.H. 901.

6. Kâînâna, in tahsîl Shâmli, 31 miles S.-W. from head-quarters. The oldest monument is the masjid in mahallâh Pîr Zadân close to mahallâh Afghânân, built by Islâm Shâh in A.H. 958. Nawâb Mukarrab Khân, in A.D. 1626, built many edifices and laid out a beautiful garden with a large tank and bâradari, now out of repairs. He constructed a dargâh near the tomb of the famous Saint Bû Alî, of Pânipat, whilst his son Rizk-ullâ Khân, built the tomb of this Saint in A.H. 1071, or A.D. 1660.¹ Other buildings of interest are:—The Masjid of Maraf Pîr on the Shâmli Road, built by Aurangzîb A.H. 1077; the Masjid Darbâr Kalan, built by Sâhab Sulţân, mother of Shaikh Muhammad Fazal, in A.H. 1051; the Masjid Afghânân, built by Shâh Jahân in A.H. 1062; and the Masjid in mahallâh Khêl, built in A.H. 1066.

7. Khâtaulî, in tahsîl Jânsath, 13½ miles S. from Muzaffarnagar, possesses IIb. four large Jain temples, and a large sarâî built by Shâh Jahân, as recorded in a Persian inscription over the entrance gate.

8. Kotesra, village in tahsil Muzaffarnagar, 11 miles N.-W. from headquarters. On the south of the town is an old ruined fort belonging to some decayed Said families. It is a remarkably large brick-built place with corner towers and cupolas of which much remains.

9. Majhêra, village in tahsîl Jânsath, 18 miles S.-E. from head-quarters. The principal remains are:—(1) the tomb of Saîd Sâîf Khân and his mother, of white marble with red sandstone in interior of dome, somewhat decorated, inscribed A.H. 972, or 1564 A.D. It was built by Saîd Muhammad Khân for himself; but his son, Sâîf Khân, having died in his father's life-time, was buried here; it is the handsomest of the Majhêra tombs; (2) the tomb of Saïd Muhammad IIa. Khân of white marble and slightly decorated, inscribed A.H. 982, or A.D. 1574, has Arabic sentences all round; (3) the tomb of Mîrân Saïd Husain, dated A.H. 1000, or 1592 A.D.²; (4) the tomb of Saïd Umâr Nûr of white marble, pillars

IIa. and dome of red sandstone, date unknown; (5) a large octagonal well of good stone masonry, with stairs and cells said to have been built in Said Muhammad Khân's father's time.

¹ Proceedings of Asiatic Society of Bengal for 1872, page 97,

^{*} Proceedings of Asiatic Society of Bengal for 1873, page 141,

- 10. Mornah, village in tahsîl Jânsath, 15 miles E. from Muzaffarnagar, has a IIb. / large masjid built by Bîbî Jhabbû, wife of Nawâb Hasan Khân, during the reign of Muhammad Shâh, in A.H. 1138, A.D. 1725. This is one of the last of the substantial Saîd buildings.¹
- 11. Sambalhèrà, village in tahsîl Jânsath, 18 miles S.-E. from head-quarters, is one of the principal seats of the Bârha Sa'îds. There is a tomb of Hazrat Ibn Salâr, son of Husain, built during the reign of Firûz Shâh, in A.H. 777, or A.D. 1375.
- IIb. The masjid was built in the reign of Shâh Jahân by Sáid Mâkhan, son of Bahâ-ad-dîn, in A.H. 1041, or A.D. 1631.2 In the adjoining village of Mahmûd-III. pûr is a brick fort with high corner towers.
- 12. Thana Bhawan, a town in tahsil Shamli, 18 miles N.-W. from head-quarters, possesses a celebrated old temple of Bhavanidevî, still a place of considerable resort. Of the Musalman period there are few buildings of any value, viz., the Masjid of Maulavi Said-ad-dîn, built in A.H. 1099; the maqbara of Bazurgon Maulavi Shaikh Muhammad, erected in A.H. 1109; and the Masjid of Pir Muhammad, built by Alamgir in A.H. 1114.

VI.—Sahâranpûr District.3

- 11. Ambahtâ (or Abahtâ Islâmnagar), town in tahsîl Nakûr, 16 miles S.-W. from Sahâranpûr, possesses a fort, three masjids and a tomb of Shâh Abûl Maâli, a celebrated personage in the seventeenth century. Of the masjids the oldest is built by Sultân Sikandar Shâh in A.H. 916, the second in Humâyûn's reign, and the third in A.H. 1168. The tomb is a fine domed building with minarets, all in good repair, and situated in the middle of the town.
 - 2. Bahâr, on the Eastern Jamnâ Canal, in tahsîl Sahâranpûr, 18 miles N. from head-quarters. In 1834, Captain Cautley discovered here an old town 17 feet below the general surface of the country and 25 feet below that of the modern town of Bahât, Numerous coins of Indo-Seythic origin with Baktro-Pâli inscriptions and other remains were discovered which stamp the place as decidedly Buddhist.
- 3. Bhagwanpûr, in tahsîl Rûrki, 18 miles N.-E. from Sahâranpûr. About IIb. five miles to the north lies Sakraudâ, possessing a mausoleum of Shâh Rak-dîn or Shâh Pungam and a ruined masjid, built in A.H. 1118—1129, or 1706—1716 A.D. The mausoleum consists of a centre room in which is the Saint's grave, surrounded by a verandah supported on elegantly-carved pillars. It has a very pleasing effect from its artistic form, which is set off with flowers and fantastic designs painted on the stucco that conceals the masonry.
 - 4. Dêoband, tahsîl, lat. 29°-41′-50″ N., long. 77°-43′-10″ E., 21 miles south from Sahâranpûr, is a town of great antiquity. It is said that the Pândavas resided here during their first exile, and the Musalmâns assert that it was one of the first fortresses taken by the celebrated hero, Sipâh Salâr Masa'ûd Ghâzî. Its

¹ Proceedings of Asiatic Society of Bengal for 1873, page 142.

^{*} Proceedings of Asiatic Society of Bengal for 1872, page 166.

² North-Western Provinces Gazetteer, Vol. II, pages 258-344, passim,

^{*} Journal of Asiatic Society of Bengal, Vol. III, pages 43 and 221 sqq.

original name was Deviban or "sacred forest," and there is still a grove near Пь. the city in which there is a temple sacred to Devî (Pârvatî). The west and north Πb .

banks of the Devikund are covered with modern temples, ghâts, and numerous satî pillars. There are 42 masjids in the town of which the most important are the Jâmi Masjid, built by Sikandar Shâh, in A.H. 916, and the Masjid Aurang-

zî bî, built in A.H. 1078.

IIb.

IIb.

IIb.

IIb.

IIb.

5. Gangon, in tahsil Nakûr, 23 miles S.-W. from Saharanpûr. The western suburb of the town contains three large maqbaras around which are grouped the smaller tombs of those who desired to lay their remains near those of the saintly personages who repose in the larger buildings. The most important is the mausoleum of the famous saint Shaikh Abdul Kaddûs, built by Humâyûn in A.H. 944, or 1537 A.D. This building is of moderate size, and although pretty enough, has no great pretensions to architectural beauty. Other buildings of importance are :the Jâmi Masjid, built during Akbar's reign, in A.H. 963; the Masjid Rêri, erected

by Jahangir in A.H. 1034, and the Lal Masjid built by Faqir Nur Muhammad in A.H. 1081. 6. HARDWÂR, in tahsîl Rûrki, 39 miles S.-W. from Sahâranpûr, has borne several names. It was formerly called Kâpila, so named after the sage Kâpila

who is said for a long time to have performed religious austerities here. The place where he lived is still shown under the name Kapilasthana. Another common name is Gangâdvâra, or "gate of the Ganges," by which it was known to Hiuen Tsiang in the middle of the seventh century, and also to the Musalman writers Abû Rihan and Rashid-ad-din. It is now best known by the name of Hardwar or Haridwar; the first name being derived from Hara, a synonym of Mahadeva or Šiva, and the second from Hari, a synonym of Vishnu. The form Haridvâra is found in the Kedara Khanda of the Skandapurana and other Vaishnava works. In the Vishnupurana it is called Haridvara, and the Ganges is said to flow from the toe of Vishnu.2 The Vaishnavas point out the Hari-ka-charan or Hari-ka-pair "the print of Vishnu's foot" in support of this belief. Amarasimha, a renowned Buddhist lexicographer, and the author of the Amarakosha, gives Vishnupadi as one of the synonyms of Gangâ. The Saivas, on the other hand, adhere to the form Haradvâra, and quote the origin of the Bhagirathi or principal branch of the Ganges, in the Kailasa of Mahadeva, in support of their theory. The term Gangadvara would seem to point out that there was originally a celebrated temple here of that name, around which the present town has sprung up. Hiuen Tsiang describes the town as being 31 miles in circumference and very populous.3 General Cunningham considers that this account corresponds very closely with the site of the old city of Mayapura as pointed out to him by the people.4 Within these limits there are the ruins of an old fort, 750 feet square, attributed to Raja Ben, and several lofty mounds covered with broken bricks. There are also three old temples dedicated to Narayanašila, to Mâyâdevî and to Bhairava. The celebrated Pairghât or "feet ghât" is

III. IIb.

outside these limits, being upwards of 2,000 feet to the N.-W. of Sarvanatha's temple.

³ Cunningham, Archaelogical Reports, Vol. II, pages 231—237.

^{*} Hall, H. H. Wilson's Vishaupurana, III, 302,

Beal, Buddhist Records of the Western World, Vol. I, page 197.

[·] Cunningham, Archavlogical Reports, Vol. 11, page 233.

The antiquity of the place is undoubted, not only from the extensive foundations of large bricks and the numerous fragments of ancient sculpture accumulated about the temples, but from the great variety of the old coins found there every year. Amongst the broken sculptures, General Cunningham was able to identify only one small figure of Buddha, surrounded by smaller figures of ascetic attendants. The temple of Nârâyanasila or Nârâyanabali is built of bricks, 9½ inches square and

- IIb. temple of Nârâyaṇaŝila or Nârâyaṇabali is built of bricks, 9½ inches square and IIb. 2½ inches thick, and is plastered on the outside. The temple of Mâyâdevî is built entirely of stone, and from the remains of an inscription over the entrance door-way, may be as old as the tenth or eleventh century. The principal statue, which is called Mâyâdevî, is a three-headed and four-armed female in the act of killing a prostrate figure, corresponding with the figures of Durgâ. Outside the modern temple of
- IIb. Sarvanât ha General Cunningham found a statue of Buddha seated in abstraction under the Bodhi tree, and accompanied by two standing and two flying figures. The great object of attraction at the present day is the Hari-kâ-charan or bathing ghât.
- III. and the adjoining temple of Gangadvara. Close by, in a small temple, is a well III. called the Brahmakund, which is most probably the same that was noticed by Hiuen Tsiang in A.D. 629, but the great Dêva temple of his days has long ago disappeared.
- 7. Јнаванне̂на, in tahsil Rûrki, 12 miles E.-S. from Saharanpûr, possesses a IIb. pretty masjid built by Nawab Haqim Khan, formerly Governor of the district, and IIb. a well, built in A.H. 1198.
- 8. Kankhal (the ancient Kanakhala), town in tahsil Rürki, 38 miles east IIb. from Saharanpür. The old temple of Dakshashara or "lord of Daksha," a synonym of Siva, lies to the south of the town, and is supposed to mark the spot where Siva spoiled the sacrifice of Daksha, and where Sati or Uma, daughter of Daksha, and spouse of Siva immolated herself in the fire. The temple was originally domed, but the dome was broken by a decayed Banyan tree, which has now disappeared. The construction of the dome, however, shows that the temple is later IIb. than the Musalman conquest. In front of the temple there is a small square building containing a bell which was presented by the Raja of Nepal in Saka 1770, or A.D.
- IIb. 1848. Around the Dakshêśvara temple there is a group of other small fanes, but none of them are of any interest or antiquity.¹
- 9. Khizbābā, town in pargaņa Faizābād of tahsīl Sahāranpūr, 27 miles N. from head-quarters. The oldest monument having any connection with the district of Sahāranpūr stood formerly near this spot, viz., the golden lât of Firūz Shāhā Tughlak, now at Dehlî. Shāms-i-Sirāj Afīf in his chronicles of the reign of Firūz Shāhā mentions the removal of the mināra-i-zarīn from the village of Tobra (variously called Topar, Topēra, Toparsak, Tohēra, Tawēra, and Nahēra) in the district of Sālaura and Khizrābād at the foot of the hills, 90 kos from Dehlî to Firūz's new capital of Firūzābād (Dehlî), where it was placed in the palace (Firūz Shāh's Koṭila) near the Jāmi Masjid. From this description of the original site of

¹ Cunningham, Archaelogical Reports, Vol. II, page 237.

² Elliot, Indian Historians, Vol. III, page 350.

³ Journal of the Archicological Society of Dehli, Vol. I, pages 29 and 75; Cunningham, Corpus Inscriptionum Indicarum, Vol. I, pages 34—36.

this pillar General Cunningham¹, in 1863, concluded that the village from where it was brought was perhaps the present Pâota on the western bank of the Jamna and 12 miles N.-E. of Khizrâbâd, whilst, in 1879, he identified the spot with the village of Bara Topra,² in the Ambâlâ district of the Panjâb, 22 miles to the S.-W. of Khizrâbâd.

The "golden pillar" is a single shaft of pale pinkish sandstone, 42 feet 7 inches in length, of which the upper portion, 35 feet in length, has received a very high polish, while the remainder is left quite rough. Its upper diameter is 25.3 inches and its lower diameter 38.8 inches, the diminution being 0.39 inch per Its weight is rather more than 27 tons. In its dimensions it is more like the Allahâbâd pillar than any other; but it tapers much more rapidly towards the top, and is, therefore, less graceful in its outline. There are two principal inscriptions on Firuz Shah's pillar, besides several minor records of pilgrims and travellers from the first centuries of our era down to the present time. The oldest inscriptions for which the pillar was originally erected comprise the well-known fourteen edicts of Asoka.3 The record consists of four distinct inscriptions on the four sides of the column facing the cardinal points, and of one long inscription immediately below which goes completely around the pillar. The last ten lines of the eastern face, as well as the whole of the continuous inscription round the shaft, are peculiar to the Dehlî pillar, and contain new forms similar to those on the rock inscription at Kâlsi. A second inscription records the victories of the Chauhan prince Vîsaladêva, dated Samvat 1220, or A.D. 1163. The minor inscriptions are of little interest or importance.

10. Landhaura, a large village in tahsîl Rûrki, 28 miles E. from Sahâranpûr, possesses an old fort.

11. Manglaur, town in tahsîl Rûrki, 16 miles S.-E. from head-quarters.

IIb. The oldest monument is the Masjid of Shâh Wilâyat, built by Sulţân Ghiâs-ad-dîn Balban in A.H. 683, as recorded in an Arabic inscription. Traces of the foundations of the fortress, said to have been built by Râjâ Mangal Sâîn, a Râjpût feudatory of the celebrated Vikramâditya, are still visible near the town.

12. Nakûr, tahsîl, 16 miles S.-W. from Sahâranpûr, is said to have been founded by Nakula, one of the Pâṇḍavas, after whom it was called Nâkula, and finally Nakûr. There is a fine Jain temple in the town.

13. Faizābād, in tahsîl Sahāranpūr, 25 miles N. from head-quarters. Two miles to the N.-W. of Faizābād lies the Badshāhî Mahāl, built by Alî Mardān in the beginning of this century. The building stands on the left bank of the Jamnā, about three miles from the foot of the Siwâliks; it has been patched up out of a few rooms belonging to a country seat of the Emperor Shāh Jahān. The renovated building is not striking in its appearance, but the remains of the fine terrace running along the banks of the river, of foundations and water-courses occupying every part of the compound, together with ruins of out-houses, prove that the old palace was handsome and commodious, if not magnificent.

III.

IIb.

III.

¹ Archeological Reports, Vol. I, pages 161-167.

Cunningham, Archaeological Reports, Vol. XIV, pages 78 and 79.

^{*} Journal of Asiatic Society of Bengal, Vol. VI, page 609 299. Indian Autignary, Vol. XIII.

Hb.

IIb.

IIa.

III.

IIb.

14. Râjûrûr, large village in tahsîl Dêoband, 19 miles S.-E. from Sahâranpûr, possesses a good masjid.

15. Râmpür, town in tahsîl Dêoband, 14 miles S. from head-quarters, possesses IIb. a fine modern Jain temple and the dargâh of Shaikh Ibrâhîm Pîr, where a religious fair is held in June, attracting a large assemblage.

16. RÜRKI, tahsîl, 22 miles from head-quarters. About four miles to the north IIb. of Rürki, at the village of Pîrân Kalhar, lies the mausoleum of Makhdûm Shâh Alâ-ad-dîn Ali Ahmad Salîm Chishțhi, built in A.H. 1036, and repaired in A.H. 1220 and 1231.

Six miles to the east of Rûrki, lies the village of Jaurâsi, possessing the Jâmi Masjid, built by Aurangzîb in A.H. 1086.

In the village of Jwâlapûr, 13 miles North of Rûrki, there is a pakka well, known as Haqîmwallâ, bearing a Sanskrit inscription, dated Sanvat 1725.

17. Saharanpür, tahsil and chief town of the district, lat. 29°-28'-15" N., IIa. { long. 77°-35'-15" E., has an old Rohilla fort, and four fine masjids built in A.H. 936, IIb. { 1054, 1078, and 1193 respectively.

18. Sarsawa (or Sirsawa)1 in tahsil Nakûr, 101 miles west from Saharanpûr, is a very ancient town with a lofty mound, which is the most conspicuous object in the landscape for many miles around. In the time of Emperor Bâbar the great mound was a strong brick fort, 1,000 feet square, with a ditch all round 120 feet broad. In the time of Akbar, Sirsawa with its brick fort was one of the chief places in the Saharanpur Sirkar. But long before the English occupation the walls had been dismantled, and the mound was overgrown with jangal. The fort had four large round towers at the corners, of which the north-east bastion still retains the commanding height of 50 feet, while the other three are 40 feet, and the level of the interior not less than 50 feet above the country. The earliest notice of Sirsawa is by Abû Rihân. The name of the place is said to have been derived from the last Rájá Širas Pál, who was attacked and defeated by Malik Násir-ad-dîn of Ghaznî. When dying, the Râjâ gave his daughter to Nâsir-ad-dîn, and begged that the fort might hereafter be called by his own name as Siras-awa. The siege lasted for three months, and one of the enemy's leaders, Pîr Mardâna Shahîd, who fell in fight with Siras Pal, now lies buried on the top of the north-east bastion. By the people he is more commonly known as Kilkili Sahib.

Sirsâwa, or Siraspattana, is celebrated as the birth-place of Bâchal Rânî, the mother of Gugâ Chauhân, who is worshipped as Gugâ Bîr by Hindûs and as Gugâ Pîr and Zâhir Pîr by Musalmâns all over Northern India, from the Himâlaya mountains to the Narmadâ.

Ten miles to the west of Sarsawa and 20 miles to the N.-W. of Saharanpûr lies the village of Sugh, in the Ambâlâ district of the Panjâb, which General Cunningham identifies with the ancient Srughna.² When Hiuen Tsiang visited the place, the greater part of the town was in ruins, but the foundations still remained. It possessed five Buddhist monasteries, one hundred Hindû temples, and many stûpas.³ Tradition and the discovery of large bricks and extensive finds of old

¹ Cunningham, Archaelogical Reports, Vol. XIV, pages 79-86.

² Archwological Reports, Vol. II, pages 226 to 231; Vol. XIV, page 134.

Beal, Buddhist Hecords of the Western World, Vol. 1, pages 185 to 189.

coins all point out the antiquity of the present site of the village of Sugh and that of the neighbouring village of Mandalpûr which had supplanted the ancient name of Srughna during the reign of Firûz Shah Tughlak.

19. Between the Sahansrâ and Shâkumrî Devî passes, in tahsîl Sahâ-IIb. ranpûr, 25 miles north from head-quarters, lies the temple of Sahansarâ Thâkur. This temple has evidently been built from the materials of a still older edifice, some remains of which are still scattered about in all directions. They are blocks of sandstone some curiously carved, indented with holes, showing that iron clamps, not cement, were used to bind them together.

A few miles further on towards the Jamna are the ruins of a fort called III. Sarwin Marwar-ka-makan. This place appears to have been intended rather as a permanent residence than as a temporary asylum in the heart of the Siwaliks.

II.—ROHILKHAND DIVISION.

I.—BADÂON DISTRICT.

IIb. 1. Alâpûr, in tahsîl Dâtâgani 12 miles S.-E. from Ba

Hb.

1. Alâpûr, în tahsîl Dâtâganj, 12 miles S.-E. from Badâon, possesses a masjid built during the reign of Aurangzib în A.H. 1071 (A.D. 1660), as appears from the inscription inside the masjid, and two Hindû temples of no remarkable architecture. There is a fragment of another inscription, dated A.H. 707, A.D. 1307, outside the

masjid, most probably belonging to a still older building.

 Badaon (or Badâyûn),² tahsîl and capital of the district, lat. 28°-2'-30" N., and long. 79°-9'-45" E. Of the earlier history of Badaon very little is known; according to a stone inscription of Lakhanapala, its first name was Vôdâmayûtâ. It was the capital of a Pala dynasty who belonged to the Rashtrakûta clan. probably connected with the Rathor rulers of Kanauj,-and who built the great III. fort on which part of the city now stands. Several of the towers still remain, and in many places the thick brick walls are still visible. The old site is about threequarters of a mile in length, and its general outline is well marked by a great mound on which half of the city now stands. The old city possessed a magnificent stone temple in honour of Siva, erected by Îsânasiva, the head of a matha or monastery during the reign of Lakhanapala in the beginning of the twelfth century, as proved by Lakhanapala's inscription discovered, in August, 1887, in the old fort walls and now deposited in the Lucknow Provincial Museum. This temple was destroyed by Shams-ad-din Iltitmish, in A.D. 1223, and the present Jâmi Masjid erected on its site. Many exquisitely-carved statues, pillars, pilasters, architraves, and ceiling stones of this beautiful temple were used as common building stones in the East gate of Iltitmish's Masjid; the best specimens of these relics have been secured for the Lucknow Museum, in February, 1888, when the somewhat ruined gate was broken down for the purpose of being rebuilt by the Musalman community.

The inscription gives the following vamsåvali:—Chandra, Vigrahapåla Dêva (son), Bhuvanapåla (son), Gôpâla Dêva (son), Tribhuvana, Madanapåla, and Dêvapåla (sons), Bhîmapâla (son of last), Sûrapåla (son), Amritapåla and Lakhaṇapâla (sons). Reference is made to the Hammîras in the reign of Madanapåla which appears clearly to point to the invasions of the Musalmâns.

The oldest monument is the Shams-î-Îdgâh about one mile from the outskirts of the city, built by Iltitmish during his governship of Badâon, between A.H. 599 and 606, or A.D. 1202—1209. It is a massive brick wall, 300 feet in length, with lines of ornament near the top which most probably were originally covered with blue glaze. There is a long inscription over the mihrâb, but it has been carefully plastered over, and only a few letters are now visible. To the right of the pulpit is a part of an inscription in one long line, apparently an extract from the Qurân.

¹ Journal of Asiatic Society of Bengal, Vol. XLI, page 113.

² North-Western Provinces Gazetteer, Vol. V, pages 157 to 160, Cunningham, Archaeological Reports, Vol. XI, pages 1 to 11.

Пb.

Close by is the shrine of Badr-ad-dîn Hazrat Shâh Wilâyat, which is so thickly whitewashed that none of its details are visible. It possesses, however, three Arabic inscriptions, one of the time of Subaktgîn, dated A.H. 391, and two of the time of Akbar, dated A.H. 981.

IIb.

The Jami Masjid of Badaon is one of the largest Musalman buildings in India, its outside dimensions being 276 feet in length by 216 feet in width. The interior court is 180 feet long by 94 feet broad. The lower part of the walls to a height of 12 feet is built entirely of sandstone blocks, the plunder of the Saiva temple of Lakhanapala and probably of several other buildings. Four of the stone pillars are lying in the courtyard just inside the gateway; these are single shafts 1 foot 61 inches in diameter, and 9 feet in length; they have 16 fluted sides with richly-carved capitals and bases. The superstructure of the old masjid is entirely of brick, but the central dome which is a late restoration of Akbar's time, contains many blocks of kankar. The outer face of the entrance gateway is built wholly of sandstone, with overlapping arches. Over the outer opening there is an inscription in two lines, which gives the date of the building in A.H. 620, or A.D. 1223, during the reign of Shams-ad-din Iltitmish.1 The main body of the masjid is formed of four rows of massive brick piers from six feet to eight feet square, standing in front of the back wall. On each of the other three sides of the court there are two rows of similar piers, now in ruins. The central portion of the masjid, as it now stands, consists of a large dome 43 feet in diameter, supported on massive walls, 17 feet thick, with a pointed arch in front, 18 feet in width and a similar arch on each side, 17 feet 9 inches in width. Outside the front arch there is another larger one of 32 feet span, over which rises the front wall of the masjid, nearly concealing the massive dome behind it. But this part of the building is of late date, having been made by Shaikh Khûbû Kôka, the foster-brother of Jahângîr, in A.H. 1013, A.D. 1604. This inscription is in two lines on a long stone which is let into the wall on the right side of the inner arch of the entrance. Another inscription on the left side of the same arch records the date A.H. 1011. To the right and left there are two smaller entrances which lead direct from the smaller streets, on the north and south, into the court of the masjid. Over the middle of the northern doorway there is an inscription bearing the name of Abûl Mujâhîd Muhammad Shâh Tughlak and the date A.H. 726, A.D. 1326, recording the restoration of the masjid by Husain, the son of Hasan. Originally the whole surface of the inner walls of the masjid was covered with raised ornamentation in blue glazed tiles. The outlines of the geometrical and flowered patterns are still quite distinct, although the coloured glaze has generally disappeared. Externally, the walls of the masjid are very plain, being relieved only by lines of simple brick mouldings. But the small towers at the four corners are richly ornamented with various patterns of geometric tracery. The extensive repairs, carried on since 1887. and unaided by Government subvention, reflect great credit on the Musalman community of Badâon.

IIb.

To the same period belong the following buildings of historical interest, viz., the dargah of Miranji, with an Arabic inscription of Shams-ad-din Iltitmish, and another of Muhammad Tughlak, dated A.H. 728; the Masjid of Ahmad Khandan, built by

¹ Journal of the Ariatic Society of Bengal, Vol. XLI, page 112, where the date is wrongly given as A.H. 628.

Ib.

Ib.

Ib.

Ib.

Rukn-ad-dîn, in A.H. 633; the house of Bûndîwallâ in mahallâh Sotahâ, with an Arabic inscription of Shams-ad-dîn Iltitmish; the Nabîkhâna of Haqîm Hâfiz Mujâhîd-ad-dîn, with an Arabic inscription in mixed Kûfî and Bahârî, dated A.H. 420; the dargâh of Sulţânjî, with an Arabic inscription of Nâsir-ad-dîn Mahmûd, the tomb of Âlham Shahîd, with an Arabic inscription, in Kûfî, of Shams-ad-dîn Iltitmish, and the Masjid of Dâdâ Hamîd, built by Nâsir-ad-dîn Mahmûd Shâh, in A.H. 648.

Besides these buildings there are four smaller masjids, viz., the Masjid of Haidar Shâh, erected by Muhammad Âdil Shâh, in A.H. 957; the Bâdâm Masjid and Khurmâ Masjid, both built by Aurangzîb, in A.H. 1080 and 1092 respectively, and the Masjid of Nîzam-ad-dîn, built by Muhammad Shâh, in A.H. 1140.

Of the older tombs now remaining at Badâon whose dates can be ascertained, all but six belong to the ninth century of the Hijra, viz., the tombs of Mirânjî, Sulţânjî, and Âlhâm Shahîd, mentioned above; the Nayî Ziârat, dated A.H. 700; the tomb of Âzam Shahîd, dated A.H. 771; and the tomb of Shâh Zâdî, dated A.H. 796. It seems very probable that those of the ninth century belong to different members of the family of the Saîd King Alâ-ad-dîn Âlam, who abdicated the throne in favour of Bahlol Lodî in A.H. 854. There is nothing either striking or peculiar in their appearance. All are simple square masses of almost plain brick-work, with some bands of blue glazed tile ornament.

The tomb of Chimni Khân, to the south of the town, is an octagonal building of $26\frac{1}{2}$ feet each side, with a room inside $27\frac{1}{2}$ feet square. The building is apparently of later date than the others, probably not older than the time of Sikandar Lodi. It is in better order than most of the others, and is more highly decorated. The battlement especially is a good specimen of rich ornamentation; the dome, however, is very low.

Close to it stands another tomb, square in form, with a side of 34 feet 4 inches; it is ornamented with a single band of dark-blue glazed tiles, and has a rather flat dome. No name is known for it, but it is simply called *chaukon*, or the "square" building. The room inside is square with the usual overlapping pendentives in the corners. As the *inscription* over the door bears the date of A.H. 957, the tomb must belong to the reign of Islâm Shâh Sûr.

The tomb of Sultan Ala-ad-dîn Alam Shah and his wife lies to the west of the town; it is 25 feet 6 inches square outside, with a square room inside. Over the door are two inscriptions, bearing the dates of A.H. 877 and 882, A.D. 1472 and 1477, carved on two different coloured sandstones; that on the left hand being white and the other red. Each inscription consists of two lines, and as both run the full length of the two slabs horizontally, the two halves of both are on different coloured stones. For the preservation of this tomb certain lands have been set aside, as shown by an inscription measuring 5 feet by $2\frac{1}{2}$ feet.

The tomb of Dâolat Khân is one of the largest tombs now standing at Badâon, being a square of 42 feet 9 inches outside with a room 28 feet square inside. Over the door there is an undated *inscription* of one line. The dome is much loftier than that of Chimni Khân's tomb, but it is dwarfed by the great mass of buildings below.

² Journal of the Asiatic Society of Bengal, Vol. XLI, pages 110 and 111,

The tomb of Shahzada Fath Khan stands on the east side of the town; it is Ib. a square of 40 feet outside with a room of 19 feet 8 inches square inside. It is ornamented with some blue glazed tiles in squares bearing the name of Allah. Over the eastern door there is a long slab bearing an inscription,1 dated A.H. 860, 1456 A.D.

Close to this tomb stands another, being a square of 43 feet externally, with IIa. walls 7 feet 9 inches in thickness, and an inner room 27 feet 6 inches square. Over the door there is the Kalimah inscribed in brick, but the great stone inscription

is gone.

Ha.

IIa.

IIa. ∨

IIb.

Hb.

Hb.

Hb.

III.

116.

116.

The tomb of Makhdûmah Jahân, the mother of Alâ-ad-dîn Alam, stands on the south side of the town. It is 367 feet square outside, with a room 23 feet 4 inches square inside. The corners are cut off in the usual way by overlapping pendentives to form an octagon for the spring of the dome. In the middle there are two brick graves; in the south-east corner there is the third grave. There is an inscription over the doorway with the date of A.H. 866, or A.D. 1461.2

To the south of this lies the tomb of one of the sons of Alâ-ad-dîn. It is exactly of the same style, but of only half the size, being 191 feet square outside, and 12 feet

square inside.

Other tombs of the same period are the dargah of Imad-al-mulk, alias Pisanhari-

kå-gumbaz, dated A.H. 820, and the takiå of Mina Shah, dated A.H. 896.

Besides the tombs just described, there are several of later date. Amongst these is the tomb of Ikhlas Khan of the Moghal period, a small, neat-looking building with stout towers at the four corners; the dargah of Jahjar Khan, built by Salîm Shâh, in A.H. 950, and the Ziârat-î-Shaikh Jalâl, built by Nûr-ad-dîn Jahangir, A.H. 1018. The tomb of Shaikh Afrid is also a very small one, and is only remarkable for its curiously-shaped minars. The tombs of Sultan Arfin, Shâh Jhandâ, dated A.H. 860, Mukbâra Shâh Ujalah, and Saîd Ahmad Shâh are of no interest whatever.

Another important inscription records the construction of a canal by Khwajah Jahan-us-Sharq, the founder of the Jaunpur dynasty, in A.H. 798, or A.D. 1395.

This inscription is on a loose slab, and not attached to any building.3

Half a mile to the west of the city, near the Shamsî Îdgâh there is a large burialground, called Qabaristân Shâhî, covered with old tombs of red sandstone, IIb. many of which are inscribed with verses from the Qurân, and belong mostly to the ninth century of the Hijra.

3. BISAULÎ, tahsîl, 24 miles north from Badâon, possesses a fine masjid, an Vimâmbâra, and a fort built by Dûndi Khân about 1750 A.D. The remains of the Shîsha Mahal or "glazed palace" built by the same ruler, are still visible.

4. KAKRÂLA, in tahsîl Dâtâganj, 12 miles south from Badâon, possesses a modern

Hindû temple and several masjids of no historical or archæological value.

5. Kôt Śālbāhan, in tahsîl Sahaswân, 20 miles north-west from Badâon, was formerly a place of great importance. The name Kôt Śâlbâhan signifies the

1 Journal of the Aziatic Society of Bengal, Vol. XLI, pages 110 and 111.

² Proceedings of the Asiatic Society of Bengal for 1872, page 49, where the date is wrongly read as A.H. 877, but corrected in Proceedings for 1874, page 100. 3 Proceedings of the Aziatic Society of Bengal for 1872, page 48,

IIb. IIb.

IIb.

 $\Pi b.$

III.

Ш.

III.

III.

III.

III.

 $\{IIb.\}$

IIb.

IIb.

Πa.

Hb.

IIb.

"fort of Sâlivâhana," but beyond a mound and a few scattered pieces of masonry no remains of this fort now exist, which, however, appears to be of the Musalmân period.

- 6. Sahaswân, tahsîl, 24 miles west from Badâon, is said to be the ancient Sahasrabâhu's fara. A mound near the Qâzî mahallâ is pointed out as the remains of Sahasrabâhu's fort. There are three masjids of some antiquity and several Hindû temples of various ages scattered over the town; but the most important temple is that which stands on the shore of the Dhandjhîl. The antiquity of this temple is undoubted, and it is held in great veneration by the Hindûs. Attached to it is a large tank on whose banks several satî pillars are erected. Besides these there is the ancient tomb of Miyân Sâhib and an old sepulchre called Rauza-î-Pirânpîr, or "mausoleum of the saint of saints."
- 7. Salimpür, small village in tahsil Dâtâganj, 19 miles E. from Badâon, possesses an old mud fort.
- 8. Shaikûpûr, two miles S.-W. from Badâon, is said to have been founded in the reign of Jahângîr by Shaikh Farîd, whose tomb still exists. Probably a settlement of some sort already existed on or beside the modern site, where the ruins of an older village called Phuliyâ Kherâ are still shown.
- 9. UJHANI, in tahsil Badâon, eight miles west from head-quarters, possesses an unfinished tomb of Nawâb Abdullâ Khân, who died here rather more than a century ago. There is also an old cemetery called Qadam-i-Rasûl, or "foot of the apostle," a mas jid built by Abdullâ Khân and an îmâmbâra of uncertain date, but certain antiquity. The Hindû temples are few, and of no interest.

II.—BARELÎ DISTRICT.1

III. 1. Âonlà, tahsil, 17 miles S.-W. from Bareli, possesses a small castle in which the Rohilla chieftains held their court, consisting of two yards, entered from the street by a plain and unimposing gateway. Along the inner walls of the yards are ranged various brick buildings whose dilapidation is more conspicuous than their size. In the outer court, against the wall which divides it from the inner, stands the dîvân-khâna, or "hall of audience," an open pillared structure which may once have had some claim to beauty.

Almost opposite the gateway stands the masjid of Sardar Khan, who died in 1772. The lofty three-domed masjid, known as the Begam's, preserving the remains of some chieftain's wife, is a very conspicuous sepulchre. The graceful proportions of the Baraburji, or twelve-domed masjid of Fath Khan, are insufficient to atone for its shabbiness and want of size.

The mausoleum of Alî Muhammad, who wrested Rohilkhand from the dominions of the Dehlî Emperors, is raised on a high plinth, ascended by a flight of about a dozen steps. The tomb itself is a large square building surmounted in the centre by a dome and at the corners by octagonal cupolas. On each wall between the cupolas rise two square-shaped minarets. The interior consists of the square dark chamber beneath the dome and its surrounding cloister. On the walls of the former, which contains the grave of the chief, are inscribed several hardly appropriate texts from the

¹ North-Western Provinces Gazetteer, Vol. V, pages 695-847, passim.

III. \ Qurân. On the same plinth as, and on either side of, the greater mausoleum are placed two other tombs. Over one of them is built a neat little masjid; the other, that of Alî Muhammad's son, Sâdullâh, is enclosed only by a light masonry screen with domed alcoves at the corners. The surrounding enclosure contains many other tombs. But the richest collection of such monuments is grouped around a magnificent stair-sided tank which faces the southern gate.

III.

Hb.

Hb.

 Πb .

III.

IIb.

2. ATTARCHENDÎ, in tahsîl Âonlâ, 10½ miles S.-W. from Barelî, was in the fourteenth century chosen as the site of a Katehrîyâ stronghold. The spot once occupied by the old Thâkurgarh or Râjpût's fort is still shown. The fort itself must have fallen to ruin before the time of the Rohillas, for Sâdullâh Khân, the son of Alî Muhammad, founded here a second castle. The remains of this brick-built fortress cover 13½ acres, its foundations and the towers on its river face being still distinctly traceable.

3. Bareli, lat. 28°-22'-9" N., long. 79°-26'-38" E., of comparatively modern origin, possesses very few buildings of any real mark, and these are a little more than a century old. The tomb of Hâfiz-al-Mulk Rahmat Khân, a short distance south-west Ib. of the city, is the oldest monument. Its precincts are entered by a rather handsome gateway, adorned with stencilled patterns whose colouring is somewhat faded. The shrine itself is a shabby domed building of plastered brick with gilted finials. Over the door is a Persian inscription recording its foundation by Rahmat's daughter in A.H. 1256, or A.D. 1839. This inscription is, however, altogether misleading. Rahmat was buried here by his prime minister, Pahâr Singh, in 1774. His son, Zulfikâr, placed the canopy and inscriptions over his tomb in the following year. It was reserved for Rahmat's daughter in her old age to repair the building and take the credit of the whole to herself. Within, in the dark space beneath the dome, lies the tomb of the great regent; that tomb is covered by an ornamental canopy of plaster on an iron frame. Above the arches of the canopy are several Arabic and Persian legends, including one yielding the date A.H. 1188, or A.D. 1775, and that other which Sâdi tells us was inscribed over the arched entrance of the palace of Farîdûn (Gulistân, chapter I). Close to Rahmat's tomb is that of Muhammad Yar, son of Ali Muhammad, built during the lifetime of the person interred therein. Ш.

The Jâmi Masjid of the Shiâs was built by Mîrzâ Hasan Razâ Khân in A.H. 1164 under orders of Asaf-ad-daula, Nawâb of Oudh (1774—1797). The masjid of the Sunnis was built by Makrand Râî about A.D. 1667, but is a less conspicuous building; attached is an orchestral gateway (naubat-khâna) about 50 years old. The masjid of Chând Khân was built A.H. 1149 and the masjid of Jahân Khân in A.H. 1168.

Partial traces of the first earthen fort built in the sixteenth century by Bâsdêo, the somewhat mythical founder of Bareli, are still to be discovered in the Kôţ mahallâ of the old city. The castle itself was destroyed in Akbar's time, and the later fort built in the new city by Makrand Râi has left no trace behind, but the high bank of the Dêoraniyâ, now occupied by the Qila police-station, perhaps marks its site. The Mîrzâi masjid and the tomb of Shâhdâna are the only remarkable buildings of the old city. The former was built by Mîrzâ Aîn-al-mulk by the order of Akbar; a chronogram of Fâizi, engraved on the masjid, remarks in Arabic that "praise is due

IIa.

III.

Ia.

Ib.

II.

III.

III.

III.

III.

IIb.

III.

to God alone," and thereby gives the date of construction as A.H. 987, or A.D. 1579. The tomb of the Muslim hermit, Shâhdâna, was built by Makrand Râi in the reign of Aurangzib. Among minor Muslim shrines may be mentioned the tombs of Badr-al-Islâm Khân and Bîbîjî.

4. Fatehganj West, or Bhitaura, village in tahsîl Barelî, 12 miles northwest from head-quarters, possesses a large obelisk of red sandstone slabs, a memorial to the British troops who fell here on the 24th October, 1794. West of it on the same hillock, which is perhaps the kherâ or mound of some forgotten village, rises the sepulchre of Najib and Baland Khân, Rohilla chieftains, who fell fighting against

the English on the same day.

5. GWÂLA PRASIDDH is the name given to the remains of an ancient city extending for about seven miles along the left bank of the Nakatiâ, from Simrâ Râmpura in tahsîl Barelî to the mouth of that river at Khâlpûr, in tahsîl Farîdpûr. These remains consist in an almost unbroken line of *kherâs* or mounds once occupied by brick temples and other edifices. The ancient coins found occasionally in these vast ruins belong mostly to the Indo-Scythian period.

6. Kabar or Shergarh, in tahsil Baheri, 21 miles N.-W. from Bareli.

Accurately, Kâbar is the ancient name of the original city, and Shêrgarh of a sixteenth century addition on its east; but the former title is applied to the whole by Hindûs and the latter by Musalmâns. Two other villages besides Kâbar and Shêrgarh, the western Dûngarpûr and Islâmpûr, are included in the limits of the town; the four formed of old one continuous city, but are now separate villages, standing each on its ancient mound. Slightly the loftiest of such mounds is that once occupied by the old Hindû citadel of Kâbar, a circular elevation about 25 feet in height and 900 feet in diameter. This is still surrounded by a deep ditch from 50 to 100 feet in width. Some remains of a large oblong building, said to have been a temple, still exist on its summit. The remnants of the second, or Musalman fort, Shêrgarh or 'Shêr Khân's castle,' are undistinguishable from the general mass of ruins. The extreme length of that mass from east to west is 3,500 feet and the breadth 2,500 feet, the complete circuit being 9,800 feet, or nearly two miles. But amidst these widely-strewn relics of the past the antiquarian may hunt almost in vain; the long-continued Musalman occupation of Kabar has swept away nearly every trace of Hindûism. Old coins are occasionally found; but the only antiquities discovered by General Cunningham were two small stone figures, one too much broken to be recognized, the other a representation of Durga slaying the buffalo demon (Mahésasura). The old Hindû city of Kâbar is said to have been founded by Râjâ Vêna; to his wife Kêţakî or Sundarî is attributed the Râņî Tâl or 'Queen's tank.'

7. Pachômî, or Wâhidpûr Pachaumî (the ancient Pañchbhûmi), in tahsîl Farîdpûr, 16 miles S.-E. from Barelî, is remarkable as containing several ancient ruined mounds which may repay exploration; for from the highest mound, heavy rains wash down numerous copper coins of the Indo-Scythian period.

8. Râmnagar, or Ahichhattra, once the capital of a mighty kingdom, the northern Pañchâla, is now but a large village in the Âonlâ tahsîl, 20 miles W.

¹ Cunningham, Archaelogical Reports, Vol. I. page 358.

^{*}Cunningham, Archeological Reports, Vol. I, pages 255—265. Beal, Buddhist Records of the Western World, Vol. I, pages 200 and 201.

of Bareli. The name of Ahichhattra is at present confined to the great fortress III. rising just outside the walls of the village, but now included in the lands of Alampûr Kôt and Nasratganj which adjoin Râmnagar on the north. This stronghold is by far the chief object of interest at or near Ramnagar, but in its ancient Buddhist stupas and modern Jain temples the village has other claims to attention. The fort should rather be called the ruins of a walled city, as its circumference is over 31 miles and its interior crowned with the foundations of old brick buildings. Its curtains and bastions are mere crumbling banks of brick, and the few scraps of standing wall seldom rise more than 3 or 4 feet from the summit of those banks. The heaps of bricks which once joined the walls are nevertheless of considerable height; they attain a general altitude of from 28 to 30 feet, rising on the west side to 35 feet, while a single tower near the south-west corner, the Sâhib Bûrj, is 47 feet raised above the road outside. Ascending these walls we find ourselves on an elevated space averaging some 15 to 20 feet above the surface of the surrounding country. interior of the fort is occupied by a mixture of brambly scrub and ploughed land. Ancient copper coins of the Mitra dynasty are frequently exhumed by the ploughman, and may be obtained in some quantity from the people of the neighbourhood. Of several mounds within the fortress the highest is that occupied by the remains of a Lingam temple near the middle of the north wall. The mound itself is III. a conical heap of bricks towering some 68 feet above the level of the plain without, and General Cunningham calculates that the temple which crowned it must have risen yet 100 feet higher. Of the latter nothing remains except the foundations and the gigantic stone lingam, once 8 feet high, and still 31 feet in diameter, III. from which the mound derives its name of Bhîm-kâ-gaja (gada), or 'Bhîma's mace.' Near it, on the summit of the mound, figures of Buddha, rifled from one of the Ib. neighbouring stupas, are worshipped by Hindus. Similar instances of mistaken worship may be noticed in Rämnagar itself, where two Buddhist statues have been installed under Hb. trees as tutelary deities (kherapati) of the village. The gods of Nasratganj are confessedly borrowed from a similar source, although not so clearly of Buddhist origin. From this mound the fort is seen to resemble an irregular right-angled triangle, with the right angle towards the north-west; and the angles of the fortification, especially on the northern side, stand out with exceeding clearness. An arched gateway, built on the south-eastern walls by the Rohillas, which was standing at the time of General Cunningham's visit, in 1863, has now disappeared. Two other mounds are seen within the fort, and a number of all sizes, from 20 to 1,000 feet diameter, without, on the north, west, and south. Of those inside the fort there is little to be said; both show traces of buildings which Cunningham considers to have been large III. Brâhmanical temples. That which stands due west of the Bhîm-kâ-gaja possesses a IIb. small dargah and a modern Hindû hermitage. On a third mound just outside the

small dargâh and a modern Hindû hermitage. On a third mound just outside the western gate are planted the foundations of a small temple; here was discovered a terra-cotta figure of Siva. Four hundred feet south of the great bastion is another extensive mound which from its ruins Cunningham believes to have been a Buddhist monastery enclosing a temple not less than 80 feet high. This supposition has been confirmed by excavations made into this mound, three years ago, by Sadr-ad-din Khân of Râmpûr, zamîndâr of Râmnagar, who found several large wrought slabs of

red sandstone, Buddhist railings, an elaborately carved ceiling stone with a dedicatory inscription of the Indo-Scythian period, and large quantities of moulded bricks, which relics are now in the Lucknow Museum. In and about the fortress General Cunningham discovered not less than 20 temples of various sizes; but except that besides the western gate and Bhîm-kâ-gaja, none yielded sculptures by which their original dedication could be absolutely identified.

The most numerous and ancient remains at Ahichhattra are, however, those of Buddhist origin. The chief stupa is that which stands on a great irregular mound nearly a mile due west of the north-west corner of the fortress, and about the same distance north-north-east from Ramnagar. The round shield-like roof of the stupa, just appearing above the heap of earth and débris that surrounds it, has given the mound the name of Chhattra (umbrella) or Pisanhari-ka-chhattar (the mill-grinder's chhattar). The portion of the ruin still left exposed is 30 feet in diameter, and attains a height of 40 feet above the neighbouring fields. Its original dimensions, 50 feet of diameter and 57 feet of height, were increased by additions to 75 feet and 77 feet respectively. General Cunningham identifies this stûpa with one which Hiuen Tsiang1 mentions as built by A soka about 250 B.C., and it certainly resembles in form the Bhilsa topes of that age. The conclusion that is was enlarged not earlier than from 400-500 A.D., is a matter of much less certainty.

To the north-west of this stûpa, distant half a mile, there is a large tank called the Gandhan Sagar, which has an area of 125 bigas, and about one quarter of a mile beyond it there is another tank called Adi Sagar, which has an area of 150 bîgas. The latter is said to have been made by Adiraja, an Ahîr, whose elevation to sovereignty was foretold by Drôna when he found him sleeping under the guardianship of a Naga with expanded hood. The waters of these tanks are collected by an earthen embankment fixed on both sides with brick of large size. The mounds to the south of the tanks are covered with large bricks, both plain and moulded; but judging from their shapes, they must all have belonged to temples. and not to stupas. There is nothing to show whether these are the remains of Buddhist or of Brahmanical temples, but from their extent it is probable that they were the former.

A few hundred yards north of the old fort and east of Nasratganj stands a far smaller hillock called Katari Khera, which is perhaps a corruption of Kottari III. Khera, or 'temple mound.' Here General Cunningham unearthed the limestone plinth and almost vanished walls of a small temple, which he at first imagined to be a Buddhist monument. But except a broken statue, which probably represents Buddha, there was nothing distinctively Buddhist about the temple. There were, however, several nude figures which the General afterwards assigned to Jain artists of the Digambara sect. On a stone railing pillar which contained six rows of such Ia. figures appeared the following dedicatory inscription :-

Mahâchârya Indranandišishya Mahâdari Pâršvapatisya Kottari.

"Mahâdari, disciple of Indranandi, to the temple of Pârsvapati." Pârs vapati is of course equivalent to Pârsvanâtha, the great Tîrthamkara, whom some suppose to share with Mahavira the honor of founding the Jaina faith. Another image apparently

Ia.

III.

III. III.

¹ Beal, Buddhist Records of the Western World, Vol. I, page 200.

naked, a small stone bearing the word navagraha, or "nine planets," and the fragment of a large pillar bearing on each of its four faces lions, the symbols of Mahâvira, completed the General's discoveries. From the character of these inscriptions he infers that the temple was erected before the fall of the Gupta dynasty. With the Jains Ahichhattra is still a place of much sanctity. A short distance north of the village, on a great mound once perhaps crested with some more ancient pile, stands the modern temple of Parsvanatha; this is a large brick building entered by a wide

colonnaded courtyard. Hb.

A short distance to the south-west of the Kottari Kherâ, there is another large mound called Chikattia Khera, which was apparently the site of a Buddhist Ш. Vihara, as numerous railing pillars, and rail-bars, some of which were inscribed, have been found, three years ago, during an excavation made by Haqim Warras Ali of . Âonlâ, zamîndâr of Nazratganj. These relics were carried off by the excavator to Aonla, but cannot be traced there.

Two other Buddhist mounds on the north-west corner of the great bastion, close III. to the Kôn wâr u Tâl, were excavated by the Survey Party of these Provinces, in February, 1888, and yielded a beautifully-carved pilaster, whose four faces are divided into different panels decorated with elaborate sculptures of Buddha's life, and numerous coins of the Mitra and Gupta dynasties with well-preserved legends. These objects have been deposited in the Lucknow Museum.

Connected with Ahichhattra is an inscription of the Gupta period at Dil-Ib. wâri, 41 miles south of the fort, but it has been damaged by constant use as a whetstone.

At Gulariya, 21 miles north, is another gigantic lingam, and the name of IIb. Bhîmlaur, one mile to the east, shows that a similar monument of Saiva worship must have existed there also.

The wealth of Brahmanical remains at Ahichhattra shows that as Buddhism declined the number of Hindû temples increased. A well-executed bas-relief of two lions, found some years ago, has an inscription showing the date of this sculpture to have been Samvat 1060, or A.D. 1004.

- 9. SARAULÎ, in tahsîl Âonlâ, 28 miles N.-W. of Barelî. The neighbouring village of Shâhpûr is a memorial of the Musalman mendicant Nirgan Shâh, whose tomb confers on Sarauli no little local celebrity. The masonry walls around the sepulchre have fallen into ruin and abound with scorpions about two inches long, who do not use their sting owing to the all-pervading sanctity of the faqîr who is buried there (!)
- 10. SENTHÂL, in tahsîl Nawâbganj, 16 miles N.-E. of Barelî, possesses the tomb of the religious mendicant Chiragh Ali Shah, where a fair is held yearly on IIb. the 1st of Kartik, lasting for a week.

11. Shâhî, in tahsîl Mîrganj, 17 miles N.-W. of Barelî, possesses a fair-sized

Hindû temple. IIb.

Ib.

IIb.

12. Shîshgarh, chief town of pargana Sirsâwan in tahsîl Bahêrî, 31 miles III. N.-W. of Bareli, possesses a ruinous fort on the summit of a hillock of trifling elevation which is, however, conspicuous in this level country.

13. Shiûpurî, in tahsîl Âonlâ, 28 miles N.-W. of Barelî. A little more than a mile south of Shiûpurî stands the ancient village of Gurgâon, said to have been founded by Drona, the guru (tutor) of the Pândavas.

III,-Bîjnôr District.1

- Afzalgarh, in tahsîl Nagîna, 34 miles E. of Bijnôr, possesses the ruins of a brick fort, built by Nawâb Afzal Khân, a Pathân, during the brief domination of his tribe (1748—1774).
- 2. Barhapura, in tahsîl Nagîna, 27 miles N.-E. from Bijnôr. In the forest, three miles east of the town, at Pârasnâth, is a most important group of extensive ruins of bricks, extending for a distance of six miles, and yielding in many places remains of sculpture and masonry, attesting the former existence of a large town, probably the capital of some principality. The ruins of a fort are still visible.
- IIb. 3. Bijnôr, lat. 29°-22′-36″ N., long. 78°-10′-32″ E., possesses a few masjids and Hindû temples of no great archæological or architectural merit. Its foundation is ascribed to the somewhat mythical Râjâ Vêṇa; he is held the pattern of kings, for in his days there was no taxation, and the money required for State purposes was derived from the sale of hand-fans made apparently by the monarch himself. Ever on the search for a ridiculous derivation, the local Varro finds in these hand-fans (bijna) the origin of the name Bijnôr. The etymology Vijayanagara is more probable, though it bears a slighter superficial resemblance to the modern word.

Two miles west of Bijnôr and nearer the Ganges are the foundations of an old town still visible. As his share encounters old bricks and other signs of a lost city, the ploughman still calls that place the castle mound (kherû) of the good king Vêna.

Five and a half miles to the north of Bijnôr, on the road to Najîbâbâd, in the village of Ṭuṇḍapura, there is a large bâolî with a Persian *inscription*, dated A.H. 1167.

- 4. Chandî, small village in tahsîl Najîbâbâd, 46 miles N. of Bijnôr. In the III. ravines of the Chandî hills, east of Hardwâr, are numerous ruins worthy of a careful exploration.
- IIa. 5. Chândrür, tahsîl, lat. 29°-8′ N., long. 78°-20′ E., 21 miles S.-E. of Bijnôr, IIb. possesses a fort-like tahsîlî, five masjids, six Hindû temples, a dargâh, called Talab III. Siyâo, built in A.H. 968, as stated in a Persian inscription, and an old well in mahallâ Sahwân with a dedicatory Sanskrit inscription.
- 6. Jahanabad, in pargana Daranagar of tahsil Bijnor, 12 miles S. of head-IIb. quarters, is remarkable for the tomb of Nawab Said Muhammad Shujaat Khan, built A.H. 1057, A.D. 1647. The shrine is surrounded by a quadrangular wall of block kankar, enclosing an area of about ten acres. The gateway by which this enclosure is entered is enfaced on the inner side with grey sandstones, and on the outer was once adorned with encaustic tiles. The tomb stands on a raised masonry basement about 10 feet high, which is ascended by stone steps. This basement is

¹ North-Western Provinces Gazetteer, Vol. V, pages 371-498, passim.

enfaced not only with the same grey stone as on the gate, but also with red sandstone of Agra. The sarcophagus is of white marble, the tomb is nailed in with a light lattice-work of red stone, and is covered by a cupola of grey sandstone supported by high pillars of the same material. On the lower part of the cupola are engraved texts from the Quran.

- 7. Kîratpûr, in tahsîl Najîbâbâd, 10 miles N.-E. of Bîjnôr, has two mahallâs Kîratpûr and Bâsî; the former is the oldest and is said to have been founded in the reign of Bahlol Lodi in the middle of the fifteenth century. The latter was peopled by Pathans in the middle of the last century, when Najib Khan, one of Ali Muhammad's officers, built the castle in Kîratpûr mahallâ, whose remains still exist. Walls of great strength are still standing on either side of the main gateway, while within there is a handsome and well-preserved masjid. Of the principal quarters inside the fort ruins only remain, and within the ramparts is one of those magnificent masonry wells so often found in the interior of Indian fortresses. Adjoining the fort, on the outside, is a large masonry tank constructed by the same chief.
- 8. Lâldhâng, small village in tabsîl Najîbâbâd, 38 miles N.-E. of Bîjnôr. In the Panduwala Sot, west of Laldhang and in the ravines of the Rawasan are numerous ruins likely to yield results worthy of the attention of the survey.
- III. 9. Mandawar, in tahsîl Bijnôr, eight miles N. of head-quarters, has been identified by St. Martin and General Cunningham with Matipura, mentioned by Hiuen Tsiang.2 The more ancient part of the site is a mound about half a mile square. III. raised some 10 feet above the rest of the town which flanks it on its western and northern sides. This mound is covered with modern buildings, but abounds in large bricks, a sure sign of antiquity. In its midst is a ruined fort 300 feet square with a height of six or seven feet above the rest of the mound; and on its south-eastern corner stands the Jami Masjid said to have been built on the site and with the IIb. materials of an older Hindû temple. As many of the squared blocks of grey sandstone which compose this building bear cramp holes on their outer face, there can be no doubt that they must have belonged to an older structure.

To the north-east of the town, about one mile from the fort, stands another large mound, crested by the village of Madiya or Mandiya, and between the two lies a large tank called K û n d a T â l, surrounded by numerous smaller mounds which are said to be the remains of buildings. General Cunningham believes that these two places once formed a single town about 11 mile long and half a mile broad. or 31 miles in circuit.

To the south-east of the town lies the Pirwali Tal, a deep, irregularlyshaped sheet of water nearly half a mile in length.

The Buddhists of the eighth century asserted it to have been produced some 600 years previous by an earthquake which accompanied the death of their renowned Saint Vimalamitra. The stupa erected over the remains of Vimalamitra stood probably near a mango grove on the western side of the Pirwali Tal. The neighbourhood of the town was at that time enriched with memorials of other "lesser vehicle" doctors (Sarvastivadas), and the sites of such buildings have been identified by General Cunningham. Thus the village of L al p ar, perched on a mound about three-quarters

III.

IIb.

III.

III.

III.

III.

Cunningham, Archaelogical Reports, Vol. I, pages 248—251,
 Beal, Le., Vol. I, pages 190—198.

of a mile to the south-east of the Jami Masjid, and built partly of ancient bricks, represents the small monastery of Guṇaprabha. North of Lâlpûr and just half IIb. a mile from the masjid, is the dargâh of Hidâyat Shâh, also constructed from the materials of more aged remains. This is believed to occupy the site of Sañighabhadra's great monastery, and another small Muslim shrine (takià), 200 yards north-west of Hidâyat's, marks the former position of Sañighabhadra's stûpa. At the time of Hiuen Tsiang's visit there were 20 Buddhist monasteries and about 50 Brâhmanical temples at Matipura, of which only heaps of ruins are left.

10. Môrdhaj, also called Munawar Jûr, in tahsîl Najibâbâd, 27 miles N.-E. of Bijnor, is a small ruined fort. Its ramparts, which have still a height of about 15 feet above the surrounding country, enclose an oblong space of 800 by 625 feet. The entrance is on the eastern side, and is still covered by the remains of an outwork. The ditch, 60 feet broad by 3 feet in length, is surrounded at a distance of about 120 feet from the main rampart by a faussebraie, or outer rampart. Portions of the brick walls were still to be traced when General Cunningham visited the place in 1863, but all these remains are fast disappearing. The bricks are of large size, being $13\frac{1}{3}" \times 8\frac{1}{3}" \times 2\frac{1}{3}"$. Near the middle of the east side there is a lofty mound called Shigri, a name which is said to be a contraction of Shergarhi, "tiger's house," or Srî Garhî; but this etymology is apparently of later date. The Shigri mound has a height of 35 feet above the interior level, and of 43 feet above the plain, and a circumference of 308 feet. A close examination shows that the outer portion of the mound is composed of brick rubbish, the remains of some large superstructure. The size and importance of this building, originally no doubt a large Buddhist chaitya, with the usual series of umbrella-like discs composing its lofty spire, and in later days probably a Brahmanical temple, may be guessed at from the fact that the entire surface of the mound to a depth of from three to eight feet and many square yards of plain surface around its base to a similar depth are covered with broken brick débris. The people state that within the memory of living men there were still portions of the superstructure standing on the mound, but that the materials were utilized in the construction or repair of bridges on the Najibabad and Kôtdwara road, which skirts the base of the old fort at a distance of about 400 yards.

From the solid appearance of the mound General Cunningham considered it to be the ruin of an old Buddhist stupa, which supposition has been confirmed through the exploration of the mound, in February, 1887, by Mr. Markham, Collector of Bijnor. Two large circular terra-cotta medals, and about two dozen smaller clay seals impressed with a figure of Buddha seated within a handsome chaitya and below the Buddhist creed formula in characters of the eighth century, and at least one thousand small Buddhist votive tablets of baked clay stamped with the figure of Buddha, the Ascetic, were excavated from the relic chamber, and presented to the Lucknow Museum. During the excavation of the mound, Mr. Markham succeeded in disclosing the usual procession path surrounding the stupa; there was, however, no trace of any railing, nor were any pieces of rails found. From the débris of an old well close to the mound, several terra-cotta figures, fragments of stone statues, and a portion of a door-lintel were brought to light.

Ha.

III.

¹ Cunningham, Archwological Reports, Vol. II, pages 237-238.

According to the people, Môrdhaj formerly abounded in stones of all kinds and sizes, wrought and unwrought, but the whole have been carried away to Patthargarh. The stone figures of gods and goddesses are said to have supplied all the temples at Najibâbâd. The name of the fort Môrdhaj is derived from Mayûradhvaja, or the "peacock standard," which was apparently the title of its founder, who is according to tradition a contemporary of the Pâṇḍavas. But a genealogy is also given which makes him the Jain antagonist of Said Salār-i-Masaūd Ghāzi, and if this be accepted, the date of Mayūradhvaja's fort cannot be fixed earlier than the beginning of the tenth century.

The whole country round the fort, for several square miles, is covered with almost uninterrupted traces of ancient ruins, chiefly composed of fragments of large bricks. The place must have been the site of a large and wealthy city. It may have been one of those many in this neighbourhood which perished in the irruption of the ruthless Taimûr Shâh at the close of the fourteenth century.

11. Nagînâ, tahsîl, lat. 29°-27′-5″ N., long. 78°-28′-50″ E., 19 miles N.-E. of Bijnôr, possesses several small, though elegant and well-kept masjids, the new Jâmi Masjid, a larger building of the same nature, a rather celebrated Hindû temple near the middle of the bâzâr, and the old Pathân fort now converted into a tahsîlî.

IIb.

 Πa .

Ш.

Ш.

III.

III.

 $\Pi b.$

III.

 $\Pi b.$

Ш.

Ш.

12. Najîbâbâd, tahsîl, lat. 29°-36′-50″ N., long. 78°-23′-10″ E., 21 miles N.-E. of Bijnôr, founded by Najîb-ad-daula in the middle of last century, still retains many a memorial of Paṭhân magnificence. To the south of the town is the tomb of the founder constructed about A.H. 1180, to its north that of his brother Jahângîr Khân constructed about A.H. 1173.

About a mile east of the town stands the dismantled castle of Patthargarh or Najafgarh built by the same chief in 1775. All the stone that could be robbed from the neighbouring and more ancient castle of Môrdhaj is said to have been used in building Patthargarh. It is a square and embattled wall, high and massive, enclosing a space of from 35 to 40 acres. At each of the four angles, and elsewhere on the intervening curtains, are bastions. There is more than one gateway, but the principal opens towards the town. The old palace of the Najîbâbâd Nawâb's stands in Nawâbganj, but the grand carved entrance gateway and a little of the frontage are all that remains; opposite the gateway in the midst of the square, are the remains of the Nawâb's orchestra (naubatkhâna).

13. Nihtaur, in tahsil Dhâmpûr, 16 miles E. of Bijnôr, possesses a handsome old masjid, to which three modern fluted domes have been added.

14. Sabalgarh, a ruined castle in the forests of tahsil Najibabad, 32 miles N. of Bijnor, is the largest of the fortified remains in the district. It is at present simply a great quadrangular wall with bastions at the four corners and other points of intervening curtains. The enclosed area amounts to about 114 acres, but no trace of the interior buildings exists. The castle is now included in the nominal village of Asafgarh which was the name of the flood-destroyed fort on the opposite bank of the Kotâwâlî. Sabalgarh is said to have been built in the reign of Shâh Jahân (A.D. 1628—1658), by Nawâb Sabal Khân.

Two miles to the north-east of Sabalgarh, to the west of the Najibabad and Hardwar road, near the villages of Sa'id Bhura and Zahir Diwan, are very extensive ruins which may repay exploration.

Opposite to Said Bhûra, to the east of the above road, near the village of Dhar-III. magarhî, are several mounds of brick ruins.

- 15. Sâhanpûr, village in tahsîl Najîbâbâd, 23 miles N. of Bîjnôr. On the outskirts IIb. of the village are several handsome satî monuments, including two of Aurangzîb's reign (1688—1707). The most important is that of Râņî Lakshmî, the wife of Râî Râjârâm, built in A.H. 1116. In the garden adjoining the Râņî Satî, north of the road to Hardwâr, there is a large bàolî built in A.H. 1126, during the reign of Muhammad Shâh of Dehlî. To the north of Râņî Satî, on the road to Nagal, there is another bâolî, built in A.H. 1109 during the reign of Aurangzîb.
- 16. Sahaspûr, in tahsîl Dhâmpûr, 41 miles S.-E. of Bijnôr, possesses several IIb. small masjids of no architectural pretensions.
- 17. Tîp, small village in pargaṇa Mandâwar of tahsîl Bîjnôr, on the left bank of the Ganges khâdir, 15 miles N.N.-E. of headquarters, possesses a kherâ of evidently great age. This mound was excavated by Mr. Markham, Collector of Bîjnôr, in January 1886; but no relic chamber or relics of any kind were found. The foundations of a square structure were, however, disclosed during the course of the excavation. Five gold coins of the Indo-Scythian king V as u dêv a and one gold coin of Bhri Shaka were found by him near but outside the base of this mound. These coins are now in the Lucknow Museum coin cabinet.

IV.—Murādābād District.1

- IIb. 1. Амкона, tahsil, lat. 28°-54′-15″ N., long. 78°-30′-30″ E., 19 miles N.-W. of Muradabad, possesses no fewer than 109 masjids, 2 karbalas, 7 sivalas, about 40 other Hindu temples and dharmsalas, 9 dargahs of special sanctity, and a great number of minor importance.
- Ha. Relics of greater antiquity than any of the other existing buildings are a bâolî, called Bâh-kâ-kûân, or "Bâwan well" and a large tank called Bânsdêo, about one mile and a half to the west of Amrohâ. The well is one of the most curious remains in the district; with the exception of the arches and vaults, which are of brick, the structure is of block kankar. To the north a flight of steps leads down to a reservoir, flanked on each side with corridors and with an apse on its other end. The corridors open into chambers, from which flights of steps lead down to similar chambers in the storey below. All these chambers also open on the well proper, which has a diameter of 15 feet. The arches are false and the cupolas built with circles of bricks that narrow in.
- Of the more modern objects of interest the first in point of importance is the IIb. dargâh of the famous Sharf-ad-dîn Shâh Wilâyat, built in A.H. 783, III. A.D. 1381; close by is the tomb of his daughter, Masammât Bakhûi. The tombs of Shâh Nasîr-ad-dîn, Abd-al-Azîz, Abd-al-Wajîd, Shâh Ghâzî, Shâh Ibû, Shâh Abûl Hadîs, Mullâ Allâh Dâd, and Miân Pîr Baksh deserve only a passing notice.
- IIIb. The Jâmi or Saddo Masjid, i.e., masjid of Sadr-ad-din, is one of the oldest existing buildings. It was originally a Hindû temple, as is evidenced by its shape and the old chain still dangling from the roof. It was converted into a masjid in the

¹ North-Western Provinces Gazetteer, Vol. IX, Part H, pages 168-221, passim.

reign of Kaiqubâd, in A.H. 686, and originally had five arches, of which the two outer ones have disappeared. It bears four inscriptions: the first of Kaiqubâd on the northern side dated A.H. 686, A.D. 1287; the second of Qanâq Khân on the inside of the northern gateway, giving the date A.H. 965, A.D. 1558; the third of Saîd Muhammad Mîr Âdil, dated A.H. 981, A.D. 1573; and the fourth is undated, but mentions that repairs were made by one Âdil Khân, who is said to have lived during the Rohilla occupation. The tomb of Shaikh Saddo or Sadr-ad-dîn, a former crier (mu'azzin) of the masjid, is pointed out under the central arch, that of his mother Ghâzia, also called Åse, under the northern, and that of a demon Zên Khân under the southern arch.

Ш

Ш.

Hb.

IIb.

Hb.

III.

III. The Masjid-î-Chilla was built during the reign of Jahângîr, în A.H. 1029, and in mahallâ Bâdshâhî Chabûtrâ is a masjid known as Mâlik Sulaimân's, which appears from inscriptions, dated A.H. 1066 and 1067, to have been built in the reign of Shâh Jahân by Shaikh Mansûr; the Chabûtrâ Shâhî, close to this masjid, was built în A.H. 1061. To the same period are attributed the two gates which are the only portions now of the fort in mahallâ Bara Darbâr. One of these is known as the Chhanga darwāza; it îs smaller than the second, known as the Murâdâbâd gate, built by Saîd Abdûl Majîd, alias Dîwân, A.H. 1051, A.D. 1641. The last building of importance is the Îdgâh, an imposing structure to the west of the town built by Shaîkh Ghulâm Ahmad some 130 years ago.

There can be no doubt that Amrohâ was formerly a large Hindû city, the ancient name of which is said to have been Ambikânagara, as the Bâh-kâ-kûân and the Bânsdêo Talâo testify its great extension. Several Hindû columns of an early date are still lying in the courtyard of Hazrat Mâlik Sulaimân's masjid.

In mauza Bhera Bharatpûr is a large khera, the site of an ancient temple, as life-size statues and dressed stones have been discovered in the mound.

BACHHRÂON, in tahsîl Hâsanpûr, lat. 28°-55′-25″ N., long. 78°-16′-35″ Е., 41 miles N.-W. of Murâdâbâd, possesses 12 masjids and one Hindû temple.

3. Bhôjpûr, in tahsîl Murâdâbâd, lat. 28°-56′-45″ N., long. 78°-52′ E., 10 miles north of head-quarters, possesses 11 masjids and a dargâh of Muhammad Hâjî.

 BILÂRÎ, tahsîl, long. 28°-37'-15" N., long. 78°-50'-30" E., 15 miles S. of Murâdâbâd, has six Hindû temples, five masjids, and one Îdgâh.

In this pargana there is considerable opportunity for antiquarian researches, as nearly every second village has an old mound, or dih, to the west of it. On the way between Bilârî and Sêondarâ stands the most pronounced of these mounds within the village lands of Karâwar, occupying 17 bigas 11 biswas of land. Diggings on the surface of it have disclosed the foundations of walls of solid hard-burnt bricks, measuring $16"\times10"\times2"$, and bearing the common devices of three parallel lines or of three concentric ovals along the top. At two different spots octagonal wells have been brought to view, built of beautifully-finished brickwork and surrounded by a masonry platform. No coins are said to have been found. Local tradition ascribes the place to have been a fort of Râjâ Karņa, mentioned in the Mahâbhârata.

² Proceedings, Asiatic Society of Bengul, for 1873, page 102.

¹ Proceedings, Asiatic Society of Bengal, for 1873, page 101, where the date is wrongly given as A.H. 980.

III.

III.

III.

Hb.

III.

III.

III.

III.

III. Another important mound is Sarthâl Kherâ, six miles south-west of Bilârî, measuring 1,200 feet in length from north-east to south-west by 1,000 feet in breadth. It is called after a mythical king Sarat, the son of Râjâ Satyavâṇa of the lunar race, and the kherâ is said to be the ruins of his palace. Close to the south-west of III. it there is another large dîh, with a village on it, called Kherâ Khâs, Râjâ Satôn-kâ-kherâ, or Satôngarh. The kherâ is said to be the ruins of the palace of Râjâ Sarat's daughter. Between the two places, there are also many other smaller mounds. The two large mounds of Sarthâl and Kherâ Khâs together evidently once formed one large city.

About two miles to the south-east of Sarthâl Kherâ lies Gumthâl Kherâ, an ancient mound, which measures 1,600 feet in length from east to west by about 1,000 feet in breadth from north to south.

Two miles to the north-east of Sarthâl is mauzâ Jargâon, standing on an ancient kherâ, said to be the ruins of the palace of Râjâ Jarasimha. Bricks similar to those of Karâwar Kherâ are dug out from this mound.

III. The kherâ in the village of Bêrņî is reputed to be the ruins of a palace of Râjâ Vêṇa.

The khera at Rania is said to be the ruins of an old village called Mustafabad.

There are kherûs in the following villages, of which, however, nothing particular is known: Kahra Kherâ, Kaithâl, Samathâl, Râjthâl, Gôrashâhgarh, Fathgarh, Baniâ Kherâ, Gursârî, Nausnâ Sêondarâ, Mithânpûr Pûja, Muhammadnagar Qasbâ, Khêtrî, Mundiâ Kherâ, Chiriâ Bhawân, Ibrâhîmpûr, Atâ, Bhattapura, Arifpûr, Kuṇḍarkhî, and Kasâwâ.

5. Hâsanpûr, tahsîl, lat. 28°-43′-28″ N., long. 78°-19′-25″ E., 33 miles W. of Murâdâbâd, possesses 12 masjids, two of which are old, and 10 Hindû temples. To the north of the town there is an old kherâ.

To the south-west of the village of Azampûr is a kherâ which is the site of ancient buildings. It is reported that there was the school of Fâîzî Fayazî, brother of Abûl Fazl, the great historian of Akbar's time. The ruins of an arched doorway are still standing. The earth of this mound is carried off by people who come from long distances, in order to give it to students to eat, as it is supposed to have very beneficial influence on the brain and memory.

III. At the villages of Jaithal and Sirsa Jujar are ancient mounds which are the remains of old castles. At the latter place portions of the walls are still visible, and there still exists a pakkâ-built doorway.

There are extensive mounds at the following places, of which nothing specific has been heard: Bijaurâ, Shâhpûr Kalân, Khâki Kherâ, and Shakûrâbâd. At the latter place are many ruined wells, built of large bricks, and several stone chabûtrâs, apparently the sites of ancient temples.

6. Muradabad, lat. 28°-51′-6″ N., long. 78°-48′-35″ E., is the old Chaupala, so called from including in its boundaries four villages, viz., Bhadaura, Dindarpur, Manpur, and Dihri. Rustam Khan Dakhini called it Muradabad in honor of Prince Murad Baksh, Shah Jahan's son. A few sati pillars are all that we

- find in the town of ancient Hindû remains. The Musalman period, however, has left III. a few relics, among which the most important is the ruined fort built by Rustam Khân in the reign of Shâh Jahân. The Jâmi Masjid owns also its existence to
- 116. Rustam Khan, in A.H. 1046, according to a Persian inscription on a slab fixed in the wall. The remaining buildings of interest are :- a tomb of Nawab Azmat-ullah, the tomb of Asabat Khan, the shrine of Shah Bulaki, the palaces of Dundi Khan,
- Hb. the Rohilla chief, and of his diwan, both built during the Rohilla period.
- III. At the villages of Sardarnagar and Nûrkherâ are old mounds, from which large stores of valuable bricks have been dug up and utilized by the neighbouring zamindars.
- NARAULÎ, în tahsîl Bilarî, lat. 28°-29'-15" N., long. 78°-45'-15" E., 24 miles 116. of Murâdâbâd, possesses five masjids and four Hindû temples.
- 8. Sambhal, tahsil, lat. 28°-35' N., long. 78°-36'-45" E., 23 miles S.-W. of Murâdâbâd. The modern town covers the summit of an extensive mound composed III.
- of the ruins of the ancient Sambhalapura. The site of an old fort is indicated by a large mound; it is variously attributed to Prithvirâjâ, to a Râjâ called Jagatsimha and to one Naharasimha. The only building left standing on the site of the old fort Hb. is the Jami Masjid, which the Hindûs claim to have been originally the temple of Hari Mandira. It consists of a central domed roof upwards of 20 feet square, with two wings of unequal length, that to the north being 50' 6", while the southern wing is only 38' 11". Each wing has three arched openings in front which are all of different widths, varying from 7 to 8 feet. The Musalmans ascribe the erection of the building to the time of Muhammad Babar and point to an inscription inside the masjid, which records the erection of the masjid by Mir Hindû Bêg, in A.H. 933, A.D. 1526, but which the Hindûs declare to be a forgery of late date. At or on the back of this slab, they say that there is the original Sanskrit inscription belonging to the temple. This masjid was repaired in A.H. 1030 by Said Qutb, and 1067 by Rustam Khan Dakhini, as stated in the last inscription. The fine dome of this building is probably unique of its kind; it is a clear hollow shell from the keystone down to the ground. The interior shape of the dome is ovoid, or like the half of an ovoid ellipse rotated on its axis. The dome is built of brick, and stands upon an octagon, and the octagon upon a square. The walls of the central square Hindû temple would appear to have been built with large bricks cased with stones, but the plaster with which the Musalmans have coated the walls conceals the material of which they are made. Probably the Musalmans stripped off most of the stone, especially such as bore traces of Hindûism, and made a pavement of the stones, turning the sculptures downwards. Musalman wings, added to the building in order to turn it into a masjid, are built of small bricks. At the side of the masjid is a tank for ablutions and a very old well. The masjid has still a chain for the suspension of a bell, such as is found in Hindû
- Ш. temples, and a passage at the back for the wheeling round of worshippers.
- About one mile to the west of Sambhal, there is an Idgah, built by Rustam Khan, III. in A.H. 1066; a tomb of red sandstone, dated A.H. 963, and inscribed with verses

^{*} Proceedings, Ariatic Society of Bengal, for 1873, page 99.

³ Cunningham, Archaelogical Reports, Vol. XII, pages 24—27.

³ Proceedings, Asiatic Society of Bengal, for 1873, page 98.

III.

III.

III.

III. from the Qurân; a large bâolî, three storeys high, built of large bricks, apparently of the Hindû period; and the bastions of a large walled garden.

There are numerous places of Hindû worship and pilgrimage, the most noteworthy being the temple of Hari Mandir and the following tirthas:—Manokâmna, Sûraj Kuṇḍ, Kurukshetra, Bânsgôpâl, Nîmsâr, and Bhagirathi; altogether

IIb. Sambhal boasts of 68 tirth as and 19 sacred wells.

A brick tower, called Bala Bûrj, of the old Musalmân fort in mahallâ Kôt was erected in A.H. 1052, as recorded in a Persian inscription. A small masonry fort in the Miân Sarâi is attributed to Nawâb Âmîn-ad-daula, who lived here about 250 years ago. The two heaps of ruins, known as Bhalleśvar and Biktêśvar, near Raî sati, are said to be nothing more than the bastions of the ancient city wall, but are most probably the ruins of ancient Hindû temples.

III. In mauzâ Chandâyan is a large kherâ formed of the ruins of stone temples and IIb. brick buildings. An old temple still exists in a fair state of preservation.

In mauzà Kasauli is a kherà, the site of an old àbàdi.

III. Another ancient place called Amrapati Kherâ is situated on the right bank of the Sôţ river and near the village of Alîpûr. About a mile to the north-west of the last place, there is another mound, called Chandrêśvar Kherâ.

9. Thákurdwára, tahsíl, lat. 29°-11′ N., long 78°-54′ E., 27 miles N. of Murádábád. This pargana contains several kherás which may repay explorations, viz., at Sarkára Khás, Farídpúr Kásim, Gotávelí, Bázídpúr, Sultánpúr, Tikhuntí Mankúa Maksárpúr, and Madhowálá.

III. At mauza Mastalipûr is an old kherû, said to be the site of houses built in Akbar's time when the village was the head-quarter of the pargana.

III. The kherâ at mauzâ Farîdnagar is said to be the ruins of a fort and town, built by Râjâ Mahêndra Singh in 1170 fasli.

10. Ujhārî, in tahsil Hasanpûr, lat. 28°-39′-30″ N., long. 78°-23′-55″ E., 29 IIb. miles S.-W. of Murâdâbâd, possesses five masjids, one Hindû temple, and a dargâh of Shâh Dâûd.

V.—Pilibhît District.1

- 1. BARKHERÂ, în tahsîl Bîsâlpûr, 12 miles S. of Pilibhît, is said to have been founded by a mythical Râjâ, named Harmal. Its name means the mound of banyan trees, but is perhaps like that of Bârîkhar, or Barkherâ in the Kherî district, derived from that of Virâța, the son of Vêṇa. The village stands on an ancient mound, the ruins of an old fortified city.
- Bîsâlpûr, tahsil, lat. 28°-18′ N., long. 79°-52′ E., 22 miles S. of Pilibhît, possesses a fine square masonry tank surrounded by dharmsâlas and temples. A few other temples of no great importance may be seen in the town.
 At the village of Marauri. 8 miles E. of Bisâlpûr are extensive ruins on the

At the village of Maraurî, 8 miles E. of Bisâlpûr, are extensive ruins on the right bank of the Khanaut river.

3. Dêorîyâ and Dêwal, two unimportant villages in tahsîl Bîsâlpûr, 20 miles S.-E. of Pilibhît, have an united interest as the modern fragments of the ancient

¹ North-Western Provinces Gazetteer, Vol. V, pages 695-847, passim.

² Cunningham, Archeological Reports, Vol. I, pages 352—357.

city Mayûtâ. Dêwal is now known to Musalmâns as Ilâhâbâs or Ilâhâbâd Dewal; it contains several plain brick rooms called temples, in one of which is Пb. deposited a very perfect Kutila inscription, dated Samvat 1049, or A.D. 992.1 But Ia. both the inscription and figure of the Varaha Avatara of Vishnu, which may be seen in the same place, and which is a famous object of pilgrimage throughout Rohilkhand, were originally found, in 1829, in the adjoining village of Garh-Gajana, "the bastioned castle," which lies on the west bank of the Khâwâ or Katnî canal (called Katha in the inscription), immediately between Dêwal and Dêorîyâ. The ancient fortification from which it derives its name is a large ruined mound about 800 feet III. square, and containing on its eastern side two small tanks. But although called a garh or fort, it was probably only the country residence of Raja Lalla of the Chhindu race, who founded it. The inscription and Varâha statue were discovered in another mound of temple ruins, about 200 feet square at base to the west of the fort mound, which most probably are the remains of the two great temples, dedicated to Siva and Parvati under the name of Devapalli, and erected by Lalla and his wife Lakshmî as stated in the inscription; but the brick and limestone walls of the buildings whose site it marks have been gradually carried off as materials for the dwellings of the villagers. Round the principal mass of ruins may be traced the remains of at III. least six other temples; and Garh-Gajana has, besides two other mounds, the ruins of

Below Dêorîyâ the Khâwâ takes a sharp eastward bend, encircling three sides of a large ruined fort, called Garh Kherâ, or "the castle-mound." This strong-III. hold stands on the lands of Dêorîya; approachable only from the southern or landward side: it has been deserted for many centuries, and is overgrown with dense jangal. Its walls have afforded material for nearly all the buildings in Dêoriya. The exact extent of the fort is not known; but the position enclosed by the Katni canal is about 6,000 feet in length from north to south and 4,000 feet in breadth, and the fort is said to be somewhat less than half a kos or just about half a mile in length. The bricks are of a size $(13" \times 9" \times 2")$ which shows considerable antiquity, and the limestone statues are all Brahmanical. But such figures are said to be discovered only in the foundations of the buildings which, if true, would seem to show that the existing remains are the ruins of Musalman works constructed of Hindû materials. Garh Khera is attributed to the mythical King Vêna, and General Cunningham believes Vêna's son Virâța to be identical with Viravarman, the uncle of that Lalla who towards the close of the tenth century founded the town of Mayûtâ in the district of Bhûshana, the modern Dêwal and Garh-Gajana, as mentioned in the Dêwal inscription of Samvat 1049. According to the inscription, Mayûtâ was a large town adorned with wells, lakes, tanks, and neighbouring parks stocked with various animals.

4. Jahanabad, town in tahsil Pilibhit, 4½ miles W. of head-quarters. Near it on the west lies the village of Baliyâ or Balâî Pasîâpûr, which contains the ancient mound named Balâî Kherâ. This is a large heap of bricks and earth, about 20 feet high at its southern end. It has a circuit of nearly a mile, and its quadrilateral form leads to the conclusion that it once was fortified. To the west are two tanks

III.

some ancient village or town.

¹ Journal of Asiatic Society of Bengal, Vol. VI. pages 777-786; Prinsep, Essays on Indian Antiquities, Vol. I, pages 321-324.

^{*} Cunningham, Archaelogical Reports, Vol. 1, page 358.

and six ruined heaps said to be remains of temples; near the south-east are the ruins of what was undoubtedly a brick temple. There is nothing now standing that can give any clue to the probable age of the town, as the bricks are removed to Jahânâbâd as soon as they are discovered. But the large size of those bricks is a proof of antiquity, which is supported by the tradition of the people, who ascribe the foundation of Balpûr or Baliyâ to the well-known daitya, or demon, Bali.

Four miles to the westward of Balâi Kherâ, there is a long lofty mound lying east and west called Paraŝûâkôţ,¹ which is said to be the ruins of a temple and other edifices that Bali Râjâ built for his Ahîr servant, named Paraŝûâ. To the surrounding villagers it is more commonly known under the title of Atâparaŝûâ, or "Paraŝûâ's high chambers." The mound is about 1,400 feet long and 300 feet broad at base, with a height of 35 feet at its loftiest point near the eastern end. On this point there are the brick foundations of a large temple, 42 feet square, with the remains of steps on the east face, and a stone lintel or doorstep on the west face. No traditions exist regarding the remains of so magnificent an edifice.

5. Pilibhir, tahsil and capital of the district, lat. 28°-38′ N., long. 79°-52′ E., possesses a masjid, built in A.H. 1181 and 1182 by Hâfiz Rahmat Khân, a miniature in brick and plaster of the celebrated Jâmi Masjid at Dehlî. Being elegant in structure, but deficient in magnitude, it makes a more superb show as a picture than the reality justifies. Besides this there is an old masjid in the small, but strongly walled, native sarâî. The remains of an old brick fort are still traceable to the west of the town.

At mauza Neorî â Husain pûr are extensive ruins, buried in dense jangal, which may repay exploration.

III. The village of Mahâfî contains the ruins of an old brick fort of great dimensions.

At mauzâ Khâz are the ruins of a large city, of whose importance and splendour several octagonal wells and a large tank with pakkâ ghâţs bear witness.

In the jangals near Samarîa Ghôs û are the remains of a mud fort.

III. The village of Pindarâ, though devoid of any ancient remains, is said to be an old site.

 PÜRANPÜR, tahsil, 24 miles E.-S.-E. of Pilibhit. This pargaņa contains several large ruined cities buried in dense jangal close to the Nepâl Tarâi.

III. A large area of the ruins near Dhanauraghât, six miles N.-E. of Pûranpûr, has already been swept away by the floods of the Sârdhâ river, and what remains is likely to be washed away in future. The ruins consist of high mounds, extending for half a mile in length and a quarter of a mile in breadth along the south bank of the Sârdhâ, and are covered with large broken bricks and fragments of glazed pottery. From the great number of ornamental bricks, scattered about the mounds, it is evident that this ancient site once boasted of several fine brick temples.

The so-called kôt near Sû â pâra, 7 furlongs to the north of Pûranpûr, is a mere mound, about 400 feet square and 70 feet high, with a rãonî of about 40 feet in width all around. Numerous ornamental bricks are found in the mound which most probably belonged to a brick temple inside the fort. These bricks appear to have been carved after burning and not moulded before burning. The surfaces of most of the bricks

Пд.

III.

Ш.

III.

III.

¹ Cunningham, Lc., Vol. I, page 357.

are divided into squares, every alternate square being sunk in a sloping direction; these cuts were made by a chisel or small hammer with one chisel end. The bricks were probably used as string courses of plinths and basements on temples and mansions.

The ruins near Shâhgarh, 10 miles west of Pûranpûr, consist of an immense fortress formed of earthen ramparts and bastions with a circuit of about three miles. The ramparts have a general height of from 20 to 25 feet above the neighbouring forests, but the bastions are considerably higher. Originally there were ditches all around, but at present there are only a few shallow hollows at the foot of the ramparts. The parapets were of brick and stone; the large size of the bricks, $20" \times 12" \times 4"$, shows that these are the ruins of very old walls. In shape this fortified town may be described as an irregular quadrangle with its larger sides running almost due east and west. There are no remains of any building inside the fort except a few kankar walls; the only relics of antiquity that are obtainable are coins of the Varmâ dynasty of Nepâl, enamelled beads and moulded bricks of the diaper pattern.

III. Another, but nameless ruined city, is buried in the jangals near the Pûranpûr road leading to Pilibhit, four miles to the south of Shâhgarh. In shape it is a rectangle, about 1,600 feet in length from east to west by 1,200 feet in breadth, with a general height of about 20 feet in the main line of walls. The whole ground is covered with fragments of glazed pottery and large ornamental bricks, the patterns of which are bold and effective.

All these ruins are locally ascribed to Râjâ Vêṇa, or the demon Bali, who is no doubt the Vîravarman of the Chhindu race, mentioned in the Kuṭila inscription of Samvat 1049, from which we learn that his nephew Lalla founded the Dêvapalli temple at Mayûtâ, the modern Hâhâbâs Dêwal in tahsîl Bîsâlpûr.

VI.—Shâhjahânpûr District.1

1. Gôlà Râîpûr, village in tahsîl Pawâyan, lat. 28°-1′-50″ N., long. 80°-0′-22″ E., 10 miles N. of Shâhjahânpûr. To the south of the present village of Gôlâ is the site of an ancient town, a very large and high kherâ or mound, extending along the rise of the Khanaut valley for about two miles. The kherâ alone remains; it is covered with large thick bricks and fragments of blue and green glazed pottery, and old Buddhist coins, both stamped and cast, are occasionally found there. The area occupied by the site of the old town and the very high mounds that remain, prove that Gôlâ must have once been a place of considerable importance. A small mud fort on the edge of the present village is of much later date. Probably the old site represents the Hi-lo, visited by the Chinese traveller Fa-hian² in A.D. 400, which possessed a vihâra of forty paces square, with a tower like a dâgaba for the reception of the skull-bone of Buddha. In the early Musalmân period, Gôlâ was the head-quarters of pargana Kânt-ô-gôlâ, as mentioned by Ziâ-ad-din Barnî, a historian who lived in the reign of Ala-ad-din Khiljî (A.D. 1296—1316), and in the Âin-î-Akbarî.

2. Jalâlâbân, tahsîl, lat. 27°-43'-23" N., long. 79°-42'-11" E., 18 miles S.-W. of Shâhjahânpûr, is said to have been founded in the reign of Jalâl-ad-dîn Fîrûz Shâh Khiljî. The ruins of an old mud fort, said to have been erected by

III.

III.

North-Western Provinces Gazetteer, Vol. IX, part 1, pages 164-202, passim.

Beal, Le., Vol. I, page XXV.

III.

III.

Ш.

Hâfiz Rahmat Khân, but very probably of older date, are situated on the high ground commanding the town.

- 3. Kânt, village in tahsîl Shâhjahânpûr, lat. 27°-48′-20″ N., long. 79°-50′ E., 9 miles S.-E. from head-quarters, possesses a ruined masjid, erected in A.H. 1018, and many old masonry houses, which attest its former importance. A kherû close to the village is said to have been the site of an old fort.
- 4. Кнега Валнета, village in tahsil Tilhar, lat. 28°-1′-40″ N., long. 79°-35′-11″ Е., 25 miles N.-W. of Shahjahanpur. About 300 feet to the west of Bajhera is a large bare mound (khera) which is the deserted site of an ancient town.
- Khudaganj, in tahsîl Tilhâr, lat. 28°-8′-20″ N., long. 79°-45′-31″ E., 24 miles
 N.-W. of Shâhjahânpûr, possesses one masjid and three Hindû temples.
 - 6. Mart, small hamlet in tahsîl Pawâyan, 42 miles N.-E. of Shâhjahânpûr, is built on an ancient dih, the deserted site of a large old fortified city, now covered with dense jangal. The ruins extend for two miles in length and one mile in breadth, and the whole area is covered with large bricks, measuring 18"×12"×6", many of which are inscribed om srisivaya in characters of the eighth century. In many places the walls of the fortifications are still rising up ten feet above the ground. Inside the jangal-clad fort, a number of octagonal wells, built of large bricks, are evidence of the skill and honesty of the masons of those days. The whole city was surrounded by an outer and inner wall and a deep faussebraie on all sides. At a short distance to the north-west of the great fortress is a large tank, one mile in length and a quarter of a mile in breadth, with pakka ghats, all round, leading down to the edge of the water. The north, west, and south banks of the tank are covered with brick débris, the ruins of large buildings, and on the east side is a high brick mound, the ruins of a large square temple, with a lingam still standing in the sanctum. From this emblem of Siva, the neighbouring village is named Mahâdêva, on the west side of which there are the ruins of another brick temple of Siva, with the lingam still intact. The high antiquity of the place is attested by the numbers of coins that are found amongst its ruins; these include punch-marked bits of silver and copper, Buddhist punched and cast coins, those of the Indo-Scythian kings Huvishka and Kanishka, and of the Indo-Sassanian period. The money of the Musalman kings is even more common from the time of Muhammad-ibn-Same down to Sikandar Lodi. This unbroken succession of the different coinages shows that the place must have been occupied continuously from the very earliest times. It is much to be regretted that a Thakkur of the neighbouring village Murâdpûr has lately dug the place in search of cheap building material as the qulis employed have ruthlessly ruined the original walls of many buildings.

The original name of the old city was apparently Matripura, as an ancient statue of Kali is still an object of worship and pilgrimage in one of the small modern temples in the small hamlet, built on the north-east side of the ancient mound.

The North-Western Provinces Gazetteer, Volume IX, page 179, mentions that a copperplate grant was found on this spot and a rubbing sent in 1871 to Dr. Rajêndra Lâl Mitra for examination. The inscription has, however, apparently never been published.

IIb.

Six miles to the south-west of Mâtî, at the small village of Thânêkâ, are extensive brick ruins, the remains of brick temples, on the east bank of a large tank. Its foundation is attributed to the mythical King Vêṇa.

7. Mîranpûr Katra, town in tahsîl Tilhâr, 18 miles N.-W. of Shâhjahânpûr,

III. possesses an old mound, the deserted site of an once important place.

Ш.

IIb.

IIb.

8. Shāhjahānpūr, capital of the district and tahsil, lat. 27°-53′-41″ N., and long. 79°-57′-30″ E., is devoid of all objects of historical or architectural interest. The city was founded in 1647 A.D., in the reign of Emperor Shāh Jahān, by a body of Paṭhāns under Bahādur Ķhān and Diler Ķhān. It possesses a ruined fort, and the Jāmi Masjid, built soon after the founding of the city, is a plain substantial

erection. The only objects that can claim notice are two masjids, built A.H. 1108 and 1155, respectively, and a few tombs, that of Bahâdur Khân being the most note-

and 1155, respectively, and a few tombs, that of Banadur Anan being the most note worthy.

III. 9. Тілная, tahsíl, 12 miles N.-W. of Shâhjahânpûr, possesses an old ruined fort in mahallâ Khatriân, and a large brick fort and residence outside the town, close to the Bareli road, built by Mangal Khân, nizam under Hâfiz Rahmat Khân. A large

III. bare kherà to the west of the town, covered with broken bricks and fragments of glazed pottery, is the deserted site of an ancient village.

III.-KUMÂON DIVISION.1

I.—GARHWAL DISTRICT.

 Adbadrî, village in pargana Chandpûr of tahsîl Śrînagar, lat. 30°-9′ N., long. 79°-16'-10" E., possesses the remains of sixteen temples similar to those found at Dwara-III. hât in the Kumâon district. The principal temple is distinguished by a raised platform or chabûtrâ in front, roofed in and leading to the small square enclosure of the usual pyramidal form, within which is the image itself. Local tradition here assigns the building of the temples to Samkaracharya, the celebrated reformer and Hindû philosopher, while in Kumâon the same style of buildings bearing traces of similar antiquity is attributed to the piety of the Katyûra Râjâs.

2. Badrînâth, village in pargana Malla Pâînkhanda, 55 miles N.-E. of Śrînagar, lat. 30°-44'-29" N., long. 79°-32'-1" E., possesses a temple of Badarînâtha, or IIb. Badarînarâyâna, an incarnation of Vishnu. The building said to have been erected some 800 years ago by Samkaracharya is of conical form with a small cupola covered with plates of copper and surmounted by a gilded ball and spire. The present temple has, however, a modern appearance, several former ones having been overwhelmed by avalanches, and an earthquake having shaken the present erection so seriously as to render necessary an almost entire restoration. The body of it is constructed of flat stones, over which is a coat of fine plaster which, while adding to its neatness, detracts from the appearance of antiquity. A short distance below the temple is the Taptakund, a tank about 30 feet square and covered with a roof of IIb. planks supported on wooden posts.

3. Chandpûr Fort, in pargana Chandpûr, lat. 30°-10' N., long. 79°-12' E. The walls and some of the ruins of the dwelling-houses are still standing. The walls must have been very strongly built, as they are formed of large slabs of cutstone, the space between them being one and a half acres. There are also two flights of steps, each formed of one solid block of stone, which are said to have been quarried

in the Dûdû-kê-tôli range, a march and a half distance from the fort.

4. DEWALGARH, capital of pargana, possesses an old temple of the Rajas of

Garhwâl. Gôpêšvar, village in pargana Nâgpûr, possesses a fine old temple, surrounded by a courtyard and repaired by Umar Singh Thapa, a Gorkhali General, in the first decade of the present century. In the courtyard stands a trident of iron with a shaft of the same material, 16 feet high, having the ancient Sanskrit letters in copper soldered on in relief in the same way as that at Bârahât in native Garhwâl. The form of the letter shows them to be of the same age as those at Barahat, and they are accompanied by four short inscriptions in modern Devanagari cut in the metal of the iron shaft; three of these are now utterly illegible.

The old inscription's records the victories of Anekamalla in the sacred Kedârabhûmi (Garhwâl). Another inscription records the erection of a royal edifice by the same Anekamalla in Sake 1113, or A.D. 1191. There is a great

III.

Hb.

116.

¹ North-Western Provinces Gazetteer, Vols. XI and XII, passim.

Journal of Asiatic Society of Bengal, Vol. V, pages 347, 485.

brass image of a Râjâ in the temple of Yâgêsvar in Kumâon, which local tradition asserts to be one with Râjâ Anekamalla.

- 6. Josнîматн, or Jyotirdhâm, in pargaṇa Painkhaṇḍa; lat. 38°-33'-24" N., long. 79°-36'-24" E., is the place of the great Jyotirlingam of Mahadeva. The building Hb. containing the image of Narasimha is more like a private residence than a Hindu temple. Pilgrims halting here put up in a large square, having a stone cistern, supplied by two brazen spouts, which yield a never-failing flow of water. A collection of temples, bearing marks of great antiquity, extend along one side of the IIb. square, being ranged along a terrace about ten feet high. In the centre of the area is a temple sacred to Vishau, surrounded by a wall 30 feet square. Several of those IIb. temples are much dilapidated, having been partially overthrown by earthquakes. The temples of Vishņu, Ganeša, Sûrya, and Naudêvî have suffered least. The statue of Vishnu is of black stone, in a very superior style of workmanship; it is about 7 feet high and is supported by four female figures, standing on a flat pedestal. There is another image of brass with wings attached, and wearing the sacred Brahmanical thread, which some assert to be of Bactrian-Greek workmanship. The image of Ganesa is 2 feet high, well carved, and polished.
- KARNPRAYÂG, village in pargana Chandpûr, lat. 30°-15'-43" N., long.
 79°-15'-29" E., possesses a temple named after Karņa, and is one of the places of pilgrimage at the confluence of great rivers. On each side of the junction of the Alaknandâ and Pindâr rivers are remains of small temples of the usual Kumâon style.
 There is an old temple sacred to Govindanârâyana at Simlî and the remains of three others.
- 8. Kepárnáth, a temple in pargaṇa Nagpūr, lat. 30°-44'-15" N., long. 79°-6'-33" E., is built on a ridge jutting out at right-angles from the snowy range below the IIb. peak of Mahapanth. It stands near the head of the valley of the Mandakini on a level spot, and is a handsome building with a neat façade adorned on either side with niches and images. A tower behind built of grey stone and surmounted by a gilded pinnacle forms the adytum of the shrine. In front of the temple are two rows of masonry houses for the accommodation of pilgrims, and behind is the courtyard forming the residence of the officiating priests. The present structure is of recent construction, the original building having fallen to ruin. It is dedicated to Sadashiû, a form of Siva, who flying from the Pandavas took refuge here in the form of a buffalo, and finding himself hard pressed dived into the ground, leaving, however, his hinder parts on the surface, still an object of adoration here. The remaining portions of the god are worshipped at four other places along the Himalayan chain: the arms (bahu) at Janganath, the face (mukha) at Rudranath, the belly (nabhi) at Mêdha-Mahêsvar, and the hair (jeta) and head at Kalpêsvar. These together form the "Pañchakedâra," the pilgrimage to which places in succession forms a great object to the Hindû devotee.
- 9. Mandhal, ruined village in pargana Ganga Salan of tahsîl Śrinagar, six miles east of Hardwar, possesses a very remarkable old temple in admirable preservation. The temple itself stands on a platform or chabûtra, 20 feet square, and at each side is a trench. Beautifully-executed heads terminate the trench at the four

Journal of Axiatic Society of Bengal, Vol. XXXVI, page 154.

IIb.

IIb.

IIb.

corners: on the south a woman's head and bust, at the west a lion, at the north a ram; the east corner is broken and defaced. A number of carved slabs, large 1b.capitals, shafts of pillars, friezes, and doorways are scattered through the neighbouring jangal. Four miles further east are the ruins of an ancient city, now known as Panduwâlâ, probably the capital of the kingdom of Brahmapura, visited by Hiuen Tsiang.1

10. Nandākinī, a river rising in the glaciers on the western slope of Trisul in pargana Badhân, lat. 30°-16'-10" N., long. 79°-46'-5" E. High up the source there is a temple to Nandadêvî, and beyond the temple a large rock, both of which are visited by pilgrims. The temple is situated near Tantarakharak above

the village of Satol.

11. Nândyaprayâg, în pargana Dasôlî, lat. 30°-19'-56" N., long. 79°-21'-29" E., possesses a temple dedicated to the Naga Taksha, hence the place is often called Hb. Takshaprayag.

12. Pandukėsvar, lat. 30°-37'-59" N., long. 79°-35'-30" E., 54 miles N.-E. of Śrinagar, possesses the temple of Yôga-badari, one of the Pañch-badari. Four copperplate grants of Lalitasûra Dêva are preserved in the temple, being

valuable records of the Katyûri Râjâs.

13. Śrinagar, a large village in pargana Dêwalgarh, lat. 30°-0'-13" N., long. 70°-48'-15" E., contains a few small temples, extremely well built; the chief temple of Kamalêsvar is of massive stone beautifully fitted together, but has very little IIb. architectural beauty. The ruins of the palace of Raja Ajayapala of the Chand dynasty must have once displayed considerable architectural pretensions and extent, Ib. as its ruins even now cover some acres of land. It was built in A.D. 1358 of large blocks of black stone laid in mortar, and had three grand fronts each four storeys high, with projecting porticoes profusely ornamented in the lower part with elaborate sculptures. It is said that no woodwork whatever was used in its construction, and this is attested by the fact that the portions still remaining have none; the windows even to the latticing being of stone, while the only doorway left is of stone carved so as to exactly resemble wood. These doors are very massive and heavy, and it must have taken immense labour to put them up. Of the older residence only one, the western wing, is standing, and it is almost in ruins. The building, especially over the doorway, is massive and quaintly ornamented. There is another wing also standing to the south; but this is of quite modern date, and is, though well built, of very simple structure.

14. VISHNUPRAYAG, a halting-place on the road from Srinagar to Badrinath, is situated on the Vishņugangâ river in pargana Pâinkhanda. There is a temple here built on a tongue of rock between the Dhauli and Vishnuganga rivers, 11

miles from Joshimath on the Mana road.

II.-KUMAON DISTRICT.

1. Almora, head-quarters of the district, in pargana Barahmandal of Hazur tahsîl, lat. 29°-37′-3" N., long. 79°-40′-20" E., possesses one masjid and several Hindû IIb. temples, but none with any pretensions to architectural merit,

¹ Beal, Le., Vol. I, page 198.

² North-Western Provinces Gazetteer, Vol. XI, pages 471-481.

2. Askôr Malla, in tahsîl Champâvat, is said to have had originally 80 forts, and hence the name. The first of these was Champachal or Lakhanpûr-kôţ, near which are the remains of the old town of Bagrihât. On Champâchal there is a temple to Mahâdêva, and on Chipula or Najûrkô t there is a great cave at which a fair is held every year, also a dry pond held sacred to the deity of the hill.

3. Bagêsvar, village in pargaṇa Dânpûr of Hazûr tahsîl, lat. 29°-56'-15" N., long. 79°-48'-52" E. The name is derived from the temple which is dedicated to Vagišvara, "the lord of speech," or according to others Vyaghresvara, "the

Hb. lord of tigers." The present temple was erected by Raja Lakshmi Chandra Ш. about 1450 A.D., but a stone inscription1 preserved in the temple shows a far earlier foundation. The slab is unfortunately much injured, especially in the right lower

corner, where the date has been obliterated. It records the grant by Srî Bhû-IIb. dêva Dêva, of the Katyûri family, of a village and land to the temple of Vyâghrêsvara, and gives the names of seven Râjâs, the ancestors of the donor. Certain tombs constructed of large tiles discovered in the neighbourhood of Bagêsvar and at Dwarahat have been assigned to Moghal colonies, and attest perhaps the presence of a non-Hindû race. III.

4. Bâîjnath, or Vaidyanath, village in pargana Dânpûr of Hazûr tahsîl, lat. 29°-54'-24" N., long. 79°-39'-28" E., is the ancient Karttikeyapura and possesses a large Hindû temple sacred to Kâlî situate in the old Ranchula fort. IIb. There are besides several old temples of the usual style, most of which are in ruins Ш. and are used as corn-lofts and store-rooms as in Dwarahat. Along the walls are old sculptures collected from different places; but one is clearly a representation of Buddha, and must have belonged to a temple of that creed which flourished here in the beginning of the eleventh century of our era according to Hiuen Tsiang.2 Two inscriptions of Udayapala Dêva, of considerable length, are found on a masonry well much worn, however, by the trickling of water over the stones on which they are inscribed. A copperplate records the grant by Indradêva in the year A.D. 1202. On an image of Vishnu in one of the old temples occurs the date A.D. 1499, and on an image of Ganêsa the date A.D. 1322, besides the date of A.D. 1203. IIb.

5. BARMDEO (Brahmadeva), or Mundiya, in pargana Kali Kumaon of tahsîl Champâvat, lat. 29°-6′-30″ N., long. 80°-11′-37″ E. About eight miles distant is the far-famed shrine of Pûrnagiri, where Parvati is adored by pilgrims from mountains and plains.

6. Bhâinskhêr, a village in pargaṇa Barāhmaṇḍal of Hazūr tahsil, lat. 29°-42′ N., long. 79°-35′-30″ E., possesses an old temple sacred to Sûrya.

7. Внікі́уа, village in pargaņa Pāli Pachhāon of Hazūr tahsil, lat. 29°-42′-8" N., Πb . long. 79°-18'-20° E. Close by is the old temple of Naulêsvar, which has more than a local celebrity among those situated at the smaller prayagas or junctions of Hb. streams.

8. Bhîm Tal, lake in pargana Chhakhâtâ of tahsîl Bhâbar, lat. 29°-20'-40" N., long. 79°-36'-16" E., possesses on its banks an old temple erected by Baz 116.

116.

IIb.

¹ Journal of Asiatic Society of Bengal, Vol. VII, page 1056; North-Western Provinces Guzetteer, Vol. XI, page 469,

^{*} Beal, Le., Vol. I, page 198.

³ North-Western Provinces Gazetteer, Vol. XI, page 519.

III.

Hb.

Bahâdur Chandra, Râjâ of Kumâon, in the seventeenth century. This temple is a fair example of the ecclesiastical architecture common throughout the hills, and has a wooden canopy (chhattri) on the top erected here as an ornament, and in some places it is said to preserve the building from rain.

In mauza Silotî of pargana Chhakhata, there are two copperplate grants, one of Baz Bahadur Chandra, dated Śake 1566, and the other of Udhyota Chandra, dated Śake 1613.

9. Champâvat, tahsîl, lat. 29°-20′-11″ N., long. 80°-7′-84″ E., was the residence of the Râjâs of Kumâon before they transferred their seat to Almorâ in the middle of the sixteenth century. The old palace is now in ruins, but the fort partly remains. Amidst the ruins of the palace, of which the base and doorway of a balcony alone remain, is a fountain about 10 feet square outside the quadrangle, and near to it are three temples on a level area, about 100 feet square, hewn into the solid rock. They are each polygonal, at the base 20 feet in diameter, and surrounded by an arched dome; all being constructed of stone with good taste and elaborate workmanship. They must be of considerable antiquity, as some apparently coëval ruins situated about the temple are in many places overgrown with forests of aged oaks.

In the temple of Balêśvar is an inscribed pillar, dated Śâke 1293, and two copperplate grants, the one of Bâz Bahâdur Chandra, dated Śâke 1586, and the other of Kalyâna Chandra, dated Śâke 1655; in the temple of Nâganâtha is a copperplate grant of Jagach Chhandra, without date, and in the temple of Ghaţotkacha, a copperplate grant of Udhyôta Chandra, dated Śâke 1609.

Govinda Pachauli possesses the following seven copperplate grants:—of Jñâna Chandra, Śâke 1341; of Vishņu Chandra, Śâke 1433, 1434, and two 1441; of Rudra Chandra, Śâke 1519; and of Kirtti Chandra, Śâke 1727.

In the village of Phulârâ, south of Champâvat, are deposited two copperplate grants: one of Vishņu Chandra, Šâke 1455, and another dated Šâke 1590.

In the village of Daḍâgâon, one mile north of Champâvat, are eight copperplate grants in the possession of Sivadatta Vishṭa:—of Jñâna Chandra, Sâke 1320; three of Kalyâṇa Chandra, Sâke 1362 and two 1383; of Haris Chandra, Sâke 1383; of Pratâpa Chandra, Sâke 1383; Sutiraṇamalla, Sâke 1390; and Kalyâṇa Chandra, Sâke 1481.

In the village of Tyârkuḍâ, one mile east of Champâvat, is a copperplate grant of Jagach Chhandra, Śâke 1632, in the possession of Pujârî Dêvadatta Tripáthî.

In the village of Chanayâgâon, one mile north of Champâvat, are two copperplate grants of Nara Chandra, Sâke 1219 and 1243, in the possession of Udai Râm Chanayâ.

In the village of Bungâtalâ, one mile north of Champâvat, are two copperplate grants of Kalyâna Chandra, Śâke 1629 and 1654, in the possession of Harasingh Chaudharî.

In the village of Ganganāû, four miles from Champâvat, are two copperplate grants of Nara Chandra, Šâke 1307 and 1377, in the possession of Bhavânidatta Pâṇḍe.

In the village of Pâû, eight miles from Champâvat, is a copperplate grant of Kîrtti Chandra, Sâke 1422, in the possession of Siromani Pandit.

In the village of Tapnipal, 11 miles from Champavat, is a copperplate grant of Jñâna Chandra, Śâke 1334 and Sainvat 1469, in the possession of Chandriya Pandit.

In the village of Raigaon there is a pillar in the compound of the temple of Maharudra with three inscriptions, dated Sake 1289, 1334 of Jñana Chandra, and 1356.

In the village of Asargaon, 24 miles north of Champavat, are two copperplate grants, Sake 1304, and of Bharata Chandra, Sake 1319, in the possession of Asukhôlia Pandit.

In the village of Tyarsaû, 15 miles from Champavat, is a copperplate grant of

Bharata Chandra, Sake 1391, in the possession of Hari Ram Pandit.

In the village of Gudamagalgaon, 28 miles from Champavat, are two copperplate grants, dated Sake 1340 and 1397, in the possession of Haridatta Pandit.

In the village of Gadi-udâ is a copperplate grant of Śrimalla Chandra, Śâke

1538, in the possession of Lôkmani Mâlguzâr.

10. Changarkhâ, a pargaṇa of Hazûr tahsîl, possesses in the Darûn sub-division the great temple of Yagêsvar where Mahâdêva is worshipped under the form Jyotirlingam.

11. Dêrî DHÛRA, or Dêh, a station on the road from Almorâ to Lohûghât, 32 miles from Almora, lat. 29°-24'-56" E., long. 79°-54'-30" E. On the northwest face of the mountain, a few feet below its crest, there are two groups of colossal grey granite piled on each other, consecrated to Mahadêva, Varahidêvî, and Bhîmasêna. Similar boulders are strewed over the surface of the surrounding mountains, especially on the upper part of the deep depression in the range immediately north. Between two of the main boulders in a recess is a celebrated

temple.

Ib.

Hb.

IIb.

IIb.

12. Dhîkulî, village in pargaṇa Kôṭa of tahsîl Bhâbar, lat. 29°-28′-5" N., long. 79°-11'-30" E. Near the village are the remains of ancient buildings a few feet from the surface, locally identified with Vairatapattana, the capital of the old king-III. dom of Govisana, visited by Hiuen Tsiang' in the seventh century. There are many fine specimens of capitals, pillars, medallions, figures of lions, and other Buddhistic designs. Many of these have been used in a building as ornaments for archways, pillars, and mantel-pieces. Some of the pillars are foliated, interspersed with birds, dragons, lions, &c. On a plateau above is an ancient well. Another set of remains exists on the Kûa-kâ-chaur, above Môhân. III.

 Dôl, village in pargaṇa Mahryûri Dôlphât of Hazûr tahsîl, lat. 29°-29′-30″ N., long. 79°-48'-25" E. Three kôs from the village stands the rather famous shrine of Kapilêsvar, with a large temple dedicated to Mahâdêva, built by Udhyôta Chand, son of Bâz Bahâdur at the supposed spot where Kapila IIb. did penance.

- 14. Gangôlî Hât, in Hazûr tahsîl, lat. 29°-39'-23" N., long. 80°-5'-24" E., possesses a temple dedicated to Kâlî. Close by to the south-west are the remains of a few old temples and a masonry well bearing an inscription.
- 15. Kôṭalgarh, a fort in pargaṇa Kâlî Kumâon of tahsîl Champâvat, lat. III. 29°-24′-30" N., long. 80°-6′-5" E. The area of the fort is about eighty yards north and III.

¹ Beal, Lc., Vol. I, page 199,

III.

south and 12 or 14 east to west, surrounded by a good stone wall eight or ten feet high and five feet thick. Kôṭalgaṛh is fabled to have been the stronghold of the arrowdemon Bâṇâsura daitya, the son of Mahâbali.

16. HAWALBAG, a hamlet six miles S.-W. of Almora, possesses the remains of a large temple dedicated to Aditya, or the sun, and a cluster of small ones also in

ruins owing to an earthquake.

17. Kôta, capital of pargaṇa in tahsil Bhâbar, possesses the ruins of an old fort, defended by thick stone walls. Close by on the banks of the Kôsi river is the romantic temple of Dêvîpûr, about 200 feet above the river on a low range of wooded hills. IIb. About six miles S.-W. lies the village of Sîtâban, where there is an old temple sacred to Sîtâ, who fled here after escaping Ravaṇa.

18. Pinnāth, village in pargaņa Bārahmaṇḍal of Hazūr tahsīl, lat. 29°-50′-45″ N., long. 79°-35′ E., possesses several temples, dedicated to Šiva as Pinakêšvara, "lord of the trident." The first is a small conical structure, eight to ten feet high, dedicated to Bhairava. The main temple is close to this on the north, a square slated edifice with the door facing the south, and figures of Rājās, &c., sculptured on the walls. The roof of the portico is framed by the Indian arch, and on its sides are represented the five Pāṇḍavas; the adytum is small, and contains nothing but two images of Šiva and Pārvatī; about eighty years ago the original pile was nearly all overthrown by an earthquake. The temple contains a copperplate grant executed by Udhyôta Chandra in A.D. 1691, and another by Bāz Bahādur Chandra, bearing date A.D. 1654.

19. Sửi Bisửng, in pargana Kâlî Kumâon of tahsîl Champâvat, possesses the famous temple of Balêśvar, in which there are deposited two copperplate inscriptions,² dated respectively Sâke 1145, or A.D. 1223, and Sâke 1345, or A.D. 1423.

III.—TARAÎ DISTRICT.

III. 1. Chaturbhûj,³ an old ruined fort in tahsîl Rudrapûr, six miles to the east of the high road, midway between Râmpûr and Nâinî Tâl. The ruins lie to the east of the villages of Mahôlî and Dâlpûr and between the Jonâr nadî and the Kakrôlâ nadî. The name was imposed by the villagers on the discovery of a four-armed stone figure amongst the ruins of a stone temple. The most prominent portion of the ruins is a ruined fort, about 1,600 feet square, with earthen ramparts 10 or 12 feet high, and from 80 to 100 feet thick. There is an entrance on the west side, near which there is a ruined mound of some height, apparently the remains of a stone temple. To the west of the fort there is a group of four mounds from 10 to 18 feet in height, in one of which the Chaturbhûj statue was found. Still further to the west towards the villages of Mahôlî and Dâlpûr there are other mounds with several tanks and wells, and the traces of numerous foundations. The bricks scattered about the plain are of large size, 12" × 9" × 2". Nothing whatever is known about these ruins.

Kâsipûr, tahsîl, 45 miles from Nâînî Tâl, is named after its founder
 Kâsinâth Adhikâri, who was a servant of Bâz Bahâdur Chandra (1638—

I Journal of the Asiatic Society of Benyal, Vol. XVII, page 376,

² North-Western Provinces Guzetteer, Vol. XI, pages 516, 528,

³ Cunningham, Archeological Reports, Vol. II, pages 238, 239.

Cunningham, Archaeological Reports, Vol. I, pages 251—255.

1678 A.D.). It is said that the site selected belonged to four villages, in one of which was a noted temple of Ujainidevi.

One mile to the east of Kâsipûr lies the old fort of Ujâîn, which General III. Cunningham identifies with the ancient city of Govisana visited by Hiuen Tsiang.1 It is 3,000 feet in length from west to east and 1,500 feet in breadth, the whole circuit being upwards of 9,000 feet, or rather less than two miles. Hiuen Tsiang describes the circuit of Govisana as about 12,000 feet, or nearly 21 miles; but in his measurements he must have included the long mound of ruins on the south side, which is evidently the remains of an ancient suburb. By including this mound as an undoubted part of the old city, the circuit of the ruin is upwards of 11,000 feet, or very nearly the same as that given by Hiuen Tsiang. Numerous groves, tanks, and fish-ponds still surround the place. The largest of these is the Dronasagara, which as well as the fort is said to III. have been constructed by the five Pandavas for the use of their teacher Drona. The tank is only 600 feet square; but it is esteemed very holy, and is much frequented by pilgrims on their way to the source of the Ganges. Its high banks are covered with sati III. monuments of recent date. The walls of the fort are built of large massive bricks, $15'' \times 10'' \times 2\frac{1}{2}$ ", which are always a certain sign of antiquity. The general height of the walls is 30 feet above the fields; but the whole is now in complete ruin and covered with dense jangal. Shallow ditches still exist on all sides except the east. The interior is very uneven; but the mass has a mean height of about 20 feet above the country. There are two low openings in the ramparts, one to the north-west and the other to the south-west, which now serve as entrances to the jangal, and which the people say were the old gates of the fort. There are some small temples on the western bank of the Dronasagara; but the great place of worship is the modern temple of Jvaladevi, 600 feet to the eastward of the fort; this goddess is also called IIb. Uj aînidêvî. Other smaller temples contain symbols of Mahadêva under the titles of Bhûtêsvar, Muktêsvar, Nagnath, and Yagêsvar; but all of these temples are of recent date, the sites of the more ancient fanes being marked by mounds of various dimensions from 10 feet to upwards of 30 feet in height. The most remarkable of these mounds is situated inside the northern wall of the fort, above which the ruins rise to a height of 52 feet above the country and 22 feet above the ramparts. The mound is called Bhimgaja or Bhimgada, "Bhima's club," probably representing the ruins of a large lingam temple. About 500 feet beyond the north-east angle of the fort there is another remarkable mound, which is rather more than 34 feet in height: it stands in the midst of a quadrangular terrace, 600 feet in length by 500 feet in breadth, being the remains of a large square temple. Close by on the east and within the quadrangle there are the ruins of two small temples. To the eastward of Jvålådêvî temple there is a curious circular flat-topped mound of earth, 68 feet in diameter, surrounded by a brick wall from 7 feet to 11 feet in height; it is called Râmgir Gôsâin-kâ-tîlâ; or "the mound of Râmgir Gôsâin." To the south of the fort near the temple of Yâgêsvar there is a third large mound, 22 feet in height, which was once crowned by a temple of 20 feet square inside. To the westward of this last there is a fourth mound, on which there are the remains of a temple 30 feet square standing in the midst of a raised

¹ Beal, Le., Vol. I, page 199,

quadrangle about 500 feet square. Besides these there are ten smaller mounds which make up altogether fourteen or just one-half the number of the Brâhmanical temples mentioned by Hiuen Tsiang. The only ruin which appeared to General Cunningham to be of undoubted Buddhist origin is a solid brick mound, 20 feet in height, to the south-west of Yâgêsvar and close to the small village of K hargpûr. The base of the mound is upwards of 200 feet in diameter, the solid brick-work at the top is still 60 feet thick; but as it is broken all around, its original diameter must have been much greater, probably not less than 80 feet. But even this larger diameter is too small for a stûpa of 200 feet in height of the hemispherical form of Asoka's time; a stûpa of that early period, even when provided with both plinth and cupola, would not have exceeded 100 feet in height. There is, therefore, probably a mistake of 100 feet in the text of Hiuen Tsiang.

THE RESIDENCE OF THE PARTY.

IV.—ÂGRÂ DIVISION.

I.—ÂGRA DISTRICT.

 Achnerâ, village in tahsil Fathpûr Sîkrî, lat. 27°-10'-47" N., long. 77°-48'-42" E., 18 miles W. of Agra, possesses a small fort, apparently of middle age, built of stone, now considerably dismantled. The old tahsili built in Samvat 1770 is now in ruins.

III.

Ia.

III.

 Πb .

Ia.

Ia.

Ia.

Ia.

2. Agra, (Akbarabad), tahsil and head-quarters of district, lat. 27°-10'-29" N., long. 78°-5'-3" E., is very rich in ancient buildings and remains of the Moghal time.

On the side of the Jamna opposite to the city are several interesting buildings and sites, viz., the Baland Bagh, a garden once belonging to Baland Khan, a eunuch of Jahangir. A great pile of masonry overhangs the river; this consists of seven wells or rather lifts for drawing water from the river, called Sat Kuiya. Below is a large tower crowned with a cupola supported on pillars, called the Battîs Khambhâ, there are twenty-four pillars below and eight above supporting the cupola. There is another cupola at the south-west corner.

The Râm Bâgh is said to be more properly Arâm Bâgh, "the garden of rest," but this name was by some accounts given to it by the Jats. The older name was Bâgh-i-Nûr-Afshân, from the name of a Musalmân lady, identified by some with Nûr Jahân, the queen of Jahângîr and the daughter of his minister, Îtimâdad-daula, whose tomb stands a short distance lower down on the same side of the Jamna. The Râm Bâgh is a large walled garden with a raised stone terrace on the west of the riverside. There are five octagonal towers or bastions surmounted by pillared cupolas at each corner of the river face; underneath, or in the body of the terrace, are a set of vaulted chambers, opening on to a lower terrace, just on the water's edge; while above or on the terrace are two buildings, open baradaris, with chambers at each end and verandahs overlooking the river. By popular tradition the Râm Bâgh was the resting-place of Babar's body, from the time of his death at Agra till it was conveyed to Kâbûl for burial; but it is generally believed that the garden was made by the Empress Nûr Jahân, who frequently resorted here with her handmaids.

The Zâhra (Zahara or Zêhra) Bâgh or Mahal, also called Sa'îd-kâ-Bagh from the tomb of a Musalman saint that stands in it, lies between the Ram Bagh and the Chini-ka-Rauza. It has a river frontage of 1,234 feet, including two towers that marked the boundary at each end of the river frontage; it extends backward from the river for 1,095 feet to the site of the ancient gateway, the foundation of which can still be traced.

On the other side of the river, but at some distance from it, between Sultanpûr and Khawaspur, is a still larger garden bearing the same or closely similar name, Zêhra or Dêhra Bâgh. Regarding both these gardens the same tradition is preserved, namely, that each was made by the Emperor Bâbar, and named after one of his daughters called Zahara.

At the centre of the river-face of the garden are the remains of a river-side III. palace (mahal), and from what is left it is evident that it is of the transition period

Cunningham, Archaelegical Reports, Vol. VI, pages 5-12.

^{*} Cunningham. Archivelegical Reports, Vol. IV, pages 93—206; North-Western Provinces Gazetteer, Vol. VII, pages 673—717; Proceedings, Asiatic Society of Bengal for 1873, page 160; for 1874, pages 100, 160—175, 209—213; for 1875, page 113.

of architecture between the later Pathan and early Moghal, corresponding therefore with the age given to it by the tradition. The ruin known as the Chini-ka-Rauza Ia. adjoins Zâhra Bâgh on the south, and having, as a tomb, to be built directly east and west, its river front does not run parallel with the river's edge nor with the wall of Zâhra Bagh. The northern wall of its enclosure ran obliquely into, and was cut off by the southern wall of the Zâhra garden, showing clearly that the latter is the more ancient erection. The enclosure is, roughly speaking, 100 yards north to south and 150 yards east to west. At each end of the river front is an octagonal tower surmounted by a pillared cupola, and the enclosure is built for the most part on arches of massive masonry. The mausoleum is at the centre of the west or river front, and is a rectangular build-III. ing nearly 80 feet square surmounted by one great central dome resting on an octagonal base with four slender shafts crowned with flower-shaped capitals at each corner. The whole of the south-western corner of the building has fallen down; but when complete, there was in the centre of each side a lofty archway opening in an oblong antechamber. These four ante-chambers or side halls all opened on the principal central chamber, an octagon with a domed roof containing two brick tombs. Four square chambers occupy the corners of the building. Underneath the main building is a large crypt supported on arches and now open on the river-side. This mausoleum was faced outwardly with what is commonly called China, but in reality with a thin coating of enamel, all of one piece, in a variety of colours and in beautiful patterns. as the remains of it still amply testify. The tomb bears no inscription, but is traditionally ascribed to Afzal Khân, a poet, who died at Lahôr in A.D. 1639. For half a mile below the Chini-ka-Rauza there are no buildings of note, although there are traces of old gardens and some mausoleums in the fields.

The next is the tomb of Îtimâd-ad-daula. This mausoleum stands in the centre of a large garden enclosure, about 180 yards square, surrounded by a substantial wall except on the river-side, where there is a raised terrace overlooking the stream. At each of the four corners of the enclosure is a tower, and there is a fine gateway in the centre of the east side. There are ornamental buildings of red sandstone at the centre of the north and south sides, and a third at the centre of the terrace. The tomb in the centre stands on a platform of red sandstone about 150 feet square, and raised about 3 feet from the ground; being a rectangular building 69 feet 2 inches square, encased on the outside with white marble inlaid with mosaic work. At each corner stands an octagonal tower of white marble which at the level of the roof of the mausoleum is surrounded by a balcony supported on brackets, and then changes its form to circular, and finally terminates in another balcony supported on graceful brackets and surmounted by a handsome domed cupola supported on eight graceful pillars. At the centre of the roof of the mausoleum stands a marble pavilion 25 feet 8 inches square on a slightly raised platform, having a canopy-shaped roof with white projecting eaves supported on 12 pillars with marble screens between them. In this are two marble cenotaphs, counterparts of those in the central chamber of the mauso-This central chamber is 22 feet 71 inches square, and there are eight inferior chambers, four oblong, one on each side, and four square, one at each corner. There is an arched entrance on each of the four sides; but the central chamber is only open on the south side, the other entrances being closed by marble screens. Besides

Ia.

the two principal tombs there are also five others in the corner chambers. The central chamber has its walls lined with marble inlaid with mosaic, and its roof is a sort of flat dome lined with fine stucco work embellished with devices in colours and gilding. The side chambers have plainer mosaic work up to about four feet from the floor, and above that is plaster ornamented with paintings of flowers, the ceilings being profusely gilded. The mosaic work has been to a great extent destroyed by the removal of the inlaid stones, the painting and gilding are also much defaced and tarnished. There is one *inscription* inside the central chamber, dated A.H. 1027, or A.D. 1617, which can hardly be the date of the completion of the building.

III. Opposite to the gateway of Îtimâd-ad-daula's tomb are the remains of the Motî Bâgh and Masjid attributed to Shâh Jahân. Beyond is a great walled enclosure III. known as Nawalganj, but probably this is a corruption of Nawâbganj; as it is said to have been built by Nawâb Sâlât Khân in the time of Shâh Jahân. At each of the four corners is an octagonal tower, and there are high buildings at the centre of the north and south side.

III.

III.

Ш.

III.

Ia.

Hûmâyûn's dilapidated Masjid in the village of Kachpûrwâ claims passing notice; an inscription gives the date of completion A.H. 937, or A.D. 1550. It was built at the expense of the historian Shaikh Zain-ad-dîn of Khawâf, one of Bâbar's literary friends. In front of the masjid are several tombs, amongst which is that of Khwâja Alî, son of Khwâja Mu'in-ad-din Ahmad, dated A.H. 968, and another dated A.H. 986.

To the east of Kachpûrwâ village is the site of Bâbar's Chahâr Bâgh and probably of his garden-palace.

About a mile east is the Achânak Bâgh. Little remains of it except a ruined entrance gate, part of a domed building in the middle of the garden, two ruined towers at the corners along the river front, and a series of vaulted chambers opening on a landing-stage that appear to have been the lower storey of a large palace. The name Achânak is said to be derived from a princess so styled, and it is attributed to the time of Bâbar.

On the river bank facing the Tâj is what remains of the Mahtâb (or Mihtâb) Bâgh. Portions of two ornamental towers built of red sandstone, one of them nearly perfect, stand about 320 yards apart at the corners of the garden along the river front. This garden is supposed to have been the site on which Shâh Jahân intended to build a mausoleum for himself to correspond with the Tâj opposite.

Crossing the river, we come to the buildings in and near the modern city of Agrâ. The fort and the buildings connected with it may be conveniently described first. The fort lies on the right bank of the river about a mile above the Tâj. In shape it is roughly a triangle, having a base half a mile in length along the river bank on the east. The two sides, north-western and south-western, are one rather under and the other just half a mile in length. The apex of this irregular triangle is at the Dehlî gate on the west. These sides, however, are broken by a series of angles, and the total circuit of the fort walls is not less than a mile and a half. The walls are about 70 feet in height, and are surrounded on all sides by a deep masonry-lined ditch or fosse. On the east or river-side the high original rampart is supplemented by a lower outlying wall, outside which runs the fosse. The sides are broken by a series of angles and projecting bastions. The main gateway crossing the ditch by a drawbridge is the

Ia.

Dehli gate on the north towards the city. In the ground-floor chamber to the right of the Dehli gate is an inscription referring to Akbar's march to Khandesh and his return to Agra, in A.H. 1014, or A.D. 1605. Another slightly inferior, called the Amar Singh gate, gives access at the southern angle; there is also a water-gate about the centre of the river front. It is commonly stated that Akbar founded the fort in A.D. 1567; but according to others the actual founder was Salim Shah, son of Sher Shâh, who held power during the interregnum of Hûmâyûn (A.D. 1545-1553). Certain it is that there was an older fort on the site of the present one, which bore the name Badalgarh. It suffered much during the earthquake of A.H. 911, and was nearly destroyed during an explosion that happened in A.H. 962. If this older fort was entirely demolished by Akbar before building the present one, he may be rightly called the founder of the one that now exists. The building was superintended by Kasim Khan, one of Akbar's commanders, and the work took eight years to complete, costing 35 lakhs of rupees.1 There is apparently no building at present in the fort precincts that can be attributed to an earlier ruler than Akbar. The fosse or deep ditch round the fort was made by Aurangzib, and it is believed that the Amar Singh gate is of later date than the rest of the outer buildings.

Crossing the drawbridge at the Dehlî gate, a massive gateway is passed, leading by a paved ascent with two turnings to the inner entrance which is flanked by two octagonal towers of red sandstone inlaid with ornamental designs in white marble and surmounted by two domes. A defaced inscription exists on the east end wall of a guard-house on the right hand under the gateway, of the date A.H. 1008, or A.D. 1599, so that it is just possible the Dehlî gate may have been added by Akbar after he came to reside in the fort, leaving Fathpûr Sîkrî. Underneath is another inscription in adulation of Jahângîr on his accession, dated A.H. 1015, he having ascended the throne in A.H. 1014.

The Moti Masjid occupies higher ground than the rest of the Imperial buildings. Built on ground sloping rapidly from west to east, the floor of the masjid, on a level with the ground on the west, is raised far above it on the east, and thus the eastern gateway is approached laterally from the north and south by two long flights of steps. The buildings of the court of the masjid, too, on the north-east and south, are supported on a series of vaulted chambers, while above them a gallery runs round the otherwise blank exterior wall, giving access to a series of small cells which are underneath the floors of the cloisters within. The mass of the building is thus considerable, and the exterior, faced as it is with plain red sandstone and unbroken except by the chambers and gallery, is somewhat gloomy in appearance. The exterior dimensions are 255 feet east and west by 190 feet north and south. The beauty of the interior, all of white marble, compensates, however, for the dull exterior. Entering the gateway there is a court 155 feet square. To the west is the masjid with a front of 142 feet in length and a depth of 56 feet, supported on a triple row of massive pillars arranged longitudinally, from which spring engrailed or Saracenic arches. The whole is surmounted by three domes, whereof the central is the largest. Interiorly these domes are very shallow. The back or western wall of the masjid is divided into beautiful panels containing sculptured devices. On the southern and northern sides are side chambers opening on the main masjid by two screens of marble lattice-work and an open doorway. These

¹ Blochmann, 'Ain-i-Akbari, page 510.

chambers also communicate by doorways with the cloisters which surround the court on all sides about 11 feet in depth and supported on a series of pillars, more slender in character than those of the masjid itself. The line of these cloisters is broken at the centre of the north and south sides of the court by archways corresponding in appearance to the gateway on the east, from which flights of stairs lead down to the vaulted basement storey below. In the centre of the court is a square tank, and a sundial pillar stands towards the south-east corner. At each of the four corners of the building is an octagonal tower, and there are also two side towers on the central wall, one at each end of the front of the masjid proper, rising above the cloisters. These are surmounted by marble cupolas, while the summits of the archways on the north, south, and eastern gateways are each adorned with three marble cupolas on pillars. The hall of worship is floored with black and white marble, marking out prayer places for 899 worshippers. The pulpit is said to be cut out of one solid block of marble. The general absence of ornament has been remarked upon as the characteristic feature of this masjid. It was built, as we learn from an inscription, between A.D. 1648 and 1655, and is said to have cost three lakhs of rupees.

Leaving the gateway of the Motî Masjid by the southern flight of steps, the road leading to the watergate, a deep paved ramp passing by some of the older buildings and by gloomy passages under the fortification, will be seen on the left opposite the south-east angle of the masjid; while just beyond on the right, you turn into what was a sort of entrance court to the palace building. Westward it communicates by the Mîna Bâzâr with the Dehlî gate, the west entrance to the Mîna Bâzâr being slightly to the south of that gateway.

The Mîna Bâzâr is said to be of Akbar's time, but this is uncertain. It formed the principal approach on this side to the palace, a southern gateway of the entrance court into which it leads, opening directly on the great court of Shâh Jahân's palace. There is a succession of courts connected with the northern entrance, whilst the southern entrance is merely a fine gateway, made up of two archways with a small court between, opening directly on the steep paved slope or ramp leading to

the Amar Singh gate.

III.

Ia.

Ia.

The Dîwân-i-Âm or Âm-î-Khâs, is an open building of red sandstone, with a flat roof supported on engrailed arches springing from four rows of square pillars. The more correct name of this building appears to be Mahal Chihal Satûn, or "hall of forty pillars." It appears to have been built subsequently to the court in which it stands and to the building which it adjoins on the east. It was doubtless intended for the shelter of suitors and the royal attendance when the monarch was seated in the hall of public audience, of which it is a continuation. The eastern or back wall of the hall is the rear wall of the court-yard now called Machchî Bhawân. The lower storey of the latter shows a blank wall towards the hall; but in the upper storey is placed a pair of lattice windows, on each side of the royal gallery. Through these persons seated in the upper chambers of the Machchî Bhawân could look down into the hall. There are also other small lattices higher up, intended to light the remaining upper chambers. In the centre of the hall is the open gallery with three arches in the front, described by Fergusson as a niche for the

¹ Fergusson, History of Indian and Eastern Architecture, 1876, page 590,

throne at the back. As far as can be judged from present appearances, this gallery did not communicate in front with the hall below, where the Emperor is supposed to have sat to administer justice; but a staircase ascends to it through the room with latticed windows on the right or north of the throne. The eastern wall of the great hall is of brick covered with plaster. The royal gallery itself is a pavilion of white marble, inlaid with jasper and cornelian in the form of flowers, ornamented scrolls, and sentences of the *Qurân*. Below it is an immense slab of white marble, on which the Emperor was accustomed to seat himself.

Besides the magnificent gateways to the north and south of the great court, there is also a lesser gateway on the east side, close to the south-east corner, leading into a small court-yard of red sandstone, which in its turn conducts to the court known commonly as the Machchi Bhawân. To correspond to this gateway there is an archway near the south-east angle of the great court.

In the south-west corner of this small court-yard and on the upper storey, not communicating with the court below, but with the upper gallery of Machchî Bhawân, is the Nagîna Masjid, a beautiful little masjid, although somewhat heavy in appearance, of white marble, standing in the centre of the west side of a small court walled in with marble slabs; it consists of three aisles, supported on three rows of short massive square plain pillars, from which spring engrailed arches supporting the roof, which is crowned with three domes. This must have been the private masjid of the palace, and was probably attended by the ladies of the court, as there is a screened passage passing from it by a staircase to the roof of the Dîwân-î-Âm, and so to the harîm; the masjid itself, too, is quite shut in from outer views. The tasbîh-khâna, however, of the masjid is an open gallery of white marble, overlooking the small court-yard. On the east of this court-yard is a staircase conducting to some old apartments of the palace of which little is known, while the gateway leading to the Machchî Bhawân is at the south-east angle.

The Machchi Bhawân court-yard has a tank in its centre and a series of chambers surrounding it on the north, south, and west sides; a roofed gallery or colonnade runs round the upper storey on a level with the Diwân-i-Âm, Dîwân-i-Khâs, and the Nagîna Masjid, and communicates with them. This court-yard is of red sandstone, and its dimensions are about 150 feet east to west by 200 feet north to south. From its position it may have formed the ante-chamber or waiting-room for nobles who had the right of entrance to the hall of private audience; for its east side is formed by the raised terrace or platform in front of that building. A flight of steps from Machchi Bhawân leads to this platform, which is on the same level as the upper gallery of that court. To the south are the royal baths, to the east the platform overlooks the river, a long railing or screen of marble alone guarding the edge, which is that of the inner or main wall of the fort.

In the centre of this east side on a slightly raised platform of white marble is placed the black marble throne of Jahângîr, a large slab of marble, in length 10 feet 7½ inches, in breadth 9 feet 10 inches, and in thickness 6 inches, supported on octagonal pedestals 1 foot 4 inches high. Round the edge of the throne runs an inscription in embossed characters, dated A.H. 1011, or A.D. 1602, three years before Akbar's death, and it consists only of praises of Sultân Salîm, son of Akbar,

Ia.

Ia.

Ia.

better known as Jahangir. Three other short inscriptions are engraved in the stone; but they are of later date, and were added after Jahangir's accession. Opposite to the black marble throne, on a similar pedestal, at the edge of the platform overlooking the Machchi Bhawan, is a similar throne of white marble.

Ia. On the south side of the platform stands the Dîwân-î-Khâs, or private hall of audience. It consists of a hall 64 feet 9 inches in length by 34 feet in breadth and 22 feet in height, opening by three arches on a portico in front and with three arched recesses to correspond on the opposite side. At the ends are two arched recesses. A small doorway at the south-east corner gives private access to the royal apartments. Above the three arches on the north and south are three small lights or lattice windows filled with screen-work. The portico in front is about the same size, and is a lofty colonnade with flat roof supported on engrailed arches springing from slender pillars arranged in pairs. At the corners there are four, at the sides three, and in the front five, openings between the pillars. Three short flights of steps lead from the level of the portico to the platform in front. An inscription runs along the frieze of the colonnade, giving the date of the building as A.H. 1046, or A.D. 1637.

At the corner of the southern upper gallery of Machchi Bhawan, abutting on the Dîwan-î-Khâs, will be found a doorway to the south from which a passage to the right leads up to a tiny masjid squeezed in amongst the buildings. This masjid is very plainly built of white marble, but the court in front is beautifully paved with alternate squares of marble and jasper. The passage to the left leads past a tasbih-khâna facing the back wall of the Dîwân-î-Khâs, and then downstairs to a small court on the east of the Dîwân-i-Khâs communicating on the south with the main harîm court, of which it is an offshoot.

Ia.

Ia.

Ia.

The main wall of the fort here takes a turn outwards, so as to project beyond the eastern parapet of the platform in front of the Diwan-i-Khas. On the bastion at the east side of the court stands an octagonal marble and inlaid pavilion of great beauty overlooking the river with an upper open storey of red sandstone surmounted by a cupola, commonly known as Saman Burj. The pavement of the court is arranged in squares of coloured marble for the game of pachisi. The ladies' baths and other offices of the palace open on it on the north. A marble screen runs round it on the river-side and another divides it from the main harim court. This court is 175 feet by 235 feet, and the whole finished with the utmost care. The three white marble pavilions overhanging the river are situated on a raised platform of white marble on the east of the court, with a tank for fountains in front of the centre or principal building. This is often called the Khas Mahal and by some the Aramgah. This is a very beautiful building consisting of a noble hall about 70 feet by 40 feet, with a colonnade or portico of the same size in front, standing on a raised platform. The colonnade has five openings to the front and three on each side, its flat roof is supported on engrailed arches springing from massive square pillars to the front. On the sides there are only half pillars; the hall opens on the colonnade by three arches, and on the opposite or west side are three archways, with windows overlooking the river. North and south at the ends are arched recesses in which are doorways leading to the side pavilions. The side walls arch up into a flat oblong ceiling, all of which as well as the south portion of the walls has been covered with beautiful paintings. This Ia.

Ia.

was no doubt the State Hall, or drawing-room of the ladies of the palace. The smaller pavilion on the north communicates with the Saman Bûrj, while that on the south is connected with a series of apartments in the south-eastern corner of the court, in style somewhat different from and superior to the other apartments surrounding the court and separated from the rest of the court by a kanût, or screen wall made of slabs of white marble placed along the edge of the platform. This may have been the Emperor's own most private chambers, or the principal Sultâna's. Some say the apartments are those of Jahân Ârâ Begam, Shâh Jahân's favourite daughter, also known as Sulţâna Begam. A similar screen encloses the north-eastern pavilion. The northern side of its court-yard is formed by the portico with screens in two or three openings, leading to the Saman Bûrj court and some marble chambers.

In. The ladies' baths alluded to as the Shish Mahal, are in the lower storey at the north-east corner of the court. The sides and ceilings are spangled over with tiny mirrors of irregular shape set in plaster. Many of these have come away, but enough is left to show the picturesque effect when the interior is lighted up. The east or river-side of the harim court being composed of the marble pavilions, with the terrace in front, the other three are made up of the women's apartments, built round the court in two storeys, a gallery running round on the level of the upper storey. These buildings are of red sandstone, and may perhaps be of Akbar's time; but there are some chambers floored and half-panelled with white marble on the north of the west side; these are possibly baths.

There is a small marble tank below the terrace of the Khâs Mahal on the east and the usual division by four paved walks running from a platform in the centre. This platform and the walks are of white marble. The beds are divided into numerous small compartments by ridges of red sandstone curiously arranged. The only main entrance to the court is through a low narrow gateway or passage under the upper storey at the south-west corner. There are also passages on the south side communicating with the adjoining palace known as Jahângir's.

Two doors underneath the platform of the Khas Mahal lead to staircases, communicating with an extensive series of underground passages and chambers running along the inside of the fortification wall and lighted by slits therein.

Adjoining Shâh Jahân's palace on the south is the Jahângirî Mahal. The exact age of this building is somewhat doubtful. It is very Hindû in character, much resembling the Jahângîrî Mahal at Faṭhpûr Sikrî, and may very probably have been built by Akbar towards the close of his reign, and appropriated as the separate residence in the fort of the heir-apparent and his family. The gateway leads by a vestibule to a domed entrance hall, whence a corridor, first to the right and then straightforward, leads to the principal hall, 62 feet 8 inches by 35 feet 2 inches, of almost purely Hindû design and almost as elaborate and elegant in design. The principal hall on the north is remarkable for its flat ceiling supported by stone struts with dragons or serpents, one carved on each, longitudinally. There is a gallery running round the top of the hall. The lesser hall on the south is about 52 feet by 29 feet, and round it runs a passage divided from it by a wall in which are latticed screens looking on to the hall.

On the west of the court, over the entrance hall in the third storey, is an open hall with three openings on each side, east and west overlooking the court, with very fine pillars and brackets.

To the right of the entrance hall is a passage leading to a small separate court, perhaps the principal queen's private lodging, with a pillared hall containing a musicians' gallery.

From the court a narrow court-yard, with sets of chambers apparently intended for the servants, runs along the back of the south wall of the main court-yard. All around this main court-yard there runs a gallery on the upper storey. To the east are a set of chambers communicating with the long narrow court-yard overlooking the river. The central entrance to it is by a porch supported on pillars, about 17½ feet in length, including base and capital, of remarkably beautiful and singular design. Two wings of the building north and south project eastwards. Above on the roof of these wings were two beautiful open pavilions with canopy roofs supported on pillars, the southern one has been bricked up, but the northern one is intact. There are 20 pillars in all, six on the east and west and four on the north and south sides. They are massive, but not lofty, and have bracket capitals that meet together, and thus form a support without any arch.

Close to this is a set of tanks to which water was raised by a series of lifts from the most or river below, and there are still traces of the water-courses. From these the various baths, tanks, and fountains of the palace were supplied, as may be seen from the names *inscribed* on the wall over the head of each supply-pipe.

The court-yard is bounded by a wall on the east in which were occasional latticed windows or doors, and at each corner an occasional tower surmounted by a domed cupola. The whole of this palace is remarkable for the Hindû character of the architecture, for the roofs, brackets, projecting eaves, carved panels, recesses, and pillars; the entablature of the main court is especially noticeable. The whole is in red sandstone and that of perishable description, so the finer work is wearing away. Most of the apartments are panelled with sandstone engraved with devices and patterns; but in some cases stucco or plaster, covered with paintings or moulded into patterns, has been employed.

There are no more buildings worthy of notice within the fort; but it may be as well to mention here the great stone vessel known as Jahângîr's bath which lies close to the tank in the cantonment gardens. It is a large bowl-shaped bath hewn out of a single stone of light-coloured porphyry or granite, in height about 4 feet 8 inches exterior, 4 feet deep inside, 8 inches in diameter at top, and 6 feet 8 inches at bottom, the edge about 6 inches thick. There are steps on the inside and outside. Ornamental compartments containing an inscription of five distiches run round the bowl on the exterior near the upper edge. The inscription is partly defaced, but mentions "Jahângîr, son of Akbar," and has the târikh A.H. 1019, or A.D. 1610. The bath was originally in Jahângîr's palace, then in the great court of Shâh Jahân's palace, whence it was removed to its present situation.

Though the so-called Sômnâth gates are in no sense an antiquity of Âgrâ, it is as well to notice that they will now be found in the harim court. They formerly stood in the great hall, when it was walled up and used as an armoury. They were

Ia.

brought from Ghaznî in 1842 and conveyed in the train of the Governor-General, Lord Ellenborough, from Fîrûzpûr to Âgrâ, but never proceeded further on their way to their proclaimed destination, Sômnâth. It seems certain that they are not the gates of the temple of Sômnâth at all, but may be those of the tomb of Sultân Mahmûd at Ghaznî.

Ia. Outside the Dehlî gate is an enclosure intended for and used as a market, called the Tripoliâ. It forms a sort of entrance court to the Dehlî gate, and is said to have been added by Shâh Jahân for the accommodation of traders. It was octagonal in shape with shops on all sides except on that of the fort ditch. There are three arched gateways to the south, south-west, and north-east.

Beyond the Tripolia to the north-west close adjoining is the great masjid, or Jâmi Masjid. This is a masjid of Shâh Jahân's reign, and from the inscrip-IIb. tion appears to have been built between the years A.H. 1053 and 1058, or A.D. 1644 and 1649. The masjid is said to have been originally called Masjid Begam from the fact that Jahân Ârâ Begam, Shâh Jahân's daughter, made herself responsible for its construction, which was completed at a cost of five lakhs of rupees. The name was subsequently changed to Jâmi Masjid, it being the great or principal masjid of the city. The masjid is built of red sandstone, and consists of a large court placed on a platform raised about 11 feet above the ground. The masjid proper is to the west of the court; it is a large building 130 feet long by 100 feet broad, supported by two rows of arches and with five openings or archways to the front, one principal and two interior on each side. Four octagonal domed cupolas stand one at each corner of the roof, a row of smaller square cupolas adorns the front, and four slender shafts or minarets rise from the four corners of the roof of the central compartment which is more elevated than the rest. The roof is surmounted towards the rear by three large domes of somewhat peculiar shape. full bottomed, which have been compared to balloons reversed and of remarkable pattern, the courses of masonry being zig-zag and alternately of red sandstone in wide bands, and narrow lines of white marble. Cloisters with flat roofs supported on pillars meeting in engrailed arches run along the northern and southern sides of the court, but are broken at the centre of each side by archways through which flights of steps give access to the masjid. The eastern side was similarly closed with a cloister, and the eastern gateway was the principal and most imposing; but this gateway and the eastern cloister were destroyed in 1857. On the northern, eastern, and southern sides there are rows of shops on the outside underneath the cloister.

Half a mile below the fort is a ruin generally known as the Rûmî Khân's havelî. Here are the extensive remains of a large palace of red sandstone with a river wall terminating in two towers or cupolas. It is said to have been the residence of Islâm Khân Rûmî, who is said to have been one Husain Pâsha of Basra and subject of the Sulţân of Turkey; he deserted the Sulţân's service and rose high in the service of Jahângîr, attaining the title of Vazîr Islâm Khân.

III. All along the river bank to the Tâj are ruins of old palaces, gardens, &c.; one considerable ruin on the water's edge is known as Shish Mahal, and also as III. Dêorhî Sâhibjî; here was Mahâbat Khân's house.

Beyond and close to the burning-ghất is a shrine known as Dargâh Jalâl-IIb. ad-dîn Bukh âri, said to have died A.H. 1057 in Shâh Jahân's time. Here were the palaces of Râjâ To daramalla and Râjâ Mân Singh.

Between the burning-ghâț and the Tâj lies an extensive garden with a water-side

Ia. building known as Bagh Khan Alam.

Outside the western entrance of the Tâj outer quadrangle stands a masjid of red sandstone on an elevated platform; this is called the Faṭhpūrî Masjid, and is said to be of the same date as the Tâj itself. It consists of a central compartment, supported on two rows of arches, and surmounted by a dome of the same shape as that of the Tâj, and on each side two compartments with flat roofs supported on double rows of pillars meeting in engrailed arches.

On the opposite side to this masjid is an octangular domed building of red sandstone rather low placed on a wide and elevated platform with rows of arcades underneath. The building contains two plain tombs of white marble, and is known as

Sahelian-ka-gumbaz.

Ib.

Ia.

The Taj Mahal, often called Rauza, or Taj-ka-Rauza, is situated on the right bank of the Jamna about a mile and a half below the fort. This great mausoleum which has been classed among the "wonders of the world" was built by the Emperor Shah Jahan in honor of Mumtaz-î-Mahal, "exalted one of the palace," the title of his favourite wife whose proper name was Arjmand Banu Begam or Nawab Alîya Begam. Like the tomb of Akbar, it stands in a large garden enclosed by a lofty wall of red sandstone with arched galleries round the interior and entered by a superb gateway of sandstone inlaid with ornaments and inscriptions from the Quran in white marble. Outside this grand portal is a spacious quadrangle of solid masonry with an elegant structure intended as a karavansarai on the opposite side. The raised platform on which the Taj stands is 18 feet high, faced with white marble, and exactly 313 feet square. At each corner of this terrace stands a minaret 133 feet in height, and of exquisite proportions, more beautiful than any other in India. In the centre of this marble platform stands the mausoleum, a square of 186 feet with the corners cut off to the extent of 33 feet 9 inches. The centre of this is occupied by the principal dome, 58 feet in diameter and 80 feet in height, under which is an enclosure formed by a screen of trellis-work of white marble, a chef d'œuvre of elegance in Indian art. Within this stand the tombs, that of Mumtaz-i-Mahal in the centre and that of Shah Jahan on one side. In every angle of the building is a small domical apartment of two storeys in height, 26 feet 8 inches in diameter, and these are connected by various passages and halls. The light to the central apartment is admitted only through double screens of white marble trellis-work of the most exquisite design, one on the outer and one on the inner face of the walls. This building, too, is an exquisite example of that system of inlaying with precious stones which became the great characteristic of the style of the Moghals after the death of Akbar. All the spandrils of the Taj. all the angles and more important architectural details, are heightened by being inlaid with stones such as agates, bloodstones, jaspers, and the like. These are combined in wreaths, scrolls, and frets, as exquisite in design as beautiful in colours; relieved by the pure white marble in which they are inlaid, they form

III.

IIb.

Ш.

the most beautiful and precious style of ornament ever adopted in architecture. This mode of ornamentation is lavishly bestowed on the tombs themselves and the screens that surround them, though sparingly introduced on the masjid that forms one wing of the Tâj, or on the fountains and surrounding buildings. The judgment indeed with which this style of ornament is apportioned to the various parts is almost as remarkable as the ornament itself, and conveys a high idea of the taste and skill of the Indian architects of that age.

IIIb. The masjid with three domes of white marble occupies the left wing and has a counterpart (javab) in a precisely similar building on the right hand side of the Tâj. This last is sometimes called the false masjid; but it is in no sense dedicated to religious purposes. On the pavement in front of the false masjid (javab) will be traced a representation of the brass ball, crescent, and spike which cap the dome of the Tâj.

The following dates of inscriptions found on the Tâj seem to show the order in which the various parts of the buildings were completed: on the outside of the west arch facing the masjid A.H. 1046, 10th year of Shâh Jahân's reign; at the end of the inscription on the left hand side of the entrance within, A.H. 1048; and on the front gateway A.H. 1057, or A.D. 1648. The last marks the completion of the building. The inscriptions on all these arches are in Tughrâ characters, taken from Sûras of the Qurân, appropriate to mourning and spiritual hope. On the front of the entrance is a passage ending with an invitation to the pure of heart to enter the garden of paradise. On the tomb of Mumtâz-i-Mahal is an inscription, dated A.H. 1040, and on the tomb of Shâh Jahân A.H. 1076.

III. Close to the Tâj on the east bank of the river are the remains of a large palace and walled garden, known as Triyâl or Tiliyâr-kâ-Baghicha, and said by some to be Mahâbat Khân's.

A little lower down are the remains of a large water-side palace; the red sandstone wall, Lâl Dîwâr, and a fine bastion or tower are still standing.

III. A little inland is a large pile of ruins; this is all said to have been a residence (haveli) of Nawab Khan, Dauran Khan Vazir Azam.

Close by is Ahmad Bukhâri's dargâh. There is a tomb resembling those in the corner courts of the outer quadrangle and a small masjid just outside the east gateway of the Tâj outer quadrangle; and in Basâi there is a tomb known as Rauza Dîwânjî.

Between Tâjganj and the south-eastern extremity of cantonments is a large walled Ia. enclosure called Bâgh Mahâbat Khân.

There are not many noticeable ruins about the cantonments. South of them lie Ib. Takht Pahlwân and Rauza Fîrûz Khân. The former name is given to a small village built close round a mausoleum supposed to be that of some wrestler of Imperial times. The name takht is given in consequence of there being a large slab of stone, 8 feet square, lying in the fields 100 yards to the west, called Takht Pahlwân. The mausoleum is a square building of red sandstone with four arched doorways and surmounted by a dome placed high on a platform supported on arches with four domed cupolas supported on pillars at the corners.

Ib. The tomb of Fîrûz Khân is supposed to be that of the eunuch of the palace to Jahângîr who built Fîrûzâbâd. There are here the remains of a large masonry tank from which the village surrounding the tank and tomb is called Tâl Fîrûz Khân; the village lies mostly within the octagonal walled enclosure of the tomb. The mausoleum is an octagonal domed building of red sandstone standing on a high raised octagonal platform underneath which is a dome roof crypt containing the remains of two tombs. On the east of the platform is a lofty portal of red sandstone, the face of which is most elaborately carved; so, too, is the whole of the interior of the main building, and also adorned with glazed coloured tiles and enamelling. The mausoleum is a large and beautiful one, and the ornamentation is Hindû in character; if built in honor of Fîrûz Khân of Fîrûzâbâd it would be of Jahângîr's time.

The dargâh known as Makhnî (or Magdî)-kâ-gumbaz consists of one central chamber with a shrine for offerings much like a Hindû temple and two side-chambers. In front is a wide and lofty portico or verandah closed at the ends and supported on four pillars. The wide eaves of the portico are supported by brackets, shaped to resemble elephants, peacocks, horses with riders; a similar ornament figures in the windows over the doorway of the chamber. The building is in fact very Hindû in character, hardly such as would be erected over a Musalmân saint or martyr. A suggestion has been made by Mr. Carlleyle¹ that this building formed part of a colonnade running all round the great Dêhra Bâgh which lay here. The history of the bâgh is uncertain, but it is by some ascribed like Zahara Bâgh near Râm Bâgh, to Zahara, daughter of Bâbar. The bâgh is also known as Bâgh Nûr Manzîl.

III. Near the village of K h wâja-kâ-Sarâî will be found the ruins of the Jôdh Bâî Mahal; this is a complete ruin. The mausoleum would appear to have been about 80 feet square with a vault underneath. It was the tomb of Jôdh Bâî, probably the Râjpût princess of Jôdhpûr whom Jahângîr married.

IIb. The Îdgâh is situated about one mile from Tripôliâ. This building stands at the west end of a great walled enclosure about 570 feet in length by 530 feet in width, having an octagonal tower at each corner and principal entrance gateway in the centre of the east side. The masjid itself is built of red sandstone, and is about 160 feet in length by 40 feet in breadth. There are five arched openings to the front supported on six pillars, the centre arch being loftier than the rest. Two slender shafts rise from the west wall of the central compartment to a considerable height. There is no inscription on the building, but it is said to be of Shâh Jahân's time.

Towards the city there will be found close to the Chhipitôlâ what are known as hammâm Allah Vardî Khân, or "baths of Allah Vardî Khân." The entrance of these is by a fine arched doorway faced with red sandstone, ornamented with carving in relief and with a Persian inscription over the doorway, from which we learn that the baths were built by Allah Vardî Khân in the reign of Jahângîr, in A.H. 1030, or 1620 A.D. Adjoining the baths on the east is a large court-yard entered by an arched gateway and surrounded with sets of chambers in two storeys.

In mahallâ Darbâr Shâhji will be found the dargâh, or masjid and shrine of Shâh Wilâyat. This building is not remarkable for its size or architecture, but rather for its antiquity and the traditions connected with it. It is a low building, in dimensions about 46 feet by 19 feet, plainly built of brick and plaster with three

IIb.

⁴ Cunningham, Archeological Reports, Vol. IV, page 110.

arched entrances on the east, and crowned with three domes in the style of transition from Paṭhân to early Moghal architecture. The central arch, the loftiest of the three, is but 5 feet 8 inches in height, and the whole building bears the appearance of having sunk into the ground up to the opening of the central arch, thus losing probably two-thirds of its height. With this sinking is connected a legend. It is said that when Shêr Shâh came to Âgrâ he allowed his camel-driver to stable camels in the masjid; this act of desecration evoked the curses of the faqîr of the masjid, Shâh Wilâyat, whereupon the masjid sank, enclosing and killing the camels. This legend makes the masjid at least as old as Shêr Shâh's time, and it is confirmed by the inscription on the Shâh's tomb, an octagonal mausoleum with a dome supported on eight pillars, close to the masjid, which gives the date of the faqîr's death as A.H. 953, the first year of Salîm Shâh's reign. Connected with the masjid are a series of cloisters, perhaps an old monastery (khânqâh).

IIb. The Akbarî Masjid is situated close to the chauk; it was built by Akbar, but was entirely restored about 1856. The building is of red sandstone and in dimensions about 84 feet by 20 feet. There are seven arched openings to the front, and the flat roof is supported on three rows of eight columns, the spaces between the columns on the south, west, and north being closed up by walls. A single dome showing only slightly inside, surmounts the eastern half of the central compartment where the mimbar stands. The roof is further relieved by four cupolas with domes supported on eight shafts, one at each corner. A paved court is in front of the masjid overlooking the street below.

In mahallâ Bâgh Hîramân is what is generally called Kâli Masjid, the IIb. proper name of which is not improbably Kalan Masjid, "the great masjid." This masjid has a very antique appearance, and has been conjectured to be as old as Sikandar Lôdi's time, which would make it quite the oldest in Agra. It is traditionally ascribed to Muzaffar Husain, grandson of Ismâil Shâh Sûfi, king of Persia, and father of the wife of Shâh Jahân, buried in Khandhâri Bâgh. If this be true, the masjid is much less ancient than it looks. In dimensions it is about 128 feet by 34 feet, and is plainly built of brick and plaster; the east front has been faced with sandstone, but most of it has fallen off. There are five compartments with arched openings to the east, and the building is crowned with five domes, of which the centre is considerably larger than the rest; similarly, the central arch rises higher than the rest, and the pediment partially conceals the dome. The domes are of the low transitional shape, rising without any bulge outwards from perpendicular basis; they are black with age, hence perhaps the name Kali Masjid. The courses of masonry in the domes are horizontal, and the whole building is of old Hindû bricks, larger and flatter than those generally used in masjids. There is a large pavement about 130 feet by 190 feet in front of the masjid, and connected with it are a school of the same period and a tasbih khana with low hemispherical domes.

Not far off is an ancient hammam, or bath of the same period, a lofty building about 60 feet in length by 34 feet in breadth, and surmounted by a large, but low, hemispherical dome.
 The masjid of Matamid Khān lies on the south side of Washershiller.

The masjid of Matamid Khan lies on the south side of Kashmiri bazar. The founder of this masjid, from whom it takes its name, was a bakhshi or treasurer to

the Emperor Jahangir. The masjid is built of red sandstone, and is in dimensions about 53 feet by 20 feet; it has three arched openings to the east front, the middle one slightly larger and higher than the others. The carving of the stone on the front is somewhat florid, the roof is crowned with three domes, rather low and flat in shape, covered with white plaster, and there are five octagonal cupolas, one at each corner of the roof.

In the outlying mahalla of Loha-ki-Mandi will be found the eunuchs' masjid, Hb. Masjid Makhan Nishan, or Hijron-ki-Masjid. This is a very elegant though not large masjid, built of pale red sandstone, and crowned with three domes of solid stone. In dimensions it is about 51 feet by 20 feet; and is made up of three compartments, of which the centre is the principal. There are three arched openings on the front or east, and two doorways in the north and south walls. In the rear or west wall of each of the side chambers, at about 51 feet from the floor, are the windows filled with beautiful stone lattice-work. At each corner of the front of the masjid is an octagonal tower, and in front of it is a large raised masonry platform 83 feet east to west and 95 feet north to south, with a tank 19 feet square in the centre, and octagonal towers at each corner. The legend of the masjid connects it with Akbar's times, it being related that the advice of a saintly eunuch, by name Yatima, was sought by Akbar in the time of drought, when the prayers of other righteous men had failed. The eunuch's prayers brought rain, but he refused to take a reward, till, on being pressed, he suggested the erection of a building which should perpetuate both his name and the Emperor's. There are no other buildings of note within the city.

Proceeding northwards from the city by the road from Bêlanganj to Balkesvar, there will be observed the remains of several gardens along the river bank opposite to Chini-kâ-Rauza, Zahara Bâgh, and Râm Bâgh. Amongst these are the following gardens: Bâgh Râi Shêo Dâs, from a nàib sùbadàr of Âgrâ in the time of Muhammad Shâh; Haqîmjî-kâ-Bâgh, or the garden of Haqîm Karîm Ali Khân, and a still better known as Rauza Jâfar Khân from a mansabdâr of two thousand in the time of Shâh Jahân. The last is a large walled river-side garden with towers at each corner; in the centre is a mausoleum, a large rectangular building on an elevated platform, one storey in height and flat roofed.

Proceeding further up the river, just below the village of Râjwarêo, will be found the Chhattri Râjâ Jaswant Singh. In the centre of a walled garden enclosure stands a square building of red sandstone, with a flat roof supported on pillars. The entire space between the pillars is filled with open lattice-work in stone of varied and beautiful patterns. Access is gained to the interior on the east or river-side by folding doors of solid stone slabs. The main doorway of the enclosure is in the centre of the river-side wall, and here a flight of steps leads to the edge of the river. The exterior wall towards the river is faced with red sandstone beautifully carved in relief with figures of long-necked vases and wreaths of flowers. The whole is in good preservation, and is a conspicuous object from the Râm Bâgh on the other side of the river. Râjâ Jaswant Singh of Jôdhpûr, the great ally of Dârâ Shikôh in his earlier and more successful days, died in Kâbûl about 1677 A.D., in the reign of Aurangzib, and it is therefore scarcely likely that his body was burnt here.

III.

Still further up the river near the temple of Mahâdêva Balkesvar is the traditional site of Mahal Râjâ Bhôja, but what Râjâ Bhôja it was, is doubtful.

III. Bâgh Lâdli Begam near the temple of Sîtalâ, is a large enclosure, about 112 yards square, surrounded by a lofty wall of red sandstone with crenelated battlements, and with towers at each corner. In the centre of the south side is a lofty arched gateway, somewhat resembling the style of Fathpûr Sîkri, and similar arched buildings and false gateways stand at the entrances of the other three sides. In the centre of the enclosure now stands a Hindû Chhattri, or pavilion erected some few years ago by the Mathurâ Sêths, the present occupiers of the garden. Here stood the tomb of Lâdli Begam, and it is also said of Shaikh Fâizî. The lady was the sister of Fâizî and Abûl Fazl, and wife of Islâm Khân, grandson of Shaikh Salim Chhishti, and Governor of Bengal under Jahângir. She died in A.D. 1608; but the Arabic inscription over the gateway shows the building to have been erected some years before in A.H. 1004, or A.D. 1596 during Akbar's reign.

Ia. Not far from the gateway is a remarkably fine bâolî or large well with staircases leading down to the water, and with underground chambers in three storeys or galleries round it.

III. There is not much to notice in the Kandhâri Bâgh, a large walled enclosure with domed cupolas at the corners, the building in the centre of which was originally the tomb of one of Shâh Jahân's queens, a daughter of Muzaffar Husain, grandson of Ismâil Shâh, king of Persia.

At no great distance west of Lâdli Bâgh and Kandhâri Bâgh in the fields north of Ib. the Sikandrâ road, is supposed to be the tomb of Sâdik Khân, Akbar's spiritual guide. This is a large and lofty octagonal building placed on a raised platform and surmounted with a dome. In the centre of each side is a recess with engrailed arch, and above each is a tier of three engrailed arched windows flanked by two square-topped doorways.

Ib. To the west of this stands on a raised platform a square open hall, supported on 64 pillars in six rows each way, the outer rows doubled and the corner groups quadrupled. The building is flat roofed and of red sandstone. At the corners of the platform are square-domed cupolas supported on four pillars; the ceilings are ornamented with paintings of flowers on polished stucco. This unique hall has been identified with the tomb of Salâbat Khân was bakhshi to Shâh Jahân, and is said to have been killed in darbâr by Amar Singh Râțhor, after whom the Amar Singh gate of the fort is named.

Ib. Opposite to the stone-horse on the Sikandrå road, about four miles from Ågrå, is the lofty arched gateway of an ancient saråi, said to be that of Îtibâr Khân Khwâja.

North of this is a large well, and south-west at a short distance a building said to Ib. be the tomb of Îtibâr Khân, but probably that of Sikandar Lodî. The building stands on a large platform about 110 feet square, supported on eight arched vaults on each side, and with domed cupolas on four pillars at each corner. The building has originally been an open bâradari, but is now walled up. The roof is surmounted with one principal dome in the centre and four inferior ones at each corner.

At a very short distance from this on the west is a very fine masonry tank partially Ib. in ruins, also said to be Îtibâr Khân's, but more commonly known as Guru-kâ-Tâl. The tank is about 180 yards square, and of considerable depth. On the south side, near the south-east angle, is the canal that feeds it with a small subordinate tank for collecting the water, and there appear to have been overflow outlets on the west.

The ancient remains at Agra of the præ-Musalman period are very few. Outside the water-gate of the fort of Agra, between the fort and the river, several square pillars of black basalt have been unearthed as well as a very massive and elaborately sculptured statue of black basalt representing Munisuvratanatha, the twentieth Jain Tirthankara, with a dedicatory inscription in Kutila characters, dated Samvat 1063, or A.D. 1006. There can be no doubt that these pillars formed the colonnade to the entrance, from the river, of some ancient Jain temple which was probably pulled down and destroyed when the fort was built.

To the south of the present fort, exactly opposite the Amar Singh gate, are the traces of a large mud fort of the early Hindû period.

3. Bâн, head-quarters of tahsîl Bâh Pinâhat, 45 miles S.-E. of Âgrâ, lat. 26°-52′-30" N., long. 78°-38′-13" E., has four gateways, but no gates, and the houses are so built as to form a fairly perfect circuit wall. Tradition ascribes the origin of Báh to Kalyân Singh, Rájā of Bhadâwar, who lived towards the close of the seventeenth century. He built a residence here and a garden called after his own name.

Another Râjâ, Bakht Singh, founded the temple of Thâkur Madan Gôpâl in the year IIb. 1752 A.D.

 BAŢĒŚAR,¹ village in tahsîl Bâh Pinâhat, 41 miles S.-E. of Âgrâ, lat. 26°-56′-22″ N., long. 78°-35'-9" E. The name of the village is derived from Sanskrit vata, "the banyan tree," near which was an image of Mahâdêva under the title of Vaţêśvaranâtha. The importance of the place would seem to date from the time of Badan Singh, Râjâ of Bhadâwar, who lived about the beginning of the seventeenth century. He built the temple of Mahâdêva under the title of Vaţêsvaranâtha in Samvat 1703,

or A.D. 1646. The cluster of 170 temples, large and small, on the bank of the Jamna form a crescent, and are mostly in honor of Mahadeva under different names, built from A.D. 1725-1762. The remains of a fort built high up in the ravine and of a III. residence constructed by the Rajas are still standing.

Close by are the ruins of the ancient town Sûryapura, represented by the two mounds called Purana Khera, or "former city" and Aundha Khera, or "overturned city." Traces of numerous temples, buildings, a small fort, and large bricks are still visible. The summit of the Purana Khera is covered by a group of seven modern Hindû temples dedicated to Pârvatî, whilst that of Aundha Kherâ is covered by five small square-domed Jain temples of comparatively recent date.

5. Bîrгнала, village în tahsîl Khairagarh, lat. 26°-55' N., long. 78°-41'-8" Е., 18 miles south of Ågrå, possesses an ancient temple dedicated to Mahådêva Lîla IIb. Vilâsa.

6. FATHÂBÂD, tahsîl, lat. 27°-1′-30" N., long. 78°-20′-30" E., 21 miles S.-E. of Âgrâ, was originally a large Hindû village, and in the Musalman period named Zafarnagar. Its name was changed to Fathabad by Aurangzib, after his victory over his

III.

Ш.

IIb.

III.

IIb.

¹ Canningham, Archeological Reports, Vol. IV, pages 221-247.

Ib.

brother, Dârâ Shikôh at Samonghar in A.D. 1638. He built a masjid on the spot on which he rested after his victory, and called it Mubârak Manzîl; he also constructed a sarâî, a tank, and planted a large grove to the south-east of the town.

- Ia. The Mubârak Manzîl is a large rectangular building of an oblong shape, 171 feet in length by 84 feet in breadth, exclusive of the projections of the towers at the corners. It has a fine octagonal tower at each corner, each of which is surmounted by a pillared cupola which rises above the roof of the building which is three-storeyed. There is a beautiful colonnade on the east side of the building composed of fluted pillars, with engrailed arches rising from and between them. Within the building, towards the middle of its inner west side, there is a compartment which is said originally to have been used as a masjid.
 - 7. FATHPÜR SİKRÎ, tahsil, and former capital of the Moghal Empire, lat. 27°-5'-38" N., long. 79°-42'-7" E., 23 miles W.-S.-W. of Agrâ. The modern town of Fathpur lies to the south-west of the ruins and palaces, and the village of Sikri to the north-east; but both are within the old bounds wall built by Akbar, which has a circumference of about seven miles. The village of Sîkrî was called Fathpûr by Akbar in memory of his conquest of Gujarât. The site may be described as an oblong measuring a mile in length and three-fourths of a mile in width. Its northern margin is bounded by a wide sandstone ridge from one to two hundred feet in height, its remainder is bounded on all sides by a battlemented stone wall 20 feet high, pierced by 12 gateways. The wall with its towers stands up bravely, but ruinous parts threaten a speedy downfall. The buildings of the Court which now remain occupy the ridge with Salim Chhishti's tomb in the place of honor at the highest point; but evidences are not wanting to show that formerly the wide, fairly level expanse enclosed by the wall was laid out in pleasure-grounds containing pleasant gardenhouses of which only traces remain. The modern town of Fathpur Sikri occupies the western end only of this large enclosure, on the level below the ridge, and partly on the ridge where the houses rise up to meet the great flight of steps leading to Salim Chhishti's dargah which overshadows the town.
- The buildings of Akbar's capital are a magnificent pile constructed during 15 Ia. years from A.D. 1571 to 1586. The dargah of Salim Chhishti and the masjid adjoining it in the same enclosure is the most important. The entrance to this enclosure is by a lofty gateway, the Baland Darwâza, reached from the foot of the hill by along flight of steps, and raised 130 feet above the plateau on the edge of which it stands. Fergusson has given an eloquent description of this masjid, remarking "that it is hardly surpassed by any in India." The measurements of the enclosure according to Fergusson are 550 feet east and west by 470 feet north and south over all, the quadrangle or court of the dargah is 433 feet by 366 feet. The masjid which occupies the west side of the court and is crowned by three domes, is 290 feet by 80 feet. Upon the main arch is a chronogram, "this masjid is the duplicate of the holy place" which gives the date A.H. 979, or A.D. 1571. The wings of the masjid are of red sandstone with lofty square pillars; but the centre is a vast vaulted hall

¹ Proceedings, Aslatic Society of Bengal, for 1874, pages 174, 175.

^{*} Fergusson, History of Indian and Eastern Architecture, page 579.

of assembly, paved with white marble, and painted about in white and delicate tints in a variety of geometric patterns.

Behind the masjid is the tomb of an infant alleged by tradition to have been the still-born child of Akbar, for which the saint Salim Chhishti substituted one, who became Prince Salim. Near this is a door purporting to lead to the cave where the saint originally lived, and the small masjid said to have been built for him by the stone-cutters.

Ia. To the left of the masjid in the court-yard there are two tombs, that of Salîm Chhishti, wholly in white marble, and the windows with pierced tracery of the most exquisite geometrical patterns. It possesses, besides, a deep cornice of marble supported by brackets of the most elaborate design; the other tomb, that of Islâm Khân, grandson of the saint, is in excellent taste, but quite eclipsed by its surroundings. An inscription on the inner wall gives the date A.H. 988, or A.D. 1581. The tombs of the women are in the centre of the north side of the court. The Baland Darwâza, or great northern gateway, was built in A.H. 983, or A.D. 1575, as appears from the târikh; it is noble beyond that of any portal attached to any masjid in India. An inscription upon the sandstone on the left hand records Akbar's return after his conquest of the Dakhin in A.H. 1010, or A.D. 1602.

To the north of the dargâh there are the houses of Abûl Fazl and his brother, Fâizî, Akbar's most intimate friends, and followers of his new religion, the tauhîd-î-Ilâhî, or "the divine monotheism."

To the east of these is the principal palace, called Jahangiri Mahal, or with less reason Jodh Bai Mahal. There can be no reasonable doubt that Jôdh Bâi was the wife, and not the mother, of Jahangir. She was the daughter of Môth, Râjâ of Jôdhpûr. Jahângîr's mother was in all probability the daughter of Râjâ Bihâri Mal, a Kachhwâha Râjpût, and sister of Râjâ Bhagvân Dâs. The proper name of this lady is not known, but the title is given as Mariam-uz-Zamāni, "Mary of the Age," the origin probably of the myth regarding Akbar's supposed Christian wife. The palace thus wrongly attributed to Jodh Bai may have been, and probably was, the residence of his zanana or some portion of it. Of Akbar's many wives the chief was Sultana Rukia, and it may be that this palace was especially appropriated to her; but the probabilities are in favour of the view that makes it the abode of a Hindû princess, possibly the mother of Jahangir. The palace consists of a series of apartments, some in two and some in three storeys, roofed with sloping slabs covered with blue enamel and occupying the north and south sides of a large quadrangular court-yard, 177 feet by 157 feet. The remaining sides are closed in by a continuous gallery. Hindû ornaments prevail in the carvings, and fragments of statues have been found here. The building itself has one main entrance on the east, a lofty and richly-carved gate, so placed as to bar all view from the outside; but it has also a passage supported on arches leading from the upper storey on the north, and carried, with screen walls on either side and a canopy overhead, down the north side of the hill to where apparently terraces now no longer existing overlooked the plain.

Close to the principal gateway of this palace is a terrace paved with sandstone flags, and formerly enclosed by a colonnade. On this terrace stand the buildings

Ib.

Ib.

III.

known as Bîrbal's house, the Christian wife's house, and the Khas Mahal, or "private chambers." In another court, but in the same neighbourhood, is a reservoir of water crossed by four causeways meeting in the centre.

On the south of the Khas Mahal, close to this reservoir, is the Khwabgah, or "sleeping apartment," supposed to have been used during the day by the Emperor and the more intimate male members of his family, on the top of which is pointed out a small and simple chamber, which Akbar used as a sleeping apartment during the heat of midday. It contains an inscription in Persian verses, eulogizing this room of the

Emperor as the highest paradise.

Behind the palace, known as Bîrbal's, is the stable-yard. Birbal's house, or Ib. more probably that of his daughter, is a beautifully-carved square building of red sandstone, two storeys high, having four chambers in the upper, which are said to have been occupied by the daughter of Akbar's General, Raja Birbal. Each of the four rooms of the lower floor is but 15 feet square, and each is ceiled with slabs of 15 feet in length by one in breadth. These ceilings rest upon bold cornices supported by deeply-arched pedentives. The rooms in the upper storey are of the same size, but crowned by massive domes formed by placing a capstone upon 16 sloping slabs, each of which stands upon an abutment, the whole supported on eight sides rising from the four walls of the room.

The house pointed out as that of Akbar's Christian wife is a living embodiment of Ib. what some regard as a myth. There is nothing but that unsafe guide, tradition, to support the story that Akbar had a Christian wife. The house is in good preservation; but the frescoes which tradition says represented scenes from Firdûsi's poem, the Shâh-nâma, have faded beyond hope of restoration. The proper name of the house was doubtless Sonâra Makân or "the golden house," a name given to it from the profuse gilding and painting with which it was adorned. It is not improbable that it was really the residence of that Hindû wife of Akbar, of whom history records that she was the mother of Jahangir, and was known by the title Mariam-uz-Zamani. Her tomb is said to be one at Sikandrå known as Rauza Mariam, and to have been erected by Jahangir.

The Khas Mahal is a flagged court-yard measuring 210 feet by 120 feet, of which the south side is formed by the buildings underneath the Khwâbgâh.

On the west angle of the Khas Mahal is a building called Jahangir's School, and from it run the remains of a screen wall leading due east to the opposite angle, where the apartments of Akbar's Turkish wife (Růmi Begamk a-Mahal) are pointed out. It should be stated that beyond tradition there is no Ib. authority for the statement that Akbar had a Turkish, any more than a Christian, wife. In the Khusru Bagh at Allahabad is a tomb said to be that of Tambôlî Begam, which may have been corrupted into Stambûlî, and thus have given rise to the myth. Most artistic are the carvings with which this dwelling is decorated. Under the wainscoting of the walls is a sort of plinth or dado about 4 feet high of the most curious fashion. On one panel is to be seen a forest view from the Himâlayas, pheasants perch upon the boughs, and tigers stalk through the jangal; on another the conventional willow of China nods to sprawling dragons; a third has palm-trees, and a fourth grape-vines and fruit-trees in full bearing. The

outside pillars have in some instances a much more realistic type than is common in Eastern art.

- Ib. At the back of Bîrbal's house is a magnificent stable-yard with 51 stables, each for two horses, in which mangers and rope rings, all of stone, still exist.
- IIb. North-west of the Khâs Mahal is a garden with a small masjid, probably for the use of the zanàna, and a gallery bounds it to the north.
- Ia. To the east of it is the Pañj Mahal, a fivefold succession of canopies or platforms, each smaller than the one beneath, supported on rows of columns. The uppermost platform is exceedingly small and the columns diminish in number from 54 supporting the ground-floor to four supporting the topmost storey. The carving of these pillars is noticeable for the variety of subjects represented.

North-east of the Panj and Khas Mahals is an open court in which is the *Pachisi* board, laid out in black and white squares in the red sandstone pavement, where the Emperor and his nobles played with slave-girls as pieces.

- III. North of this is the Ankh Michauli, which was probably a treasury, and the Ib. Dîwân-î-Khâs or "chamber of privy council," a curiously-constructed building, having in the centre a pillar with an immense capital from which four stone bridges lead to the four corners of the room.
- III. Close to the Ankh Michauli is a small platform shaded by a canopy of four pillars in Jain architecture, where, according to tradition, sat a Hindu teacher (guru) tolerated by Akbar.
- By a colonnade, now partly destroyed, the Emperor passed from the Dîwân-î-Ib. Khâs to the Dîwân-î-Âm, a small hall with a deep verandah looking upon a large court-yard, surrounded by open cloisters for the accommodation of suitors. This was doubtless the Imperial court of justice held partly in the open air after the fashion of similar halls at Âgrâ and Dehlî.
- To the north of the Dîwân-î-Âm is a large quadrangular building, known as the III. Mint. It is a kind of outwork or barbican, with a large number of dark vaults and a hall described as "the hall of account." There is some confirmation of the tradition in the fact that Faṭhpūr is included in the list of Akbar's and Jahângîr's mints.
- The remaining objects of interest lie at some distance to the west and under the higher parts of the rock from those just described. Among them may be mentioned III. the waterworks by which the water of the lake was supplied to all parts of the palace by means of a series of Persian wheels and a system of reservoirs.
- Ib. The Hathi Pol, or "elephant gate," is a massive structure. About 20 feet from the ground the spandrils of the main arch are flanked on each side by a colossal elephant; their trunks, interlaced as in the art of fighting, once, according to tradition, surmounted the keystone of the arch; but Aurangzib is said to have removed the heads.
- Ib. The Sangîn Bûrj, a grand bastion, adjoins this gateway; it is said to have been the commencement of the fortification begun by Akbar, but discontinued in deference to objections raised by the saintly Salim Chhishti.
- III. Below the Hâthi Pôl is the Hiran Minâr, or "the antelope tower," about 70 feet in height, studded with imitations of elephants' tusks, from which circumstance it is often called "the elephant tower."

III.

III.

Ш.

IIb.

- Ib. The large karavânsarâî, called the Kâshmîr Sarâî, lies between the Sangîn Bûrj and the elephant gate.
- 8. Fîrûzâbâd, 1 tahsîl, lat. 27°-8′-37″ N., long. 78°-25′-56″ E., 26 mîles E.-8.-E. IIb. of Âgrâ, built by Fîrûz Khân, or Fîrûz Khwâja, one of Jahângîr's eunuchs, possesses a fine masjid, several dargâhs, five Hindû temples, and the remains of a large tank.
- IIb. The tomb of Fîrûz Khwâja is of white marble, and stands on the road from Fîrûzâbâd to Âgrâ; but the inscription on it contains only verses from the Qurân.
- IIb. Near Firûzâbâd is a tomb and a small masjid adjoining it. The tomb covers the remains of 'I waz Beg Khân Bahâdur Hizabi Jang, who died in A.H. 1189, as recorded in a Persian inscription.
- Three miles to the south-west of Fîrûzâbâd, near the ravines of the Jamnâ, are the ruins of the old city of Chandwâr which, judging from the remains which still cover the surrounding country for miles, viz., ruined temples and masjids, dilapidated octagonal mausoleums, fallen entrance-gates, and such like works of costly strength, must have been an important place in a fiscal and military point of view. Close to it stands the village of Sûfîpûr, named after Shâh Sûfî, a faqir of some celebrity in the reign of Akbar.
- Ib. The Shah was buried on a brow of a deep ravine, a handsome tomb being erected over his remains. The mausoleum is still in good order, and forms a picturesque object in the midst of the desolation of the Jamna ravines in the vicinity of Chandwar and Firûzâbâd. There are several dâlâns, a handsome gateway, and small masjid comprised within the building.
 - 9. HATHKANT, village in tahsil Bah Pinahat, 51 miles S.-E. of Agra, has the remains of an ancient fort.
- 10. Îtimâdpür, tahsîl, lat. 27°-13′-50″ N., long. 78°-14′-22″ E., 12 miles E.-N.-E. of Âgrâ, possesses a masjid and five Hindû masonry temples. To the west of the town is a large square masonry tank, in the centre of which there is a two-storeyed octagonal building surmounted by a dome. This building is approached by a causeway raised on 21 arches starting from the north-east side of the tank. A little north of this latter point is a one-storeyed building similar to that in the centre of the tank, but accompanied by a Musalmân tomb. It is known as Bûṛhiâ-kâ-talâo, possibly a corruption for Buddhi or Bôdhi Tâl, as several small sculptures of the Buddhist faith have been discovered in the mud at the bottom of the tank.
 - 11. Jågner,² in tahsil Khairågarh, 31 miles S.-W. of Ågrå, possesses the remains of an ancient fort, now in ruins, but an object of some architectural interest, apparently built by Jagmal Råo, Ponwår, as an inscription bears the date Samvat 1628 or A.D. 1571. Outside the entrance gateway of the fort is a large tank or båoli cut out of the solid rock of the hill constructed by the famous Sûrajmal Jât. Near the town was a tank constructed by Ålî Vardî Khân in the days of Akbar; it is now a cultivated land. Beyond the town a long flight of steps leads up to the hill known as Bâbâ Gwâla. Near it is a cave.

¹ Proceedings, Asiatic Society of Bengal, for 1874, page 176.

Cunningham, Archaeological Reports, Volume VI, pages 24 to 32.

- III. On the heights above Jâgnêr and Satmâs,¹ there are a number of cairns or Ib. heaps of stones, probably the sepulchral remains of the aborigines of the country.
- 12. Jajão,² in tahsíl Khairágarh, 22 miles S. of Ágrâ, is remarkable for possessing a very large and grand royal sarâi with a very lofty gateway which is higher than the lofty gateway of the Lâdlí Bâgh at Ágrâ. The gateway is built of red sandstone and contains three storeys, and is surmounted by a chattri or pavilion and two
- IIb. domes. There is a very fine masjid on the west side of the sarâî built of red sandstone, with a long Arabic inscription on a slab of white marble over the central qibla apse of the masjid. Jajão is evidently an ancient Hindû place, as several ancient sculptures have been found there.
- 13. Kassaundt, village in tahsîl 'Îtimâdpûr, 18 miles E. of Âgrâ, possesses the ruins of a series of 52 forts, called Bâwan Garhî, and an ancient tank of masonry, called Hâthi-kâ-hauz. The bricks are very ancient, being two feet in length and nine inches in thickness.
- 14. Kågåraul, itlage in tahsil Khairågarh, it. 27°-1′-28" N., long. 77°-53′-50″ E., 14 miles S.-W. of Ågrå, is a place of some antio ity, and the present village stands on a mound of the débris of an old fort. The remains of a massive wall composed of huge blocks of red sandstone, some of them beautifully carved, are found in the western part of the village, but most of it is buried in the mound. The name of the village is probably derived from the combined names of Råjå Rôl, who is the traditional founder of the place, and his father, Råjå Khångar; Khångarôl being corrupted to Kågåraul. Ancient remains are frequently found or dug up, such as sculptures, images, and old coins.
- IIb. The tomb of Shaikh Ambar, called the barah khambha, is about a quarter of a mile to the north of the village; it is a fine mausoleum of red sandstone in the Fathpur Sikri style. The roof is supported by twelve pillars and is surmounted by a dome. There are four graves under the canopy, and it is said there is a large baoli beneath, now covered over.
- 15. Кнагаасан, 5 tahsil, lat. 27°-1′-28" N., long. 77°-53′-50" Е., 18 miles S.-W. of Âgrâ, has the remains of a mud fort which is said to have been built on the site of an ancient fort built of brick. The village itself stands on a large and ancient kherâ; about 400 feet to the north there is an old tîlâ, and about 500 feet to the east there is another tîlâ, called Taisu Tîlâ, in which ancient sculptures are often found.
 - 16. Kherâ,6 small village in tahsîl Fathpûr Sîkrî, 27 miles S.-W. of Âgrâ, is the site of an ancient town of large size. On the ridge of the hill or a little distance to the north-east of the village there are several sepulchral cairns.

Single Control

17. Kirâolî, village în tahsîl Faṭhpûr Sîkrî, 15 miles W.-S.-W. of Âgrâ, pos-III.) sesses an old masonry bûradarî, the remains of a city wall and a masjid ascribed to IIb. } Paṭhân times.

Ib.

¹ Cunningham, Archaeological Reports, Vol. VI, pages 33 to 39.

² Cunningham, Archeological Reports, Vol. IV, page 213.

^{*} Cunningham, Archwological Reports, Vol. IV, pages 208 and 209.

^{*} Cunningham, Archaeological Reports, Vol. IV, pages 210 to 213.

⁵ Cunningham, Archaeological Reports, Vol. IV, page 210.

[&]quot; Cunningham, Archaelogical Reports, Vol. VI, page 13.

Hb.

Ib.

III.

18. Pinâhâr, small town in tahsîl Bâh Pinâhât, 33 miles S.-E. of Âgrâ, possesses three Hindû temples, a large tank, a masonry wall around the town, and a fort.

19. PARNA, village in tahsîl Bâh Pinâhât, 52 miles S.-E. of Âgrâ, possesses a fort

III. on a cliff near the right bank of the Jamna.

20. Semrà, small town in tahsil 'Îtimâdpûr, lat. 27°-19'-56" N., long. 78°-7'-10"

E., 14 miles N.-N.-E. of Agra, possesses a fine masonry temple and tank.

21. Sikandrâ,¹ or Bihishtâbâd, village in Âgrâ Sadar tahsîl, lat. 27°-13′-1″ N., long. 77°-59′-33″ E., five mîles N.-W. of head-quarters. It has been supposed that the Âgrâ of the earlier period of the Lôdi dynasty was at Sikandrâ or divided between Sikandrâ and the Lôdî Khân-kâ-tîlâ, a quarter of the present city of Âgrâ. Remains of the sites of innumerable buildings on each side of the road from Âgrâ to Sikandrâ and round about Sikandrâ itself are still to be seen, of many of which it is impossible now to discover who the founder or what the particular purpose for which they were built.

The baradari of Sikandar Lôdî, built in A.D. 1495, is a square building of red sandstone, 142 feet on each side, and comprises two storeys with a vault below the ground-floor containing about forty chambers. Each corner of the building is surmounted by a short ornamental octagonal tower. This building is commonly known as the tomb of Akbar's Christian wife, because Akbar interred his wife Mariam-uz-Zâmâni, the mother of Jahângîr, here. The tomb is in the vault below, and in the centre of the upper storey is a white marble cenotaph.

The Hans Mahal, attributed to Akbar's minister and friend Râjâ Bîrbal, is situated about eight miles beyond Sikandrâ. The palace is entirely ruined; the original extent of the palace must have been somewhere about 380' by 200', judging by the traces of foundations of walls and the mounds of earth formed by débris.

But the distinctive feature of Sikandra is the famous tomb of Akbar,2 a vast Ia. pyramidal pile of arched galleries, flanked at intervals with cupola pavilions and crowned with elaborate marble relievos varied in colour and fantastic in design. It stands in a large garden of 150 acres in extent surrounded by lofty walls with four gateways midway on each side. The building is of five storeys, each smaller than that below it, the topmost storey being of white marble and surrounded with beautiful screens of the same material. In the centre is the jaicab of Akbar's tomb, made of a single marble block, and the pedestal on which was deposited the Kôh-î-Nûr. The words 'Allahu Akbar and Jalla Jalaluhu are inscribed on the head and foot of the sarcophagus, and round about it the ninety-nine beautiful names of Allâh are sculptured in alto relievo in a remarkably fine Arabic tracery. The inscription, consisting of 36 distiches, on the walls of the enclosure makes no mention of the Prophet, and thus harmonizes with Akbar's religious views, whilst it at the same time completely refutes the story of Akbar's "conversion on the death bed." This upper storey is now open to the sky; but formerly there was a canopy of gold and silver brocade suspended over the platform, and hangings of similar material in the openings of the cloisters all round. These, with many other valuable adornments of the place, were carried off

¹ Proceedings, Asiatic Society of Bengal, for 1874, pages 213 to 218,

^{*} Fergusson, History of Indian and Eastern Architecture, page 583.

by the Jât Râjâ, Jawâhir Singh. The marble stones which flagged the entrance of this crypt were also carried off to Dîg by Jawâhir Singh. Akbar's tomb is in a vault below the ground-floor, and bears no inscription. The mortuary hall is nearly 38 feet square, and is surrounded by other chambers of small size containing tombs of less distinguished members of the Imperial family, viz., the graves of two daughters and granddaughters of the monarch, and one as recent as A.D. 1838, being the tomb of Sulaimân Shikôh, son of Shâh Âlam of the Dehli family, who with his two wives is buried here.

The garden is said to have existed in Akbar's time, but the tomb is erroneously spoken of by Fergusson as one of Akbar's buildings. It was built by Jahangir; for one of the inscriptions, on the south or outside front of the great gateway, states that Jahangir completed the work in the seventh year of his reign, or A.D. 1612. There are, besides, three other records, but all undated.

The general design of this unique building is apparently a direct imitation of some such buildings as the old Buddhist Vihàras. Probably the intention of the architect was to crown the topmost storey with a domical chamber over the tombstone, the raised platform in the centre of the upper cloister, 30 feet square, being the foundation.

II.—FARRUKHÂBÂD DISTRICT.1

- Amritrûr, village in tahsil Alîgarh, 14 miles N. of Fathgarh, has the remains III. of an old fort.
- 2. Bhôjrêr, village in Sadar tahsîl, six miles S. of Fathgarh, was founded by HI. Râjâ Bhôja of Mâlwâ, who built here a mighty fortress. The traces of considerable fortifications are still visible; but it is possible that these are of far later date. A castle was built here by Ghîas-ad-dîn Balban (1266—1286).
 - 3. Bishangarh, small town in tahsîl Chhibrâmâû, 23 miles S. of Fathgarh, possesses a castle which is enclosed within a large wall and ditch.
- Синівкамай, tahsíl, 17 miles S.-W. of Fathgarh, possesses the remains of a III. large ruined castle and of an old sarái.
- 5. Farrukhârân, lat. 27°-24′ N., long. 79°-40′ E., three miles N.-W. of Fathgarh, the head-quarters station. Farrukhâbâd is completely surrounded by a triangular embankment or wall, as high in some places as 20 feet, and from 10 to 12 feet thick. This enceinte is guarded at intervals by bastions or rather flanking towers, and these walls are entered by ten gates. The fort used to stand on the same mound as had been occupied by the old Bamtela castle of Mâud, and before that by a stronghold of King Drupada. As originally built, A.D. 1714, by Nawâb Muhammad, it was a mud structure flanked by 20 earthen bastions and surrounded by a ditch of the same depth as a man's height. It contained a palace called the Barâ Mahal and a masjid called Jâmi Masjid. It had three gates opening to the north, but these and later buildings are all in ruins. A little masjid is the only relic of the Nawâbs that has been left here. The number of both masiids and Hindù temples in
- III. Nawâbs that has been left here. The number of both masjids and Hindû temples in the town is large, but none of these buildings is of much antiquity or much architectural merit.

III.

¹ North-Western Provinces Gazstteer, Vol. VII, pages 211 to 402.

- 6. FATHGARH, the head-quarters of the district, lat. 27°-22′ N., long. 79°-41′ E. Ib. The principal building is the fort; its mud walls were originally surrounded by a ditch and flanked by 12 bastions, but are now much out of repair, and could perhaps be easily scaled. The original castle was built by Nawâb Muhammad Khân (A.D. 1713—1743).
- 7. Indargarh was a castle whose remains may be seen in the eastern corner of Pûrab Râi village in pargaṇa Saurikh of tahsil Tirwâ, 32 miles S. of Faṭhgaṛh. III. It was founded towards the close of the last century by the notorious Uday Chand Tiwâri.
 - 8. Kampil, village in tahsil Kaimganj, 28 miles N.-E. of Fathgarh, is of great and undoubted antiquity, as its name Kampilya appears already in the Mahabharata. Kampilya was the capital of southern Pañchala, and here King Drupada held his court; it is famous as the scene of the svayamvara of Drupadi, the beautiful daughter of Drupada, who married the five Pandava brothers. There are no traces of old buildings, but only a succession of undulating grounds rising in some places to high mounds with broken bricks thinly scattered here and there. The site of Raja Drupada's palace is pointed out as the most easterly one of the isolated mounds on the banks of the Bûr Ganga; it is about 400 feet long and from 200 to 250 feet broad, rising to 20 and 25 feet in height. Squared kankar blocks are seen everywhere, and apparently the walls of the ancient temples must have been built of those stones; mouldings and even figures are found on some of them. Whatever ancient buildings may have existed at Kâmpil when the Musalmans first took possession of the Gangetic Doab must have been swept away by Ghias-ad-din Balban, who built a fort here, and by Muhammad Tughlak, who in A.H. 745, or A.D. 1344, encamped his army near Kâmpil.

The only remains of note are the ruins of a domed tomb of a Musalman martyr named Makin, an ancient temple sacred to Ramesvara Mahadeva, built of bricks and stone in alternate layers, and several Jain temples, with some inscribed statues.

9. Kanauj, tahsîl, lat. 27°-3′ N., long. 79°-59′ E., 33 miles S.-E. of Fathgarh. Of the great city of Kanauj, the ancient Kanyâkubja, which for many hundred years was the Hindû capital of Northern India, the existing remains are few and unimportant. In A.D. 1016, when Mahmûd of Ghaznî approached Kanauj, the historian relates that "he here saw a city which raised its head to the skies, and which in strength and structure might justly boast to have no equal." At a still earlier date, in A.D. 634, we have the account of the Chinese pilgrim Hiuen Tsiang,3 who describes Kanauj as being 3½ miles in length and three-quarters of a mile in breadth. The city was surrounded by strong walls and deep ditches, and was washed by the Ganges along its eastern face. The earliest notice of the place is undoubtedly the old legend of the Purâṇas, which refers the Sanskrit name of Kanyâkubja or the "hump-backed maiden" to the curse of the sage Vâyu on the hundred daughters of Kuśanâbha. In comparing Hiuen Tsiang's description

IIb.

IIb.

¹ Cunningham, Archaeological Reports, Vol. XI, pages 11 to 13.

^{*} Cunningham, Archwological Reports, Vol. I, pages 279—293; Journal, Bombay Branch, Royal Asiatic Society, Vol. XIV, page 37.

³ Beal, i.e., Vol. I, pages 206-223.

of ancient Kanauj with the existing remains of the city, General Cunningham was unable to identify even one solitary site with any certainty, so completely has almost every trace of Hindú occupation been obliterated by the Musalmâns.

The boundaries of the modern town may be roughly defined as triangular, the three angles being marked by the shrine of Hâji Harnâyam on the north, the tomb of Tâj Bâj on the south-west, and the masjid and sepulchre of Makhdûm Jahâniya on the south-east. But the modern town is a mere northern fraction of the ancient city, whose traces are found as far south as Mîrân Sarâi and Râjgîr Hâr. Surrounding groups of ruins and mounds of masonry débris show where stood the towers, the palaces, and the temples of the past. Old tiles, old coins, and old pieces of broken sculpture encounter the ploughshare in its course through the neighbouring fields. The removal of the ancient bricks with which those fields are strewn has hitherto proved a task of despair.

Such is the Kanauj of to-day, a country-town whose chief claims to interest are the traces of a mighty past. Strong in numbers, these traces are weak in their indistinctness. Miles of broken bricks convey little meaning to the antiquary and still less to the historian. The relics of the Hindû dynasty were demolished by the arrogant intolerance of Islâm, and by destroying the later marks of Muslim power time is avenging the Hindûs. But some antiquities there are, and these will be found chiefly in the old citadel. This sandy elevation occupies the northern angle and all the highest ground of the modern town. Its north point is the shrine of Haji Harnayam, its south-west the temple of Ajaypal, and its south-east the remains of a large bastion called the Kshem Kali Burj. Each of the three faces is about 4,000 feet in length. That to the north-west is protected by a water-course which may once have been an artificial ditch, that to the north-east by the cliff and the little Ganges, and that to the south by a fosse which has since become the high street. On the river face the mound rises to a height of 60 or 70 feet above the lowlands, on the watercourse face to about 40 or 50 feet, and on the street face to some 30 or 40 feet. The situation is a commanding one, and must have made Kanauj a strong and important position. The people point out the sites of two gates; but as both these gates lead to the river, it is certain that there must have been a third on the land side. Its name seems to vaunt Ajaypal's temple as the oldest relic in the citadel; but it is merely a modern building on an ancient site. The existing shrine is nothing more than a small square structure containing the somewhat mutilated figure of a Around the temple are scattered mounds strewn with broken bricks, broken statues, and the traces of broken walls. General Cunningham identifies its founder with that Tômar Jaypal, who was conquered by Mahmud of Ghazni and killed, in 1022, by the Chândella Rájá of Kâlinjar; but the name was not uncommon among the Rathors also, and in our search for the original builder helps us little.

III.

IIb.

III.

Near it on the east are the remains of the Rang Mahal, said to have been built by the same Ajaypal; but it was built about 1685 A.D. by Said Muhammad Kanauji, and named jasmine or little pearl (motiya). The name and perhaps the building were altered when the Audh Governor, Raja Naval Rai Kayath, took up his quarters here in 1750. It is probable, therefore, that the ruins are less than two centuries old; but even of ruins little survives, and the bulk of the site is

cultivated. Still, however, may be seen the remains of a strong brick wall faced with kankar blocks, and behind it at various intervals of other walls similarly built. The length of the utmost wall is 240 feet and the distance from it of the hindmost is 180 feet, so that 240 by 180 feet may be taken as the original dimensions. It is strengthened in front by four towers or buttresses, each 14 feet broad.

Another building to which tradition assigns a præ-Musalman origin is the Hb. Dîna or Jâmi Masjid, known to Hindûs as Sîtâ-kâ-Rasûî. It stands on a lofty mound in the very heart of the old citadel. That it was once a cloistered Hindû structure and that it was remodelled to suit the purposes of Musalman worship, there is not the slightest doubt. A luckily-preserved copy of the now muchobliterated inscription over the entrance doorway shows that the building was regenerated in A.H. 809, or A.D. 1406, in the reign of Ibrahim Shah of Jaunpur. The masjid itself is a pillared room, 108 feet in length by 26 feet in width, supported on four rows of columns. The roof is flat excepting the centre and ends, which are covered with domes formed of circles of stones gradually lessening until they meet. In front of the masjid there is a courtyard 95 feet in width, the whole being surrounded by a stone wall 6 feet in thickness. The exterior dimensions are 133 feet from west to east by 120 feet. In 1838 there were still standing on the three sides of the courtyard portions of the original cloisters formed of two rows of pillars. The masjid itself was then confined to the five openings in the middle of the west side, the seven openings on each flank of it being formed of only two rows of pillars, the same as on the other three sides. The masjid now consists of a single room supported on 60 pillars without any cloisters, but originally the masjid itself was supported on 20 pillars with cloisters on each flank and also on the other three sides of the courtyard; the whole number of pillars was then 128. To make up this number we have the 60 pillars of the present masjid and no less than 58 spare capitals still lying in the courtyard, which together make up 118, or within ten of the actual number required to complete the original design. The pillars of the Jami Masjid may be seen in their original Hindu form at the sides of the small doorways in the north and south walls of the court.

Side by side on a stone plinth in the southern centre of the citadel stand the tombs of Bâlâ Pîr and his son, Shaikh Mahdî. These are almost identical in construction, though the western is the larger of the two. Both are square stone buildings surrounded by flattish domes which rise from octagonal bases. Each has at its four corners light cupolas supported by slender pillars. The striking appearance of these buildings is due rather to grace of proportion than to any wealth of decoration, for both are plain in their neatness. Shaikh Kabîr, commonly called Bâlâ Pîr, is said to have been tutor to the brother Nawâbs Dalel and Bahâdur Khân. The former governed Kanauj in the days of Shâh Jahân, and in the same reign died Bâlâ Pîr, in A.H. 1076, or A.D. 1665, as the inscription on his tomb shows.

A fragmentary inscription, written in characters of the twelfth century, and apparently belonging to the time of the earlier Râthor kings, as well as another slab, dated Samvat 1548, were found a few years ago near these tombs, and were deposited in the Farrukhâbâd Town Hall.

IIb. Another important tomb within the citadel is that of Said Muhammad Kanauji, the tutor of Aurangzib and the founder of Miran Sarai.

IIb.

Hb. The most noteworthy of the monuments outside the old fortress is the shrine of Said Shaikh Makhdûm Jahaniya Jahangasht, alias Jhamaji. That tomb crowns a lofty mound in the Sikhana or Shekhana quarter, some 330 yards south-east of the citadel and 40 feet above the surrounding fields. On the same mound stand two plain square sepulchres. The tombs are one and all enclosed by a wall with turrets at its four corners and an entrance gate on its southern side. On the steps leading up to this portal were in 1838 found a broken statue of Lakshmi and a pedestal with a short inscription, dated Samvat 1193. The shrine of Makhdûm is a common-looking structure 35 feet square, and was, according to a mutilated inscription which once surrounded the doorway, founded by one Said Raja in A.H. 881, or A.D. 1476, during the reign of Husain Shah of Jaunpur. The building was once seriously damaged by an earthquake and repaired in A.H. 1209, or A.D. 1794, by Abbas All, as stated in an inscription. The panels of its back wall are adorned with tablets bearing the name of Allah and suspended by sculptured ropes. This decoration must have been at least suggested by, if not converted from, the Hindû design of the bell and chain.

IIb. At Râjgîr, an ancient brick-strewn mound on the Kâli nadî, three miles S.-E. of Kanauj, is the tomb of Makhdûm Akhai Jamshîd Sâhib. He was a friend of Makhdûm Jahâniya, and his sepulchre, built in A.H. 842, or A.D. 1438, was restored by the Emperor Aurangzîb.

IIb. There is another mausoleum on the banks of the Kâli nadi, with a high dome, and surrounded by high walls. An inscription over the gate informs us that it is the resting-place of Shaikh Nâgah, who died in A.H. 1009, or A.D. 1600.

North-east of Kanauj, on the Kâli nadî stands Ismâîlpûr Nûr-ad-dîn; IIb. here is a tomb, which the Emperor Bâbar is said to have raised over the grave of Chandan, the martyr.

Of the Buddhist kings who ruled Kanauj so long, neither coins nor ruins preserve the slightest memorial. The monuments mentioned by the Chinese pilgrim have left not a track behind. Toilsome search merely enabled General Cunningham to guess vaguely at the probable sites of four. A relic temple of Ašoka he places at Kapatiyâ or Kaptêśwarî village, three monasteries and a chapel containing a tooth of Buddha on the large mound of Lâla Misar Tôlâ immediately south of Kshem Kâli Bûrj, another chapel sheltering a colossal statue of Buddha, on the large mound in the midst of the Bhatpuri quarter, and two Hindû temples of Siva on the mound of Makhdûm Jahâniya.

- KHĀIRNAGAR, in tahsîl Tirwâ, 40 miles S.-E. of Fathgarh, possesses a brick fort built by Rotan Singh on an old kherâ.
- 11. Khudaganj, village in Sadar tahsîl, 14 miles S.-E. of Fathgarh, possesses IIb. a masjid, and a sarâî built by Yakût Khân in A.D. 1739, as an inscription on one of the demolished portals showed.
 - 12. Makrandnagar, suburb of tahsil Kanauj, 31 miles S.-E. of Fathgarh, once perhaps an integral part of Kanauj city, still shows a few traces of antiquity. The now almost dry Sûrâjkuṇḍ to the south-east of the village is an ancient place of worship. Close by is a temple of Siva, which is said to have replaced an older shrine.

III.

Hb.

¹ Proceedings, Asiatio Society of Bengal, for 1873, page 201.

III.

To the south-west of the village are three mounds covered with broken bricks, pottery, and a good deal of fragmentary sculpture.

- 13. Muhammadâbâd, village în Sadar tahsîl, 12 miles S.-W. of Faṭhgaṛh, was founded by Muhammad, first Nawâb of Farrukhâbâd, who erected a castle on the old mound called Kal-kâ-kherâ which the Châṇḍella Râjpûts had of yore made the base of their operation against the aboriginal Bhyârs. One tower or bastion called Râî Sâhib-kâ-bûrj is the only remaining part of Muhammad's stronghold.
- 14. Pakha Bihar, village in Sadar tahsil, 20 miles W. of Fathgarh, is the famous Buddhist vihara close to Sankisa which excited the admiration of the Chinese pilgrim, Hiuen Tsiang. The whole village stands on a mound, but the site of the old Buddhist vihara is quite unmistakable from its square form and great size. It lies to the south of the village, and is simply called khera or "the mound." The bricks found here are 15"×8"×2", but they have all been rubbed smooth, and must therefore have belonged to some building of consequence. Near its north-east corner was found the large statue of Buddha, which is now set up in "Belon-ka-Mandir." Similarly all the clay seals inscribed with the profession of the Buddhist faith which are so common in Pakhna Bihar, came out of the great mound.
- Half a mile to the north of the village there is a fine large tank called Mahitala, on the western bank of which are the remains of four Brahmanical temples, as all the Brahmanical figures now in the village are said to have been III. found there. The Buddhist ruin at Bihar corresponds only with the site of the great monastery described by Hiuen Tsiang,2 which according to his account was situated at 20 li or rather more than three miles to the east of Sankisa. The foundation of the monastery most probably dated from the time of the Indo-Scythians, as a fragment of an inscription which General Cunningham obtained from the mound certainly belongs to one of their kings Kanishka, Huvishka, or Vasudeva. Coins of these princes are also found in considerable numbers at Bihar. The great mound of ruins lies to the south of the village; it is about 1,000 feet long from north to south by 700 feet broad from east to west. There are two parts higher than the rest, one of which at the southern end is 250 feet long from east to west by 200 feet broad from north to south, the other is about 100 feet square. The former General Cunningham takes to be the remains of the great monastery and the latter to be the remains of a stûpa. General Cunningham excavated here a number of Buddhist rail-bars, carved bricks, moulded terra-cottas, and inscribed clay seals.
- 15. Pilkhāna, large village in pargaņa Shamsābād, W. of tahsīl Kāimganj, 20 miles W. of Faṭhgarh, possesses an extensive mound of close upon 5,000 acres, in itself an evidence of antiquity. The village is entirely surrounded by water, and was clearly a fortified place. Sculptures of early date are occasionally dug up from the kherā. Judging from the name, it may be the Pilo-shan-na of Hiuen Tsiang³ which General Cunningham⁴ places at Bilsar, a village in the same neighbourhood, but in the Îṭâh district. Pilkhāna is five miles north of Sankisa; the distance, therefore, from Sankisa which Hiuen Tsiang gives as 200 li, would have to be corrected to 20.

¹ Cunningham, Archeological Reports, Vol. XI, pages 31 to 38.

² Beal, Le., Vol. I, page 202.

² Beal, Le., Vol. I, page 201.

^{*} Archaeological Reports, Vol. XI, pages 13 to 22.

- IIb. }

 16. RAUSHANÂBÂD, village in tahsîl Kâimganj, 13 miles N.-W. of Faṭhgaṛh, possesses a masjid and a masonry well built by Bîbî Raushan Jahân in A.H. 1149, or A.D. 1736. Within the well is a stone tablet bearing a chronogram now almost illegible.
- SAKRÂWA, Sakrâî, or Sakargâon, village in tahsîl Tirwâ, 31 miles
 S.-W. of Fathgarh, has the remains of a brick castle built by Âmin-ad-daula in the beginning of this century.
 - 18. Sankîsa,¹ or Sankîsa Basantpûr, village in Sadar tahsîl, 23 miles W. of Faṭhgaṛh, is of great importance as having been identified with the great city Saṅkâsya or Kapitha, which formed the capital of a large kingdom in the fifth century. The earliest record connected with the town is contained in the travels of the Chinese Buddhist pilgrims, Fah Hian² and Hiuen Tsiang.³ Sankîsa was one of the most famous places of Buddhist pilgrimage, as it was there that Buddha was believed to have been descended from the trayastrimsa heaven by the ladder of gold or gems, accompanied by the gods Indra and Brahmâ.
- III. The modern village of Sankisa is perched on a mound of ruins about 41 feet high, 1,500 feet in length from west to east, 1,000 feet in breadth, and now known as the qila or "fort." About 1,600 feet to the south of the fort is a mound of solid brick-work surmounted by a temple of Bisâridêvî, and 400 feet to the north of this temple mound is the capital of an ancient pillar bearing a well-formed figure of an elephant standing, but wanting the trunk and tail. The capital is of the well-known bell-shape corded or reeded perpendicularly with a honeysuckle abacus as in the Allahâbâd pillar, and is clearly of the same age, or the third century B.C.

Due south from the temple of Bisaridevi some 200 feet is a small mound of ruins, apparently the remains of a stupa; and due east at a distance of about 600 feet there is an oblong mound 600 feet in length by 500 feet in breadth, which is known as Nivi-ka-kot. The term kot is applied in Sankisa to any mound of ruins, and Nivi is probably the person's name who brought the spot into cultivation, but the mound would appear to contain the remains of some large enclosed building like a Buddhist monastery. It is covered with broken bricks of a large size and fragments of stone, and at the south-east and north-east angles and also on the north are large circular mounds which are probably the remains of stupas. The fort and the different mounds all round the temple form a mass of ruins some 3,000 feet in length by 2,000 feet in breadth or nearly two miles in circuit; but this would appear to comprise only the space occupied by the citadel and the religious edifices which clustered around the three holy staircases.

The city itself which would appear to have surrounded this central mound on all sides was enclosed with an earthen rampart 18,900 feet or upwards of 3½ miles in circuit. The greater part of this rampart still remains, the shape being a tolerably regular dodecagon. To the east, north-east, and south-east are openings which are traditionally said to be the positions of three gates of the city and a village bearing the name of Pâor Kheriyâ, or gate village, lies outside the south-east gap in the rampart.

¹ Cunningham. Archaelogical Reports, Vol. I, pages 271 to 279; Vol. XI, pages 22 to 31.

^{*} Beal, &c., Vol. I, pages XXXV-XLIII.

^{*} Beal, Lc., Vol. I, pages 202 to 205,

III.

Hb.

III.

III.

To the north-west at a distance of about three-quarters of a mile is the ruined mound of Agahat (see Sarâî Agahat in the Îţâh district), which doubtless formed a portion of the old city.

To the south-east of the Sankisa ruins is the tank of the Nâga, called Kârewar or Kândayat Lâl, which may be identified with certainty with the dragon tank described by Fan Hian. General Cunningham excavated here a large collection of ancient coins, *inscribed* clay seals, sculptured soapstones, and terra-cotta figures of an early period.

- SAURİKH, village in tahsil Tirwâ, 25 miles S.-E. of Fathgarh, possesses a
 famous well, and to the west the remains of a castle.
 - 20. Shamsabad, town in tahsil Kaimganj, 18 miles N.-W. of Fathgarh. Some three and-a-half miles distant on the Ganges cliff is the side of the old town of K hâr, founded about the beginning of the thirteenth century by a Rathor descendant of King Jayachchhandra. All that remains of the old town is a large mound called the kôt, or fort of the Khôr Rajâs. This mound rises about 30 feet above the level of the alluvial lowlands, and seems to have been carved out of the old cliff. It contains besides the tomb of Aziz-ullâ, that of one Sanjad Salîm.
 - 21. Tâlgrâm, town in tahsîl Chhibrâmâû, 24 miles S. of Fathgarh. On the south of the town used once to stand an old brick castle, but its memory survives only in the mound which marks its site and in the name of the Garhi quarter.
 - 22. Thàtià, small town in tahsil Tirwâ, 36 miles S.-E. of Fathgarh, possesses outside the town on the south a high mound marking the spot occupied until 1858 by a castle, the home of some Bâghel Râjpûts.
- 23. Tirwâ, tahsîl, 25 miles S.-E. of Fathgarh, contains one of the principal castles in the district, and from it the Bâghel owner of the castle derives the title of Râjâ. A former chief of the family, Râjâ Jaswant Sîngh, built a large and handsome IIb. tank, with flights of steps leading down on either side to the water. On three sides are corridors and rooms for the use of bathers, and on a level with the water are other smaller chambers built in the walls of the tank for the same purpose. A lofty gateway forms the entrance. Near this tank is a temple of Durgâ; it is an IIb. extremely handsome structure of stone which has been carved with great taste. The temple and the tank are the two finest buildings of their class in the district.
- 24. Yākūtganj, village in Sadar tahsil, 3½ miles S.-W. of Faṭhgaṛh, originally IIb. called Sarāi Nūri, seems to have at first consisted of a sarāi and masjid, built by a faqîr named Miyân Nūri Shāh. The old masjid is still standing, and the chronogram which ends the *inscription* on its wall shows that it was erected in A.H. 1086, or A.D. 1675.

III.—ÎŢÂH DISTRICT.1

III. 1. Äliganj, tahsîl, 34 miles S.-E. of Îtâh, possesses a large mud fort built by Yâkût Khân, alias Khân Bahâdur Khân, in A.D. 1747, as appears from an inscription engraved on a slab of stone which was removed from the fort, and is now in the possession of Karâmat Khân. The same Yâkût Khân built two unpretending masjids in the town and a massive tomb of block kankar on the fort to the memory 1 North-Western Provinces Gazetteer, Vol. IV. pages 108—218, passim.

of the Musalman saint, Hamza Shahid; two towers of the tomb with the connecting wall and a gateway facing the north still remain. Beneath the fort lies the plain tomb of Yakut Khan in the midst of an enclosure surrounded by a low wall of block kankar.

At the village of Salî, there is a large well with a Tughrâ inscription, near the shrine of Shâh Badr-ad-dîn, and a bâolî, built by Mîrzâ Muhammad Yusuf, during the reign of Akbar, in A.H. 977.

 Augreya, village in tahsil Aliganj, 27 miles S.-E. of Îţâh, possesses a small brick fort of the last century.

- 3. Atranjî Kherâ, village in tahsil Îtâh, 10 miles N. of head-quarters. Local tradition says that in ancient times, before the invasion of the Musalmans, the ancestors of the celebrated Chakravarti Raja Veņa, who was the chief Raja of these parts, built a strong fort which was surrounded by a large and III. flourishing city, and the fort continued the residence of the Rajas, till Shahabad-din Ghori, in 1193 A.D., utterly destroyed the fort and city. Near the present village is a great mound measuring 3,960 feet in length, 1,500 feet in breadth, and 65 feet in height, the site of some ancient and important place. Coins of all sorts are frequently found on it. General Cunningham,2 in 1862, identified Atranji Khera with the site of Pi-lo-shan-na (Virasana), visited by the Chinese Buddhist traveller, Hiuen Tsiang3 in the seventh century, whilst, in 1877, he changed his opinion and identified Bilsar4 in tahsil Aliganj with this ancient Buddhist place. The mound itself is covered with broken bricks of large size and fragments of statues, mostly Brâhmanical. There is a temple of Mahâdêva on the mound, and there are five lingas in different places, of which one is six feet in Hb. height. The great ruined mound of Atranji is, therefore, probably the site of some ancient Brâhmanical establishment.
- Äwa, or Åwagarh, town in tahsîl Jalêsar, lat. 27°-26′-40″ N., long.
 78°-31′-22″ E., 12 miles W. of Îţâh, possesses a formidable mud-built fort, of the native type, surrounded by a deep moat nearly a mile in circumference.
- BARÂÎ, village in tahsîl Îţâh, nine miles N.-W. of head-quarters, possesses,
 on a lofty hillock to the east of the village, the remains of a large mud fort, one of the Chauhân strongholds.
- 6. BASUNDRÂ, village in tahsîl Îtâh, 10 miles S.-W. of head-quarters. Near it is Kherâ Basundrâ or Bâsimdharâ, one of the old Chauhân strongholds, which still contains the remains of a large earth fort.
- III. } 7. Bileâm, town in tahsil Kâsganj, 19 miles N.-E. of Îţâh, built on a lofty and extensive kherâ, was founded by Chauhân Thâkurs about 570 years ago. Some remains of the Chauhân fort are still visible as well as of hundreds of Musalmân tombs which are mostly inscribed. In the vicinity of the present town and for some distance many remains of large buildings are to be found, which show that in ancient times Bilrâm must have been a place of considerable importance.

Ш.

III.

¹Cunningham, Archaelogical Reports, Vol. I, pages 268-271; Journal, Asiatic Society of Bengal, Vol. XXXV, page 165.

^{*} Archaelogical Reports, Vol. I, page 269.

Beal, Le. Vol. I, page 201.

^{*}Cunningham, Archaeological Reports, Vol. XI, pages 13-22.

8. Bhàrgàon, Bhàrgàin, or Bharugàon, village in tahsil Aliganj, 33 miles N.-E. of Îtâh, possesses a number of Musalman tombs, from which it is supposed that it was the scene of some great battle. There are two dargahs belonging to former Pirs of the Chhishtis. The name of the village is said to be derived from Bhàrgava, a rishi of remote antiquity.

9. BILSAR,1 or Bilsand, small village in tahsil Aliganj, 37 miles N.-E. of Itah, stands on a high mound, and has a second large mound to the south. Its former consequence is proved by the fact that the town was the residence of a Râthor Râjâ so late as three or four hundred years back. The Râjâ built a strong fort on the top of the high mound in the middle of the village of which the remains III. still exist. The present village with all its mounds and fields strewn with broken bricks covers a nearly square area of somewhat more than 2,000 feet each side, or rather less than half a mile. The great mound which is more than 33 feet high stands in the very midst of the village, and divides it into two distinct portions, which are known as Bilsar Pachiya and Bilsar Purva, or western or eastern Bilsar. To the south of the latter there is a third division of the village called Bilsar Patti, which means simply the outlying quarter or division of Bilsar. General Cunningham identifies this place with the Pi-lo-shan-na of Hiuen Tsiang,2 who describes the capital as being two miles in circuit. The people were chiefly heretics (Brahmanists) and there were few Buddhists; but they still had two monasteries with three hundred monks, while the heretics had five temples. Inside an ancient monastery in the midst of the town there was a stupa 100 feet in height, which was said to have been built by Asoka. General Cunningham found the remains of carved or moulded bricks of very large dimensions, fragments of a pierced lattice in carved terra-cotta, and two round pillars, bearing inscriptions of Kumāragupta, dated Gupta-Samvat 96, as well as two square pillars belonging to a temple of the Gupta period.

10. DAULESAR, village in tahsil Itah, 10 miles west of head-quarters, possesses

III. the remains of a fine old fort of the Chauhâns.

 DHAMRÎ, village in tahsil Alîganj, 18 miles east of Îţâh, has a mud fort to the S.-W. of the village.

12. Îтан, head-quarters of the district, lat. 27°-33′-50″ N., long. 78°-42′-25″ E., is said to have been founded about 500 years ago by Sangrama Singh, a Chauhan Thakur and descendant of Prithvîrajâ of Dehlî, who built a mud fort, which is still in existence to the north of the town.

13. Jalesar, tahsil, lat. 78°-20′-52″ N., long. 27°-28′-16″ E., 23 miles S. of III. Îtâh, possessed once a fort of some consideration, of which nothing now remains but a shapeless mound with ruined walls of block kankar. Its erection is ascribed to Râṇa Katira of Mewâr, who was contemporaneous with the fall of Chitôr in IIb. A.D. 1403. The Fort or Jâmi Masjid was repaired in A.H. 1138, as stated in a Persian inscription. The shrine of Hazrat Pir Zarî was built in A.H. 1012. Near the town are some old mounds or tilâs, and ancient Hindû coins are frequently found there.

¹ Beal, Le., Vol. I, page 201.

III.

¹ Canningham, Archeological Reports, Vol. XI, pages 13—22.

² Cunningham, Archaelogical Reports, Vol. IV, page 215.

14. Kâdirganj, village in tahsil Aliganj, 32 miles N.-E. of Îţâh, possesses to III. the west on a high mound of earth the remains of a fort built of block kankar, and III. a dargâh of Sujâat Khân partly in ruins, built in A.H. 1104, during the reign of Âlamgir, as appears from an Arabic inscription.

Kâsganj, tahsil, lat. 27°-48'-5" N., long. 78°-41'-36" E., 19 miles N. of Îţâh,

IIb. possesses a fine masjid remarkable for its curious and numerous minarets.

16. Malâwan,¹ village in tahsîl Îtâh, 13 miles S.-E. of head-quarters, possesses the remains of an old temple, the foundation of which was built with large bricks, measuring 15"×8"×2½", and 5½" in thickness, with a buttress extending nine feet. The facing of the superstructure was originally composed of large blocks of carved

kankar. The temple was built upon a slight mound raised with earth and covered a

space of about 75 feet square.

III.

III.

III.

Hb.

III.

17. Marhara, village in tahsil Îţâh, 12 miles N. of head-quarters, contained three shrines of great repute; one only is now extant, but the remains of the others are still visible. The ruined tombs contained the remains of Saîd Abdûl Jalîl Bilgrâmi, who came here in A.H. 1017, or A.D. 1608, and died here, and those of Saîd Shâh Jalîl Bukhârî, who settled here during the reign of Alamgir. The tomb still standing is that of Saîd Shâh Barkat-ullâh, one of the Pîrzâdah family. It was built by Shujâat Khân, in A.H. 1142, or A.D. 1729, and the Deautiful masjid adjoining it was built by Muhammad Afzal, a resident of Mârhara, in A.H. 1145, or A.D. 1732.

18. Nidhault, village in tahsil Îtâh, 10 miles W. of head-quarters, possesses the remains of a fort built by Khushâl Singh, âmil of the Nawâb of Farrukhâbâd.

19. NÜH KHERÂ, VİLLIZE İN TABSÎL JALÊSAR, LAT. 27°-31′-33″ N., long. 78°-28′ E., 19 miles S. of Îţâh, has extensive mounds marking the site of some important ancient town, and consists of a large fort mound with remains of the outworks and partially defined moat. Numerous fragments of sculptures found over the whole place belong apparently to the Buddhist period, though possibly some of the temples were converted to use as Brâhmanical shrines.

At Kherâ Kundalpûr, close to Nûh, there was a very large Buddhist temple which was dismantled quite recently by Râjâ Pitambar Singh of Âwa, who used the stone in temples and other buildings at Âwa.

There are also remains of a Buddhist temple at the village of Bari.

20. Nyurar, village în tahsîl Îţâh, four miles N.-E. of head-quarters, possesses

a fine Hindû temple.

21. Patiali, village in tahsil Aliganj, 22 miles N.-E. of Îtâh, is a very old place mentioned in the Mahâbhârata. It stands on a high mound, in great part the natural bank of the Ganges, but considerably raised by the ruins of the mud and brick houses which have been built on it from time immemorial. The remains of a large fort covering an area of 117 to 124 square yards, and built by Shâhab-ad-dîn Ghorî, are still visible. It was surrounded by strong thick walls of block kankar and bricks and a moat, but the greater part of the materials of which the walls were constructed has been carried away by the inhabitants of Patiâli to build their houses. Many of the kankar blocks still remaining in the walls are

¹ Journal, Asiatic Society of Bengal, Vol. XXXVI, page 168.

Hb.

Hb.

III.

Hb.

Ho.

carved on one side, showing that they must have formed parts of other buildings before being used for the fort. According to tradition numerous temples were pulled down, the images were buried beneath the foundations of the walls, and the materials of which the temples were built were employed by the conqueror in the construction of the walls,

22. Sahâwar, village in tahsîl Kâsganj, 24 miles N.-E. of Îţâh, possesses the IIb. dargâh of Faqîr Tâj-ad-dîn, the only remains of any antiquity in the place.

23. Sakît,¹ town in tahsîl Îţâh, 12 miles S.-E. of head-quarters, was founded according to tradition by Râjâ Sakat Dêva, a Chauhân Thâkur and descendant of Prithivirâjâ of Dehlî, who built a fort here of which no traces are left. On a neighbouring hill the foundations of a great old kankar-built masjid are still visible, which was erected in A.H. 684, or A.D. 1285, in the days of Sulţân Balban as apparent from an Arabic inscription. A second masjid was built in A.H. 947, or A.D. 1540, in the times of Shêr Shâh, and a third one during the reign of Akbar by Khwâjah Ibrâhîm Badakshî, in A.H. 970, or A.D. 1562. The dargâh of Misrî Shahîd was erected in A.H. 1001, during the reign of Shâh Jahân, as stated in a Persian inscription.

24. Saraî Aghat, small town in tahsîl Alîganj, 43 miles S.-E. of Îtâh, was founded towards the close of the seventeenth century by Khizr Khân, Muhammad Khan, and Rasal Khan, Pathans of the Tuyah Khail, and built the sarai Abdurrasûl and a masjid, of which the latter alone now remains. The memorial IIb. stone of the sarâi is now over the door of the house of Haqim-ullâh Khân in Sarâi, and is dated 1097, or A.D. 1685, in the 29th year of the reign of Aurangzib Ghazni.2 To the west of Sarâi is a lofty and extensive kherâ 40 feet in height, and about half a mile in diameter at the base, the northern portion of which is built over with brick-III. houses. This is Aghat or Agahat, and it is indebted for its name to muni Agastya. The mound is covered with broken bricks of large size, which alone is a sure test of antiquity; gold, silver, and copper coins of all ages and images of Buddha are frequently found.5 On the opposite site of Sarai and less than a mile off is Sankisa in the Farrukhâbâd district, and there is every reason to believe that Agahat in older times formed a part of the great Buddhist town Sankisa which was

25. Sôron, town in tahsîl Kâsganj, lat. 27°-53′-40″ N., long. 78°-47′-35″ E., 27 miles N.-E. of Îţâh, is a place of remote antiquity. It was originally called U kallakshetra, but after the demon Hiranyakesu had been slain here by Vishņu in his Varâhâvatâra, the name was changed to Sukarakshetra, or "the place of the good deed." The ancient town is now represented by a mound known as the qila or fort, which is one quarter of a mile in length from north to south and somewhat less in breadth. The only buildings on it now are the temples of Sîtâ Râmjî and the tomb of Shaikh Jamâl; but it is covered with broken bricks of large size, and the foundations of walls can be traced in all directions. Popular tradition

visited by the Chinese travellers, Fah Hian in the commencement of the fifth, and

by Hiuen Tsiang in the seventh century.

¹ Proceedings, Asiatic Society of Bengal, for 1874, page 104.

^{*} Proceedings, Asiatic Society of Bengal, for 1874, page 105.

³ Cunningham, Archaelogical Reports, Vol. I, page 276.

^{*} Canningham, Archaeological Reports, Vol. 1, pages 255-268.

ascribes the present remains to one Râjâ Sô madatta of Sôron; but the original settlement is attributed to the great Chakravarti Râjâ Vêṇa. Though many of the temples are said to be of very ancient origin, the only ones of any consequence IIa. are the Sitâ Râmjî temple and that of Varâhajî, to the north of the city. The latter contains a statue of Varâha-Lakshmî; the temple of Sîtâ Râmjî was destroyed during the reign of Aurangzîb, and was a few years ago restored by a wealthy Baniyâ by building up the places between the pillars with plain whitewashed walls. The style of the pillars is similar to that of the pillars in the south-east corner of the quadrangle of the Quṭb at Dehlî, which bear the date of Sańvat 1124, or A.D. 1067. There are numerous pilgrims' records on the temple, the earliest of which bear the date in Sańvat 1226, or A.D. 1169, so that the erection of the temple cannot be placed later than A.D. 1000.

26. Thàna Daryaoganj, village in tahsil 'Aliganj, 28 miles N.-E. of Îṭah, possesses the remains of a brick fort built beneath the old bank of the Ganges by Khân Bahâdur Khân, âmil of Azamnagar.

IV.—IŢÂWAH DISTRICT.1

- AHERIPURA, town in tahsil Bharthnâ, 20 miles S.-E. of Iţâwah, is a place of comparatively modern date, but about half a mile to the west there are the remains of an old village site, or kherâ.
- 2. Airwâ, village in tahsîl Bidhûna, 27 miles N.-E. of Iţâwah, is built on and around a lofty kherâ, which indicates that the place is of great antiquity. On the road to Bidhûna a little to the south-east of the village are the remains of a Buddhist or Jain temple evidently of very ancient date, the foundations of which, consisting of massive blocks of kankar, may still be traced.

This undoubtedly ancient place represents most probably the site of the well-known city of Âlavî, mentioned in Buddhist works, and described as "a city near a large forest" (âṭavî), referred to by Fa Hian³ under the name A-lo. The town of Âlow, mentioned by Sp. Hardy in his Manual, and the country of Âlaweï, quoted by Colonel Yule in his Cathay, are apparently only different names of the same spot, as well as the famous town of the Jainas, called Âlabhiyâ or Âlabhî.

3. AJÎTMAL, or Sarâî Ajîtmal, village in tahsîl Aurâiyâ, 24 miles S.-E. of Ha. Iţâwah, possesses an old sarâi constructed by Ajîtmal, Kâyath, in A.H. 1049, or A.D. 1639, in the 15th year of Shâh Jahân's reign, as is apparent from a Persian and Sanskrit inscription over the gate of the sarâi.

About a quarter of a mile to the west is Qasba Bâbarpûr, which is evidently a place of much greater antiquity than Ajîtmal.

4. Asâî Kherâ, small village in tahsîl Iţāwah, seven miles west of head-quarters, on the right bank of the Jamnâ, possesses the remains of an old fort built by Chandrapâla. It is said by tradition to have been one of the gates of Kanauj, and is also identified with the Asî visited by Mahmûd in A.H. 409 or A.D. 1018. Asâî Kherâ seems to have been an important place of the Jains, as many statues of different Tirthamkaras, dated Samvat 1018, 1114, 1205, 1221, 1223, and 1230, have been discovered there, which are now deposited in the Lucknow Museum.

III.

¹ North-Western Provinces Gazetteer, Vol. IV, pages 405-472, passim.

² Beal, *i.e.*, Vol. I, page XLIII.

- IIb. 5. Aurâiyâ, tahsil, 42 miles S.-E. of Itâwah, possesses two good masjids built by Umar Khân, the Rohilla Governor of Aurâiyâ, 150 years ago, five
- Hindû temples, and numerous pakkû wells, on some of which there are traces of inscriptions.

The village of Ammâ Shaganpûr, 12 miles S.-W. of Aurâiyâ, possesses a masjid, built in A.H. 1052, during the reign of Shâh Jahân.

- 6. BÉLA, village in tahsîl Bidhûna, 42 miles E. of Itâwah, is situated on a lofty kherâ, and was formerly a walled town, as traces of the old gates still remain.
- 7. Bidhûna, tahsîl, 32 miles E. of Iţâwah. To the north of the village are the ruins of an old fort, which from a distance have a somewhat picturesque appearance.

Two miles N.-E. of Bidhûna is the village of Bisâhi built on a small kherâ where, in 1873, a Thâkur cultivator found two copperplate grants of Govindachandra Dêva of Kanauj, dated respectively Samvat 1161, or A.D. 1104, and Samvat 1174, or A.D. 1117. The two original plates are now in the Lucknow Museum.

- 8. Chakarnagar, village in tahsîl Bharthnâ, 16 miles S.-W. of Iţâwah. The modern village is little worthy of note; but the old town, the site of which is two miles west of the present village, must have been a place of great antiquity and considerable size. There is an enormous khera there, which can be seen from a III. great distance. It is now covered with brush-wood, but traces of buildings may be discovered here and there. To the west of the kherâ is a magnificent well, built of Ib. blocks of kankar, evidently very old. Popular tradition says that the city in the time of the Pandavas was so large that one gate was at Saratal and the other gate at Bharêh, though these places are 30 miles apart. This story derives some appearance of support from the fact that bricks are found at a depth of five or six feet in the surrounding villages. The khera is said to have been named Ekachakra, whence came the name of the modern place, and it is mentioned under this name in the Mahabharata. General Cunningham,2 however, identifies the modern Årå or Åramnagar in the Shahabad district of Bengal with Ekachakra of the Mahabharata.
- 9. Iţāwah, chief town of the district, lat. 26°-45′-31″ N., long. 79°-3′-18″ E. The Jāmi Masjid³ is the principal building in the city; it is situated on some high ground, and is curious as having been originally an old Hindû or Buddhist structure. The style of the propylon before the dome is the same as that of the Atala and Jāmi Masjids at Jaunpûr, whilst the round buttresses at the back and coëval ornamentations fix the period of its conversion. The main portion of the building is of block kankar with fragments of blue stone in the walls and portions of at least ten granite columns of varying lengths. The average length of them is five feet five inches with a thickness of eight inches, but one at the gate where it is used as an architrave exceeds seven feet in length. There are also plain pillars of red and light-coloured sandstone, and some have been cut in two and appropriated to various purposes. The propylon is 47 feet in height and a little less in width. Within the

¹ Journal, Asiatic Society of Bengal, Vol. XLII, pages 314-325; Indian Antiquary, Vol. XIV, page 101.

^{*} Archwological Reports, Vol. III, page 73.

^{*} Journal, Asiatic Society of Bengal, Vol. XXXVI, page 74.

building is 20 feet in depth, the centre portion bearing the dome is a little wider. A block of granite 5 feet by 1½ feet is let into the front of the propylon, and from its lotus ornamentation would seem to be of Buddhist origin. Only one of the kangura or pinnacles remains on the building; but they doubtless extended across to the propylon. The small portions of wall where the plaster has fallen show the well-known scroll denticulated pattern. Over the south chapel right across the centre an arched chamber some 20 feet by 20 feet and 18 feet high, has been constructed. Its roof has been moulded with pieces of nodular kankar set in lime, which alone appear to keep it together. It would appear to have originally formed part of a cloister, and that there were four rude chapels, each with 16 pillars, and a larger chapel in the middle, intended for the image. The courtyard is enclosed by a mean brick wall, and now contains a small chaitya about nine feet square covering a Musalmân tomb, where four plain pillars support a flat roof with eave-stones of red sandstone projecting some two feet out on each side.

IIIb. The Âsthala is the principal Hindû temple; it is situated within a walled enclosure in a grove to the west of the city, and is entered by a fine gateway. In the inner courtyard of the temple is a curious pillar which goes by the name of Garudji-kâ-khambâ. It is much smaller at the base than at the top, and is surmounted by a stone cage containing an image of Narasiniha, or the man-lion incarnation of Vishņu. The sides of the pillar are covered with carvings, the principal feature in which is the serpent.

Another important Hindû temple is that of Mahâdêva Tikshi, or Śiva of the Mount, which is pleasantly situated in the ravines between the Jamnâ and the city.

- IIb. The bathing ghâts along the Jamnâ are lined by several temples of some standing, that of Dhâmanê svar being evidently the most ancient. The finest is the Bisrântghât built some 400 years ago. The Bisrânt and temples are situated below the hill on which stood the Itâwah fort, the remains of which still attest its former strength.
- III. The fort appears to have been built on an ancient kherâ which is raised above the level of the surrounding country. The remains of the gate are still to be seen on the east side of the hill; on the south or riverside the double wall, the inner line of which was furnished with massive bastions, may still be traced. There are also the ruins of twelve towers at intervals on the circuit of the hill showing that the fort must originally have been of great extent. A bâradarî is the only building now standing on the hill, and this is of recent date; to the west of the bâradarî are two ranges of underground rooms (taikhânah) and a very deep masonry well.
- 10. Harchandpür, village in tahsil Phaphünd, 30 miles E. of Iţâwah. To the west of the village is a large square mound of earth dedicated to the worship of a deity called Jokhai, who is represented by a stone containing what are apparently crystals of amethyst.
 - 11. Kudarkôr, village in tahsîl Bidhûna, 24 miles N.-E. of Iţâwah, is a place of great antiquity as is evident from the height of its site. From the name and the configuration of the ground it is clear that it was in old days a fortified place. The famous minister of Asaf-ud-daula of Audh, Miyân Almâs Ali Khân, built here

ARCHÆOLOGICAL SURVEY LISTS, N.-W. PROVINCES,

, fort, with sixteen bastions, on the ruins of the old kôt. An inscription of Takshadatta, recording in later Gupta characters the erection of a residence for Brâhmanas, was found, in 1875, amongst the ruins of the fort, and is now deposited in the Lucknow Museum.

- 12. Mûnj, village in tahsîl Itâwah, 14 miles N.-E. of head-quarters. From the site and height of its khera, it must have been a place of great note in former days. II. It is identical with the Mûnj which was taken by Mahmûd of Ghaznî in A.D. 1017. The position of the great gateway of the Rajpût castle with the traces of two great bastions on either side is still pointed out. On the north side of the kherå is a curious square well built of block kankar. The sculptured appearance of some of the blocks would seem to show that they once formed part of some earlier building.
- 13. Pâlikhand, village in tahsîl Bharthnâ, 14 miles E. of Itâwah, possesses a modern castellated fort built on an old khera, and commanding the modern village. III. There is here an old temple of Palakadêvî, the tutelary deity of the place from Hb. which it derives its name.
- 14. Phaphund, tahsil, lat. 26°-35'-30" N., long. 79°-30'-25" E., 36 miles E. of Itawah, is built on a khera or old town site, and is fairly raised. Raja Bhagmal III. built the old fort, on the site of which the present tahsili has been erected as well as a masjid in A.H. 1211, or A.D. 1796. Near the masjid is a masonry well, and some IIb.

distance down the mouth is an inscribed slab. There are four masonry tanks, eight Hindû temples, three masjids, and four dargâhs, in the town. Πb .

IIb.

15. Râhan, village in tahsîl Itâwah, 11 miles N.-E. of head-quarters, possesses an old temple dedicated to Dêvî Ratnâvatî.

Here was found, in 1869, a copperplate grant of Govindachandra Dêva of Kanauj, dated Samvat 1166,2 or A.D. 1109.

16. Saraî Ikdil, village in tahsîl İtawah, six miles E. of head-quarters, possesses a masjid and a sarâi built by a eunuch named Ikdil Khân in A.H. IIb.1042, or A.D. 1632.

V.—Maînpurî District.3

- 1. Akbarpûr Aunchhâ, village in tahsîl Mâinpuri, 17 miles N.-W. of headquarters, contains the remains of a great brick and mud fort on the top of a very III. high mound. The old buildings on the khera were of block kankar, and numerous fragments have been collected and placed in a ruined temple where a fair is held every year. The figures discovered represent the various incarnations of Vishnu and other similar Vaishnava subjects.
- 2. Alî Kherâ, village in tahsîl Bhongâon, 91 miles N.-E. of Mâînpurî, stands on a high mound marking the position of a deserted site of an ancient town. III.
- 3. Anjanî, village in tahsil Maînpuri, three miles N. of head-quarters, possesses the ruins of a small mud fort, on the summit of a large kherâ. Close by III. and still upon the crest of the mound which is of great extent, are the ruins of a Buddhist chaitya constructed of kankar blocks.
 - Journal, Asiatic Society of Bengal, Vol. LVI, pages 77—82.
 - Proceedings, Asiatic Society of Rengal, for 1876, pages 130 to 135.
 - 5 North-Western Provinces Gazetteer, Vol. IV, pages 641-772, passim.
 - * Journal, Asiatic Society of Bengal, Vol. XXXVI, page 163.

- About two miles west of Anjani lies the village of Jasrao containing the ruins of two Buddhist shrines. These are both 50 feet by 30 feet, and each has a III. platform 19 feet by 12 feet, built of well-cut kankar blocks without cement and quite plain. Nearly all the Buddhist ruins about here would seem to belong to the time of the decay of the purer faith.
- 4. Asauli, village in tahsil Bhongaon, three miles N.-E. of Mainpuri, is perched on an old mound which rises some 40 feet from the level of the plain. III. The mound is of great extent running nearly east to west, it is perhaps half a mile long and of about the same width, and in former times there probably stood a large Buddhist vihara on its western end, where many carved blocks of kankar are scat-
- 5. Azamābād Ārāon, village in tahsil Shikôhābād, 24 miles W. of Mainpuri, III. stands on an old khera.
- 6. Bhanwat, or Bhawat, village in tahsil Bhongaon, six miles S.-E. of Mâinpuri, has the remains of a large ruined building, which belonged to an old family III.
- 7. Bharaul, village in tahsîl Shikôhâbâd, 17½ miles W. of Mâinpuri, contains the remains of a pakkû tank and a masjid. III.
- 8. Bhongaon, tahsil, 91 miles E. of Maînpuri, contains on a high mound the ruins of a large fort, built in Akbar's time. The fort appears to have been partly III. or entirely built of bricks perhaps without cement, for many of them have been dug out and removed, and the present appearance of the ruins shows that for a long time mud must have been freely used to prop the structure.
- 9. Ekâ, large village in tahsîl Mustafâbâd, 34 miles N.-W. of Mâînpuri, possesses on its north side a mud fort of Raja Hira Singh. Ш
- 10. Hatao Sarifpür, village in tahsil Mainpuri, 20 miles N. of head-quarters, possesses an old temple of some importance, at which a fair is held every year. The Hb. fragments of sculpture lying about are very numerous, and appear to have belonged to some older building.
- 11. Jанма̂t, village in tahsîl Shikôhâbâd, 36 miles S.-W. of head-quarters, possesses an old temple of Durgâ. IIb.
- 12. Karhal, tahsîl, lat. 27°-0'-5" N., long. 78°-58'-45" E., 17 miles S. of Mainpuri, has the remains of a brick fort on the summit of a mound of great extent. III. Ancient solid brick blocks are often found cut into ornamental patterns with a tool. Fine kankar blocks are rare here, and stone is quite unknown, hence the use of
- 13. Karîmganj, village in tahsîl Mâinpurî, six miles N. of head-quarters, was once a much more noticeable place. The adjoining khera is now abandoned, and this III. was once the centre of a considerable town. The kherâ stands on the west of the road with a long lake curving around it, and approaching it on its west side. The mound is of very great extent, being at base 530 by 330 paces, and stands between 40 and 50 feet above the level of the country. There are very few remains of the old town; on the road is the fragment of a gateway and on the ground beyond the road there are signs of another gateway. On the top of the khera stand some remains of a mud fort built by Khan Bahadur Khan. The fort built round a Ш.

Ш.

courtyard seems to have been an ample, but not unusually large, one. The place where the well was and the elephants stood is still pointed out.

- III. About 1³/₄ miles to the west is the village Th âk u râ containing the remains of an early Hindû temple.
- 14. Киексари, or Khâirâgarh, village in tahsil Mustafabad, 42 miles W. III. of Mainpuri, has an old fort of the Chauhans and a still older one said to have been IIb. built by Raja Sauman. There is also a temple of Mahadeva.
- 15. Kishnî, village in tahsîl Bhongâon, 22 miles S.-E. of Mâinpuri, is built III. on a lofty large kherû where traces of Buddhist buildings have been brought to light.
- 16. Kuraoli, town in tahsil Mainpuri, 14 miles N. of head-quarters, possesses IIb. four masjids and nine Hindû temples and an old fort mound now being levelled and IIb. converted into a market-place.

Two miles south of Kurâolî lies the village of Rasemâ, where is a large and III. ancient kherâ having the remains of a small Buddhist chaitya.

- 17. Mahôlî Shamsherganj, village in tahsîl Bhongâon, 22 miles S.-E. of Mâînpurî. Close to the village there is a celebrated *kherâ* covered with broken pottery and carved stones.
- 18. Mainpuri, chief town of the district, lat. 27°-14'-15" N., long. 79°-3'-5" E., III. possesses an old Chauhan fort constructed partly of mud and partly of bricks. There is an old Jaina temple built of brick, and another comparatively new building in the Lohâi mahallâ known as Dêohra. The plaster trellis-work of this latter structure IIb. is strikingly graceful in spite of the poorness of the material. It has also two small doors of irridescent green iron tastefully and simply ornamented at intervals with delicate tracery beneath which red and other coloured glass has been inserted, but only visible enough to light up the tracery. The effect is very good, though the meanness of the material is not worthy of the skill displayed in the iron workmanship or of the delicate green colouring and fine carving bestowed on it. None of the Hindû temples or the Musalman masjids are remarkable in any way for their size, their Hb. H appearance, or their antiquity.
- 19. Mustāfābād, tahsil, 34 miles N.-W. of Maînpurî, possesses a mud fort built by Shîûghulâm at the end of the last century and an old well known as Dûdhadharî, from the purity of its water.
- 20. Naushahr, hamlet in tahsîl Shikôhâbâd, 34 miles S.-W. of Mâînpurî. The roadside between Naushahr and Shikôhâbâd is strewn with fragments of a former town consisting of wells, tombs, and the remains of houses, the courtyard and walls of one of which still remain standing. Naushahr was evidently a place of considerable importance as the town proper was from a quarter of a mile to half a mile long, and extended beyond this in an unconnected way for another quarter of a mile.

 IIb. It was founded in the reign of Shâh Jahân by Hâji Abû Saîd, whose tomb, as well as
- IIb. It was founded in the reign of Shâh Jahân by Hâji Abû Saîd, whose tomb, as well as that of Atikulla Khân, his relation, still exists.
- 21. Nonaira, large village in tahsîl Maînpurî, nine miles N.-W. of head-quarters, stands on a very extensive ancient mound which rises from the plains to a height of about 40 feet. On the eastern spur of the mound are traces of the foundations of an ancient temple, whilst to the north stands the fort, in the construction of

which have doubtless been employed most of its materials, as remains of heavy cornices are seen cropping out of the foundations.

- 22. Padham, or Parham, village in tahsîl Mustafabad, 34 miles N.-W. of Mainpuri, stands on the top of one of the loftiest mounds of the Gangetic Doab. III. The kherà stretches from north to south upwards of three-quarters of a mile with a breadth of rather less than half a mile in the widest part. The antiquity of the place is attested by the number of old coins that are found amongst its ruins. These include punch-marked coins, specimens of the Buddhist satrap Saudasa, coins of the Indo-Scythian kings Kanishka and Huvishka, and coins of the Indo-Sassanian period. The money of the Musalman kings is even more common from the time of Muhammad bin Same down to Akbar. This unbroken succession of the different coinages shows that the place must have been occupied continuously from the very earliest times, and yet nothing of man's work now remains but a few coins buried in a mound of rubbish. The Brahmans refer the foundation of the place to Parikshit, the son of Arjuna, and they point to the Parikshit Kund as IIb. an incontestable proof of their story. There are several fine old wells, built of blocks of kankar, of which one at the northern end is 12 feet in diameter. The bricks are also very large, $19" \times 9^1_2" \times 3"$. The only actual remains of an old building are in the walls of the Pañjpir Masjid, near the south end of the mound. This was IIb. originally the site of a great Hindú temple as shown by the pillars and bands of ornament and the pieces of an amalaka fruit pinnacle which are still lying about.
- 23. Pendhat or Pain dhat, village in tahsîl Mustâfâbâd, 29 miles N.-W. of Mâinpurî, is a Hindû tîrtha of something more than local repute, and possesses Ib. two temples of no great antiquity and no architectural merit, where a large mêla is held in the month of Mâgha. The principal shrine is said to have been erected in commemoration of the eponymous hero of the village, Paindhat or Pânduvamŝi, who fell on that spot in behalf of Prithvirâj against Jayachchhandra of Kanauj. The other shrine contains a fine large figure of Buddha, seated on a sinhâsana or throne with recumbent lions at the base, and elephants and other carved accessories at the sides. This must at one time have adorned a Buddhist temple of considerable size and pretensions.
- 24. Râprî, village in tahsil Shikôhâbâd, 44 miles S.-W. of Mâînpurî. From the remains of buildings, masjids, tombs, wells, and reservoirs still existing, it is clear that Râprî must have been a large and prosperous town. Many buildings were erected by Shêr Shâh and Salîm Shâh, and traces of the gate to one of the royal Ib. residences still exist. The oldest remains are the ruins of an Îdgâh, of large size, built in the time of Alâ-ad-dîn Khiljî by Malîk Kâfûr in A.H. 711, or A.D. 1311, according to an inscription found over the central recess of the western wall. This Îdgâh is built of brick, but the great peculiarity about it is the nature of the bricks of which it is built. The whole of the brick-work has been covered with plaster, and to this plaster surface the masjid was no doubt indebted

There are still the remains of an old fort visible.

III.

¹ Cunningham, Archivelogical Reports, Vol. XI, pages 38 and 39.

² Proceedings, Asiatic Society of Bengal, for 1868, page 63.

⁴ Cunningham, Archaelogical Reports, Vol. IV, pages 217-221.

^{*} Proceedings, Asiatic Society of Bengal, for 1878, page 156.

for any further ornamentation beyond the blue tiles, as might indeed be seen in the arches of the small recesses in which the kalimah was inscribed or formed in plaster on small circular medallions. In many places, however, the plaster has entirely fallen off, leaving the brick-work bare and exposed. The greater portion of the bricks are moulded into patterns, but placed promiscuously in the wall along with other bricks which are plain. The patterns moulded on these bricks are sometimes in the form of scrolls, sometimes of squares, and sometimes of angular It is evident that this Idgah is entirely built of bricks which had belonged to some ancient Hindû brick temple in the neighbourhood which the Musalmans had destroyed under Ala-ad-din Khilji. There does not seem to have ever been more than one huge western wall to this Îdgâh, and which wall terminates at each end with a plain massive tower with sides sloping inwards in the Pathan style. The dimensions are as follows: total length including towers 157 feet 10 inches, length from tower to tower at front 129 feet 2 inches, mean thickness of wall 6 feet, circumference of towers at base 45 feet, diameter of towers at base 15 feet, thickness of wall of towers 3 feet 8 inches. As the walls of these towers slope very greatly inwards, the diameter at the top of the towers will be a very great deal less than at the base, viz., 11 feet 6 inches at top. There are eleven recesses in the walls, including the central apse in front, three of which are 3 feet 10 inches in depth, and the remainder 2 feet 10 inches. The outward breadth of the central apse is 7 feet 6 inches, decreasing inwardly with a concavely curved back divided into three faces and surmounted by a hemispherical arch above. Along the west side of the wall there are five square-shaped buttresses 3 feet in depth by 7 feet 6 inches in length. In the space to each side of the central buttress at the back of the walls there are two flights of stairs projecting from the wall and in the northern one of these two recesses there is a doorway which is 7 feet 4 inches in breadth outwardly, but which suddenly contracts to about 3 feet and passes through the wall to the right or north side of the central apse by a narrow doorway of only 2 feet 3 inches in width. The plan of this Idgah is very peculiar, and differs from all others existing. The wall is surmounted by the usual semi-elliptical shaped battlements peculiar to India. The entire height of the wall is about 30 feet 6 inches, and with the addition of the crenelations it is about 32 feet.

At a short distance from the southern end of the Idgah are two remarkable mausoleums standing in a dargâh, containing the tombs of Pir Faddû and his family. These mausoleums are of a square shape, domed and built of red sandstone. The sides of the mausoleums are composed of beautiful open stone lattice-work similar to that found in tombs at Agra, but in this instance in red sandstone instead of marble. In each mausoleum there are three marble tomb-stones inscribed with quotations from the Quran.

There are some head-stones of marble and red sandstone still almost perfect and covered with legible Arabic inscriptions in Garhî close by to Râpri.

25. Sarsåganj, village in tahsîl Shikôhâbâd, 27 miles S.-W. of Mâînpurî, possesses several modern Jain temples, and a very handsome little masjid whitened over Hb. and with the red stone of which it seems to be built picked out in floral ornamentation over the surface.

 Πb .

- 26. SAUJ, old village in tahsîl Karhal, 24 miles 8. of Mâînpurî, stands on an ancient kherû.
- 27. Shikôhîbîd, tahsîl, lat. 27°-6′-5″ N., long. 78°-38′-10″ E., 34 mîles W. of Mâinpurî, contains a mound on which formerly stood the fort, several masjids, and Hindû temples of no great antiquity or architectural merit.
- 28. Takrāra Daulat, small village in tahsil Karhal, 24 miles S.-W. of Mâinpuri, possesses some remains of interest and a considerable *kherâ*, at which there is a large fair every year.

VI.—MATHURA DISTRICT.1

- Arîng, town in Sadar tahsîl, lat. 27°-29′ N., long. 77°-34′-11″ E., 12 miles
 W. of Mathurâ, possesses three small Hindû temples, the ruins of a fort constructed
 last century, and a sacred tank, called Kilôlkuṇḍ.
- 2. Aurangabad, village in Sadar tahsil, two miles S. of Mathurâ, contains the ruins of a handsome red sandstone masjid, built in the time of Aurangzib, which presents rather a stately appearance, being faced with stone and approached from the road by a steep flight of steps.
- 3. Baldeo (Baladêva), town in tahsîl Mahâban, 10 miles S.-E. of Mathurâ, derives all its celebrity from a temple founded three centuries ago; this building, though large and richly endowed, is neither handsome nor well-kept. It includes within its precincts several cloistered quadrangles where accommodation is provided for pilgrims and the resident priests. Outside the temple is a brick tank, about 80 yards square, called variously Kshîr Sâgar (ocean of milk) or Kshîrkuṇḍ, or Balbhadrakuṇḍ. In this tank, it is said, was accidentally discovered the
 - or Balbhadrakuṇḍ. In this tank, it is said, was accidentally discovered the image of Baladêva, now recognized as the local deity.

 4. Barsâna, small town in tahsîl Chhâtâ, 31 miles N.-W. of Mathurâ, is according to modern Hindû belief the home of Kṛishṇa's favourite mistress, Râdhâ. It is built at the foot and on the slope of a hill originally dedicated to Brahmâ and
- known as Brahmâ-kâ-Pahâr. The summit of this hill is crowned by a series of temples, in honour of Lârlijî, a local title of Râdhâ. These were all erected at intervals within the last 200 years, and now form a connected mass of buildings with a lofty wall enclosing the court in which they stand. Each of the successive shrines was on a somewhat grander scale than its predecessor, and was for a time honoured with the presence of the divinity; but even the last and largest is an edifice of no special pretension. A long flight of stone steps broken about half way by a
- IIb. temple, in honour of Râdhâ's grandfather Mahibhân, leads down from the summit to the town, which consists almost entirely of magnificent mansions all in ruins, and lofty but crumbling walls now enclosing vast desolate areas which once were busy courts and markets or secluded pleasure-grounds. The Bhânokhar tank, with broad flights of steps and flanking towers, was built by Rûp Râm in Samvat 1666, according to a Sanskrit inscription on a pillar inside the ruined tank. On the margin of this tank is a pleasure-house in three storeys known as the Jal Mahal, supported on a series of vaulted colonnades opening on to the water. Near the bâzâr there is a large bâolî, still in excellent preservation, which was erected in Samvat 1764, according to a Sanskrit inscription.

¹ North-Western Provinces Gazetteer, Vol. VIII, pages 171-231, passim,

ration.

IIb.

5. Bathan, village in tahsil Kôsî, 30 miles N.-W. of Mathurâ. On the outskirts IIb. of the village is a large tank with a stone ghât; and at a distance of two miles the sacred wood of Kokila-ban, a very picturesque spot, where an annual fair is held in Bhâdon. In its centre is a temple with a large and well-kept garden and various buildings for the accommodation of pilgrims and spectators, all on the margin of a fine sheet of water connected with a masonry tank of very eccentric configu-

 Bisâwar, town in tahsîl Sadâbâd, 17 miles S.-E. of Mathurâ, contaîns two Hindû temples and a Musalmân shrine in honour of Barâ Miyân.

7. BRINDABAN, town in Sadar tahsil, nine miles N. of Mathura, the legendary spot where Krishna passed much of his youth, is, as might be expected, essentially a town of temples and ghats. There are computed to be within its limits as many as a thousand temples. The four oldest temples are those of Gobind Dêva, Gopînâth, Jagal Kishôr, and Madan Mohan, built under Akbar's protection.

The first-named is not only the finest of this particular series, but is the most Ia. impressive religious edifice that Hindû art has ever produced, at least in Upper India. The body of the building is in the form of the Greek cross, the nave being 100 feet in length and the breadth across the transepts the same. The central compartment is surmounted by a dome of singularly graceful proportions, and the four arms of the cross are roofed by a waggon vault of pointed form, not as is usual in Hindû architecture composed of overlapping brackets; but constructed of true radiating arches as in the Gothic cathedrals. The walls have an average thickness of 10 feet and are pierced in two stages, the upper stage being a regular triforium, to which access is obtained by an internal staircase. This triforium is a reproduction of Musalman design, while the work both above and below it is purely Hindû. The arches are decorative only, not structural; the spandrils in the head have mostly been struck out, leaving only the lintel supported on the straight jambs without any injury to the stability of the building. At the east entrance of the nave there is a small northex 15 feet deep, and at the west end between two niches and incased in a rich canopy of sculpture, a square-headed doorway leads into the antarâla, a chamber some 20 feet by 20 feet. Beyond this is the garbhagriha flanked on either side by a lateral chapel. each of these three cells being of the same dimensions as the antarâla, and like it vaulted by a lofty dome. Under one of the niches at the west end of the nave is a tablet with a long Sanskrit inscription, recording that the temple was built in Samvat 1647, or A.D. 1590, by Maharaja Man Singh Deva of Jaypur, as stated in another inscription on the exterior of the north-west chapel. On the south side of the antarala stands a large domed and pillared chhattri of very handsome and harmonious design, erected by Rani Rambhavati of Mewar in Samvat 1693. or A.D. 1636, as stated in an inscription on one of the four pillars.

Ib. The next temple is that of Madan Mohan, one of Krishna's innumerable titles. The temple consists of a nave 57 feet long with an antarâla of 20 feet square at the west end and a garbhagriha of the same dimensions beyond. The nave has three openings on either side and a square door at the east end; its total height would

³ F. S. Growse, Mathurd, Allahabad, 1883, pages 241-257; Journal, Asiatic Society of Bengal, Vol. XLI, page 313.

seem to have been only about 22 feet, but its vaulted roof has entirely disappeared; the upper part of the antarala tower has also been destroyed. That surmounting the shrine is a plain octagon of curvilinear outline tapering towards the summit. Attached to its south side is a tower-crowned chapel of similar character, but much more highly enriched, the whole of its exterior surface being covered with sculptured panels, its proportions are also much more elegant. Over its single door is a rather defaced Sanskrit inscription; a side-post of one of the doors on the south side of the nave bears an inscription with the date Sanvat 1684, or A.D. 1627; but it simply records a successful pilgrimage made by a native of Kanauj in that year. The courtyard is entered after the ascent of a flight of steps through a massive square gateway with a pyramidal tower which groups very effectively with the two towers of the temple.

Ιδ.

The temple of Gopînâth, which may be slightly the earliest of the series, is said to have been built by Râesilji. The temple corresponds very closely both in style and dimensions with that of Madan Mohan, and has a similar chapel attached to the south side of the shrine. It is, however, in a far more ruinous condition; the nave has entirely disappeared, the three towers have been levelled with the roof, and the entrance gateway of the courtyard is tottering to its fall. The special feature of the building is a curious arcade of three bracket arches serving apparently no constructural purpose, but merely added as an ornamental screen to the south wall which already had a fine boldly-moulded plinth. The terrace on which the arcade stands has a carved stone front; the antarâla arch is of handsome design, elaborately decorated with arabesque sculptures.

Ib.

The temple of Jagal Kishör, the fourth of the old series, was built in Samvat 1684, or A.D. 1627, in the reign of Jahangir. The antarâla which is slightly larger than in the other temples, being 25 feet square, has the principal entrance at the east end, as usual, but is peculiar in having also, both north and south, a small doorway under a hood, supported on eight closely-set brackets carved into the forms of elephants. The nave has been completely destroyed. The antarâla arch is an interesting composition with a fan-light of pierced tracery in the head of the arch and a group above representing Krishna supporting the Gobardhan hill.

Ib.

The somewhat later temple of Râdhâ Ballabh is in itself a handsome building, and is further of special architectural interest as the last example of the early eclectic style. The ground plan is much the same as in the temple of Hari Dêva at Gobardhan, and the work is of the same character, but carried out on a larger scale. The nave has an eastern façade 34 feet broad, which is in three stages, the upper and lower Hindû and the one between them purely Musalmân in character. The interior is a fine vaulted hall, 63 feet by 20 feet, with a double tier of openings north and south; those in the lower storey having brackets and architraves, and those above being Musalmân arches as in the middle storey of the front. These latter open into a narrow gallery with small clerestory windows looking on to the street. Below the three centre bays of the colonnade are open doorways, and the two at either end are occupied by the staircase that leads to the upper gallery. Some of the carved panels of the stone ceiling have fallen; but the outer roof, a steep gable of stone, is as yet perfect.

Some of the smaller temples, though of ancient date, have often been renewed, and possess no special architectural merit. Since 1813, however, some magnificent temples have been raised, and of those the temples of Krishna Chandrarâma, of Śri Ranga Nâth, of Râdhâ Raman, of Râdhâ Indra Kishôr, and of Râdhâ Gôpâl demand special notice. There are in Brindâban no secular buildings of great antiquity.

- 8. Снаимина, village in tahsîl Chhâtâ, 12 miles N.-W. of Mathurâ, has the III. remains of a large brick-built sarâî, said to have been constructed in the reign of the Emperor Shêr Shâh, a temple of Bihârijî and two ponds known as Bihâri-
- IIb. kund and Chandokhar. In the old topographies the sarâi is described as situated at Akbarpûr, a name now restricted to the next village, since the discovery of an ancient sculpture supposed to represent the four-faced (Chaumukhā) god, Brahmā. It is in reality the capital of a Buddhist pillar with a lion at each corner and an apparently naked female in each of the four intervening spaces, the upper border being roughly carved with the Buddhist rail pattern.
- 9. Chhātā, tahsîl, lat. 27°-43'-22" N., long. 77°-22'-56" E., 21 miles N.-W. of Ib. Mathurâ. The principal feature of the town is its large fort-like sarâi with battlemented walls and bastions and two lofty gateways of decorated stone work and considerable architectural merit. It is locally said to have been built in the reign of Shêr Shâh, but may with greater probability be ascribed to Akbar, in whose time it was, if not begun, at least almost certainly completed. The name is locally derived from the Chhattradhâranalîla which Krishna is said to have celebrated here; but there is no legend regarding such an event, and in all probability the name refers merely to the stone chhattris that surmount the sarâi gateways. At the foot of the sarâi wall stands an old-looking mandir ascribed to the reign of Shâh Lahâr, but built on the site and with the materials of a much older.
- IIb. the foot of the sarâi wall stands an old-looking mandir ascribed to the reign of Shâh Jahân, but built on the site and with the materials of a much older temple.
- IIb. There is a temple of Yaśodhâ Nandana at the village of Nandgâon, which was erected in Samvat 1635, according to a Sanskrit inscription.

In the village of Karahla there is a jhula (swing), dated Samvat 1690.

- 10. Ganésvara, village in Sadar tahsîl, three miles N.-W. from Mathurâ. On 1b. a tîlâ to the S.-E. of the village is the umbrella of a Buddhist stûpa of red sandstone, about six feet in diameter.
 - 11. Gobardan, town in tahsil Mathurâ, 16 miles W. of head-quarters, is a famous place of Hindû pilgrimage, and occupies a recess in a narrow sandstone hill, some four or five miles in length and an average elevation of 100 feet. This is the hill which Krishna is fabled to have held aloft on the top of his finger for seven days and nights to cover the people of Braj from the storms poured down upon them by Indra when deprived of his wonted sacrifices; it is ordinarily styled by Hindûs the Gîrî-râj, or royal hill. The town clusters round the margin of a very large irregularly-shaped masonry tank, called the Mânasi-Gaṅgâ. At one end its boundary is formed by the jutting crags of the sacred rock, on all the other sides the water is approached by long flights of steps. It is said to have been first brought into its present shape by Râjâ Mân Singh of Jaypûr in Akbar's reign.

1 Cunningham, Archaelogical Reports, Vol. XX, page 52.

Hb.

but it has since been repaired at great cost by the Râjâs of Bhartpûr. The break in the hill where it enters the town is called Dân Ghâţ from the tradition that it was there that Kṛishṇa stationed himself to intercept the milk-maids (gopî) to levy a toll (dân) on the milk they were bringing in. Close to the Mânasi Gaṅgâ is the famous temple of Haridêva in the same style as the Brindâban series, but a few years earlier in date, viz., about 1560 A.D. The roof of the nave, which was a near approach to a vault and the most interesting feature in the building, was perfect until 1872,

16.

IIb.

when it began to fall in, and was soon afterwards entirely demolished by a Baniya who had volunteered to repair the temple at his own cost. On the opposite side are two stately cenotaphs raised in memory of Randhir Singh and Ran

IIb. two stately cenotaphs raised in memory of Randhir Singh and Baldêva Singh, Râjâs of Bhartpûr. Both are of the same design, consisting of a lofty and substantial square masonry terrace with corner kiosks and lateral alcoves and in the centre the monument itself still further raised on a richly decorated plinth. The

IIb. cenotaphs of Sûrâj Mal, the founder of the Bhartpûr dynasty, erected on a beautiful artificial lake called the Kusum Sarovar by his son, Jawâhir Singh, may, although it dates only from the latter part of the last century, claim notice here.

At the south-eastern foot of the Gîrî-râj or Govardhan hill, just below its highest point, stands the village of Anyor. At the present day the hill is dedicated to the worship of Krishna, and here at Anyor is celebrated the Gîrîrâj pûjâ, or adoration of the sacred hill, and also the Annakûţ, or commemoration of Krishna's sacrifice. It is, however, quite certain that in early days the hill was not dedicated to the worship of Krishna only, for outside the village there still exists a large statue of Buddha with an inscription of the Indo-Skythian period.

12. Gökul, town in tahsîl Mahâban, four miles S.-E. of Mathurâ. Though bearing a name of many legendary associations, it is in reality only the modern waterside suburb of the inland town of Mahâban. All the traditional sites of Krishna's, though described in the Purânas as being at Gökul, are shown at Mahâban, which is in fact the place alluded to wherever Gökul is mentioned in Sanskrit literature. However, in consequence of its retaining the ancient name, the modern suburb is considered much the more sacred place of the two. The temples are very numerous, but they are all mean in appearance and modern in date, and the only noteworthy ornament of the town is a large masonry tank, constructed some 30 years ago.

IIb. 13. HATHĀNA, village in tahsîl Kôsi, 33 miles N.-W. of Mathurâ. A temple of some size and very considerable local celebrity dedicated to Lakshmî Nârâ-yaṇa, stands on the margin of an extensive lake faced on the temple side with masonry ghâts.

14. JAIT, village in Sadar tahsîl, nine miles N.-W. of head-quarters. Near the III. Jamnâ is a small jhîl with the statue of hooded serpent, half ruined, in it.

15. Jawara, town in tahsîl Mât, 12 miles N.-E. of Mathurâ. Here is the sacred grove of Chandraban, named after Chandravatî, with a Bhairâgi's cell under the tutelage of Bâlmukuṇḍ, also a dargâh of Mir Sâhib Shaikh Saddu.

¹ Cunningham, Archwological Reports, Vol. XX, page 49.

IIb.

IIb.

IIb.

116.

116.

16. Khâtrâ, village in tahsil Chhâtâ, 25 miles N.-W. of Mathurâ. The Khadira-ban, one of the twelve sacred woods of Braj, from which the local name is derived, lies immediately outside the village. Adjoining it is a tank with a stone ghât called Krishnakuṇḍ, and on its bank a temple of Baladêva with rather a handsome cenotaph in memory of one Rûp Râm built by his widow 40 years ago. A temple with the title of Gopînâth is said to have been founded by the famous

IIb. Todaramalla of Akbar's time. There are three other temples and two small lakes.
17. Kôsî, tahsil, 27 miles N.-W. of Mathurâ. The name Kôsî may possibly be

connected with the sacred grove of Kôtban which is close by, but it is popularly believed to be a corruption of Kuśasthali, another name for Dvâraka. In confirmation of this belief it is pointed out that there are in Kôsi places named Ratnâkarkuṇḍ, Mâyâkuṇḍ, Bisâkhakuṇḍ, and Gomatîkuṇḍ just as there are at Dvâraka. There is a large stone walled sarâi said to have been built by Khwâja Itibâr Ķhân and a large masonry tank constructed at the same time. Though there are numerous temples and four masjids, they are all modern buildings and of no architectural merit. The temple of Kherâ Dêvata near Gumtî tank is said to have been erected by Makaradhvaja in Sañvat 700, according to an inscribed slab preserved inside the temple. The takiâ of Yasin Shâh was built in A.H. 1198.

IIb. At the village of Kôt wân there is a well, called Môriwallah, near Sûrâjkuṇḍ, which was built in Samvat 1772, according to a Sanskrit inscription.

18. Kôṛâ,¹ small village in Sadar tahsîl, three miles N. of Mathurâ, is the ancient Kutakban, or Katakban. It possesses a large kuṇḍ, with a masonry causeway 1,300 feet long and 4½ feet thick, built across an extensive hollow to the north-east of the village. The causeway has four small pointed arches, with thin walls inside, for regulating the flow of the water. Several small pillars of some old Buddhist building are built into this causeway. Similar pillars have been found on the northern bank of the kuṇḍ.

III. To the north of the kund there is a long mound, on the edge of which a long brick wall has been dug out to furnish materials for a village wall. Towards the eastern end there are the remains of a brick ghât leading down the kund. This mound has yielded 16 railing pillars, each two feet eight inches high by seven inches broad and three and-a-half inches thick. Each pillar is ornamented in front with either a man or woman standing on a prostrate figure; on the back are two full-blown lotus flowers in the middle, and two half-lotus flowers at the top and bottom. Each pillar is pierced with three holes for the usual rail-bars. A large head was also discovered with a crown or flat-topped head-dress, and a group of two females standing side by side under a large tree, which is fully represented on the back of the stone.

19. Kursanda, town in tahsîl Sadâbâd, 20 miles S.-E. of Mathurâ, possesses IIb. four small Hindû temples.

20. Lohaban, small village in tahsîl Mahâban, three miles N.-E. of Mathurâ, on the eastern bank of the Jamnâ, is one of the twelve great bans, or groves. It is

¹ Cunningham, Archaeological Reports, Vol. XX, page 50.

^{*} Cunningham, Archaelogical Reports, Vol. XX, page 46.

popularly ascribed to an asura, named Loha or Lohajangha, whose image is now represented by the lower half of a broken figure standing at a short distance of the temple of Gôpinátha. Offerings of iron are made here at the annual festival and on all occasions whenever pilgrims may happen to come.

Mr. Growse points out that in the Vṛi hat kathâ of Sômadêva there is a story of Lohajangha, a Brâhman of Mathurâ, who was miraculously conveyed to Lankâ. Hence he reasonably infers that the name is at least as old as the 11th century A.D.

21. Mahâban,¹ tahsîl, five miles S.-E. of Mathurâ. Mathurâ and Mahâban are closely connected by legend, for Kṛishṇa though born at the one was cradled at the other. The temples are all exceedingly mean and of no antiquity; the largest and also the most sacred is that dedicated to Mathurâ Nâth, which boasts a pyramidal tower (śikhara) of some height and size, but the material is brick and the design commonplace. A great part of the town is occupied by a high mound where stood the old fort; upon its most elevated point is shown a small cell, called Syâm Lâla, believed to mark the spot where Yaśodâ gave birth to Mâyâ or Yoganidrâ substituted by Vâsudêva for the infant Kṛishṇa.

But by far the most interesting building is a covered court called the Assi Khambha, 80 pillars, which has been appropriated by the Hindus as the scene of Krishna's infancy under the name Chhatti-palna. In its present form it was erected by the Musalmans in the time of Aurangzib to serve as a masjid; and as it now stands, it is divided by five rows of 16 pillars each into four aisles or rather into a centre and two narrower side aisles with one broad outer cloister. The external pillars of this outer cloister are each of one massive shaft cut into many narrow facets with two horizontal bands of carving, the capitals are decorated either with grotesque heads or the usual four squat figures. The pillars of the inner aisles vary very much in design, some being exceedingly plain and others as richly ornamented with profuse and often graceful arabesques. All these interior pillars agree in consisting as it were of two short columns set one upon the other. The style is precisely similar to that of the Hindû colonnades by the Qutb Minâr at Dehli, and both works may reasonably be referred to the same age. As it is probable that the latter were not built in the years immediately before the fall of Dehli in 1194, so also it would seem that the columns at Mahâban must have been sculptured before the assault of Mahmûd in 1017, for after that date the place was too insignificant to be selected as the site of any elaborate edifice.

This supposition is supported by a long inscription of Raja Ajayapala Dêva, dated Samvat 1207, or A.D. 1150, which is recorded on a pillar of the masjid, the inscribed upper half being placed upside down.

But the most remarkable feature about this masjid is that more than one-half of the southern end consists of the mandapa of a Hindû temple almost undisturbed. There are no less than 18 pillars belonging to this one temple, which still retain their original positions. The strongest proof of these being still in situ is the fact that several of the Hindû roofs yet remain. The centre roof and the four corner roofs consist of the usual honeycombed circles rising one above the other. The central roof has five concentric circles: the corner ones have only two. The other three remaining

Пb.

III.

Ib.

¹ Cunningham, Archaeological Reports, Vol. XX, page 43.

oblong roofs are flat ceilings, with a lotus flower in the middle, and a square panel on each side. In the angles of the bracket capitals of the centre and corner roofs there are ornamented pendants, either for the reception of figures or for lamps.

At the north end of the Assi Khambhâ Masjid, there is a small tomb of Said IIb. Yahya of Mashad under a nîm tree. As he is the reputed recoverer of the fort of Mahâban from the Hindûs, it is probable that he has destroyed the temple and built a masjid in its place. This event must have taken place in the reign of Alâ-ad-dîn Khiljî, or A.H. 695—715.

There can be little doubt that Mahâban was the site of some one or more Buddhist monasteries since Fa Hian¹ distinctly states that these establishments existed on both sides of the river, and fragments of Buddhist sculpture have occasionally been brought to light within the precincts of the fort.

III. 22. Mâr, tahsîl, 12 miles N. of Mathurâ, possesses an old mud fort, and within its enclosure stands the tahsîlî and police-station. It is one of the stations in the Hindû pilgrimage of Vanayâtrâ, and is said to derive its name from the milk pans (mât) here upset by Krishna in his childish play.

In the subordinate hamlet of Chhahiri, a little higher up the stream, is the IIb. sacred grove of Bhandirban with a small modern temple, rest-house, and well in an open space in the centre. Just outside is an ancient fig tree which Krishna and his playmates Balarâma and Sudâma are said to have made their goal when they ran races against each other. In the town are three other small temples IIb. and two modern masjids.

23. Mahwan, small village in Sadar tahsil, 13 miles S. of Mathura, is situated on a long high mound on the west of the Ågra road. The mound is covered with broken bricks and fragments of stone, amongst which General Cunningham found a small piece bearing the representation of a lower part of a flight of steps. On the third step from below, a pair of feet still remain, and on the bottom step there is a kneeling figure with hands joined in adoration. Below the sculpture there is engraved the number 23 in characters of the Indo-Skythian period. The figure on the bottom step probably represents the nun Pundarikavariti king, by which transformation she was able to make her way to the foot of the Samkâsya flight of steps by which Buddha was to descend from heaven to earth. After having seen Buddha she resumed her proper figure as a nun. The stone is only 5½ inches broad, and most probably formed part of a pillar of a small Buddhist railing. The same scene is represented on a small bas-relief of soapstone which was found at Sankisa itself.

24. Mathurà, head-quarters of the district, lat. 27°-30′-16″ N., long. 77°-43′-44″ E. In the Brâhmaṇical city of Mathurâ, in A.D. 634, the Hindû temples were reckoned by Hiuen Tsiang⁴ at five only, while the Buddhist monasteries amounted to 20 with 2,000 resident monks. The number of *stiaps* and other Buddhist monuments was also very great, there being no less than seven towers containing relics

Beal, Le., Vol. 1, page XXXVII.

² Cunningham, Archaelogical Reports, Vol. XX, page 41.

^{*} Cunningham, Archwological Reports, Vol. I, pages 231—244; Vol. III, pages 13—46; Vol. XVII, pages 107—112; Vol. XX, pages 30—39; F. S. Growse, Mathura, 3rd edition, pages 103—158.

^{*} Beal, I.c., Vol. I, pages 179-183.

of the principal disciples of Buddha. But notwithstanding this apparently flourishing condition of Buddhism, it is certain that the zeal of the people of Mathura must have lessened considerably since A.D. 400, when Fa Hian1 reckoned the body of monks in the 20 monasteries to be 3,000, or just one-half more than their number at the time of Hiuen Tsiang's visit in A.D. 634. From these accounts of the Chinese pilgrims it would appear that the Buddhist establishments at Mathurâ must have been of considerable importance, and this conclusion is fully borne out by the number and interest of the recent discoveries made in the different mounds near Mathura. There are a great number of lofty earthen mounds around the town which are covered with fragments of stone and brick. Nothing, however, is known about them, although every one of them has a separate name. The numerous fragments of stone which are found upon them show that they are not old brick-kilns, as might have been supposed from their vicinity to the city. Apparently they are natural mounds as are found everywhere along the lower course of the Jamna, and which have usually been taken advantage of for the sites of forts or temples. Thus the old fort of Mathura, on the bank of the Jamna above Sital-ghat, is perched upon a similar mound, and so also is Aurangzîb's Masjid in the middle of the Katrâ IIb. square.

Most of the names of these mounds refer to the Brahmanical divinities; but there are two of them, such as the Anand tila and the Vinayak tila, that are unmistakeably Buddhist, and which may possibly refer to the two stupus of Ananda and Upali (the vinayaka, or teacher of vinaya) as described by Hiuen Tsiang.

The Jamalpur mound and its neighbourhood, the Kankali or Jaini tila and the Katra mound have yielded numerous Buddhist remains. The first of these mounds would seem from the Pali inscriptions found on statues, pillars, and basorelievos to have been occupied by several different monasteries. The most numerous remains were portions of stone railing of the type used to enclose Buddhist shrines and monuments. Three large seated figures of Buddha and the bases of some thirty large columns were also found; it was chiefly round the bases of the last that the inscriptions were engraved. Most of the sculptures were executed in common red sandstone, and were of inferior workmanship compared with the specimens found in the neighbourhood.

The Kankali tila lies at the side of the Agra and Dehli road, much nearer the city than the Jamalpur mound. On the summit stands a fragment of a carved Buddhist pillar venerated at the present day as the supposed image of the goddess Kankali. In the hill itself were found buried two colossal statues of Buddha, each 71 feet high. Here also was found the large figure of an elephant standing on the capital of a pillar with an inscription of the Indo-Skythian King Huvishka. During the extensive excavations, carried on by Dr. Burgess in January, 1888, and by Dr. Führer in January, 1889, a large number of very interesting Bauddha and Jaina relics have been unearthed, namely, a four-faced lion-capital of the Indo-Skythian period; a massive door-jamb, the three faces of which are divided into

III.

¹ Beal, Lc., Vol. I, page XXXVII.

 Πb .

panels of equal size and containing scenes of domestic life represented under temple façades of the Nasik cave pattern; several beautifully-wrought panels, bearing inscriptions in the Maurya alphabet; 12 large statues of Digambara Tirthamkaras, bearing inscriptions dated in the regnal years of the Indo-Skythian Kings Kanishka, Huvishka, and Vasudêva; and two colossal statues of Padmaprabhanatha, dated Samvat 1036, or A.D. 978, and Samvat 1134, or A.D. 1088, being donative gifts of the Śvetambara community of Mathura. Probably, on this mound stood the Upagupta monastery mentioned by Hiuen Tsiang, which General Cunningham identifies with the Yasa Vihara inside the Katra.

The third Buddhist site is in the vicinity of the Katrâ, not far from the IIb. Kankâlî tîlâ. Here, at the back of the temple of Bhûtêśvara Mahâdêva, is a rather high hill, on the top of which stood a Buddhist pillar of extraordinary dimensions, carved in front with a female figure, nearly life-size, bearing an umbrella and above her head a grotesque bas-relief representing two monkeys, a bird, and a misshapen human dwarf.

III. In a large ruinous tank near the temple, called Balbhadrakund, some good specimens of the cross-bars of a Buddhist railing were found; these were enriched with various devices. Among the antiquities may also be mentioned the III. ruins of the walls of the old city.

At the distance of about a mile to the south-west of these is a group known as the Chaubâra and Chaurâsi mounds. In the centre of one of them was found a masonry cell yielding a small gold relic-casket containing a tooth. This does not exhaust the list; indeed, it is probable that much yet remains to be done in the way of thorough exploration of the mounds with which all the fields between the large Kankâlî and Chaubâra mounds are dotted.

Besides the Buddhist remains many Jaina statues of the Digambaras were found, inscribed in characters of the first century A.D., and of the Švetāmbaras, inscribed in characters of the eleventh century. On the decline of Buddhism and Jainism, Mathurā acquired that character for sanctity which it still retains as the reputed birth-place of the deified Krishna. At the present day it has no lack of stately edifices with which, as described of old in the Harivamsa, "it rises beautiful as the crescent moon over the dark stream of the Yamunā," but they are all modern. The neighbourhood is crowded with sacred sites, which for many generations have been reverenced as the traditionary of Krishna's adventures; but, thanks to Musalmān intolerance, there is not a single building of any antiquity either in the city itself or its environs. Its most famous temple, that dedicated to Keŝavadêva, was destroyed in 1661 A.D., in the reign of the iconoclastic Aurangzib. The masjid erected on its ruins is a building of little architectural value; but the natural advantages of its lofty and isolated position render it a striking feature in the landscape.

The so-called Katra in which it stands is an oblong enclosure like a sarai, 104 feet in length, by 653 feet in breadth. In its centre is a raised terrace 172 feet long and 86 feet broad, upon which now stands the masjid occupying its entire length, but only 60 feet of its breadth. About five feet lower is another terrace measuring 286 feet by 268 feet. There may still be observed let into the Musalman

pavement some votive tablets with Nagari inscriptions, dated Samvat 1713 and 1720, or A.D. 1656 and 1663.

The Railway from Mathurâ to Brindâban has been cut through the lower terrace of the Katrâ in January, 1889, and during the excavations several interesting Buddhist sculptures have been discovered, as well as a mutilated *inscription* of the Maukhari King, Mahâditya.

At the back of the Katrâ is the modern temple of Keśavadêva, a cloistered quadrangle of no particular architectural merit. Close by is a very large quadrangular tank of solid masonry, called the Potarakund, in which, as the name denotes, Krishna's "baby linen" was washed. There is little or no architectural decoration, but the great size and massiveness render it imposing. A small cell on the margin of the tank, called indifferently Kârâgarh ("prison-house") or Janma-bhûmi ("birth-place") marks the spot where Vâsudêva and Dêvakî were kept in confinement, and where their son, Krishna, was born.

Hb.

III.

III. At the back of the Potarakund, and within the circuit of the Dhûl-kôţ, or old ramparts of the city, is a very large mound, which would seem to have been the site of some large Buddhist establishment.

The temple of Bhûtêsvara Mahâdêva overlooks the old and ruinous Balbhadrakuṇḍ, and is in its present form a quadrangle of ordinary character, with pyramidal tower and cloister built towards the end of last century. The site has probably been occupied by successive religious buildings from most remote antiquity, and was at one time the centre of Mathurâ, which has now moved away from it more than a mile to the east. In the earlier days of Brâhmaṇism, before the development of the Kṛishṇa cultus, it may be surmised that Bhûtêsvara was the special local divinity.

In an adjoining orchard, called the Qâzî's Bâgh, is a small modern masjid, and in connection with it a curious square building of red sandstone. It now encloses a Musalmân tomb, and in all probability was originally constructed for that purpose, though it has nothing saracenic about it, and is a good specimen of the pure Hindâ style of architecture, with characteristic columns and square architraves supported on brackets instead of arches. Similarly, almost all the oldest buildings that now remain in and about the city are houses or tombs that were constructed for Musalmâns by Hindâs and in purely Hindâ style.

On the riverside stands the Satî Bûrj, a tower of red sandstone commemorating, according to the best authenticated tradition, the satî of the widow of Râjâ Bihâr Mal of Jaypûr, erected by her son, Râjâ Bhagvân Dâs in A.D. 1570. Its present height is 55 feet, and it has four storeys; originally it was of much greater height, but the upper part was demolished by Aurangzib. It is now surmounted by an ugly plaster dome, added apparently about the beginning of the present century.

Near the Kankâlî tîlâ is the Siva Tâl, or Siva's tank, erected according to two memorial inscriptions in Sanskrit and Persian² by order of Râjâ Patnî Mal of Banâras in A.D. 1807. The basin of great depth is enclosed by a high wall with corner kiosks and a small arched doorway in the centre of three of its sides.

¹ Journal, Ariatic Society of Bengal, Vol. XXXIX, page 117.

² Proceedings, Asiatic Society of Bengal, for 1873, page 16.

IIb.

- IIb. The Jâmi Masjid stands in the very heart of the city; it was erected according to a Persian inscription over the principal entrance, by Abdunnabî Khân in A.H. 1071, or A.D. 1661, during the reign of Aurangzib, apparently on the ruins of a Hindû temple. It has four lofty minarets which, with other parts of the building, were originally covered with bright-coloured plaster mosaics, still preserved on a few panels; on these must have chiefly depended its beauty, as the style of architecture is ungraceful.
- IIb. Another small masjid in the suburb of Manôharpûr was built during the reign of Muhammad Shâh in A.H. 1158, or A.D. 1745, as appears from an inscription² over the centre arch.
- III. At the upper end of the Jamna the remains of the old fort, called by the people Kans-ka-qila, and said to have been first built by Raja Man Singh of Jaypur, the chief of the Hindu princes at Akbar's Court, form the most noticeable sight. Here was the gigantic observatory constructed by Man Singh's still more famous successor on the throne of Amber, the great astronomer, Sawar Jay Singh. He was appointed by the Emperor Muhammad Shah his Viceroy for this part of India in A.D. 1721, and it must have been about that time that the observatory was erected; the buildings have now entirely disappeared.

From the fort a succession of ghâts, all simple flights of stone steps with occasional shrines and kiosks, line the edge of the water down to Jamnâ Bâgh below the city. About the centre of the river front is the most sacred of all the ghâts, marking the spot where Krishna sat down to rest after he had slain the tyrant Kânsa, and hence called the Visrânt ghât. The small open court has a marble arch towards the edge of the water, which distinguishes it from all the other landing-places, and on the other three sides are various buildings erected at intervals during the last century and-a-half by several princely houses, but none of them possesses any architectural beauty.

Close by is a natural water-course said to have been caused by the passage of the giant's body as it was dragged down to the river to be burnt, and hence called the Kansa Khai.

- Ib. The Jamnâ Bâgh is a large walled garden situated on the bank of the Jamnâ; it contains, beside a smaller monument, two handsome cenotaphs (chhattri) in memory of Maṇi Râm and Pârikhji. Besides, there are sixteen modern Hindâ IIb. temples, both small and large, which demand a passing notice.
- 25. Magôra, village in Sadar tahsîl, 13 miles S.-W. of Mathura, on the road III. to Bharatpûr, possesses a rudely-sculptured stone with six lines of inscription, recording the performance of a satî in Samvat 1420. The place is called Mangodala in the inscription.
- 26. Mônā,3 or Mônamêyî, small village in Sadar tahsîl, seven miles W. of head-quarters, lies about half-way between Mathurâ and Gôbardhan. Near the village Ib. there is an old wall with a large inscribed slab forming part of the terrace. The slab is eight feet in length by three and-a-half feet in breadth. The Pâli inscription

¹ Proceedings, Asiatic Society of Bengal, for 1873, page 12.

² Proceedings, Asiatic Society of Bengal, for 1873, page 16.

³ Cunningham, Archeological Reports, Vol. XX, page 48.

was originally nearly three feet long; but the whole of the right half has faded away, and only the left half now remains. The inscription is one of the oldest that has yet been found in the Mathurâ district.

- 27. Nandgâon, village in tahsîl Chhâtâ, 29 miles N.-W. of Mathurâ, is the reputed home of Krishna's foster-father, and has a spacious temple of Nand Râijî on the brow of the hill overlooking the village. The temple though large is in a clumsy style of architecture, and apparently dates only from the beginning of last century; it consists of an open nave with choir and sacrarium beyond, the latter being flanked on either side by a rasûî and a sêj mahal (i.e., a cooking and sleeping apartment) and is surmounted by two towers (sikhara). It stands in the centre of a paved courtyard surrounded by a lofty wall with corner kiosks. Besides, there are eight small temples, and one on a larger scale standing in a courtyard of its own half up the hill, and is much in the same style and apparently of the same date as the temple of Nand Râi, or probably a little older. At the foot of the hill is the sacred lake called Pân Sarovar, a fine sheet of water with noble masonry
- ghâts on all its sides. 28. Non Juil, small town in tabail Mat, 30 miles N. of Mathura. The entire centre of the town is occupied by a very extensive brick fort, built about the year 1740 III. by Thakur Dêvi Singh, one of the officers of the Bharatpur Raja. Outside the town is a Musalman Maqbara, called the dargah of Makhdam Sahab Shah Hasan Ghori, 16. traditionally ascribed to a Dor Raja of Kol, who flourished some 300 years ago, and constructed out of the wreck of a Hindû temple. The building is of interest from its possessing the same feature, broken pillars, as is found in the Assi Khambhâ at Mahaban. The pillars, 20 in number, are exceptional in two respects: first, as being all of uniform design, an anomaly in Hindû architecture; secondly, as being, though of fair height, each cut out of a single block of stone. The shaft of each pillar is plain except for four deep scroll-shaped notches half way between the base and capital. The result is to make each pillar work as if it were in two pieces, one placed above the other. This peculiar method is probably the survival of an older one, in which large blocks not being procurable, the column had been in fact constructed of two
- 29. Pali Khera, small village in Sadar tahsil, three miles S.-W. of Mathura, on the high road to Sonkh, possesses an old khera, in which Mr. Growse discovered a second Bacchanalian group, similar to that which was obtained at Mathura by Colonel Stacy in 1836, and which is now in the Indian Museum at Calcutta. In the same mound Mr. Growse found in situ three bell-shaped bases of large octagonal columns at 13 feet distance from one another, at the three corners of a square. The fourth had completely disappeared. The four pillars must, therefore, have supported a canopy over the combined sculpture of which the Bacchanalian group was perhaps only the pedestal.
- 30. PARKHAM, dold village in Sadar tahsil, 14 miles S. of Mathura, is situated on a low mound. It is remarkable for the possession of the oldest statue that has

pieces.

Canningham, Archaelogical Reports, Vol. XX, page 47.

² Mathera, page 115.

³ Journal, Aslatic Society of Bengal, Vol. XLIV, page 212.

^{*} Cunningham, Archavlogical Reports, Vol. XX, page 40.

 Πb .

 $\Pi b.$

III.

yet been found in the Mathurâ district, which has yielded so many sculptures of the Indo-Skythian period. The statue is a colossal standing figure of a man cut in the round, seven feet in height from head to foot and two feet broad across the shoulders. It is made of grey sandstone, and still retains many traces of having been highly polished. The most interesting point about this statue is an *inscription* in two lines on the upper surface of the base pedestal, one line outside the left foot and the other outside the right foot. As the characters are those of the Asoka period, the statue must belong to the third century B.C.

- 31. Râdhâkuṇṇ, small town in Sadar tahsil, 16 miles W. of head-quarters, is occasionally called Śrikuṇḍ, or "holy well," and has grown up on the margin of the sacred pond from which the locality derives its name. The two lakes, called respectively Kṛishṇakuṇḍ and Râdhâkuṇḍ after the name of the god and his favourite mistress, are faced on all sides with stone ghâts, and only parted from each other by a broad terrace of the same material. The town is crowded with temples and rest-houses (dharmsâlas), but none of them are of any antiquity or special architectural merit.
- 32. Râl, small town in Sadar tahsil, 12 miles N.-W. of head-quarters, is said to derive its name from having been the scene of one of Krishna's many battles. There are in the town three cenotaphs (chhattri) and the remains of a fort and a masonry tank, constructed at the end of last century.
- 33. Râvâ, village in tahsîl Mahâban, eight miles N.-E. of Mathurâ, derives its name from a fort, founded by one Râi Sên a century ago, where the police-station now stands.
- 34. Săpâbâb, tahsîl, 24 miles S.-E. of Mathurâ, possesses in the main street IIb. a large temple with an architectural façade; but the most conspicuous building in the town is a modern glittering white masjid. There are two other small masjids, a tomb of Mâmûn Bhânjâ (nephew and uncle), dated respectively A.H. 1152 and Ia. 1156, and four Hindû temples. The tahsîlî, which occupies the site of an old fort, is a small, but substantial, building, with a deep fosse and pierced and battlemented walls.
- 35. Sahār, small town in tahsîl Chhâtâ, 18 miles N.-W. of Mathurâ, possesses IIb. several old buildings with carved stone gateways of some architectural pretension. A number of handsomely-carved pillars, the remains of an ancient temple, were dug up here by Mr. Growse, and are now in the Mathurâ Museum.
- 36. Sahpāū, village in tahsīl Sādābād, 31 miles S.-E. of Mathurā, possesses a modern Jain temple dedicated to Neminātha; it stands immediately under the site of the old fort, which is well raised, and occupies an area of 13 bīghas. Many old Jain statues and large slabs of carved block kankar have been exhumed on the site of an ancient Jain temple. Close to the village in the fields is a large square domed building of some architectural merit, raised to commemorate the self-immolation of some Thākur's widow.
- 37. Shànpûr, village in tahsîl Kôsî, 36 miles N.-W. of Mathurâ, possesses Пъ. three small masjids and a small Hindû temple.

Mathura, pages 375-377.

- III. Nearly opposite is the hamlet of Chaukî, with remains of a fort erected by Nawâb Ashraf Khân and Arif Khân. There is a double circuit of mud walls, with bastions and two gateways of masonry defended by outworks, and in the inner court a set of brick buildings, now fallen into ruin.
- 38. Shergarh, village in tahsîl Chhâtâ, 22 miles N. of Mathurâ, derives its пате from a large fort, now in ruins, built by the Emperor Shêr Shâh. The village possesses 12 small Hindû temples, one Jain temple, and three masjids.
- 39. Sônkh, village in Sadar tahsil, 16 miles S.-W. of head-quarters, possesses III. the remains of an old fort, of which some crumbling walls and bastions are still visible.
- 40. Surîr, small town in tahsîl Mât, 22 miles W. of Mathurâ, possesses three IIb. small Hindû temples of no architectural pretensions.
 - 41. Tumaulă, village în tahsîl Kôsî, 21 miles N.-W. of Mathurâ, possesses a Ib. very large tank, partially filled up, in which a life-size statue of Buddha was discovered some years ago. The antiquity of the tank is attested by the enormous size of the bricks used in the foundations.

¹ Cunningham, Archwological Reports, Vol. XX, page 53.

V.—JIIÂNSÎ DIVISION.

I.-Jalaun District.1

- 1. Akôrî,² small village in tahsîl Orâi, 14 miles S.-W. of Jalâun, is the site of the great battle between Parmâl of Mahôbâ and Prithvîrâj of Dehlî, in A.D. 1172. Near the village stood till lately, as tradition says, a jayastambha, or "pillar of victory"; at present a nîm tree marks the reputed site of the jayastambha, and pilgrims still visit the place. Orâi is famous in Chand's Râsa as being the place near which the great final battle between Parmâl's troops and Prithvîrâj was fought, ending in the total defeat of the former; and certainly the extensive level plains between Kûnch and Orâi would very likely have been selected as the great battle-ground between armies, each consenting to forego all advantages arising from the natural features of the country and seeking a trial of sheer strength, not skill, for such was the great battle near Orâi according to all accounts.
- 2. Jalaun,3 tahsil and formerly head-quarters of the district, lat. 26°-8′-33″ N., long. 79°-22′-24″ E. In the outskirts of the town stand the ruins of a small fort, the former residence of the Marâtha Subâhdârs, with the remains of very fine buildings inside. The formes of the arches and the carvings on the slabs forming the arches are very good, but they are all modern. Near the fort are several collections of fragments of ancient sculptures, one of which is that of a figure seated cross-legged with the hands held up opposite the chest, supported on the intertwined tails of two Nâgas with human heads and bodies. Tradition says that the present ruined fort was built on the site of another one, and that in laying the foundations of the present one many fragments of statues were exhumed. No ruins besides this fort, however, exist in or about the place now.
- 3. Kālpî, tahsil, lat. 26°-7′-49″ N., long. 79°-47′-22″ E., 26 miles E. of Jalâun. The old town of Kâlpî stands on a bluff cliff of clay overhanging the Jamnâ. The ruined fort occupies the highest position, and commands the passage of the river; it has broken walls only on the three land sides, the river-front being inaccessible. III. Inside there are a few ruined buildings of the Marâțha period. To the westward there are many old tombs and masjids, now in ruins. At the north-west corner there is a piece of ground called Prabhâvati Mandî, or the "splendid market-place," where old Buddhist and Hindû coins are found in the rainy season.

Kâlpî was the birthplace of Mohês-dâs, a poor Brâhman who afterwards became famous as Râjâ Bîr-bar or Bîr-bal, the companion of Akbar. Kâlpî was also the residence of the holy Shaikh Barhan, who died at 100 years of age in A.H. 970, or A.D. 1562: he was buried in his cell, the site of which is not now known. According to Firishta the fort of Kâlpî was built by Vâsudêva,

¹ North-Western Provinces Gazetteer, Vol. I. pages 301-601, passim sub suce

⁵ Cunningham, Archaelogical Reports, Vol. VII, page 39.

³ Cunningham, Archaelogical Reports, Vol. VII, page 13.

Cunningham, Archaelogical Reports, Vol. XXI, pages 131-133.

Râjâ of Kanauj, the contemporary of Bahrâm Ghôr. But the people of the place know nothing of this doubtful chief, and attribute the building of Kâlpî to an ancient Râjâ, named Kâlibdêva. The earliest mention found of Kâlpî is the notice of its capture by Qutb-ad-dîn Aibaq in A.H. 593, or A.D. 1196.

The principal remains at Kâlpî are the tomb of Madâr Sâhib, of Ghafûr Ib. Zanjânî, of Chôr Bîbî—a square enclosed by trellises, of Bahâdur Shâhîd, and the great enclosure called Chaurâsi Gumbaz, or "eighty-four domes." There is a large statue of a lion at another tomb which is assigned to a barber. All these tombs are without any inscriptions, except that of Madâr Sâhib, which has a Persian inscription of the time of Akbar on the wall of the Naqqârkhâna.

The only remarkable building, however, is the Chaurasi Gumbaz. It is said to be the tomb of Lodi Shah Badshah, and some people even assign to it Sikandar Lodî; but we know he died near Agrâ, and that his body was carried to Dehli. The Chaurasi Gumbaz is built of blocks of kankar laid in lime and mortar. All the ornamentation is in stucco with flowered borders and bands. Altogether the style corresponds very closely with that of the Lodi period, and the people may be right in their attributing it to a Lodi prince. The building itself is only remarkable for its size, being 125 feet square outside and about 80 feet high,—seven narrow arched openings, divided by thick square piers. The whole building is divided, something like a chess-board, into eight lines of piers and seven lines of open space, thus forming 64 piers, all connected by twice 49 arches with the 49 intervening spaces covered by flat roofs. In the middle there are four piers omitted, and the square space thus obtained is covered by a lofty dome which rises about 60 feet above the flat terraced roof of the main body of the building. There are four small domes covering the four corner intersections, and there is a small domed turret over each of the sloping towers at the outer corners. But the appearance of the great central dome rising from about 40 feet or more cylindrical neck above the terraced roof is extremely bold and imposing. The meagre appearance of this domed tower might easily have been softened by the addition of a second storey rising from the next inner line of piers to within a few feet of the spring of the dome. The piers vary from six feet two inches to eight feet eight inches square, and the arches from six and-a-half feet to nine and-a-half feet span. Altogether the building is very solid, and is likely to last for a long time. No one can explain why the tomb is called Chaurâsi Gumbaz, or "eighty-four domes." There are only 40 intersecting spaces in the roof after deducting intersections in the middle, which are covered by the main dome. These, with the four corner turrets and the great dome, make only 45 possible domes, so that the name of Chaurasi Gumbaz is decidedly incorrect. The original name may have been Chalisi Gumbaz, or the "forty domes," which would have been strictly correct, as well as in accordance with a favourable Hindû number.

The present town of Kâlpî occupies a site to the south-east of the original old town and the great mass of ruined tombs and masjids. In Śrî Bâzâr there is an inscribed tomb dated A.H. 953; the entrance-door of Pattigalî bears a Persian inscription of A.H. 1081; and the well of Shaikh Abdul Ghafûr Zanjânî has a

III.

Hb.

III.

Persian inscription, dated in the 12th year of Aurangzib's ascession to the throne of Dehlî,

- At the village of Akbarpûr, or Aţaurâ, eight miles S.-E. of Kâlpî, there IIb. is a Sanskrit inscription of Samvat 1672, on the Chaukhanda of Rûpan Gurû, recording the erection of a temple in the time of Jahângîr.
- 4. KÜNCH,¹ tahsîl, lat. 25°-59′-30″ N., long. 79°-11′-55″ E., 16 miles S.-W. of Jalâun, possesses a number of remains of the Hindû period in the shape of pillars, architraves, &c. Two domes on twelve pillars each, called bâra-khambhâ, are traditionally ascribed to the commanders of Pṛithvîrâjâ, when he invaded Mahôbâ. There is also another dome which, however, is said to be a Musalmân tomb. Near one of the old domes is a small pool, called Chorâ Tâl, which is said to have been dug by Chorâ or Champat Râî, one of the commanders in Pṛithvîrâjâ's army, on his invasion of Mahôbâ. The domes, however, are all Musalmân; the pillars are indeed Hindû, and so are the other stones used in the construction; but, as usual, they have been misplaced by the Musalmân builders; the roof, a brick dome, is of a style not anterior to the early Moghal period.
 - In the citadel at Kûnch is the tomb of one Mahmûd Shâh Ghâzî; it was built during the Bundela ascendancy between Samvat 1650—1700. This Mahmûd Shâh is the reputed builder of the masjid at Îrichh in the Jhânsî district.
- III. At the village of Mahêspûr there is a mud fort.
 - 5. Madhogarh, tahsîl, lat. 26°-24′-15″ N., long. 79°-15′-23″ E., is devoid of any antiquarian remains. There are brick forts at the villages of Râmpura, Narol, Umrî, and Hajîpura, and earth forts at the villages of Gopâlpûr, Rudaulî, and Cher.
- 6. Orâî, tahsîl and head-quarters of the district, lat. 25°-59'-5" N., long. 79°-29'-35" E., 12 miles S.-E. of Jalâun. The old town of Orâi stood on a hillock of considerable size, southwards of Nâyâbasti, the present village of Orâi. On the hillock are the remains of a brick fort, of which one ruinous tower with a Musal-IIb. mân tomb still exists. The tomb of Pîr Sarwânî in the same neighbourhood is entirely built of the remains of an old Hindû temple of the Chandella period. In the old town principally carved stones of black granite of the Chandella pattern, scattered about as door-steps and posts, are rather numerous, and no doubt Orâi was formerly a place of some importance.
- At the villages of Hardôî Mâfî and Bajhera Kherâ are formidable III. earth forts, with high brick bastions on the four corners.

II.—JHANST DISTRICT.2

1. Barûâ Sâgar, town in tahsîl Jhânsî, 12 miles S.-E. of head-quarters. To the north-west of the town is a fine old castle on the border of the lake, said to lb. have been built about 130 years ago by U dit Singh, the Bundela Râjâ of Orchhâ. The ground-floor consists of large vaulted rooms, the large windows of which look out upon a deep precipice near the lake, and a winding staircase leads to the first floor. The rooms at the top are surrounded by a terrace overlooking the lake.

¹ Cunningham, Archwological Reports, Vol. VII, page 39.

¹ North- Western Provinces Gazetteer, Vol. I, pages 362-601, passim and coce.

There is a wide stone road winding round the rock upon which the fort is built, which leads right up to the second storey. The lake is the most attractive feature in the landscape.

On the north-east end of the embankment there is a small hillock with a ruined temple of the Chandella period. A little further to the east, close to the Ib. banks of the lake, is a small unique temple of the early Chandella period, measuring 15 feet by 12 feet, and built of massive blocks of grey granite without mortar. The temple proper consists of four small cells, each of which has a slightly ornamented door, and is capped with a kalasa resting on a low pyramidal row of stones. Over three of the doors is a small figure of Ganêsa, whilst the fourth contains a figure of Durgâ. The portico in front of the temple is supported on five massive pillars, with cruciform capitals, topped by large architraves and massive slabs. The temple is locally called Ghuguâ Math from the neighbouring village Ghuguâ.

On the village lands, about a little less than three miles to the west of Barúa Sagar, near the village of Phatera, is a temple-tower of the ninth century, built on the summit of a dih, and called Jarah-ki-Math, constructed of solid blocks Ib. of sandstone, richly carved with figures from the Hindû pantheon, which have been much defaced by the Musalmans. Externally it measures about 22 feet by nine feet, but originally it extended at least another nine feet in an eastward direction. It is built in the form of a sikhara, the outline of which is simple. A great portion of the east façade is covered with "horse-shoe" diaper work, and profusely ornamented with figure carving of a high class nature. On the north and south sides project hooded balconies, and the west is broken up by buttresses. The interior is square, and contains an image of Siva and Pârvatî. At the angles are eight massive stone shafts of the later Gupta period, which support lintels carrying a beautifully-carved ceiling. There are several masons' records on the lintels in characters of the later Gupta period, and a fragmentary inscription of the same time on a statue of Durgâ.

Close by, on a neighbouring hillock, are the remains of a Chandella temple.

At the village of Bangâma, one mile to the west, on the banks of the Betwâ, are the ruins of a large temple of the Chandella period.

III.

III.

Hb.

Ib.

Jains.

2. Bhander, a fairly old town in tahsil Jhansi, 24 miles N. of head-quarters. Jain remains, as carved granite stones of the Chandella period, may be seen in all parts of the town, degraded to door-steps or corner-stones or pillars of cow-sheds; and the principal masjid, built in Aurangzib's time, consists in great part of Jain pillars with cruciform capitals, resembling on a small scale the famous masjid at Kanauj. Between the site of the present town buildings and the Pahûj river there is a rather extensive hill, now almost deserted, but bearing evidence in caves and deep-cut tanks, in wells shaped in the solid stone, and in remains of temples brought together to form a masjid, of having once been occupied probably by a large establishment of

Other small hills in the neighbourhood bear evidences of a like kind; and at Ib. Bharaulî, three miles south-east of Bhânder, there is a perfect temple of the Chandella period, built of solid stone, mostly granite, the interior being elegantly carved with figures. In plan it is cruciform, and the centre is occupied by a lingam.

III.

III.

whilst the arms of the cross are utilized as porches. The western entrance is elaborately ornamented, and the shafts on each side of the doorway leading to the sanctum are unique. The sanctum is roofed by a fine cusped ceiling supported on stone lintels carried on columns. The outside forms a sikhara, and is crowned by a kalasa. The whole is in a fair state of preservation, and standing as it does between the defile of two rocks, looks very picturesque.

3. Gehrahô, small village in tahsîl Mâû, 25 miles S.-E. of Jhânsî, possesses Ib. on a hillock an old Chandella temple, of hewn stones and decorated by sculptures, in a fair state of preservation. The temple is built on the usual plan of an entrance hall, a central hall, and a sanctum with the door to the east. It is 36 feet long by 20 feet broad, and about 40 feet in height above its terrace. The central hall is open at the sides, with broad seats all round, backed by sloping parapets. The entrance door to the sanctum is richly decorated; on the face of the door-step is represented Ganga on her crocodile. The temple is dedicated to Siva, who is represented over the centre of the entrance with Brahma on his right and Vishņu on his left, and the navagrahas, or nine planets, arranged between them. The sanctum still contains a famous lingam of black basalt, called Guraiya Mahadêva. The lower part of the spire is perpendicular, but the upper part is sloping with a very slight curve. On the perpendicular sides are 10 niches containing figures taken from the life of Siva. In the upper part of the spire the angles only are ornamented, all the middle spaces being left quite plain. The temple was built during the reign of the Chandella Prince Kirttivarman, as recorded in an inscription near the entrance door.

A broken image of Neminâtha, with a record of Samvat 1228, is lying in the courtyard of this temple; originally it came from the bank of a large lake half a mile to the north of the temple.

4. GÜRSARÂÎ,¹ village in tahsîl Garothâ, 40 miles N.-E. of Jhânsî, contains 11b. nothing ancient. The fort, although not apparently built on a rock or hillock, is an imposing-looking structure, with great outer masonry walls and fortifications, the buildings high raised within to fully 250 feet. Its northern side is bordered by a large lake with built-up edges forming steps to go down to the water.

About four miles east of Gûrsarâi, and half a mile off the road, there is a cluster of 12 small villages, called Sirwabaran; in the midst of these villages, which are all situated close to each other at the foot of a clump of hills, are two tanks called Amar Tâl and Râi Tâl. Both are ascribed to the Chandellas; on the banks of Râi Tâl is a great roundish boulder with two inscriptions of Sanvat 1604 and 1608. At the upper end of the Râi Tâl stands a ruined temple of dressed stone; it is a mere heap of ruins, but the chamber inside is still entire. It appears that the Musalmâns have to answer for the destruction of the temple, as one of their style of rubble-built towers exists still at one corner of the mass of ruins. Close by, but separated from it by the spur of one of the hills running along an edge of the tank, there is another temple: of this the entrance is still standing, and forms a striking object in that wild, solitary spot. It is in the old Chandella style, massive architraves supported by pillars with bracket capitals; the stones are held together by iron

¹ Cunningham, Archaelogical Reports, Vol. VII, page 31.

cramps; all are dressed and many carved into easy geometric patterns. On a rock close to the second temple is cut a statue of Dêvî, and near it a line of inscription records the name of the sculptor in Samvat 1190. On a rocky mound to the south of Râi Tâl is a bâradarî of rubble and mortar. From the style of construction it appears to be Musalmân; but the disposition of the chambers, a hall surrounded by a verandah, its having at one end a chamber with only one door and no window, show it to have been a Hindû structure, built during the Musalmân ascendancy. This is confirmed by an inscription on the rock on which it stands, from which it is apparent III. that a satî was performed here in Samvat 1676, during the reign of Bîr Singh Dêo of Orchhâ. Perched on top of one of the hills there is a small shrine of no particular interest; it has a bulbous dome, which of itself settles the question as to its antiquity.

 Kishnî Khûrd, small village in tahsîl Mâû, 18 miles S.-E. of Jhânsi, possesses the remains of a Chandella temple of the oldest known style.

At the village of Arjar, three miles further north, there is a large tank with an inscription of Raja Sujan Singh of Orchha, dated Samvat 1728 and A.H. 1082.

III. At the village of Sakrâr, four miles further north, are the remains of a Chandella temple on a brick mound. A large number of sati pillars are scattered round this kherâ.

6. Îrichн, town in tahsîl Môth, 42 mîles N.-Е. of Jhânsî, possesses several ancient remains, but all are used up in Musalman structures. 'The Jami Masjid Ia. in the fort is a fine specimen of its kind, and consists of a group of small domes round a large central one; the domes are all supported on massive pillars formed by building up a square pillar of rubble with old Hindû pillars at the four corners. The result is a very massive square low column: the same system of building is employed in the cloisters, all edges having a Hindû pillar inserted or built in as a facing. The central hall, from its size, height, and the evident massiveness of all constructive details, produces a striking effect. The domes are all hemispherical, with perhaps the slightest possible inclination towards a bulge; these domes are crowned by foliated caps of enormous size, which make the form of the domes unpleasing. The colours used are red, blue, yellow, and green; the arches are of stone and brick, as also the walls. An inscription2 dated A.H. 815, or A.D. 1412, is let into the wall on the left of the main arch; according to it the masjid was built by Qazî Zia-ad-din, brother of Khân Junaid, the imperial jagîrdâr of Dehlî, during the reign of Mahmud Shah. From the style of construction it evidently belongs to the time of Aurangzib. It is, however, possible that an older masjid was repaired, and the enormous caps then added to the domes in Aurangzib's reign. There are also the remains of walls and gateways in the fort. III.

The fort appears to have been originally built in the same style as the one at Jaitpûr in the Hamîrpûr district, but of square stones set without mortar, forming a facing to a rubble cone, and diminishing in steps towards the top. Of the original Hindû fort a fragment, namely, the portion jutting into and re-curving in the river,

Ib.

¹ Cunningham, Archwological Reports, Vol. VII, page 33.

² Proceedings, Asiatic Society of Bengal, for 1874, page 69.

 $\Pi b.$

alone exists. Tradition asserts that the lowest portion of the gateway which is still sound is Hindû. But the Musalmans, when they appropriated the place, appear to have discarded the Hindû design of the original fort, and to have built a fort enclosed on all sides, the walls on the land side being built in all probability along the remains of the original Hindû walls, and that on the river side being added by themselves, thus leaving out entirely the re-curved portion of the original Hindû wall that juts into the river. At present even the Musalman walls are in ruins, as they were originally not massively built. These were probably erected during or after Akbar's reign. The fort of Îrichh, into which the assassin of Abûl Fazl had been driven as a last refuge, was besieged, the wall breached, and the fort taken by orders of Akbar in the 47th year of his reign.1 The present walls, therefore, are subsequent to this period. There are five gates, two of them have inscriptions, dated A.H. 1055. The Musalman tombs and the other masjids are of no particular interest. Among the pillars used up by the Musalmans in their tombs are some with the peculiar Hindû block interposed, cutting up the length of the long pillars into two and some into three portions. In the village itself there is a sati pillar with a record of Samvat 1699, and a baoli with an inscription of Samvat 1690.

About four miles from Îrichh down the Betwâ river, there is a hill called Dêokâlî. Tradition says that here was the palace of Hiranyakasipu. In the river just below is a deep kuṇḍ; the story states that from the top of this hill Hiranyakasipu caused his son, Prahlâda, to be thrown into the river, which here is bottomless. The marks of Prahlâda's foot are shown on a rock in an oblong hole three inches by one and-a-half or two inches wide.

About six miles to the south-east of Îrichh, near the village of Pathâ-III. Sigaulî there is a large lake with the ruins of a large Chandella temple. A colossal statue of Vishņu is still well preserved.

The village of Pûnch, four miles north-west of Îrichh, possesses a formidable IIb. mud fort with high walls and brick bastions on the four corners.

7. Jhānsì, head-quarters of district, lat. 25°-27'-30" N., long. 78°-0'-37" E. Ia. On a rock overlooking the town is a fort built of stone by Bîr Singh Dêo, Râjâ of Orchhâ, in the reign of Jahângîr, and strengthened with outworks taking in all the rock outside. In A.D. 1744 Nârû Śaṅkar, a Marâtha leader, made great additions to the fort and founded the present town. The city wall was erected by Shêo Râo Bhâo, subâhdâr, between A.D. 1796—1814, and is furnished with strong arched gateways of stone. The fort outworks continue the city wall with irregular outline, but very thoroughly. Naturally the place is exceedingly strong, and the fortifications are most durably constructed.

Immediately outside the city walls on the east side there is an extensive lake IIb. called Lakshmi Tal, on the banks of which are several good temples, but of no architectural merit. On the west side of the city outside the walls there is another but less extensive lake, called Aukheya Tal.

8. Mâû, tahsîl, lat. 25°-14'-40" N., long. 79°-10'-45" E., 40 miles east of Jhânsî, III. possesses an old brick fort with bastions on high ground. In the time of the

¹ Blochmann, Min-i-Akbari, page 169.

- Marâțhas Mâû was partially fortified with a high stone wall, but the fortifications were never apparently completed. There are several Hindû temples hidden behind walls of no architectural or antiquarian merit; the Jain temple, however, with its solid spires and many cupolas, presents a fine appearance.
- III. Two miles east of Mâû, near the village of Marhâ, are the remains of an old Chandella temple, of which the sanctum is still standing.

About four miles to the south of the tahsil is a hillock called Roni, on the summit of which stands a small temple sacred to Kedaranatha, apparently built of the materials belonging to some old Chandella temple.

9. Ranipür, small town in tahsîl Mâû, 36 miles S.-E. of Jhânsî, possesses a remarkably fine Jain temple with two high steeples and a multitude of cupolas running all around the high and extensive enclosure wall of the temple.

10. Salôn, small village in tahsîl Jhânsî, 23 miles N.-W. of head-quarters, possesses an old Hindû temple in a fair state of preservation, constructed by the Chandellas of coarse-grained, hard granite, dressed and carved into easy geometric patterns.

III.—LALITPÜR DISTRICT.1

- 1. Banpur Khas, large village in tahsil Mahroni, 21 miles E. of Lalitpur, possesses a quarter of a mile to the east of the village a Hindû building, called naudvari, in fair condition and erected during the Musalman ascendancy, and to the south of the village four Jain temples, built about Samvat 1200, as is apparent from several inscribed statues inside the temples.
- Bar, small village in tahsil Mahroni, 16 miles N.-E. of Lalitpür, possesses close to the village on the embankment of a tank two, and on a neighbouring hillock four, Hindû brick maqarbās, slightly decorated, built at the latter end of the fifteenth century, of no particular interest.
- 3. Chândpûr,² old deserted town in tahsîl Lalitpûr, 18 miles S. of headquarters. The remains of Chândpûr are just half way from Dûdâhî and Dêogarh, being seven miles to the north-west of the former and upwards of six miles to the east of the latter. The old town of Chândpûr is completely deserted, there being not even a single house standing; but over the space of half a mile from Jahâzpûr towards the north-east there are many traces of buildings, amongst which are found several groups of ruined temples, partly Jain and partly Brâhmanical. They belong all to the beginning of the twelfth century, as is apparent from the few inscriptions found amongst the ruins of the temples. On the embankment of a large lake stands the life-size figure of an elephant, beautifully decorated with carvings, and bearing an inscription of Samvat 1207.
- 4. Deogarh, old deserted site in tahsîl Lalitpûr, 22 miles S.-W. of head-III. quarters, immediately overhanging the river Betwâ. The fort of Karnâlî rises above the plain on the south to a height of about 300 feet. Here the Betwâ makes a great sweep to the westward enclosing the projecting headland of Deogarh and its

Ib.

IIb.

/?

¹ Nort h- Western Provinces Gazetteer, Vol. 1, pages 361-601, passim sub coce,

² Cunningham, Archaelegical Reports, Vol. X, page 96.

³ Cunningham, Archaelogical Reports, Vol. X, pages 100-110.

III.

Ib.

fort on three sides. The site is a singularly picturesque one. To the south a long flight of steps called Rajghati, leads from the brow of the fort to the waters of the Betwa, which here rush between the rocks with a roar which is heard from above the overhanging cliffs. The fort itself is quite overgrown with jangal and infested by wild animals; but on the eastern side the dreariness of the view is relieved by the ruins of an extensive group of Jain temples. The principal temple consists of an Ib. open pillared hall or arcade, 42 feet three inches square, with six rows of six plain pillars. The centre opening is eight feet three inches between the pillars. In the middle of the hall, a platform, raised between the four central pillars with a back wall towards the outside, is covered with a large collection of colossal naked Jain figures, some of which are inscribed in characters of the ninth century. The sanctum, which is a massive building, 39 feet two inches by 34 feet three inches outside, is reached by a low opening or hole only one foot nine inches wide, and contains a colossal statue of Rishabhanatha. In front of the hall, at a distance of 16 feet nine inches, there is a detached portico or canopy supported on four massive pillars upwards of two feet square at base. On one of these pillars there is a very valuable and interesting inscription of Raja Bhojadêva, dated in Samvat 933 and Sake 784, the latter date being expressed in words as well as in figures. The great value of this inscription is that it fixes absolutely the date of Bhôjadêva of Dhara in A.D. 862. Besides this, there are several other valuable records, viz., a long inscription of the later Gupta period, and several others dated Samvat 1051 and Sake 1358. An inscription of Samvat 1481, or A.D. 1424, was found some years ago close to this temple and sent to the Indian Museum; it records the dedication of two Jaina images by a Jain priest, named Holi, during the reign of Shah Alambhaka of Mandapapura, i.e., Sultan Hushang Ghori, alias Alap Khan of Mându in Mâlwâ.

In the neighbourhood of the great Jain temple there are about 22 small temples more or less ruined. Judging from the *inscriptions*, the temples of this group range in date over three centuries, from A.D. 862 to 1164.

Outside the river-gate of the fort, at the head of a flight of steps leading down to the Betwå and near a figure of Dêvî, there is a short inscription in two lines of Gupta characters. On another part of the rock near the river-gate there is a very neatly-engraved inscription of eight lines of peculiar characters, each letter having a saucer-shaped head formed by a curve under the straight lines of the mâtra. The inscription was recorded by Vatsarâjâ, the minister of the Chandella Râjâ Kîrttivarman, after whom the fort appears to have been named Kîrttigiridûrga, in Samvat 1154, or A.D. 1097. There are several other records in caves close to the bank of the Betwå, dated Samvat 1114, 1126, 1545, and 1549.

But the most interesting monument now remaining at Dêogarh is a solitary square temple on the plain below, about half way between the fort and the village. It was dedicated to Vishņu, and belongs to the later Gupta period, as it possesses all the characteristics of the style of the Gupta period, although its pyramidal roof points to a later date than that of the flat-roofed temples of Sanchi, Irân, and Tigawâ. The Gupta temple of Dêogarh is laid out on the usual Hindû

¹ Journal, Asiatic Society of Bengal, Vol. LII, pages 67-80,

plan of squares. The whole occupies nine equal squares, of which the temple itself forms the middle square, while the remaining eight squares form a terrace, about five feet all round. The temple is 18 feet six inches square outside, with the entrance on the west, leading to a sanctum of nine feet nine inches square. On each of the four sides of the terrace there was a flight of steps leading up to a portico or verandah supported on four large pillars. Two of these pillars still remain complete, but fallen, and there are portions of two others of the same design lying on the edge of the terrace. From the position of the two unbroken pillars it is certain that they must have stood near the temple, although there are no pilasters attached to the walls with which these pillars could have been connected to form a portico. But high up on each wall there are the remains of four beams or architraves which once projected from the building for the purpose of supporting a flat canopy over the sculpture in the niche below. A piece of one of these beams, between three feet and four feet long, still projects on the east side, and still carries a portion of its roofingslab. Now, the lower side of these projecting beams is 13 feet six inches above the original level of the platform, and therefore the pillars which carried their outer ends must have been of the same height.

The walls of the temple on both sides of the arches are quite plain. Over the doorway there is a frieze with five bases of beehive shape, very elaborately finished. Above them there is a line of dentils with lions' faces, the whole surmounted by the bold string-course which is common to all the temples of the Gupta period. To the right and left in the usual positions at the corners of the doorway stand the two conventional figures of the Ganges and Jamna, the former supported on her crocodile, the latter on her tortoise: on the other three sides the ornamentation is limited to one large panel in the middle containing a group of figures in alto-relievo. Each of these panels is five feet in length and between three feet and four feet in breadth. A feature peculiar to the Déogarh temple is the wide platform on which it stands, with its continuous row of sculptured panels on all four sides. Each face of the Dêogarh temple had 16 alto-relievo sculptures, two feet six inches in height by one foot 101 inches in breadth, which were separated from each other by nine inches pilasters with side grooves, so as to fix the slabs in their places. In the middle of each face leading up to the platform there was a staircase flanked by side walls with two alto-relievos on the outer faces. Thus there were 20 sculptured panels on each of the four sides, or 80 altogether. Apparently the side walls of the staircases terminated in solid blocks which were sculptured on three faces. The drawing of the figures is generally spirited, and the attitude is not only easy, but graceful, and the expression often dignified. There is no inscription of any kind about this temple, and not even a single letter or mason's mark by which its age could be fixed definitely.

5. Dûdâhî, small village in tahsîl Lalitpûr, 19 miles 8. of head-quarters, is situated on a ridge to the north of the Râm Sâgar, a large lake which stretches eastward for nearly a mile to the fort of the Dungria hill, with a uniform breadth of nearly half a mile. That Dûdâhî was once a place of some importance is proved by the extent of its ruins, which cover both banks of the lake. The most

¹ Cunningham, Archwological Reports, Vol. X. pages 90-96.

Ib. consists of two groups of two temples with spires, called by the people Sarahi Mathiya or "tall temples," a small Varâha shrine with a figure of a boar under a four-pillared canopy, a small Linga temple, and a second Linga shrine close to the temple of Brahmâ. There is a second boar statue on the bank of the lake and a small one near the Varâha temple. There are also the remains of two Jain III. temples, one of which contains a naked standing figure, 12 feet high.

16.

The largest temple is built on a very peculiar plan: in form it is a cross with two long limbs and two short limbs meeting in the middle. The central portion consists of two rooms with a doorway between them, so that there is no back wall against which a statue could be placed. The whole of the outer casing of the spire has fallen down, the lintels of the doors have been removed, and there is no trace of any pedestal for the reception of the statue. It was, however, most probably a Jain temple, which once possessed a platform running round the walls of the two rooms for the enshrinement of the statues of the 24 Tirthamkaras. and which had been wantonly wrecked by hostile Brâhmans. This Jain temple consists of two rooms already mentioned, each of which opens into a pillared hall. The two halls are connected by a narrow passage running along each side of the two central rooms. In front of each hall there is a large pillared porch and a smaller one in the middle of each of the side passages. The building is, therefore, perfectly symmetrical, the two longer ends to the east and west being exactly alike, as well as the two side projections. By this arrangement the great spire rises exactly over the middle of the building, which is more pleasing than the usual plan of placing the highest spire at one end of the temple. The extreme dimensions of the building are 52 feet long by 37 feet broad, with a height somewhat greater than the length. The joint length of the two centre rooms is 19 feet and the breadth of the main body of the building, including the two side passages and their outer walls, is also 19 feet, so that the spire rises from a central square of 15 feet.

The second temple is one of the rare examples of a shrine, dedicated to Brahmâ. It is built on one of the common plans of a Hindû temple with a small entrance porch, a large hall of assembly 25 feet square, supported on four pillars, Ib. and a dark sanctum reached through a small vestibule. Altogether it is only 421 feet long by 25 feet broad; but though comparatively small, it is one of the most richly decorated temples. Every architrave is deeply carved on its underside in a variety of patterns, all in the style of the beautiful honeycombed designs of the ceilings. The four central pillars of the hall are singularly graceful in their proportions and unusually lofty for the small size of the temple, being nine feet six inches in height to the base of the bracket capital. Over the centre of the sanetum doorway there is a three-headed figure of the bearded Brahmâ with his goose supported by the navagrahas or "nine planets," four on one side and five on the other. The central position of the figure places the dedication of the temple to Brahmâ beyond dispute. All the six inscriptions now existing at Dûdâhî are in this temple; the earlier ones are engraved in Kutila characters of the 10th century, the others are in ruder characters of a somewhat later date. From these records it would appear

that the temple was built by Devalabdhi, the son of Krishna and Asarvâ, and the grandson of the Chandella Râjâ Yaśovarman, about A.D. 1000. At this very time, as we learn from Abu Rìhân, Dûdâhî was a very large town.

III. The second group of temples lies half a mile to the west in the midst of a dense jangal. The whole are known as baniyâ-kâ-barât, or "the baniyâ's marriage company." They are all in ruins, and most of the stones have been carried off; but the foundations are still standing, and many of the statues still remain, but all more or less broken.

- 6. Jhalònî,¹ village in pargaṇa Tâl Bahat of tahsîl Lalitpûr, 25 miles N.-W. of head-quarters. About 16 miles to the north of Chandêrî, the road to Gwâliâr passes over a low range of hills with a lake at the foot. On the top of the pass there is a tall slab, 18 feet in height, called chîra, or "the slab," with a Devanâgarî inscription in seven lines, dated Samvat 1351 and Sake 1216, or A.D. 1294.
- 7. Lalitpür, head-quarters of district, lat. 24°-21′-34″ N., long. 78°-27′-50″ E. IIIb. In the town there is a small masjid 19 feet 4 inches square, built entirely of Hindû materials, or perhaps it is part of a Hindû temple, only slightly altered. It is called Bânsâ, and bears an inscription in Devanâgarî letters of the time of Fîrûz 8hâh. The erection of the masjid must therefore be later than the date of this inscription, Samvat 1415, or A.D. 1358. The pillars of the masjid apparently must have belonged to three or four different temples, as they are of very different sizes as well as of different patterns. There are six fluted pillars of sixteen sides, which are very fine specimens of Hindû work. Many carved stones of black granite may be seen as isolated posts and door-steps, and at one place there are Jain remains of square pillars with cruciform sur-capitals, now part of a Hindû temple, of no architectural pretensions.

Close to the town there are four Jain temples called Chatarpâl, built of IIb. stones some 250 years ago; they are of no particular interest.

Other buildings of interest are the Ås båolî, erected in A.H. 877; another bâolî, built in Samvat 1681; and a shop erected in A.H. 1100. There are also a large number of satī monuments, some of which are inscribed in Samvat 1402, 1734, 1752, 1763, and 1803.

At the village of Barode, 10 miles south-west of Lalitpûr, there are two large slabs inscribed in Samvat 1167 and 1405 respectively.

8. Madanpür, small old village in tahsil Mahroni, 38 miles S.-E. of Lalitpür. There are six temples, all more or less ruined. The oldest of these are three Jaina temples situated to the north of the town, where the original town is said to have stood. Two others (known as the Barâ and Chhotî Kachêris) are at the north-west corner of the lake, and the sixth, a temple of Mahâdêva, at some distance to the north-east of the lake, of which only the shrine remains, covered outside with sculptures. On the north side of the village there is a Jain temple with an inscription dated Samvat 1206, or A.D. 1149, which contains the name of Madanapura. But the most interesting and valuable inscriptions are preserved

Ib.

Ib.

¹ Cunningham, Archaeological Reports, Vol. XXI, page 176,

³ Cunningham, Archaeological Reports, Vol. XXI, page 175.

² Cunningham, Archaeological Reports, Vol. X, page 98; Vol. XXI, pages 171-175.

III.

IIb.

in a small open pillared building supported on six square shafts, which is known by the name of baradari. On the pillars of this small building there are engraved two short records of the great Chauhan Prince Prithviraja, which are of singular interest and importance. Each of these consists of only four lines; but they are of supreme historical value, as they record the date of Prithviraja's conquest of King Paramardi (Parmal) and his country Jejakabhukti in Samvat 1239, or A.D. 1182; whilst in the Mahoba Khand of Chand's Prithvi Raj Rasa the date of the Chandella war is given as Samvat 1241, or A.D. 1184. A third short inscription on another of the pillars seems to show that the present pillared arcade was originally the hall of a temple dedicated to Siva.

Five miles to the S.-E. of Madanpûr is the village of Bikaurâ, on the left bank of the Jâmini river, which possesses some small ruined temples. Markherâ, on the opposite bank of the river, also has a small temple.

9. Saurâî, large old village in tahsil Mahronî, 37 miles S.-E. of Lalitpûr, possesses three stone temples of the Chandella time. The largest one is a Jain temple dedicated to Adinâtha, the other two temples are Vaishṇavî. The best preserved of these temples is the Jaina structure. It has a small portice in front 10 feet 2 inches square, the whole temple being only 21 feet 6 inches long by 13 feet broad. But in spite of its smallness, it is a fine building, as it is richly ornamented outside with two rows of sculptures, of which some are the usual naked standing figures of the Jainas, while the rest are Brâhmanical figures. In the village there are two slabbuilt temples dedicated one to Vishṇu and the other to Gaṇeŝa: both temples have porticoes; the latter is flat-roofed, and the former pyramidal. On an upright slab at a well there is an inscription of Samvat 1707, or A.D. 1650. Saurâi must once have been a very flourishing place.

10. Sîrônî Khurd, small village in pargana Bânsî of tahsîl Lalitpûr, 12 miles N.-W. of head-quarters, possesses several modern Jain temples built of brick, mortar, and old temple ruins with a good compound wall. Both inside the compound and lying about the jangal outside the compound are many ancient statues of the Jain Tirthainkaras, some of which are *inscribed* and dated Sanvat 1252. Inside the largest temple there is a statue of Sântinâtha, which is remarkable for its size, being two storeys high.

Inside the compound of Santinatha's temple, some careful baniya has stood up and supported with brick and lime buttresses a huge slab 5 feet 10 inches by 4 feet, on which there is a rather perfect Kuṭila inscription of 46 lines, recording that during the reign of Mahêndrapâla Dêva, son of Bhôja Dêva, in Samvat 964, on the third of the dark half of the month Margasiras, the illustrious Undabhaṭa bhaṭa, being in residence at Siyaḍôni, made certain religious grants to a Vishnu temple at that place. This statement is interesting, because it shows that Undabhaṭa was a general or feudatory of the paramount sovereigns of the country, the rulers of Kanyakubja.

This is the inscription referred to by Dr. Fitz Edward Hall,2 of which a copy by a native had been supplied to him by General Cunningham; but which, though

¹ Cunningham, Archaelogical Reports, Vol. XXI, page 170.

² Journal, Asiatic Society of Bengal, Vol. XXXI, page 6.

intended for a fac-simile, was so very inaccurate that he could make but little out of it. General Cunningham did not know whence it had come: he says "it is believed to have been found somewhere in the Gwâliâr territory, but the actual site is not known." Mr. Fleet suggested that it was to be looked for in the neighbourhood of Sîronj, 160 miles south by west of Gwâliâr. Sîronj, however, is full 60 miles N.-E. of Sîrôni. Dr. Burgess re-discovered this important document in November, 1887.

Outside the compound of the modern Jain temples is standing an exquisite Ib. torana, or gateway, which, though half-ruined by neglect, is still singularly beautiful, and ought to be carried away to a place of safety.

A little further to the east, on the opposite bank of the Kherâr river, at the village of Satgato, are the remains of a large Vishņu temple round a bâolî. A large number of fine sculptures are scattered about, which undoubtedly belonged to the magnificent fane to which the big Sîrônî inscription refers. There are round the bâolî several satî pillars, dated Samvat 1040, 1434, and 1453.

- 11. Surahar,³ or Surar, old town on the high road between Lalitpûr and Chandêri in tahsîl Lalitpûr, 10 miles W.-N.-W. of head-quarters, possesses a small temple, only 12 feet 8 inches square outside, with three figures of Vishņu in niches outside; the door faces the west. There is also an old inscribed satî pillar, on which occurs the name of the village.
- 12. Tâl Bahat, town in tahsîl Lalitpûr, lat. 25°-2′-50″ N., long. 70°-28′-55″ E., 26 miles N. of head-quarters, possesses to the east of the town on the summit of a longish range of primitive rocks extensive masonry battlements enclosing a fort. The fort and buildings might be worth a general survey: though not old, they are so entire as to show very well on a small scale the style and arrangements of a Marâțha fortification and of their secular architecture.

Inside the fort are the ruins of a temple, sacred to Vishņu in his boar avatāra, said to have been built some 200 years ago. In front of the entrance is a big Hanumân, painted red and crowned. The vestibule is oblong and groined; from about eight feet up the walls they are painted. First there are six bands including the one on the spring of the groins. The first or lowest contains a procession of persons in Marātha state dress on foot, on horses, elephants, &c. The second is divided into panels containing planets and gods alternately; the third is a very elaborate decorative band chiefly of plants and worth copying; the fourth and fifth are much narrower and also merely decorative; and the sixth is broader and divided into compartments by palm trees, each space containing a figure. The roof is in large panels divided by fillets of flower pattern, and each filled with flowers and some figures in the two middle compartments. The whole is so faded that it is difficult to make out the minuter details and merit of the work from below; but the paintings could easily be restored by a simple and effective application, which would preserve them vivid for years.

¹ Journal, Asiatic Society of Bengal, Vol. XXXIII, page 227,

² Indian Antiquary, Vol. XV, page 108, note.

² Cunningham, Archwological Reports, Vol. XXI, page 176.

Inside is a handsome groined room, the mandapa of the temple: it has been used for cooking in and the paintings are smoked, but could perhaps also be revived. The threshold of the inner gate of the south-west entrance has been taken from some ancient temple.

There is a large group of sati monuments beyond the fort on the border of the IIb. lake, most of which are dated Samvat 1735. On the tomb of Pir Taj Baj there is a long Arabic inscription of A.H. 874.

VI.—ALLAHÂBÂD DIVISION.

I.—Allahâbâd District.1

1. Allahabad, head-quarters of district and seat of Government, North-Western Provinces and Oudh, lat. 25°-27'-43" N., long. 81°-54'-12" E., is the ancient Prayaga, the well-known place of pilgrimage at the junction of the Ganga, Yamuna, and Sarasvatî where Akbar built his fort of Illahabas, or Allahabad as it was afterwards called by Shah Jahan. The name of Prayaga is recorded by the Chinese pilgrim Hiuen Tsiang³ in the seventh century, and is in all probability as old as the reign of Asoka, who set up the stone pillar about B.C. 240, while the fort was not built until the end of the 16th century.

According to Hiuen Tsiang the city was situated at the confluence of the two rivers, but to the west of a large sandy plain. There were two sampharamas with a few followers who belonged to the Hinayana, or Lesser Vehicle, and several Brâhmanical temples. To the south-east of the city, in a champaka grove, there was a stûpa which was built by Aśoka; although the foundations had sunk down, yet the walls were more than 100 feet high at the time of Hiuen Tsiang's visit. By the side of it was a stûpa containing hair and nail relics of Buddha. Near this last stûpa was an old saingharama where Dêva Bodhisattva composed the Satasastravaipulyam, refuted the principles of the Hînayana, and silenced the Brahmanas. In the midst of the city there was a Brâhmanical temple beautifully ornamented, and celebrated for its numerous miracles, to which the presentation of a single farthing procured as much merit as that of 1,000 gold coins elsewhere. Before the principal hall of the temple there was a large tree with wide-spreading boughs and branches, and casting a deep shadow which was said to be the dwelling of an anthropophagous demon. The tree was surrounded with human bones, the remains of pilgrims who had sacrificed their lives before the temple, a custom which had been observed from time immemorial. There can be little doubt that the famous tree described by the Chinese pilgrim is the well-known akshaya vata, or "the undecaying Banian tree," which is still an object of worship at Allahâbâd. This tree is now situated under ground at one side of a pillared court which would appear to have been open formerly, and which is probably the remains of the temple described by Hiuen Tsiang.

The temple is situated inside the fort of Allahâbâd to the east of the Ellenborough barracks and due north from the stone pillar of Asoka and Samudragupta. Originally both tree and temple must have been on the natural ground level, but from the constant accumulation of rubbish they have been gradually earthed up till the whole of the lower portion of the temple has disappeared under ground. The upper portion has long ago been removed, and the only access to the akshaya vata now available is by a flight of steps which leads down to a square pillared courtyard,

Ia.

Ia.

IIb.

¹ North-Western Provinces Gazetteer, Vol. VIII, Part II, pages 156-203, passim.

² Cunningham, Archaeological Reports, Vol. I, pages 296—301.

³ Beal, Le., Vol. I, pages 230-234.

Ia.

The wall stones and roofing slabs are of massive 18 feet six inches inside. square blocks of grey sandstone, whilst the pillars are plain with old cruciform capitals. Several masons' marks, similar to those found in the masjids at Jaunpur, are still traceable. The several statues standing in the niches of the hall are all modern and of very inferior workmanship, whilst the only existing inscription is a tablet, dated Samvat 1832, presented by Râjâ Gôpâla of Bettiâ, invoking the help of Ganêsa and eulogising the sanctity of the spot. The court has apparently once been open to the sky, but it is now closed in to secure darkness and mystery for the holy Fig-tree. The akshaya vata is next mentioned by Rashid-ad-din in the Jamiuttawarikh, in which he states that the "tree of Prag" is situated at the confluence of the Jamna and Ganges. As most of his information was derived from Abu Rihan, the date of his notice may with great probability be referred to the time of Mahmud of Ghazni. In the seventh century a great sandy place, two miles in circuit, lay between the city and the confluence of the rivers, and as the tree was in the midst of the city, it must have been at least one mile from the confluence. But nine centuries later in the beginning of Akbar's reign, Abdûl Kâdir speaks of the "tree from which people cast themselves into the river." From this statement is clear that during the long period that intervened between the time of Hiuen Tsiang and that of Akbar the two rivers had gradually carried away the whole of the great sandy plain and had so far encroached upon the city as to place the holy tree on the very brink of the water. Long before this time the old city had no doubt been deserted, for we know that the fort of Illâhâbâs was founded on its site in the 21st year of Akbar's reign, that is in A.H. 982 or A.D. 1572.

As the old city of Prayaga has totally disappeared, we can scarcely expect to find any traces of the various Buddhist and Brahmanical monuments which were seen and described by the Chinese pilgrim in the seventh century. Indeed, from their position to the south-west of the city it seems very possible that they may have been washed away by the Jamna even before the final abandonment of the city, as the course of that river for three miles above the confluence has been due west and east for many centuries past. At any rate it is quite certain that no remains of these buildings are now to be seen; the only existing ancient monument being the well-known monolith which bears the inscriptions of Asoka, Samudragupta, and Jahangir. As Hiuen Tsiang makes no mention of this pillar, it is probable it was not standing at Prayaga in his days. From a short Asoka inscription of four lines recorded on the pillar and addressed to the rulers of Kausambi, it is evident that it was originally erected at Kausambi, and it is highly probable that it must have been brought to Prayaga by Firûz Shah Tughlaq, whose removal of the Khizrabad and Mirath pillars to Dehli gives countenance to this suggestion.

This pillar is a single shaft of polished sandstone 35 feet in length with a lower diameter of two feet 11 inches and an upper diameter of two feet two inches. The capital of the column was no doubt of the usual bell-shape of Asoka's other pillars, but of this there is now no trace. The circular abacus, however, still remains with

I Journal, Asiatic Society of Bengal, Vol. III, pages 106-118, and 257; Vol. VI, page 566 seqq., page 963 seqq., page 1049 seqq.

² Cunningham, Corpus Inscriptionum Indicarum, Vol. I, page 37 seqq.

its graceful scroll of alternate lotus and honeysuckle resting on a beaded astragalus of Greek origin. This was once surmounted by the statue of a lion; but the lion must have disappeared many centuries ago, as when the pillar was erected by Jahangir in A.D. 1605, it was crowned by a globe surmounted by a cone. The great inscription of Asoka containing the same series of six edicts which are found on the other four pillars is engraved in continuous lines around the column. The letters are uniform in size and are very neatly and deeply engraved. But a great portion of the third and fourth edicts comprising seven lines has been ruthlessly destroyed by the cutting of the vain-glorious inscription of Jahangir, recording the names of his ancestors. Two lines of the fifth edict are nearly intact, but nearly the whole of the remainder has been lost by the peeling off of the surface of the stone. The sixth edict is complete with the exception of about half a line. Immediately below the Asoka edict comes the long and well-known inscription of Samudragupta.1 upper portion of this inscription is confined between a crack in the stone on its left and two short Asoka inscriptions on its right. The lower one of these, consisting of five lines, refers to Asoka's queens, and the upper inscription, consisting of four lines. is addressed to the ruler of Kausambi. Of middle age inscriptions there is no trace: but the mass of short records in rudely cut modern Nagari covers quite as much space as the two inscriptions of Asoka and Samudragupta. Above the Asoka edicts there is a mass of this modern scribbling equal in size to the Samudragupta inscription. But besides this the whole of the Asoka inscription is interlined with the same rubbish which is continued below on all sides of the two shorter edicts. one of which has been half obliterated by the modern letters. Regarding these minor inscriptions James Prinsep2 remarks that it is a singular fact that the periods at which the pillar has been overthrown can be thus determined with nearly as much certainty from this desultory writing as can the epochs of its being re-erected from the more formal inscriptions regarding the latter event. Thus, that it was overthrown some time after its first erection by the great Asoka in the middle of the third century before Christ, is proved by the longitudinal or random insertion of several names in a character intermediate between No. 1 and No. 2, in which the (m) and (b) retain the old form. On one of these names he remarks: "It would have been exceedingly difficult, if not impossible, to have cut the name No. 10 up and down at right angles to the other writing while the pillar was erect, to say nothing of the place being out of reach, unless a scaffold were erected on purpose, which would hardly be the case since the object of an ambitious visitor would be defeated by placing his name out of sight and in an unreadable position." The pillar was erected as Samudragupta's arm, and there it probably remained until overthrown again by the Musalmans, for we find no writings on it of the Pala or Sarnath type, i.e., of the tenth century; but a quantity appear again with plain legible dates from Samvat 1297-1640, or A.D. 1240-1583. It is remarkable that these occupy one side of the shaft, or that which was uppermost when the pillar was in a prostrate position. The ill-executed Nagari names

¹ Journal, Bombay Branch, Royal Asiatic Society, Vol. IX, page CXCVI; Prinsep, Indian Antiquities. Vol. I, pages 233—235.

^{*} Journal, Asiatio Society of Bengal, Vol. VI, page 967 seqq.

with dates Samvat 1864, or A.D. 1807, show that ever since it was laid down on the ground again by General Kyd, the passion for recording visits of piety or curiosity has been at work. There are seven dates ranging from Samvat 1297 to 1398, or A.D. 1240-1341, five ranging from Samvat 1501-1584, or A.D. 1444-1527; three ranging from Samvat 1632-1640, or A.D. 1575-1583; and three of Samvat 1864 or A.D. 1807. These dates combined with the total absence of any mediæval Dêvanagarî inscriptions are sufficient to show that the pillar was standing out of the reach of pilgrims scribbling from the time of the Guptas until that of the early Musalman Kings of Dehli. There are twelve dated inscriptions coming down to near the death of Muhammad Tughlaq. There is not a single record of the time of Firûz Shâh Tughlaq, which seems to show that he may have re-erected this pillar with its globe and cone like those at Dehlî. But if he did set it up, it must have been drawn down again during the troubled times of his immediate successors, as the dates begin again in A.D. 1407 and 1408. It was still lying on the ground at Prayaga in the time of Akbar as is apparent from a short record of the famous Birbal, the companion and favourite of Akbar, dated Samvat 1632, or A.D. 1575. It was next set up by Jahangir in A.H. 1014, or A.D. 1605, to be pulled down by General Kyd in A.D. 1798. It was once more scribbled upon in A.D. 1807; and finally, in 1838, it was set up as it stands at present.

Ib. The only other existing Hindû monument of any interest is a mutilated life-size statue of a horse sculptured in white sandstone which was exhumed from a field near the village of Dalêlganj, a quarter of a mile to the west of the fort. The upper part of the body is incised with a large number of Buddhist symbols, such as the svastika, the srivatsa, and the nandâvarta marks, which seem to show that it belonged to the Buddhist period of Prayâga. Besides these, there are several Nâgarî pilgrims' records, of which one bears the date Samvat 1646, or A.D. 1589, during Akbar's reign.

In mauzàs Dârâganj, Alôpî Bâgh, Colonelganj, and Bârutkhâna there are several IIb. fine Hindû temples, the earliest being of the time of Akbar, but of no great architectural beauty or antiquarian merit. Near the temple of Alôpî Dêvî at Dârâganj and that of Śivakoţî at Bârutkhâna there are several satî pillars, bearing symbols generally found on these stones, viz., the crescent moon, the sun, and a human head; while on one pillar there is a figure in outline resembling a water-bottle, to the neck of which a cork is tied, that is attached to the upper angle of a square bearing a disc, and the upper margin of which has a number of turret-like objects on it.

On the north-east side of the Fort, near the banks of the Jamna, there is a colossal figure of Hanuman, sculptured in a prostrate position; the carving is very rude and massive, and it cannot be older than the time of Akbar.

The remains of the Musalman period are few and of no great interest.

III. The most important building is the Khusrû Bâgh in mahalla Khuldabad, a quadrangle surrounded by an embattled wall, built in A.H. 1010, and originally the pleasure-garden of Jahangir. It was named after his ill-fated son Khusrû, who died in A.H. 1031, or A.D. 1621, and whose tomb together with those of his mother, Shah Begam, dated A.H. 1014, and his sister, dated A.H. 1034, and the house of

Ia. the Tambôlî Begam, form the chief features of the place. Other places are: Sarâî Khuldâbâd, built A.H. 997; Masjid Shâh Mahâbat-ullah, built A.H. 1063; Masjid Darra Shâh Hajjat, built in A.H. 1108 by Dil Rûba Shâh; Masjid Darra Shâh Ajmal, built in A.H. 1088; and Masjid Qadam Rasûl, built A.H. 1184.

In the burial-ground in mahallâ Kydganj are the following inscribed tombs: Hafîzah Begam, A.H. 880; Umar Khân, 976; Yusuf Alî, 1158; Alî Quli Beg, 1171; Zainab-al-Majâd, 1172; Abdul Muttalab, 1173; Muhammad Taher, 1179; Muhammad Yusuf, 1180.

2. ARÂÎL, ancient village on the Ganges, in tahsîl Karchhâna, four miles S.-E. of Allahâbâd. The date of its foundation is unknown; but it was partially rebuilt by Akbar, who called it Jalâlâbâd. This name has now been lost, and the city, what remains of it, is known by its ancient title. It contains two ancient Hindû temples, in honor of Somês varanâtha, and one temple in honor of Bêni Mâdhojî, in which is deposited a Sanskrit inscription, unfortunately much defaced.

At the village of Dêorakh, in the temple of Somêsvara Mahâdêva, there is an inscribed pillar, dated Samvat 1674.

- 3. Bâra, tahsil, lat. 25°-15′-11″ N., long. 81°-45′-29″ E., 18 miles S.-W. of Allahâbâd, has a small high mound, the ancient site of a large Hindû temple, whose carved stones and bas-reliefs are lying about especially in front of a small mediæval temple called Bhairava-kâ-mandir.
- 4. Bîthâ,1 or Bhitâ, small village in tahsîl Karchhâna, 11 miles S.-W. of Allahabad, possesses extensive mounds of ruins of the ancient Buddhist city Bithabhayapattana. The remains of this ancient city extend in a slightly curved line for about a mile and-a-half in length in a direction from south-south-west to north-north-west, ending in the rocky islet of Sujan Deo in the Jamna. This rock was originally the most northerly point of the low ridge of sandstone which bounds the villages of Bîthâ, Dêoriyâ, Bîkar, Mankûâr, and Sâripûr on the east; but the continuous encroachments of the Jamna at last cut it off from the main land, and it now stands in the midst of the river, a bluff and picturesque pinnacle of rock, 60 feet in height. It was formerly crowned by a Hindû temple, Ib. called Sujan Dêo, by which name the rock is still known; but the temple was destroyed in the reign of Shah Jahan by Shaista Khan, who in A.H. 1055. according to a Persian inscription,2 erected an open octagonal cupola 21 feet in diameter, which still exists, and in which the Hindûs have now placed a lingam. in whose honor annually a large melà is held in the month of Kârttika, to which thousands of pilgrims flock. Below the temple, on the surface of the solid rock the five Pandavas are sculptured in high relief. There are no ancient inscriptions in the scarp of the rock; the only ancient remains are a few masons' marks corresponding to those sculptured on the old Buddhist and Hindû stones in the masjids at Jaunpûr.

On the cliff opposite Sujan Dêo, about 200 yards to the south, stands the small village of Dêoriya, which now forms the northern extremity of the ruins of this

Hb.

IIb.

IIb.

¹ Cunningham, Archaeological Reports, Vol. III, pages 46-52; Vol. X, pages 5-9.

Proceedings, Asiatic Society of Bengal, for 1874, page 100.

extensive city. In the rocky ridge to the south are the well-known sandstone quarries, and close to them are some square-shaped fields raised high above the surrounding lands in which the plough still turns up inscribed Buddhist statues of the Indo-Skythian period, pillars and architraves of the Gupta period, ancient Buddhist coins, pieces of black-coloured pottery, ancient enamelled beads, stone umbrellas, and stone seats. Several statues and architectural fragments, both Buddhist and Brâhmaṇical, are collected together under the different pîpal trees in the village, amongst which there is a standing figure of Buddha Asvaghosha, four feet six inches high, with a five-headed snake canopy, and worshipped by the villagers under the name of Śringârî Dêvî. On the very edge of the cliff overhanging the Jamnâ, opposite Sujân Dêo, there is a high artificial mound that was most probably the site of the original temple which gave its name of Dêoriyâ to the village. Numerous dressed stones are scattered about and lying at the foot of the mound, but all more or less broken and damaged.

From Bîthâ to Dêoriyâ the distance is nearly half a mile, part of the high ground between the two places being an artificial embankment connecting the rocky ridge of Dêoriyâ with the high mound, called Dhî, of the large mass of ruins to the south, which are about 1,500 feet in length. To the south-west of the Dhi lies the principal mass of ruin now called Garh or "the fort." It is very nearly square in form, the north face being 1,200 feet in length outside and the other three faces about 1,500 feet each. Apparently, the rampart is only an enormous earthen mound from 35 to 40 feet in height and of great thickness, its base being not less than 200 feet. But a section made by General Cunningham disclosed a massive brick wall 61 feet thick at top, with a slight batter on the outside, at 100 feet from the extreme edge of the slope. The fort must therefore have been surrounded by a strong brick wall which could not have been less than 45 feet in height, including the loopholed parapet. But as the mass of earth outside this mass is much too great to have been washed from the inside by the annual rains, it is clear that there must have been an outer line of works forming a faussebraie or râonî, at a distance of 25 or 30 feet beyond the main line. In the course of time the ruins of the two walls, combined with annual washings of the rains, would gradually fill up the space between them, and form the gentle slope of the present mound. At all the four corners and at a few intermediate points, the earthen mounds rise to a still greater height, showing the position of the towers of this strong fort. At the western angle there are two of these lofty mounds standing close together, but with a deep gap between them, which must have been the side of one of the principal gates of the old fort. Two other gaps on the north-east and south-east faces show the probable position of two other gates, the former leading to the northern part of the town, outside, including Dêoriyâ, and the latter to the east, towards a long mound of brick ruins, the remains of some important buildings. The whole of the interior of the fort was once raised to a height of 15 or 20 feet, but about one-third has been gradually lowered by the action of the annual rains, leaving only a single mound in the midst of the hollow. This was most probably the site of an ancient Buddhist temple, as a large statue of a royal personage was unearthed therefrom, and a large pillar (panchamukha) with five Buddhist figures, sculptured in bold relief,

III.

and an inscription in the lat character—now in the Lucknow Museum—and dressed stones as well as ornamental bricks, were obtained by digging in it.

III.

III.

To the south-west of the fort there is another extensive mass of ruins which once formed the southern quarter of the town. It is almost triangular in shape, the northeast and north-west faces being each 1,500 feet in length, while the south face is 2,000 feet; the height varies from 10 to 20 feet. The bricks of the walls are of large size, 18"×11"×3". To the east of the northern half of the town there is a small square fort, 200 feet inside, with an average height of 30 feet. Further on, in the same direction, there is a large lake, 3,000 feet in length from north to south and 2,000 feet in breadth; its size and form are due to the artificial embankment which connects the northern end of the mass of ruins, called Dhî, or "the mound," with the rocky ridge to the south of Dêoriyâ. Numerous broken statues and fragments of pillars, architraves, &c., both Buddhist and Brâhmanical, are collected together under the pipal trees of Bithâ, and lying on the embankment of the great lake. Amongst these the most prominent are three pieces of coping stones of Buddhist railings, one of middle size and quite plain, the other eight and three-quarter inches high and six and-a-half inches thick, bearing a short inscription in characters of the Indo-Skythian period; whilst the third is only six and-a-half inches high and five and-a-half inches thick. The last two are ornamented in front with a line of bells surmounted by a beaded circle, similar to the decoration of the Bharhut stupa. Two fragments of a straight torana beam, one sculptured with three standing figures and the other with an open-mouthed crocodile and two standing figures, are certainly pieces of a Buddhist gateway; but the drawing is rude, and the workmanship coarse. Besides these there are several broken railing pillars with the rail-sockets on both sides, and a flat rail-bar with a full-blown lotus flower on one side. But the commonest specimens of antiquity at Bitha are what may be called stone stools or seats. They are generally about 15 inches in length, and always supported on four feet. All are hollowed out on the top in the direction of the length; some are nearly plain, but the greater number are highly ornamented. One of the narrow ends must have been the front of the stool, as the two feet of one end were generally found curved in the form of half lions, while the two back feet were quite plain. A band of flowers ornamented what may be called the frame of the stool, while the hollowed portion at top represented the cushion.

About half a mile to the east of Bithâ is the small hamlet of Pañchmuhâ, "the five heads," which is the name of the stone capital of a monolith, bearing four human figures standing, with a leopard or lion sitting on its haunches. The figures are coarsely executed, and have suffered much from the weather.

About half a mile still further to the east is the village of Mankûâr, where the gosâin of Dêoriyâ has a garden. In the garden there is a very perfect figure of a seated Buddha with a head-dress like that now worn by the abbots of Bhûtân; it is a plain cap fitting close to the head, with long lappets on each side. The figure is naked to the waist and clad below in a dhôtî which reaches to the ankles; the eyes are half-closed as if in meditation. On the pedestal is a wheel in the middle with a man seated in meditation on each side, and a lion at each corner accompanied by an inscription of two lines in clear Gupta characters, dated Gupta Samvat 126, during the reign of Kumâragupta Mahêndra. The statue has been discovered

some 20 years ago in the brick mound between the five rocky hillocks called Pañchpahâr, a short distance to the north-east of Mankûâr. All the bricks used in the village were brought from this mound, besides several fragments of pillars now built into the eastern gateway of the garden. This Pañchpahâr mound was most probably the site of a Buddhist monastery.

In the low rocky range of hills which bounds the great lake of Bithå and Dêoriyâ to the east, near the village of Mankûâr, there are several small caves and a number of niches and rude figures of the Brâhmanical period carved in the rock. Over the doorway of the largest cave known as Sîtâ-kâ-Rasûî, or Sitâ's kitchen, there is an inscription in three lines of well-formed characters of the ninth century. On a separate rock lying before a cave, and perhaps fallen down from it, there is a short inscription in two lines of similar characters, dated Samvat 901. On the top of one of the flat rocks close by there are some well-defined footprints which are clearly due to the ingenuity of the masons who were employed in the neighbouring quarries. There are two prints of a man's feet, two of a cow's feet, and two of a calf's feet; these prints are known by the name of Surâ-gâi or the chaurâ-tailed cow.

In the bâzâr of the small village of Bîkar, a quarter of a mile to the northeast of Bîthâ, several fragments of Brâhmaṇical statues, such as of Narasimha, Siva, and Nandî, are collected under the pîpal tree. On the top of a rock to the north-east of Bîkar, and overhanging the right bank of the Jamnâ going towards Sâripûr, there is a perfect statue of Chandikâ Mâyâ. Close by there is a rock inscription of six lines, recording the erection of a temple in honor of Kâlî by the architect Bhihkha in Samvat 1685. A little further on, there are sculptured in the solid rock several figures of good workmanship, all being representations of the different avâtâras of Vishņu. Close by there is an inscription of two lines carved on the rock in characters of the ninth century.

At Sâripûr on the Jamnâ, half a mile to the north-east of Bîkar, and beyond the end of the hills, there is a small square obelisk, or lower part of a pillar, with a Gupta inscription of 13 lines on one face containing the name of Kumâragupta Mah-êndra.

The great antiquity of the Buddhist city of Bîthâbhayapattana is vouched for by 10 ancient inscriptions on statues and pillars which, though all unfortunately very brief, are amply sufficient to show that Buddhism was the prevailing religion at Bîthâ during the Indo-Skythian period, as well as during the reign of the Guptas. As the latest Buddhist records found at Bîthâ date from the time of Kumâragupta Mahêndra, and as Hiuen Tsiang does not mention this important place, though Bîthâbhayapattana was on the direct route from Kausâmbî to Prayâga, it is evident that Bîthâbhayapattana must have been destroyed immediately after the reign of Kumâragupta Mahêndra. In the ninth century, we see the Brâhmaṇas occupying Bîthâ, as is evident from the rock inscriptions, of which one is dated Samvat 901 or A.D. 844.

- IIb. 5. Châîl, old village in tahsil Allahâbâd, 16 miles west of head-quarters, possesses two sandstone masjids.
 - 6. CHILLA, small village in tahsil Bara, 14 miles S.-W. of Allahabad, is celebrated for its possession of a large stone dwelling-house which is said to have Conningham, Archeeological Reports, Vol. XXI, pages 8 and 9.

Ib.

been the residence of the two famous Banaphar heroes Alha and Udal. The building stands in the middle of a small fortified enclosure called kôt, which has a thick earthen rampart faced with stone both inside and outside, and four towers at the corners. It has also a ditch all around with a stone counterscarp. The house itself is a square of 46 feet, each side divided by pillars and walls into 25 small bays, in five rows each way. To the north is the entrance with a long slab seat on each side covered by a low roof supported by short pillars. The middle compartment is open to the sky, and thus forms a small court-yard. The five compartments on the south side form five separate rooms, each with its own door. The two compartments on the north-west are walled in to form a separate room with its door to the south. Similarly the two others on the south-east form a single room with a door to the west. Each of these rooms is lighted by a stout stone trellis, and two similar trellises give light to the inner parts of the body of the building. Each compartment is between seven and eight feet square, and the total height is 8 feet 10½ inches.

The roof is flat. Four pillars of the same pattern, but less massive, are now used to support some broken slabs of the roof. These are said to have been brought from above, where they supported a canopy where the inmates used to sit. With its massive ramparts which completely covered the building from view, the place was capable of being defended for some time. All the doorways are slightly ornamented, but more especially the door-sills. The corner rooms and side walls have stout trellises of a simple pattern. The pillars are also slightly decorated. There are no inscriptions; but the letter (n) of an early form was found in two places. From its form it is evident that the building must be as old as the eighth century. This building is of great interest as so few specimens now exist of early Indian domestic architecture.

7. GARHWÂ,¹ jangal fort in tahsîl Bâra, 25 miles S.-W. of Allahâbâd and six miles N.-W. of the East Indian Railway Station Shiûrâjpûr, contains the ruins of the ancient city of Bhaṭṭagrâma.

The site is a depression amongst the low scattered spurs of the Kaimûr hills, which here approach the Jamnâ, and until a few years ago was surrounded by a thick belt of jangal. The present name of Garhwâ, or "the fort," is a complete misnomer, as the place is only a square enclosure around a group of temples without any strength as a military position. The loopholed parapets which give Garhwâ a defensive appearance were built by the Bâghel Râjâ Vikramâditya of Bâra about A.D. 1750. The recent age of these parapets is proved by one of the corbels used to support them bearing a mutilated inscription in modern Nâgarî with the figure of a horse, which is half cut away to form the slope of the outer face of the corbel. The place is besides situated in the bed of a small stream and in very low ground, which is more or less commanded on all sides. The walls are of little height and are not protected by a ditch: an oversight which could not have happened in this position if the place had been intended for defence.

As it now stands, Garhwâ is a stone enclosure of pentagonal form, the largest side on the west being 300 feet, north side 250 feet, and each of the two short eastern

III.

¹ Cunningham, Archivological Reports, Vol. III, pages 53—61; Vol. X, pages 9—15. Proceedings, Asiatic Society of Bengal, for 1874, page 124.

faces only 180 feet. Access is obtained by a small doorway on the south side, and by two small postern gates, one at the west end of the northern face, and the other near the northern end of the eastern face. On the west and east of the fort there are two fine tanks, from 500 to 550 feet in length and 200 to 250 feet in breadth, on the brinks of which the remains of ghâts of cut stone are visible, and in the neighbouring jangals a great number of cut stones are lying about which appear to have formed parts of these flights of steps leading down from the level of the fort to the water's edge. In the lowest corner of the ghâts there are projecting stones placed at intervals which were intended for bathers to stand upon just above the level of the water. The two tanks have been formed by the western and eastern walls of the enclosure acting as embankments right across the natural bed of the rivulet which flows past the ruins.

Within is an inner fort having one entrance on the east side and originally walled off from the outer enclosure. Some of the pillars forming the inner square of this enclosure are still standing, and show a cell-like arrangement resembling a modern sarâi. These rooms were most probably used as priests' houses, or for the reception of minor statues, as three carved doorways are still in situ. The pillars of these cells are of various devices, from plain voluted shafts of red sand-stone to those elaborately carved all over in panels, and belonging to different ages. Most of these pillars have the lower part of the shaft eight-sided, and the middle sixteen-sided, while the upper is plain. The capitals are ornamented with four-armed human figures, or animals such as elephants, tortoises, or alligators at each corner.

- The oldest remains as yet discovered in Garhwa belong to the age of the Ib. Guptas. These are all of pink sandstone and of a much finer grain than the grey sandstone of the mediæval statues. These architectural relics were exhumed close to the western wall of the fort, near the mediæval Brâhmanical temple still standing, and are of the greatest interest, as they are of superior execution, and most undoubtedly belong to the period of the Guptas whose inscriptions were found along with them. The sculptures upon them are remarkable for their bold and deep carving, as well as for the good drawing and the easy and often graceful These remains consist of two massive square pillars, attitudes of the figures. upwards of nine feet in height, which probably formed the sides of the entrance to a large Gupta temple, two round pillars with lion capitals, and a fine architrave measuring 13 feet three and-a-half inches in length, which are now in the Lucknow Museum. Several inscriptions of the time of Chandragupta, Kumaragupta, and Skandhagupta, dated Gupta Samvat 86, 98, and 140 were discovered along with these remains.
- The next remains in point of antiquity are three seated colossal statues of Ib. Brahmâ, Vishņu, and Šiva, inscribed in Kuṭila characters of the 10th century. In a small room against the wall in the north-west corner of the enclosure are 10 Ib. large statues representing the avâtâras of Vishņu. Near the south-west bastion is a small temple containing a colossal figure of Sûrya and the navagrahas, or nine planets.

The only existing temple stands in the south-west corner of the enclosure; it is 16. about 38 feet long by 24 feet broad, with the entrance towards the east, and in front of it at a short distance there are two baolis. The temple consists of two parts, an open pillared hall or mandapa, which is about 28 feet long by 24 feet broad, supported on 16 pillars, and a sanctum or garbhagriha, which is a square of about 10 feet, with the corners indented and with niches in each of the three unattached faces. As all the statues have been removed from the outside as well as the inside of the temple, there is nothing to show to whom it was dedicated. Even its very name has been lost, and neither the inscription of the builder, nor the records of pilgrims who afterwards visited the shrine, make any mention of the god to whom it was dedicated. From the 11 inscriptions recorded on the faces of the pillars inside the temple it would appear that the temple was first opened in Samvat 1199, or A.D. 1142. The founder of the temple was Ranapala of Bhattagrama. The name of the latter is no doubt preserved in that of the present village of Bhargarh, one mile and-a-half to the north of Garhwa. The ground between the two places is covered with stones and broken bricks, showing that Bhattagrama must have been much more extensive in former days. Near the temple there stands a large statue representing the Kalkî Avatâra of Vishņu, which has been mistaken by General Cunningham for the Raja who built the fort; it is broken in two pieces, and the head of the horse is gone, but it is valuable as showing the Hindû military costume half a century before the Musalman conquest.

In the mound to the south of the fort or temple enclosure several sculptures, a number of carved bricks, and terra-cotta pieces of pillars and pilasters of an early date, similar to those found at Bilsar, Sankisa, and Bhitargâon, are collected under the trees. No traces of any buildings are to be found; but the number of carved bricks and the evidently artificial character of the mound itself are sufficient to show that this was the site of several brick buildings and certainly of one brick temple.

8. Ginjà Hill, an isolated mountain in tahsil Bâra, 40 miles S.-W. of Allah-âbâd, about 800 feet in height, stands out prominently in the plain close to the exit of the Tons river from the Vindhya hills. It is 1,326 feet in total height above the sea, and is similar in appearance to many of the hills about Kâlanjar and Ajaygarh. The hill is said to be three kôs, or nine miles in circumference at the base. The top of it is a narrow ridge of perpendicular rock about 200 feet in height, while the lower part is a steep slope all round, thickly covered with jangal.

At rather more than half-way up the ascent there is a large reservoir of water about 200 feet round. Up to this point the ascent is tolerably easy, but above the tank it becomes very steep and difficult, and is much impeded by thorny jangal. On the south face of the top the scarped rock overhangs very considerably, and forms a large open hall, or rock shelter, about 100 feet long by 40 or 50 feet broad, and of irregular height, varying from 20 to 25 feet. It is closed at both ends by rough walls; but the whole of the front is open. In the middle of the rock at the back there is an inscription of three lines of the Indo-Skythian period in red paint with some rude drawings of men and animals. It is a record of Mahârâjâ Śrî Bhìmasêna, dated Samvat 52, in the fourth fortnight of the hot season, the 12th

Ib.

¹ Cunningham, Archwological Reports, Vol. XXI, page 119.

III.

IIb.

IIb.

day. To the right and left of the inscription there are several very rudely-drawn figures of men and animals sketched in outline in red paint. Their age is doubtful, as they have no connection with the inscription.

9. Jhúsí, small town in tahsíl Phúlpûr on the north bank of the Ganges, three miles E. of Allahábád, is the ancient Pratishthánapura, the residence of Purûravâs, the first prince of the lunar dynasty. The only remains now existing are the ruined forts of Samudragupta and Hamsagupta. Fifteen years ago 24 gold coins of Kumáragupta were unearthed here. Close to each fort is a deep well built of large stones. Several Hindû temples and a masjid in and near the town are of no architectural or antiquarian merit.

A copperplate inscription, recording a land grant of the illustrious Trilochanapâla Dêva, son of Râjyapâla Dêva, son of Vijayapâla Dêva, in Samuat 1084, was discovered in Samuaragupta's fort mound in A.D. 1830, which speaks of Pratishthânapura being opposite to Prayâga.

At the village of Firûzpûr there is an inscribed tomb, dated A.H. 1090.

10. Karrâ,² large town in tahsîl Sirâthû on the south bank of the Ganges, lat. 25°-41′-55″ N., long. 81°-24′-21″ E., 41 miles N.-W. of Allahâbâd. The ancient town of Karrâ is reckoned as one of the nine holy places of Northern India. There is still a temple of Kâlêśvara, from which the place has received the name of Kâlanagara. It is called Kâlokhala in a copperplate inscription dated in Samvat (i.e. Hijra) 965 during the reign of Akbar Shâh Ghâzî, recording a grant made by Râjâ Râmachandra of Rewâ. Karrâ, however, is mentioned as a place of pilgrimage by Ibn Batuta in A.D. 1340. The town is also said to have been called Karkoţakanagara, because the hand (kara) of Satî fell down here when she burnt herself at her father's sacrifice (yâga).

III. The fort of Karrâ stands on a very lofty mound overlooking the Ganges; it rises up about 120 feet above the river-bed and from 80 to 90 feet above the road at its base. The walls are of bricks faced with stone, the older or Hindû portion being of massive blocks of sandstone. The whole is now in a ruinous state. The fort is 900 feet long from north to south by 450 feet broad from east to west. Its foundation is attributed to Jayachchhandra, the last Hindû Râjâ of Kanauj. Of course it belonged to Jayachchhandra, but the place is certainly very much older, as several earlier Hindû coins have been found, and as an inscription, which was formerly on the gateway and is now in the Indian Museum at Calcutta, is dated in Samvat 1095, or A.D. 1035, during the reign of Râjâ Yaśaḥpâla. This record is, therefore, 160 years anterior to Jayachchhandra.

IIb. Karrâ is famous for the tomb of a very holy saint named Khwâja Karrak, who died A.H. 709, or A.D. 1309, as recorded in an Arabic inscription. The tomb was repaired in A.H. 894, or A.D. 1488, as is apparent from a Persian inscription. It consists of an oblong canopy seven feet four inches by three feet, supported on pillars, which covers a common plaster tomb screened by a cloth. The saint was living at Karrâ when Jalâl-ad-dîn Firûz Khîljî was treacherously murdered by his nephew, Alâ-ad-dîn Muhammad on the 17th Ramzân A.H. 695, i.e., on the 27th July, 1295.

Asiatic Researches, Vol. XVII, page 621; Journal, Asiatic Society of Bengal, Vol. XXXI, page 8, note; Indian. Antiquary, Vol. XVIII, page 33.

² Cunningham, Archaelogical Reports, Vol. XVII, pages 88-95.

IIb. The tomb of Kamâl Khân, who died A.H. 989, or A.D. 1581, is very like one of the later Paṭhân buildings at Dehlî. It is a square of 33 feet outside with a chamber of 24 feet. Just below the springing of the dome the square is changed to an octagon on which stands a plain hemispherical dome surmounted by a tall, thin pinnacle. The tomb stands in the middle of a court-yard with domed entrance rooms on the north and south and east sides and a masjid on the west. At the four corners there are massive round towers with domed roofs and ornamented battlements. The surrounding walls also have the similar ornamented battlements, and altogether the tomb of Kamâl Khân is a fine specimen of the later Paṭhân architecture.

The ruins of Karrâ extend for upwards of two miles along the western bank of the Ganges with something more than a mile in breadth. The present town is only a mere shadow of its ancient grandeur. On ascending one of the rising grounds, everywhere as far as the eye can reach there is a vast expanse of mounds covered with ruined tombs, masjids, and idgâhs. The place looks just like old Dehlî, where the dead occupy much more ground than the living. The decay of Karrâ began with the removal of the head-quarters of the district to Allahâbâd after the foundation of the fort by Akbar in A.D. 1575.

At Bazar Ghat immediately below the fort there is a small desecrated Hindu temple surrounded by a chabûtrâ or terrace, near which there is a headless figure of Durga, besides a lingam and a figure of Nandî to show that the temple must have been dedicated to Siva. The present chabûtrâ was built in A.H. 1111, or A.D. 1699 as recorded in a Persian inscription let into the wall. A short distance below the ghat there is a well standing in the bed of the river, which the people call the minâr, as it looks like a stout hollow pillar; but it is simply a well which the Ganges has isolated by its encroachments.

IIb. The Jâmi Masjid was built by Maulvi Yaqûb in A.H. 978, or A.D. 1570, and repaired by Qurbân Ali from A.H. 1012—1014, or A.D. 1603—1605.

The rauza of Shaikh Sultan was erected in A.H. 1061, or A.D. 1650.

The tomb of Shah Khub Allah contains five Persian inscriptions, dated A.H. 1061.

Karrâ is still much frequented by pilgrims, more particularly on the 7th, 8th, and 9th of the waning moon of Ashâḍa, when about 100,000 people are said to assemble for the purpose of bathing.

IIb. The village of Dârân a g a r possesses a masjid built in A.H. 1071; the tomb of Sa'îd Fazl-ullah, dated A.H. 1008, and the tomb of Ghulâm Husain, dated A.H. 1128.

IIb. The village of Kâch Daryâ Bard contains the rauza of Quțb Alam, dated A.H. 1116; the village of Ismâilpûr the rauza of Faqir Hâshim, dated A.H. 1038; the village of Shâhzâdpûr the masjid of Allâh Dâd Khân, built in A.H. 1138, and a slab inscribed in A.H. 1076.

11. Kararı, town in tahsil Manjhanpûr, 33 miles W. of Allahâbâd, possesses the ruins of an ancient fort.

12. Katkå, small village in pargana Khairâgarh of tahsîl Mejâ, 26 miles S.-E. of Allahâbâd, possesses on the west bank of the Tons river, opposite the village, and close to the railway bridge, a very curious sculptured obelisk. From its position on the west bank of the river and facing the east, it may be a satî monument;

III.

Ib.

¹ Cunningham, Archwological Reports, Vol. XXI, page 120.

but there is nothing about the sculptures on the five faces that is peculiar to the known sati pillars of later times. The obelisk is $3\frac{1}{2}$ feet high, with two long faces of 20 inches and two short faces of 12 inches. The upper part above the four sculptures slopes backward like the roof of a Drâvidian temple, with three knobs on the top of the ridge.

The principal sculpture represents a Râjâ on horseback with his umbrella-bearer behind him, very much after the fashion of the Gupta gold coins. On the opposite face there is a four-armed figure of Bhainsâsurî Dêvî; with one hand she holds a leg of the buffalo and in two other hands a sword and shield. On one of the short sides there is a seated figure holding a cup in his right hand; and on the fourth side there is a figure of Gaṇêsa. There is no inscription on the obelisk; but the sculptures and ornaments have so much in common with those of the Gupta period, that there can be no reasonable doubt that this curious monument belongs to a very early date, not later than the third or fourth century of our era.

- III. 13. Кнага̂дарн, old ruined fort in tahsîl Mejâ, 26 miles S.-E. of Allahâbâd, is situated in the village of Khâra in talukâ Chaurâsi, near the southern bank of the Tons river.
- 14. Kôh Inâm, ruined village in pargaņa Karrâ of tahsîl Sirâthû, 24 miles W.-N.-W. of Allahâbâd, was razed to the ground for rebellion in 1858. It possesses a ruined masjid, which, according to a Persian inscription, was built by Qâzî Hasâmad-dîn Hasan during the reign of Fîrûz Shâh Tughlaq, in A.H. 786, or A.D. 1384.
- 15. Kohnrâr, or Kohrâr, village in pargaṇa Khairâgarh of tahsîl Mejâ, 23 miles
 III. S.-E. of Allahâbâd, possesses near the south bank of the Tons river the ruins of an old
 Ib. fort and to the south of the village an old bâolî with steps down to the water.
 - 16. Kosam Inam² and Kosam Khiraj, two small villages on the north bank of the Jamna in pargana Karari of tahsil Manjhanpûr, 28 miles W. of Allahâbâd, are the ancient site of Kauśambi, one of the most celebrated cities in ancient India, whose name was famous amongst Brahmanas as well as Buddhists. The city is said to have been founded by Kuśamba, the tenth descent from Purûravâs; but its fame begins only with the reign of Chakra, the eighth in descent from Arjuna Pandû, who made Kauśambi his capital after Hastinapura had been swept away by the Ganges.

III. The present ruins of Kauśambi consist of an immense fortress formed of earthen ramparts and bastions, with a circuit of 23,100 feet, or exactly four miles. The ramparts have a general height of from 30 to 35 feet above the fields, but the bastions are considerably higher; those on the north face rising to upwards of 50 feet, while those at the south-west and south-east angles are more than 60 feet. Originally there were ditches all round the fortress, but at present there are only a few shallow hollows at the foot of the rampart. The parapets were of brick and stone, the large size of the bricks, which are 19" × 12½" × 2½", shows that these are the ruins of very old walls. In shape the fortress may be described as an irregular rectangle with its longer sides running almost due north and south. In three main

¹ Proceedings, Asiatic Society of Bengal, for 1880, page 72.

² Cunningham, Archeological Reports, Vol. I, pages 301-312; Vol. X, pages 1-5; Vol. XXI, pages 1-3.

points therefore of name, size, and position the present Kosam corresponds most exactly with the ancient Kausambi as it is described by the Chinese pilgrim Hiuen Tsiang1 in the seventh century. The great object of veneration at Kausambi was the celebrated statue of Buddha in red sandalwood, which was devoutly believed to have been made during the lifetime of Buddha by a sculptor whom King Udâyana was permitted to send up to the trayatrimsa heaven while the great teacher was explaining the law to his mother, Mâyâ. The statue was placed under a stone dome within the precincts of the palace of Udâyana, which is described by Hiuen Tsiang as being situated in the very middle of Kausambi. This description shows that the place must have occupied the position of the great central mass of ruin which is now covered by a small modern Jain temple dedicated to Parasvanatha. By the people, however, it is generally called Dêora, which was the old name of the mound, and which therefore points unmistakeably to the position of the ancient temple that once held the famous statue of Buddha. The foundations of large buildings are still traceable both to the east and west of the temple, and a large collection of Jain sculptures of the 11th century was dug up by General Cunningham on the side of a high mound, 50 yards due east from the modern Jain temple. In the people's houses many sculptured stones lie hidden, as numerous terra-cotta figures of the Buddhist period, the rounded end of a torana beam of a Buddhist gateway, sculptured with an open-mouthed crocodile, pieces of a coping-stone of a Buddhist railing ornamented with a row of bells, a small capital with a pair of winged lions sitting back to back on the abacus, and a bell-shaped drum below, and several sculptured pillars of a Buddhist railing were obtained by offering rewards to the people. The discovery of these undoubted Buddhist remains is alone sufficient to prove that some large Buddhist establishment must once have existed inside the walls of Kauśâmbî. The coins found at Kosâm range from the very earliest punch-marked bits of silver and copper down to the time of Akbar; many of them are inscribed in old characters earlier than the beginning of the Christian era.

The only other existing relic of Buddhism inside the fort is a large stone monolith2 similar to those of Allahabad and Dehli, excepting only that it bears Ib. no Asoka inscription. This column is now standing at an angle of 5°, about onehalf of the shaft being buried in a mound of brick ruins. The portion of the shaft above ground is 14 feet in length, and close by there are two broken pieces measuring, respectively, four feet six inches and two feet three inches. General Cunningham made an excavation completely round the pillar to a depth of seven feet four inches without reaching the end of the polished portion of the shaft. All these figures added together give a total length of 28 feet; but the pillar was no doubt several feet longer, as the shaft of all the five known monoliths exceeds 30 feet. The smallest diameter is 291 inches, or nearly the same as that of the Lauriya-Arâ-Râj pillar, and as the diameter increases in nearly the same proportion, it is evident that the Kausambi pillar most probably had about the same height of 36 feet. The statement of the people that the Kausambi pillar has been leaning in the present position as long as they can remember is curiously corroborated by the fact

IIb.

¹ Beal, Lc., Vol. I, pages 235-237.

² Proceedings, Aziatic Society of Bengal, for 1870, pages 291-293.

III.

that an inscription dated in the reign of Akbar is cut across the face of the shaft at an angle of about 50°, but parallel to the horizon. It seems certain, therefore, that the pillar was in its present position as early as the reign of Akbar, and further, as this inscription is within reach of the hand, and as there are also others engraved beneath the present surface of the soil, it is evident that the pillar must have been buried as we now see it for a long time previous to the reign of Akbar. The inscriptions recorded on the Kausambi pillar range from the age of the Guptas down to the present day. The only record of the earliest period is the name of a pilgrim in six letters; at the top of the broken shaft there is an incomplete record of three letters in characters of the fourth or fifth century. The next inscription in point of time consists of six lines in characters of the sixth or seventh century. As this record is placed on the lower part of the shaft, from three feet to four feet beneath the present ground level, and as the lines are perpendicular to the sides of the shaft, it is clear that at the time when it was inscribed the pillar was still standing upright in its original position, and that the surrounding buildings were still in perfect order. This inference is fully borne out by Hiuen Tsiang's account of the ancient palace of Udâyana with its great vihâra, 60 feet in height, and its stone dome forming a canopy over the statue of Buddha, all of which would seem to have been in good order at the date of his visit, as he carefully mentions that the well and two bathhouses used by Buddha as well as the dwelling-house of Asanga Bodhisattva were in ruins. Just above this inscription there are several records in the peculiar shellshaped letters as found on most of the other pillars throughout Northern India. The remaining inscriptions, which are comparatively modern, are all recorded on the upper part of the shaft. That of Akbar's time in Nagari is followed by a short record of a goldsmith in three lines, below which is a long inscription, dated in Samvat 1621, or A.D. 1564, in the early part of Akbar's reign, detailing the genealogy of a whole family of goldsmiths; in this inscription the name of Kausambipura occurs.

In a field near the great monolith a group of Siva and Pârvati was exhumed; the figures are standing side by side, each with the right hand raised and the open palm turned to the front. In his left hand Siva holds a water-vessel, while Pârvatî carries a trisûl. The head-dress of Pârvatî is a most elaborate construction. On the base there was an inscription of several lines, of which only the two upper ones now remain; it records in early Gupta characters that the statue was dedicated during the reign of Bhimavarman in Gupta Samvat 136. Bhimavarman was most probably the Râjâ of Kausâmbî and a tributary prince under the great Skandhagupta. Inside the fort a large lingam was found, bearing four heads with three eyes each, and with the hair massed on the top of each head. The discovery of this costly symbol of Mahâdêva and of the old statue of Siva and Pârvatî shows that the worship of Siva must have been firmly established at Kausâmbî at some former period, and as Hiuen Tsiang mentions the existence of no less than 50 Brâhmanical temples at the time of his visit, it is probable that the large lingam and the statue of Siva and Pârvatî may have belonged to one of those early temples.

About one mile and-a-half to the south-east of the fort of Kosam there is a large earthen mound, called Tikri, which rises from 40 to 50 feet above the

general level of the country, in which a cave has been excavated. The excavation consists of two rooms facing the east, the outer room was 11 feet long by eight feet three inches deep, with a doorway four feet wide leading into the inner chamber, which is 11 feet six inches broad by 13 feet three inches deep. This inner chamber has a long, raised seat or couch on the south side. Both chambers are now only four and-a-half feet to six feet in height. On the eastern face just half-way up the slope there is a brick wall, which appears to have been the brick wall of another chamber. There are quantities of broken bricks at the foot of the mound and in the fields close by, where fragments of stone are also found. This brick wall is probably the remains of a lower storey, which agrees with Hiuen Tsiang's account of the residence of Vasubandhu Bodhisattva as an ancient brick chamber. No traces of the great monastery of Goshira with its stupa 200 feet in height are left; but the name appears to be preserved in that of the neighbouring village of Gopsahsâ. There are no remains of walls now visible, although there are numerous fragments of stone and quantities of broken bricks scattered about.

17. Koṛwâ, small village în pargaṇa Jhûsî of tahsîl Phûlpûr, 11 miles S.-E. IIb. of Allahâbâd. Two miles to the south-west there is an old Hindû temple in the village of Kankrâ.

III.

IIb.

III.

Ia.

18. Lachhagîr or Kasaundhân, famous bathing-place of the Hindûs on the north bank of the Ganges, in tahsîl Handiâ, 24 miles S.-E. of Allahâbâd, possesses the ruins of a large fort. It is fabled that here stood the lac palace of Duryôdhana in which the Pâṇḍavas were planned to be burnt, but escaped unhurt.

The village of Damgarh possesses a masjid, erected in A.H. 1198, and the tomb of Said Shah Basit Ali, dated A.H. 1196.

19. Ман, small village in tahsíl Handiâ, 17 miles E. of Allahâbâd, possesses an III. old ruined fort near the village of Jalâlpûr.

20. Mânda, village in tahsîl Mejâ, 38 miles S.-E. of Allahâbâd, possesses an old IIb. stone fort.

21. Malakah, small village in tahsil Soraon, two miles north of Allahabad. About a mile west of this village there is an extensive mound called Hatgauha dih at the village of Shiûpûr. Many sculptured fragments are scattered about the place.

22. Markhâmâû, village in tahsîl Sorâon, 15 miles N. of Allahâbâd, appears to be a Musalmân town built on a Hindû one, as many mounds are in the neighbourhood covered with broken bricks and fragments of sculptured stones.

23. Pabhôsâ, small village on the north bank of the Jamnâ, in tahsîl Manjhanpûr, 32 miles S.-W. of Allahâbâd, is the ancient Prabhâsa. The famous hill of Pabhôsâ is three miles to the north-west of the great fort of Kauŝâmbî, and not more than two miles from the present village of Kosâm and Pâli, which formed the old city outside the walls of the fort. High up in the face of the hill there is an artificial cave in an inaccessible position. The whole face of the hill in front of the cave is now a mere mass of débris, the refuse of old quarries. The cave has a door, measuring two feet two inches by one foot nine inches, and two windows, measuring, one foot seven inches by one foot five inches. The cave itself is a regular quadrangle measuring nine feet by seven feet four inches, with a height of three feet three inches. On the south side of the cave there is a stone bed and pillow for the use of an hermit

IIb.

IIb.

III.

IIb.

III.

covered with 10 early Gupta inscriptions. On the west wall of the cave, opposite the entrance door, there are three inscriptions, one in Maurya characters, recording the construction of the cave by Åshådhasêna, and two of the Gupta period, being short pilgrims' records. Above the left top corner of the entrance door of the cave there is a historically valuable inscription of seven short lines in the Maurya alphabet recording the construction of the cave by order of Åshådhasêna, the maternal uncle of the son of Gôpâla, the King Bappa Agnimittra, and son of Gôpâlî, of the race of Vaipidara, in the completing 10th year (of his reign).

According to the popular belief there is a Naga inside the cave, of which everybody has heard, but which no one has seen. The cave was entered for the first time by officers of the Archæological Department of these Provinces on the 24th March, 1887, on which occasion measurements and impressions of the inscriptions were taken. The cave is no doubt the rock cave of the venomous serpent in which Buddha after having subdued this dragon was supposed to have left his shadow, and the cave and its legendary Naga were, no doubt, in existence at the period of the Chinese Buddhist pilgrims' visits to Kauśâmbî, viz., Sung-Yun,1 in A.D. 519 and Hiuen Tsiang2 in A.D. 636. The Chinese pilgrims mention that there was a stûpa of Asoka about 200 feet high beside the cave; traces of a large brick building are to be found on the summit of the hill above the cave. The pilgrims also note that close by there was a site where Buddha used to take exercise, and a second stupa containing some of his hair and some nail parings. Sick people used to visit the place and pray for their recovery. No traces of these places are now visible; it is very probable, however, that the present modern Jain temple of Padmaprabhanatha erected in Samvat 1881, or A.D. 1824, which is built on a platform immediately below the scarp, occupies the site of some ancient building. On the face of the rock at several points there are short inscriptions in Gupta characters, being records of the quarry-men. On an eminence near the foot of the hill to the east there is a small tank called Dêokund, with a small Hindû temple on the bank.

24. Panasa, old village in tahsil Karchhana, 19 miles S.-E. of Allahabad, situated around ravines at the junction of the Tons with the Ganges, stands on an old tila, or mound.

25. Sikandrå, village in tahsîl Phûlpûr, 26 miles N.-E. of 'Allahâbâd. About a mile off in a north-westerly direction is the small village of Mâlîpûr, in which is the tomb of Sa'îd Sâlâr Mas'ûd Ghâzî.

26. SINGRAUR,³ village in tahsil Sorâon, 18 miles N.-W. of Allahâbâd, is the ancient Śringivîrapura. The old tomb of Singraur stands on a bluff head-land on the north bank of the Ganges. Its name is said to be derived from Śringivîra Rishi, whose shrine stands on an isolated mound on the extreme west point of the position. It is called the *sthâna* of Śringivîra Rishi, but is a comparatively modern vaulted room of brick before which a few fragments of sculpture are collected.

¹ Beal, Le., Vol. I, page CVII.

^{*} Beal, Lc. Vol. I, page 237.

² Cunningham, Archeological Reports, Vol. XI, page 62.

Inside there is a group of Siva and Pârvatî and a small figure of the sun in a four-wheeled chariot drawn by seven horses. Only the northern or inland position of the mound is now occupied by houses. On the highest point, which is about 50 feet, there is a chabûtrâ, or terrace overlooking the bed of the Ganges, and on another high IIb. point to the north-west of the last there is a masjid with a small tomb of Muhammad Madâri inside its courtyard; here there are two Hindû pillars. The whole mound is a mass of bricks chiefly of large size, 16 to 18 inches long by 11 inches broad. Singraur is said to have been a very large place in former days; but the Ganges first undermined its southern face, and swept away a large portion of the town, leaving a precipitous cliff some 90 feet in height. Since then the river has deserted the place, and only a small branch now passes under Singraur in the wide channel where the whole stream of the Ganges once swept along. Singraur is famous as the scene of the last act in the great rebellion of Khân Zamân and his brother, Bahâdur, against Akbar.

Half a mile to the north of the village is a large mound 18 feet high, called Sûrya Bhîtâ, or "mound of the sun." It is 50 feet broad at top and 150 feet at base, and is thickly strewn with broken bricks. It is most probably the ancient site of a temple to the Sun. Innumerable coins are found at Singraur comprising all the oldest types, with the exception of the punch-marked pieces.

27. Sorãon, tahsil, 13 miles N. of Allahâbâd, is built on an extensive old III. mound. Many broken statues, dressed stones, and bricks are scattered about the place, which show that Sorãon was once a place of some importance.

II.-Bândâ District.1

1. Ansûvâjî, famous pilgrimage place on the south bank of the Paisuni, in tahsîl Karwî, 15 miles S. of the tahsîlî and 64 miles S.-E. of Bândâ, has on a large basalt-rock close to the bank of the river two inscriptions, one dated Samvat 1520, Vaisâkha sudi 3, gurau; the other undated, but apparently of the same age. On a neighbouring rock there is a large figure of Hanumân, crudely hewn out of the solid basalt rock by one Bhagvândâsa, sculptor. Up in a cave of the high cliff of the overhanging rock there lives a noted Hindû faqîr.

An as û y â, the wife of Rishi Atri, was one of Daksha's 24 daughters. According to the Purânas, she practised severe penance for ten thousand years, and by virtue of the religious merit that she thus acquired she created the river Mandâkinî, and by its waters maintained the fertility of the country during a 10 years' drought.

- 2. Atrahat, village in tahsîl Pailâni, 14 miles N. of Bândâ, possesses four IIb. Hindû temples of no great architectural or antiquarian merit.
- Augasî, small town in tahsil Babêru, 26 miles N.-E. of Bândâ, possesses on the south bank of the Jamnâ a masjid which from an inscription appears to have been built in the time of Shâh Quli Sulţân in A.H. 989, or A.D. 1572. Adjoining III. the masjid there is a raised fort.

A copper-plate grant of the Chandella Rājā Madanavarman, dated Samvat 1190, was found here in 1877, the original plate of which is now in the Library of the Asiatic Society of Bengal.²

Ib.

¹ North-Western Provinces Gazetteer, Vol. I, pages 361-601, passim, sub voce,

² Journal, Asiatic Society of Bengal, Vol. XLVII, page 73; Indian Antiquary, Vol. XVI, page 207.

III.

4. Bândâ, head-quarters of the district, lat. 25°-28′-20″ N., long. 80°-22′-15″ E., possesses 66 masjids, 161 Brâhmanical and five Jain temples. Of the masjids, the chief in point of size and interest is that situated near the ruined palace of the late Nawâb; it was built by Alî Bahâdur, the last Nawâb. The oldest and most celebrated Hindâ temples are the two, sacred to Bhâmisvarî Dêvî and to Bhâmisvara Mahâdêva, situated on opposite sides of the hill to the south-west of the town. They are of a good size, and have long flights of stone steps leading up to the summit of the hill. The style of building is superior to that of the other temples in the town, and some portions are probably of considerable antiquity.

One mile to the west of Bândâ, on the left bank of the Kên river, close to the village of Bhurendî, are the ruins of a fort called Bhûragarh, built by Râjâ Gumân Singh of Jaitpûr, about 1746 A.D.

- Bargarh, small town in tahsil Mâû, 12 miles S. of tahsil and 80 miles S.-E.
 of Bândâ, possesses the ruins of a fort built by Hindûpat, Râjâ of Paṇṇâ, some 300 years ago.
- 6. Barha Kotra, two small villages on the south bank of the Jamna, in tahsîl Mâû, 11 miles E. of tahsîl and 82 miles S.-E. of Bândâ, possess the remains of a magnificent temple, a truly beautiful specimen of mediæval Hindû sculpture and Ib. architecture. Its position on a high projecting point overlooking the Jamna is a very fine one, and both in size and decoration the fane was worthy of its site; it is, besides, raised on a plinth or platform of 11 feet. The temple is dedicated to Siva under the name of Karkotaka Naga. It consists of the usual sanctum containing the lingam with the entrance on the east, as is usual with linga-shrines. The mahamandapa, or great hall, is 25 feet square, the roof being supported on four magnificent columns, each upwards of 14 feet in height. These are placed eight feet eight inches apart on a raised platform one foot and three and-a-half inches in height. On each of the four sides immediately opposite each pillar there is a square pilaster nearly 10 feet high at five feet distance; and between each pair of pilasters there are two octagonal pillars of the same pattern as the larger columns and of the same height as the pillars. The architraves covering these pillars are massive beams, about two feet square in section and very elaborately ornamented on each face. Between each pair of pillars there was formerly a cusped arch, now fallen down. The central roof of the mandapa has fallen down, but a portion of the side roof still remains. The usual arrangement is to cover this portion by overlapping stones, projecting one over the other from the outer and lower rows of pillars until the space between the two rows of pillars is roofed over. But in this temple the arrangement is quite different, the whole of the surrounding verandah, as it may be called, being roofed in by long sloping slabs which are very deeply cut with three horizontal recesses which imitate the courses of the over-lapping roofs. In the recesses there are rows of small seated Naga kings with snakes' hoods over their heads. On the west side three of these sloping slabs still remain in situ, and at the north corner there is a single slab of wedge shape, that is, narrow at the top and broad at the bottom, showing that the same arrangement of roof was continued at angles. With the remains still lying on the ground it seems certain that there must have been a small

¹ Cunningham, Archieological Reports, Vol. XXI, page 4.

porch, or hall, on each side to the north and the south, and a third on the east side forming the entrance. Externally the view from the east would have presented three pyramidal domes in front; the middle one being higher than the others, with the tall spire of the sanctum behind. There is no *inscription* now remaining, the only writing being a few pilgrims' records, of which one is dated as early as Samvat 1141, showing that the temple must have been erected about the end of the 10th century A.D. The people call the temple Bar, or Bhâr Devâl, which is probably meant for Barâ Devâl.

In the face of the hill nearly due south from Barha-Kotra, and about a mile and-a-half distant, there are two large caves known by the name of Rikhian, or III. the dwellings of the Rishis. They are apparently old quarries partly built up in front with dry stone walls to form rooms. Two pillars help to support this roof. The larger cave is 341 feet long by 171 feet broad and six and-a-half feet high. Inside, against the back wall, there is a large collection of statues which were most probably taken from the Barha Kotra temple after it had become ruinous. The principal statue is a figure of Vishnu with 12 arms; it is four feet high by two and-a-half feet broad. There are also figures of Kali and Ganesa, and of 42 goddesses, which are most probably a portion of the Chaunsat Yoginis, as several of them are represented with animals' heads. The second cave is 22 feet long by 16 feet broad and seven feet high, with one pillar in the middle to support the roof. It has a projecting porch in front of the entrance built with square stones; it has also two holes, or small windows, to give light. Inside there is a seated figure of a three-headed goddess with 16 arms; it is two feet eight inches high by one foot nine inches broad, and most probably represents Durga. On the surface of the rock there are several pilgrims' III. records, but all of the 15th century A.D. Outside there is a small temple with a sanctum only, four feet 10 inches square and a flat roof, nine and-a-half feet high. Two other temples in ruins are close by. At the foot of the hill there is a large tank, 600 feet in length, which is supplied by a small stream coming over a waterfall. The place is considered holy, and is visited by numbers of pilgrims.

 Bilgãon, village in tahsíl Girwân, 18 miles S.-E. of Bândâ, possesses five Hindû temples.

IIb. The village of A k b a r p û r possesses an îdgâh, erected in A.H. 1072, during the reign of Aurangzib.

IIb. 8. BISAURA BUZURG, village in tahsîl Girwân, 18 miles S.-E. of Bândâ, possesses five Hindû temples and one small masjid.

9. Chitrakûţ,¹ a celebrated hill and place of pilgrimage on the left bank of the Paisunî, in tahsîl Karwî, five miles S.-E. of tahsîlî and 50 miles S.-E. of Bândâ. The holy hill of Chitrakûţa, or the "many-hued peak," is famous as the residence of Râma, Sîtâ, and Lakshmaṇa, during their exile from Ayodhyâ, and also as the abode of the sage Vâlmîki, the reputed author of the Râmâyaṇa. A narrow paved footpath with a continuous belt of small temples encircles the foot of the hill, which is crowded with pilgrims at all times of the year. This path was constructed some 200 years ago by one of the Râjâs of Paṇṇâ for the convenience of pilgrims

IIb.

¹ Conningham, Archaelogical Reports, Vol. XXI, page 10.

Hb.

III.

performing the ceremony of circumambulation. The temples, however, are all modern, and there are no inscriptions. Fragments of sculpture and pieces of carved stone are found lying about the foot of the hill, but there is nothing to show that the place is an old one. Kâm tâ is the name of the village close by the hill, and the hill itself is often called Kâmtâ. The real name is Kâm adâgiri, or the "hill of the giver of plenty," or the "desire-giving hill." The hill itself is still covered with jangal; but there are no Rishis, as the Brâhmaṇas of the present day all live in comfortable houses below.

Of late years the small town of Sîtâpura, situated also on the left bank of the Paisunî river, one mile to the north of Kâmtâ, has rivalled the fame of the holy Chitrakûţa. Here the river Paisunî forms a long straight reach, both broad and deep, on the banks of which there are numerous temples and bathing ghâţs, or flights of steps leading down to the water. Some of the temples are said to be old, but they are all so smudged with whitewash that it is quite impossible to judge of their antiquity. The name of Sîtâpura is, however, quite modern, as it was called so at the beginning of the present century; the old name was Jayasimha-pura.

The Gupta Godâvarî, or "concealed Godâvarî," is a small stream which issues from a cave in the hills about nine miles to the south-west of Chitrakûţa. The stream is one of the objects of pilgrimage. It is from eight feet to ten feet broad and three feet deep, and falls into the Godai Nâlâ. There is a long Devanâgarî inscription inside the cave, but it is comparatively modern.

10. Dadhwâmânpûr Garrampûr, village in tahsîl Badausâ, 12 miles S. of Ib. tahsîlî and 37 miles S.-E. of Bândâ, possesses the remains of an old Chandella temple.

11. Girwân, tahsîl, 10 miles S. of Bândâ. On a small hill near the town there is a place regarded as sacred by the Hindûs, consisting of a figure or etching called Bharatijî on the face of the rock which the inhabitants believe to have been miraculously produced. There is on the same hill an image called Bhûtanâtha, which is also an object of worship.

12. Gonpâ,¹ village in tahsîl Badausâ, six miles S.-E of tahsîlî and 30 miles S.-E. of Bândâ. To the east of the village, where an embankment has been thrown across between two ranges of hills to form a tank, there is a pair of old Ib. temples standing together on the same platform. They are simply known as "Chandellî temples," as all old buildings are designated throughout Bundelkhand. Both temples have the river goddesses Gangâ and Yamunâ at the bottom of their door-jambs, but they are not standing on their symbolic animals, the crocodile and tortoise. The animals, however, are present, but are made very small and are mere accessories at the feet of the figures. The larger temple is built on the usual plan of an extensive hall, a central hall, and a sanctum with a door to the east. It is 55 feet long by 48 feet nine inches broad, and is still about 40 feet in height above the plain, but not more than 30 feet above its own terrace. It was originally dedicated to Vishņu, as there is a figure of that god over the middle of the entrance doorway. On each of the two sides there was a pillared portico to which on the south side was

¹ Cunningham, Archeological Reports, Vol. XXI, page 13.

attached a small temple 13 feet square outside with the entrance on the north leading into the mandapa of the larger temple. This small fane was dedicated to Lakshmi as shown by the figure over the centre of the entrance door. But at some later date both temples were appropriated by the Saivas, who placed lingas inside which are still in situ. The spire of the smaller temple is gone, but nearly the whole height of the spire of the larger one is still standing, save only the kalasa or pinnacle. The lower part is perpendicular, but the upper part is sloping with a very slight curve. On the perpendicular sides there are two rows of figures, each two feet in height, amongst which Siva, Kâlî, Gaņeša, Vishņu, and Brahmā can be recognized. In the upper part of the spire the angles only were ornamented, all the middle spaces being left quite plain. The roof of the mandapa of the great temple is altogether gone, and the stones now cover the floor. There are a few pilgrims' records of the 11th century.

One mile and-a-half to the west of Gonda on the present road leading from Karwi to Banda, lies the village of Rauli. To the south-west of the village there are two large caves in the middle of a hillock overlooking the place. Numerous broken sculptures of exquisite workmanship are scattered about, proving that there once stood a magnificent temple.

- 13. Gulrampür, village in tahsil Badausa, 16 miles S.-E. of tahsili and 41 miles S.-E. of Banda. Near the village there is a small stone temple on the top of a rocky Ib. hill called Bilhariya Math, in the midst of the valley, overlooked by the great fort of Marpha. The hill is 70 feet high. On the lower terrace towards the south there are the remains of two other temples which have been dismantled to furnish III. materials for the small fort of Birgarh, at a short distance to the north near the village of Bhagalanpurwa. Its walls are built entirely of squared stones, amongst which jambs, pillars, pinnacles, mouldings of many kinds, inscribed stones, and several roofing slabs are to be found. The temple on the hill is a small one; but it is highly ornamented, and it is otherwise remarkable for its picturesque situation. It consists of a sanctum eleven and three-quarter feet outside and four and-a-half feet inside, with a portico in front nine feet square. The spire is still standing with the lower amalaka-pinnacle in situ, but the upper part is gone. On the outside there are two rows of figures of which the lower ones are 19 inches in height. The temple was dedicated to Vishnu, who is represented over the centre of the entrance, with Brahmâ on the right and Siva on his left, and the navagrahas, or nine planets, arranged between them.
- JASPURA, small village in tahsîl Pailânî, four miles S. of tahsîlî and 17 miles
 N. of Bândâ. Near the village there is an old ruined fort, named Abhaipûr.
- 15. Kâlanjar,¹ celebrated hill-fort and town in tahsîl Badausâ, 20 miles S.-W. of tahsîlî and 33 miles S.-E. of Bândâ. The fort of Kâlanjar is one of the most famous places in India. It stands on an isolated flat-topped hill of the Vindhya range, which here rises to a height of 800 feet above the plain. The lower part of the ascent is tolerably easy, but the middle portion is very steep, while the upper part is nearly perpendicular and quite inaccessible. The main body of the fort lies

Journal, Asiatic Society of Bengal, Vol. XVII, pages 171—313 seqq.; Cunningham, Archwological Reports, Vol. XXI, page 20.

from east to west, is oblong in form, being nearly a mile in length by half a mile in breadth. At the north angle there is a large projecting spur nearly a quarter of a mile square which overhangs the town; and on the middle of the southern face there is another projection of about the same size, but triangular in shape. The distance between the entrance points of these two projections is nearly one mile. The whole area is therefore considerably less than a square mile, while the parapet walls are nearly four miles in length.

Kâlanjar has been occupied from the most remote times. It is mentioned in the Vedas as one of the tapasyasthinas or "spots adopted to practices of austere devotion." In the Mahâbhârata it is stated that whoever bathes in the lake of the gods at Kâlanjar acquires the same merit as if he had made a gift of thousand cows. In the Padmapurâṇa it is named as one of the nine holy places in Northern India. But all these notices refer solely to the sanctity of the hill as the resort of ascetics. The name of Kâlañjarâdri, or the "hill of Kâlañjara," is said to have been derived from Śiva himself, who as kâla or "time" causes all things to decay (jara), and who is therefore the destroyer of all things and the god of death. The ascetics of Kâlanjar were therefore devoted to the worship of Śiva.

The oldest historical mention of Kâlanjar as a fortress is in A.D. 1023, when the place was besieged by Mahmûd of Ghaznî during the reign of the Chandella Râjâ Ganda Dêva. Its erection as a fortress is universally attributed to Chandravarman, the traditional founder of the Chandella family; but the inscriptions are silent as to Chandravarman, and give Nannuka as the founder of the family. There is, besides, good evidence to show that Kâlanjar was a famous fortress even before the rise of the Chandellas. The Kalachuris of Southern India claim descent from a son of Siva, named Krishna, by a Brahmani mother, who slew the King of Kalanjarapura, and afterwards took possession of the "nine lakh country" of Dahala Mandala (or Chedi).1 Now the Chedis or Kalachuris had possession of Dahala Mandala (Tipura, or Tewar on the Narbada) as early as the sixth century, when they came into contact with Mangalisa Chalukya. Their occupation of Kalanjara must, therefore, have occurred some time earlier. This event may have given rise to the Chedi or Kalachuri era, which dates from A.D. 248. But the fort of Kâlanjar must already have existed for some time before it attracted the notice of the Kalachuri chief, Krishna. It seems highly probable, therefore, that the fortress may have been founded at least as early as the beginning of the Christian era.

There are two entrances to the fort of Kâlanjar, of which the principal is on the north side towards the town, and the other at the south-east angle leading towards Paṇṇâ; this latter, which is still called the Paṇṇâ gate, is now closed. The other entrance is guarded by seven different gates which beginning from below are named as follows: (1) Ålam, or Ålamgîrî darwâza; (2) Gaṇêśa darwâza; (3) Chandî, or Chauburjî darwâza; (4) Budhabhadra darwâza;

(5) Hanuman darwaza; (6) Lal darwaza; and (7) Bara darwaza.

There is an ascent of about 200 feet up to the lowest gate, which is a battlemented building in the modern Musalman style. Over the archway there is a

¹ Rice, Mysore Inscriptions, page 64.

rhyming Persian inscription of three lines recording the constructing of the gate by Muhammad Murâd in A.H. 1084, or A.D. 1673, during the reign of Aurangzib, when it was made as strong as the "wall of Alexander." Above this there is a steep ascent, chiefly by steps, to the second gate called Ganêsa darwâza. At a short distance higher up in the bend of the road stands the third gate, named the Chandi darwaza. There is a double gate with four towers, on which account it is also known as the Chauburji darwaza, or the "gate of the four towers." At this gate there are several pilgrims' records of various dates, Samvat 1199, 1572, 1580, and 1600. The latest of these, Samvat 1600, or A.D. 1543, records the final capture of the fort by Shêr Shâh, a mistake of two years. On the first door-jamb there is a much older inscription of 15 lines in later Gupta characters. fourth gate named Budhabhadra is the gate of the "auspicious planet Mars (Budha)." It is also named svargarohana, or "heaven-ascending gate," owing to the stiff climb required to reach it. It possesses only one inscription of a pilgrim, dated Samvat 1580, or A.D. 1523. On a rock between this and the next gate there is an inscription of the 11th century. The fifth gate, or Hanuman darwaza, is so named after a figure of the monkey-god carved on a slab resting against the rock. There is also a reservoir called Hanumankund; there are, besides, numerous rock sculptures which are very much weather-worn. Two inscriptions of pilgrims are dated in Samvat 1530 and 1580. On the ascent beyond there are many weather-worn figures carved on the rock representing Kali, Chandika, Siva and Pârvati, Ganêsa, the bull Nandî, and the lingam. There is also a small cave or niche containing a broken figure of Hanuman and several pilgrims' records, dated Samvat 1560 and 1600. The sixth gate, called the Lal darwaza, stands near the top of the ascent; it is covered with several short inscriptions of pilgrims. Carved on the rock outside there is a long inscription of the Chandella time. To the west of this gate in the raoni, or faussebraie, immediately above the Kambhorkund, there is a colossal figure of Bhairava cut in the rock. There are also two figures of pilgrims represented carrying water in the usual manner in two vessels fixed to the end of a banghi pole. Near one of them there is a long inscription in later Gupta characters. A short ascent leads to the seventh or uppermost gate, called Barâ darwâza, or the main gate. As it stands now, it is undoubtedly modern, and its late date is confirmed by the only inscription attached to it of Samvat 1691, or A.D. 1634.

Ib. Inside the fort on the north face are four places of note, named, Sitakund, Sitasej, Patal Ganga, and Pandukund.

Sitakund is a natural reservoir under shelving rocks, and is reached by three steps from the rampart. On the rock over the kund there is a sitting figure about two feet high, resting on one hand, and near it what appears to be a basket of fish. Near this figure there are several *inscriptions*, one of which is dated Samvat 1640, or A.D. 1583.

Sitasej is a small cave or recess containing a stone bed and pillow for the use of an hermit, covered with inscriptions of Samvat 1597 and 1600. Over the entrance door there is an inscription in characters of the eighth century.

Ib.

The Pâtâl Gaugâ is a large deep well or reservoir cut in the rock. The water is deep and is constantly dripping and trickling from the roof and sides. The oldest inscription found there is of Samvat 1339, or A.D. 1282; the next is of Samvat 1500, or A.D. 1443, and a third of Samvat 1540, or A.D. 1483. Next comes a record of the Emperor Humâyûn in Persian, dated A.H. 936, or A.D. 1529. The latest is of Samvat 1640, or A.D. 1583, during the reign of Akbar.

The Pâṇḍukuṇḍ is a shallow circular basin about 12 feet in diameter, into which the water is constantly trickling from the crevices in the horizontal strata. This kuṇḍ is undoubtedly old, as it possesses a short inscription in Gupta characters.

Near the middle of the east face there is a natural hollow, in the bottom of which has been excavated in the rock a small reservoir with steps all round. This is called the Bodhi, or Bûrhiyâ Tâl; its waters are believed to possess very great healing powers.

At the south-east angle is situated the Panna or Bansakar gate, which is now closed; it is covered by a small outwork. There are three gates, on which there are some pilgrims' records of Samvat 1550 and 1600.

North of the Paṇṇâ gate in the scarp of the hill below the rampart there is a small pool of water, called Bhairon-kâ-Jhirkâ, or Bhairava's well, with an old record of Samvat 1195, or A.D. 1138. Above the kuṇḍ there is a colossal figure of Bhairava carved in the rock, with several records, the oldest of which is dated Samvat 1194 or A.D. 1137.

Further on in the same direction there are three places of note named Siddh-kâ-guphâ is kâ-guphâ, Bhagwân-sêj, and Pâni-kâ-amân. The Siddh-kâ-guphâ is merely a small excavation in the perpendicular rock formed for performing penance in it, with a long Sanskrit inscription of Râjâ Jațiladhî. Bhagwân-sêj is a stone couch and pillow similar to that of Sîtâsêj, but smaller and cut under a projection of the rock. Beyond this is the excavation called Pâni-kâ-amân; it is very low and entered by a small door about two feet six inches high, the flat roof is supported by four pillars slightly decorated. There are neither inscriptions nor sculptures at these places.

Near the middle of the south face is the Mṛigdhâra, or "antelope's spring," a small pool in an inner chamber of the rampart into which the water is constantly trickling. There are several pilgrims' records of the 16th century. The spring is no doubt supplied from the great reservoir of Koṭhtîrtha on the high ground close by.

Kothtîrth is a large reservoir, nearly 100 yards in length, with several flights of steps and many remains of sculpture. On the steps there are many pilgrims' records of the 16th century, and on the north bank of the tank there is a masjid of the time of I s l a m S h a h, built of old temple materials, with one inscription of the Gupta period and many of the 11th century.

The great lingam temple of Nîlakantha is situated in an outwork in the middle of the west face of the fort. The upper gate, leading into the outwork, is attributed to Râja Paramârdi Dêva, or Parmâl (A.D. 1167—1203); there are several inscriptions, but all of the 16th century. A second gate which leads into the

courtyard of the temple has no inscription; but on the rock on the right hand of the descent there are numerous small caves and niches, with many statues and several inscriptions of the Chandella time. The actual shrine of Nîlakantha is a small cave with the remains of a fine mandapa or hall in front. The façade of the cave has been very rich, but is now much broken and hidden by numerous coats of whitewash. On the jambs of the door there are figures of Siva and Parvati with the Ganga and Yamuna rivers; these are of the Gupta period: the pillars of the hall are later and belong to the time of the Chandellas. The roof of the mandapa is now gone, but most of the pillars and pilasters still remain, forming a square with four on each side and four in the middle. In roofing the corners are cut off to form an octagon. The lingam is made of a dark-blue stone, four and-a-half feet high, and has three eyes. It is at present the chief object of worship at Kalanjar, and to judge by the pilgrims' records, it has been equally popular for many centuries. Just outside the mandapa of Nilakantha there is a deep kund or rock-cut reservoir, called svargarohana, and to the right of the kund in a rock recess or niche there is a colossal figure of Kala-Bhairava, 24 feet in height, standing in two feet of water. The sculpture is 17 feet broad, has 18 arms, and is ornamented with the usual garlands of skulls, with snake-earrings and snake armlets and a serpent twined round the neck. In the hands are various objects, of which the most prominent are a sword, a bowl of blood, &c. Beside this statue there is a figure of the skeleton goddess, Kâlî, four feet in height, which is now standing in water upwards of a foot in depth. The water trickles from above and falls on these figures. Beyond this sculpture there is a closed portion in the wall of the outwork, above which on the outside there is an inaccessible cave.

Outside the walls of the fort on the north face and about half way up the hill there is a small isolated rock some 15 feet long by 10 feet in height. On this rock there is sculptured a famous lingam, named Balkandêsvara, and beside it the figure of a pilgrim carrying Ganges water at the two ends of a banghi pole. Over the head of this figure there is an old inscription of one line of Gupta characters, one inch high. There is a similar figure with the same inscription down in the plain below, called Sarwan Bâbâ.

On the north face of the hill and about 60 feet or 70 feet above the plain there is a fine stone-walled tank called Gangassar, 160 feet in length by 120 feet in breadth. It has a continuous flight of steps on three sides, and only a narrow flight in the middle of the fourth side. A long flight of steps leads to the top of the embankment. The whole of the steps and walls are formed of cut stones, including numerous carved pillars, bracket capitals, and broken statues. On this site there has once been a very fine temple as shown not only by these remains, but by a colossal figure of Vishnu, 13 feet in length, reclining on the serpent Ananta. There are no inscriptions, but it seems highly probable that the inscribed figure of the water-carrier, now fixed in a shed a short distance below, must have been taken from this site.

The town Kâlanjar itself contains numerous relics of the past, chiefly of the Musalman period. Several old masjids, dating from the time of Akbar downwards, and inscribed A.H. 1012, 1122, 1131, and 1155, are in different stages of decay. The

III.

16.

III.

IIb.

IIb.

temples.

oldest is situated at the foot of the hill and attributed to one Shaikh Wâlî, a contemporary of Akbar. The town is furnished with three gateways, built in the time of Aurangzib.

IIb. 16. Karwî, tahsîl, 42 miles S.-E. of Bândâ, possesses five masjids of no merit, and five Hindû temples built by the Marâthas, of which the one known as Ganêsa Bâgh is admirable both for its execution and design.

Half a mile to the west of Karwî lies the town of Tarâhwan, which possesses six Hindû temples, five masjids, and the ruins of a brick-fort, built some 250 years ago by the Surkîs of Gahôrâ.

Three miles south-east of Karwî, on the high road leading from Karwî to the Mânikpûr station of the East Indian Railway, near the hamlet of Kalû, there are the ruins of a small Chandella temple of exquisite workmanship.

One mile further on, there are the ruins of an old temple, called Haihaitî Mandir, on the top of a picturesque hill, overlooking the village of Khoh. Fragments of statues of Kâlî, Gaņêśa, Šiva, and Pârvatî, as well as ornamented pillars, door-jambs, lintels, and pinnacles are scattered about at the foot of the hill.

- 17. Khandeh, village in tahsîl Bândâ, 13 miles N.-W. of head-quarters, contains 16 Hindû temples of no great importance.
- Кнартіна, village in tahsil Pailani, eight miles N. of Banda, possesses four IIb. Hindu temples and one masjid.
- 19. Laurt, or Lokhri, 1 village in tahsil Mâû, 10 miles N.-E. of tahsîlî and 52 miles S.-E. of Bândâ, is situated at the northern foot of the Vindhya hills. To III. the south-west there is a small fort and to the east of the fort there is a stone platform on which the villagers have set up 24 images of the Chaunsât Yoginis. Between the fort and the village there is a tank, on the bank of which stands a large stone elephant, seven and-a-half feet long and three and-a-half feet broad by five and-a-half feet high to the top of the head. There is an inscription on the elephant, dated Sañvat 1516, or A.D. 1459. The elephant and the statues most probably belonged to some temple which was ruined during one of the early campaigns of the Musal-mâns. On the bank of the lake and in the fields close by are the ruins of some Jain
 - 20. Majhgawân, or Râjâpûr, town in tahsîl Mâû on the right bank of the Jamnâ, 20 miles N.-W. of tahsîlî and 59 miles E. of Bândâ, the residence of the Hindû poet Tulsî Dâs, possesses several fine Hindû temples built in the time of Akbar, of which that dedicated to Somêsvara is the most important.
- III. 21. Marphâ,² hill fort in tahsîl Badausâ, eight miles S. of tahsîlî and 32 miles S.-E. of Bândâ. The great fort of Marphâ is but little known, although it is as large and as lofty as either Kâlanjar or Ajaygarh. It is situated on a high projecting hill, 12 miles to the north-east of Kâlanjar. There are four gates to the fort, two to the left and two to the right; the space within occupies about 385 acres. The fortification walls with bastions are mostly in ruins, and inside there are three ruined Jain temples and one ruined Hindû temple dedicated to Siva under the name of Pañchavaktra. In these temples there are several inscriptions, but not old

¹ Cunningham, Archaelogical Reports, Vol. X, page 15.

² Cunningham, Archaeological Reports, Vol. XXI, page 12.

and of very little value. There is one long inscription of three lines, dated Samvat 1404 (A.D. 1347), Kârttika sudi 14, gurau, in the Siddhitungarâjye, or during the reign of Siddhitunga, and mentions the fort under its original name, Madharpa. Two others in small letters are Jain records of the Milasamgha, dated Samvat 1407 and 1408. They contain no kings' names and are confined to the names of the donors of the statues dedicated, and of the high priest at the time of dedication. As Marpha is not mentioned by any of the Musalman historians, it seems probable that it was not occupied as a fort until Kalanjar had fallen. The fort is now completely deserted and overrun with jangal, in which both tigers and leopards find cover.

- 22. Marwal, village in tahsîl Babêru, 12 miles N.-E. of Bândâ, possesses a small fort in a ruinous condition near the banks of the Gararâ river.
- III. 23. Mât, tahsîl on the right bank of the Jamna, 70 miles E. of Banda. One mile and-a-half to the north-west of Mâû, near the hamlet of Rithorâ, there are two ruined temples of small size, but of fine workmanship. The larger one is only III. 101 feet square outside, with a portico on the north in front of the entrance, supported on two nicely-carved pillars. The temple has fallen backwards and the enshrined figure is lying inside crushed beneath the roof. On the face of the door-step there are represented two crocodiles, each carrying two women with children in their laps. There is a figure of Kâlî outside, from which it may be inferred that the temple was dedicated to the worship of Siva. The pillars are of early mediæval style.

The second temple is similar to the first, and was also dedicated to Siva, as it still III. possesses a group of Siva and Pârvatî. The entrance door also is similar to that of the other temple; but the jambs which are still standing have figures of the Ganges on her crocodile and the Yamuna on her tortoise.

Five miles to the west of Mâû, in the hamlet of Pûra, close to the village of Hatovâr, there are the ruins of a large lingam temple of the Chandella type, the III. sanctum of which is still standing. To the west of the temple there is a twostoreyed priests' house, consisting of 10 cells, built of large blocks of sandstone and Ib. beautifully ornamented, being a good specimen of the domestic architecture of the Hindus of the middle ages. Close by under a pipal tree is an inscribed statue of Durga of the Chandella period.

At the village of Biria, six miles west of tahsili, there is an inscribed red sandstone slab of the Chandella time.

24. Naravani, village in tahsil Girwan, 20 miles S.-E. of Banda, possesses five Hindû temples.

25. Oran, village in tahsil Badauså, 20 miles E. of Banda, possesses on the west of the village the ruins of a small fort.

26. PACHNEHÎ, village in tahsîl Pailânî, eight miles N. of Bândâ, possesses seven Hindu temples and one masjid.

27. PAILÂNÎ KHÂS, tahsîl, on the right bank of the Kên river, 20 miles N. of Bândâ, possesses a masjid in good preservation, built according to a Persian inscrip-IIb. tion on its walls, in 1702 A.D. by one Himmat Bahâdur Kâsim, ruler of Pailâni at the close of the reign of Aurangzib.

IIb.

III.

Hb.

28. Râmnagar, village in tahsîl Mâû, 10 miles W. of tahsîlî and 61 miles E. of Ib. Bândâ, possesses on the banks of a large tank the ruins of a large temple of the Chandella period, elaborately carved, and in general design and execution similar to the Bar Devâl of Barhâ Kotrâ. The sanctum has gone entirely, but many stones still remain to show that it was highly decorated. The mandapa, or great hall, is 40 feet square, and supported on eight highly-decorated pillars. Close to the temple Ib. there is a priests' house built of large blocks, in a fair state of preservation.

One and-a-half mile to the west of Râmnagar, on the high road leading to Karwî, there is a large lake of the Chandella type, on the banks of which the remains of a large temple are scattered about.

III. of a large temple are scattered about.
 Four miles further on the north side of the road there is a large cave, called
 III. Vâlmîki's hermitage, high up in a steep hill. Inside the cave there are several

inscribed statues, both Brahmanical and Jain, of the 15th century.

29. Rasin,1 old village in tahsil Badausa, four miles N. of tahsili and 29 miles S.-E. of Banda, is the ancient Rajavasini. It lies at the foot of a granite hill, and its mounds, ruined temples, and broken sculptures all show that it must once have been a place of considerable consequence. There are also 19 fine old tanks of the Chandella time. On the side of the road, at the foot of the hill and to the north of the village there are several sati pillars, with a large standing female figure holding Ib. a child in her left arm. On the east side of the road there is a small mound, faced with squared stones. On the top are several statues, of which the most prominent is a figure of Ganêsa. The platform was certainly the site of a temple, and it is accordingly now called Sivala, or "the temple of Siva," and sometimes also Ganesa from the principal figure. Amongst the broken sculptures there are many fragments of a colossal figure of the skeleton goddess, Kali, eight feet high and four feet broad. The figure has 24 arms and is surrounded by a number of small skeleton females of the same kind, both sitting and standing. The goddess herself is represented standing on the back of a prostrate male figure; she has a deeply-sunken stomach with a very long-tailed scorpion between the ribs. On the mound there are several other sculptures, such as Durgâ with 10 arms, a large figure of Hanumân six feet high, and the upper half of a statue of Narasimha, or "man-lion" of life size. A little further on there is a group of ruins, the principal object of which is the entrance door of a temple, which is still standing apparently in situ, with some fragments built into a piece of rough wall on each side. The site is accordingly known simply as darwaza, or "the door." Amongst the stones collected here there is a complete pilaster, five feet two inches in height, and a piece of a 12-sided pillar. There is also a 10-armed figure of Durga and several sati stones, of which one bears a nearly obliterated inscription. In the village itself there is a Sivala built IIb. of old materials.

IIb. On the top of a hill overhanging the town there is a temple of Ratannatha; it is not very old, and bears no inscription.

On the top of another hill, about one mile to the east of the village, but nearly two miles by the winding pathway, there is the famous temple of Chandî Mahêsvari, situated in a dense jangal. The building is much smaller than the

16.

¹ Canningham, Archaeological Reports, Vol. XXI, page 15.

Goṇḍâ temple, and has no figures on the outside, but only simple mouldings. The sanctum is only 12 feet outside and eight feet by seven and three-quarter feet inside, with a niche in the back wall and a lingam in the middle. The mandapa or hall in front is slightly oblong, being 18 feet eight inches by 17 feet seven inches. The hall is open at the sides, with two broad seats, three and-a-half feet wide, backed by sloping parapets. There is a small portico in front, nine feet wide by six feet deep. The enshrined statue of the goddess has four arms, and is two feet in height. Close by there is a tank hewn out of the rock 80 by 50 feet. There are two inscriptions on the temple, an old record of the Chandella period in two long lines, without date, and a record of seven short lines, dated Samvat 1466, or A.D. 1409.

Two miles to the south-west of Rasin, near the village of Birpûr, there are the remains of a small Chandella temple, of which the sanctum is still standing.

Hb. The village of Donâ possesses a masjid built in A.H. 1103, during the reign of Aurangzîb.

- 30. Sihondâ, town in tahsîl Girwân, 11 miles S. of Bândâ, possesses the remains of a large fort on a hill to the south-west of the town near the Kên river. There are said to have been at one time 700 masjids and 900 wells within the town; the former have all fallen into decay with the exception of four, and the latter have been almost all choked up. On the top of another hill, called Khatri Pahâr, near the town there is an old temple, dedicated to Aûguleśvarî Dêvî, of considerable repute among the Hindû population. Local traditions assume that Sihondâ was an important city in the heroic period of early Indian history. There are, however, to all appearance no remains in its immediate vicinity of any great antiquity and few, if any, earlier than the Musulmân period.
 - 31. Simaunî, village in tahsil Babêru, 18 miles N.-E. of Bândâ, possesses the remains of a fort built by Sulţân Shâh Qulî. A masjid built by the same person, and bearing an inscription dated A.H. 988, or A.D. 1581, still exists.
- 32. Sindhan Kalan, village in tahsil Pailani, 20 miles N. of Banda, possesses III. 10 Hindû temples and two masjids. The traditionary account of the village is that it was formerly the point of junction (samdhi) of the Ken and Jamna rivers, and thence received its name.

III.—FATHPÜR DISTRICT.1

- Amaulî, decayed town in tahsîl Korâ, 42 miles W. of Fathpûr, possesses
 many masjids, tombs, and large brick dwelling-houses now all in ruins. There is a
 fine sheet of water adjoining the town with picturesquely wooded banks.
- 2. Aphüî,² village in tahsil Khâgâ, 29 miles S.-E. of Fathpûr, is a very old place with a mound 10 to 12 feet in height, covered with broken bricks. The mound is called C h a u k i, because it was one of the stages on the old Hindû road leading from Kanauj through Karrâ to Prayâga. There are several fragments of stone sculptures under a nîm tree. It is mentioned by Alberûni³ under the name of

III.

III.

 $\Pi b.$

North-Western Provinces Gazetteer, Vol. VIII, Part III, pages 93—142, passim; Growse, Supplement to the Fathpiir Gazetteer, Allahabad, 1887, pages 7—40, passim.

³ Cunningham, Archaelogical Reports, Vol. XVII, page 96.

³ Sachau, Alberuni's India, Vol. I, page 200.

Hb.

Abhâpûrî, as being 20 farsakh distant from Prayâga. The name of Aphûi is applied to a group of villages, namely Ismâîlpûr-Aphûi, Ganj-Aphûi, Râmpûr-Aphûi, Baraiyapûr-Aphûi, and Sunâwardeh-Aphûi. This use of its name shows that Aphûi must once have been a place of some consequence.

- 3. Asnî, village in tahsîl Faṭhpûr, 10 miles N. of head-quarters, is a place of IIb. pilgrimage, the chief shrine being that of the Asvinî Kumâras, the two sons of the Sun, which gives its name to the place, and which has been gradually shortened to Asnî. It was here that Jayachchhandra of Kanauj deposited his treasures before his last flight with Mahmûd.
- III. The old fort built by Haranâtha in A k b a r's time, is still standing on the bank of the Ganges, with very large bricks in its lower walls. But the principal mass of ruins consists of a large mound covered with broken bricks and pottery. The mound stands on the very brink of the Ganges on a projecting promontory within the lands of Chak-Pihâna. It is about 200 feet square; there are no traces of walls on the surface, but the bricks are old, as they are of comparatively large size, $12'' \times 8\frac{1}{2}'' \times 2''$. The only point of note is a small terrace or platform, dedicated to Dâna Bîr, or the demon Dâna.

That Asnî is undoubtedly an old site, is proved by an inscription² of Mahîpâ-ladêva, dated Samvat 974, on the face of a square sandstone pillar, found in 1867 at Asnî, and now in the Municipal Garden attached to the Town Hall of Fathpûr. Possibly Asnî may turn out to be the old Buddhist site described by Hiuen Tsiang³ under the name of 'O - y u - t'o, though no Buddhist remains have as yet been found.

A ferry-boat plies to the opposite shore in the Râi Bareli district, where there is a picturesque group of modern temples, the reputed site of an hermitage of the Rishi Garga.

- 4. Asoтна́в, village in tahsil Ghâzipûr, 14 miles S.-E.-S. of Fathpûr, is the ancient Aśvatthâmapura. Its original site is indicated by an extensive brick-strewn mound, two or three farlangs to the south of the fort, built by Arâru Singh in the first half of last century. On the highest part of it is a small modern enclosure which bears the name of the eponymous hero Aśvatthâma, the son of Drôṇa, but was evidently the site of an ancient temple of Mâhâdêva. Part of the sikhara has been set up as a lingam, the gurgoyled water-spout makes a trough for a well, and many other sculptured fragments are lying about, or have been built up into walls. On a smaller mound further to the south are five large Jain figures of the Digambara sect; the people call them the five Pâṇḍavas.
- 5. Aurâî, village in pargana Haswâ of tahsîl Fathpûr, 12 miles S.-E. of head-III. quarters. At the village of Tiksariyâ there is an extensive mound, evidently an ancient site, and a group of Hindû figure sculptures has been collected under a tree.
- 6. Ванџа, village in pargaṇa Ayah Sah of tahsil Ghazipūr, 13 miles W.-S.-W. Ib. of Faṭhpūr, possesses a small ruinous temple, known by the name of Kakora

¹ Cunningham, Archaelogical Reports, Vol. XVII, page 99.

³ Indian Antiquary, Vol. XVI, page 173.

² Beal, 4.c., Vol. I, page 225.

Bàbà, dating apparently from the 10th century. The sikhara, or tower, is of moulded bricks; the cella which it covers has pillars, architraves, and ceiling, all of carved stone, as in the more perfect example of the same style at Tindulî. It must have been orginally dedicated to Mâhâdêva, and was probably re-named about 200 years ago, when it was very roughly and ignorantly repaired, many pieces of the doorway being built up into the ceiling and other parts of the fabric. These stones, with one exception, Mr. Growse succeeded in extracting, and on putting them together, so little of the design was found wanting that he was able to re-erect the doorway in its original position. The so-called Kakôra Bâbâ is a recumbent statue of Nârâyaṇa, with Lakshmî at his feet, Brahmâ seated on a lotus growing out of his navel, and Seshanâga forming a canopy over his head. A smaller and more rudely executed figure of precisely similar design was found on a mound by the road side, which marks the older village site.

7. BINDKÎ, town in tahsîl Kalyânpûr, 18 miles W.-N.-W. of Fathpûr. Here were found some years ago in the course of excavations six stone slabs, one the lower part of a door-jamb, and another an architrave, six and-a-half feet long, with an antique pediment in the centre, supported from below by a small flying

figure.

III.

IIb.

Ib. to the Mauhâr railway station, is a very interesting temple tower of the 10th century A.D., a rare example of very early brick architecture. The cella is of stone, in the same style as the Mahobâ and Khajurâho temples, but the sikhara which surmounts it is of elaborately moulded brick. It was repaired plainly, but not badly, about one hundred years ago by a Brâhmana of the neighbourhood, who added the present porch. Of the original stone porch only a few fragments remain.

 Deomâî, village in tahsîl Korâ, 31 miles W.-N.-W. of Fathpûr, possesses a large sheet of water with modern temples on its banks and three broad flights of steps.

North of the village, on the road to Shiûrâjpûr, is a fine masonry tank now much dilapidated, built circa A.D. 1700.

A little further on the road is a baoli with a descent of 50 steps, built in 1720

by a banya of Kora.

9. Dhàrà, village in tahsil Khakhrêrû, 37 miles S.-E.-S. of Fathpûr, possesses a temple of Dêvi, which is of high popular repute, though a mean, shabby building. It probably occupies an ancient site, though the actual remains of the older shrine are of no special interest or antiquity.

10. FAȚHPÛR, head-quarters of the district, lat. 25°-55'-18" N., long. 80°-52' E., is said to have been founded in A.H. 917, or A.D. 1519, by Fațhmand Khân according to an inscription found in a Hindû temple at Dendâ Sâî in tahsîl Khakhrêrû.

There are no buildings in the town of Fathpûr of historical or antiquarian interest, except the maqbara of Nawâb Abd-us-Samâd Khân, adjoining the ruins of his fort, built A.H. 1111, or A.D. 1699, the garhî of Nawâb Ahmad Husain Khân of Bindaur, and the maqbara and masjid of Nawâb Bâkir Âlî Khân, built A.H. 1075. The latter occupy a conspicuous position at the junction of four main thoroughfares, and, being surrounded by a small garden, they form a picturesque

IIb.

and pleasing group in a singularly mean and unattractive town, though in themselves they are of no special architectural merit.

The tomb of Nawab Abd-us-Samad Khan stands in extensive and IIb. well-wooded park-like grounds, and has stone areades and traceried windows; but it is a heavy, ill-designed structure, and would seem to have been hastily raised after the premature death of the founder's eldest son, Abu Muhammad, in A.H. 1121, or A.D. 1702, as stated in a Persian inscription.

The masjid in Takiâ Ausârgarh bears the date 1181, and the grave of Karam Bêg near the Idgah is inscribed A.H. 1180.

In the Municipal Garden stands the Asnî pillar of Mahîpâladêva, dated Samvat 974. Around this pillar is grouped a collection of miscellaneous antiquities from different parts of the district, illustrating, with some degree of adequacy, the style of architectural decoration that prevailed in the neighbourhood during the period immediately prior to the earliest Musalman invasion.

11. GARHÎ JÂR, village in tahsîl Kalyanpûr, 19 miles W. of Fathpûr, possesses a fort and the rauza of Bahadur Khan, built in the time of Aurangzib, Hb. remarkable for its architectural beauty. The mausoleum is a large square building with a central dome, four smaller domes at the corners, and a bangala on each of the four sides. It is crowded with the tombs of his descendants. His son, Alam Khān, has a smaller monument with a single dome, at the other end of the village. In it the place of honour is occupied by what is said to be the grave of a favourite horse which was killed in battle. Both buildings are plain and unornamented. There is a ruinous masjid, called the Ulthi Masjid, so overthrown that great blocks of III. horizontal masonry now stand perpendicular.

Hb. At Dalel Khera, a hamlet of Barhat, is another large domed tomb of about the same date, and belonging to the same family.

12. GHAZÎPÛR, tahsîl, nine miles S. of Fathpûr, has the remains of a strong fort, III. and is said to have been built about A.D. 1691 by Arâru Singh.

About a mile to the north, in the village of Pain a, are the extensive ruins of an ancient fortified town. The circuit of the wall, with its gates and towers, can be III. distinctly traced, and in the centre of the high broken ground which it encloses is an inner citadel, further protected by a broad and deep moat. The town is said to have been originally a stronghold of the Chandellas, and may very probably be of still higher antiquity; but nothing is known of its history. The citadel was re-built by Araru Singh of Asothar, who probably gave it the name of Fathgarh, by which it is now known.

13. Gunta, village in tahsîl Kalyanpûr, 15 miles N.-W. of Fathpûr. General Cunningham1 conjectures on topographical grounds and from a calculation of distances that this may be the site of the Buddhist monastery of Vasubandhu. mentioned by Hiuen Tsiang.2 But the existing mounds seem to be the natural high bank of the Ganges intersected by ravines, and the only remains of antiquity are a few groups of small sculptured fragments of the character of the ninth or tenth century A.D. These are for the most part heaped on small masonry terraces which seem to be the sites of the original temples.

III.

Archaelogical Reports, Vol. XI, page 57.
 Beal, Lc., Vol. I, page 225.

14. Haswa, or Hanswa, small decayed town in tahsil Fathpûr, seven miles S.-E. of head-quarters, was originally named Champâvatî; but when, according to the legend, the three brothers Hamsadhvaja, Mayûradhvaja, and Sankhadhvaja settled here, Hamsadhvaja changed the name of the place to Hamsapura. There are, however, no ancient remains at present visible, except a ruined old fort in the centre of the town, on the top of which there is the dargâh of Alî-ad-dîn, sister's son of Qutb-ad-dîn, who lost his life in single combat with Râjâ Hamsadhvaja.

15. Hathgâon, town in tahsîl Khâgâ, 18 miles E. of Faṭhpûr, is the ancient Hastigrâma, situated on a high mound about 20 feet high, which is said to have been a fort of Râjâ Jayachchhandra. On the highest point stands a ruinous masjid known as Hâthikhâna, or Jaychandî Masjid, apparently constructed from the wreck of four small Hindû temples. There are 24 pillars in all, arranged in four aisles of six columns each, with a masonry wall at the back and sides. The temple doorway, a handsome piece of sculpture, has been set up by itself as the entrance to the masjid enclosure. The date of the columns is not later than the 10th century. Eight are square in shape, and far more massive than the others; four are square pilasters with a band running up the centre of each face; four are twelve-sided; four are eight-sided below, sixteen-sided in the middle, and round at the top; and the remaining four are made up of odds and ends. In all of them the main shaft is topped by two or three capitals, or other blocks of more or less incongruous character, in order to raise them to the required uniform height.

There is no tradition as to the time when they were re-arranged as at present. General Cunningham¹ conjectures that this was done by one of the Sharqi kings of Jaunpûr who ruled all this part of the Doâb, and who were noted for their religious intolerance. But the only basis for this supposition is a slab lying loose in a small modern masjid close by, which bears a Persian inscription, dated A.H. 854. This would correspond to A.D. 1450, at which time Mahmûd Shâh was king of Jaunpûr. But this slab has no connection with the Jaychandi Masjid, as it was brought from a field at some little distance. From the word qabar which occurs in the second line, it appears to have belonged to the tomb of some person whose name is given as Yûsuf.

Other buildings of precisely similar character are the Asî-khambhâ at Mahâban in the Mathurâ district, the so-called Parmâl's palace at Mahobâ in the Hamirpûr district, and the masjid in the citadel of Bijapûr in Southern India. All are very unsuitable for Musalmân worship, and probably were never intended to be so used, except once only, to signalise the triumph of Islâm over Hindûism.

Close by there is a stone pavilion, or baradari, built in the time of Jahangir.

About two miles from Hathgâon near the spot where the Sasûr-khadêri river crosses the road to Husainganj, there is a stone elephant called Jagannâth. It is represented as sitting down, with its trunk stretched out on the ground, and an ornamental square pad bound on to its back.

16. Husainganj, or Chaunkâ, village in tahsîl Faṭhpûr, eight miles N. of III. head-quarters, possesses the remains of an old fort.

III.

Ib.

Ш.

¹ Archaelogical Reports, Vol. XVII, page 98.

- 17. Jâfarganj, decayed town in tahsîl Kalyânpûr, 20 miles W. of Fathpûr, IIb. possesses a large masjid built by Nawâb Bâkir Alî Khân, or his brother Jâfar, and at each end of the bâzâr is a gate.
- III. The ruins of the Nawâb's fort are a mile or so away nearer the bank of the Jamnâ.
- 18. Khairâî, village in tahsîl Khakhrêrû, 25 miles S.-E.-S. of Fathpûr. Adjoin-III. ing the village is a circular mound, the site of a temple, of which only the foundations remain in situ, with traces of broad flights of steps leading up from the plain below. Several huge blocks of sandstone are lying about; and, in the village, let into the wall of a small modern shrine, and in other places, are some mutilated figures and architectural details.
- In an extensive mound a little to the east, called garhi, Mr. Growse dug up three spiralets of a sikhara, three and-a-half feet high, covered with the ornamentation characteristic of the 10th century A.D.
- 19. Кналина, village in tahsil Kora, 21 miles N.-W. of Fathpur, possesses three IIb. masjids, two baradaris, a sarai, a tank, and a garden called Bâdshâhî Bâgh, built by Aurangzib to commemorate his victory over Shûja Shâh. Though too modern to be styled antiquities, the Emperor Aurangzib's sarai and garden pavilions are of some architectural and historical interest.

The sarâî covers more than 10 acres of ground, and has as many as 130 sets of vaulted rooms. There are two handsome double-storeyed gates surmounted by minarets; the walls are embattled, and in the centre of the square is a domed masjid.

The garden has an area of about 18 acres; is enclosed by a wall with corner towers, and contains three reservoirs of cut stone with provisions for fountains. A broad terrace runs the whole length of one side, and on it stand two elegant pavilions. Underneath this terrace, outside the garden-wall, is a very large tank, more than 800 feet square; its boundary wall on the north side seems never to have been built.

- The town has grown up round the sarâi, and contains a very large number of modern temples; two of them are large and picturesque groups of buildings with fine tanks attached to them.
- 20. Khakhrèrë, tahsîl, 29 miles S.-E. of Fathpûr, possesses a small mound, called garhî, by the side of the Khâgâ road, where a temple once stood. This was destroyed by the Musalmâns, who used the materials to construct a grave-yard masjid on the same site. This latter erection had apparently fallen into ruins in 1852, and the bricks were then used, for a third time, in the construction of the tahsîlî. All the carved stones were left on the spot; these consist chiefly of architraves and doorjambs, handsomely carved in the style of the 10th century.

In the tahsîl office there is an inscribed slab, dated A.H. 703, during the reign of Alâ-ad-din Muhammad Shâh I.

III. 21. Korâ, tahsîl, 29 miles N.-W. of Fathpûr, possesses the ruins of a large fort which still presents an imposing appearance. It was built by Râjâ A û ga Dê va on the site formerly called Mahâkâya, and entirely re-built by Vijaya Singh, called Bijli Khân, after becoming a Musalmân. The fort was occupied as a tahsîlî till shortly before the mutiny, when it was dismantled. Now nothing remains of it but the masjid, and this, too, would seem to be of later date than the reign of Akbar,

which is the time when Bijli Khan is said to have lived. The site is a high cliff commanding a fine view of the Arind ravines.

The fort and all that end of the town of Korâ which adjoins the fort are called Argal. Possibly the fort was so named as forming a natural "bar" or barrier (argala) against the approach of an invader. Similarly, Arind, the name of the river, is a contraction for Arindama, "the subduer of enemies," which would seem to refer not so much to the depth of the stream as to the inaccessibility of its broken banks.

It is not impossible that the name Argal was subsequently given to the small secluded village in the Korâ pargaṇa, buried in the ravines of the Arind river, where the Gautam Râjâ has for many years had his principal seat. This would account for the insignificance of the remains at the latter place.

Korâ possesses, besides, a fine tank, about 340 feet square, built by Zain-al-Abdîn, the local governor, under the orders of Vazir Mîr Almâs Alî Khân; a bâradarî, on the opposite side of the road to the further end of a garden; it is a large, massive, and handsome building, 100 feet long and 50 feet high. The garden has an imposing entrance gate in two storeys. 43 feet high and 70 feet broad. There is another smaller pavilion on the margin of the tank.

There are four masjids, of which that of Saqî Muhammad Sulţân is the oldest, dating from A.H. 968; the next is the Jâmi Masjid dating from A.H. 1000; whilst the masjid of Nûr Muhammad was built in A.H. 1065, and the masjid of Muhammad Dâyam in A.H. 1143.

The Arind river is crossed by a low, but massive bridge of 12 arches, built about one hundred years ago. The older Moghal bridge is still in existence, immediately under the fort, about half a mile to the west, but is earthed up to above the crown of the arches, and has cultivated fields on both sides of it, the river having completely deserted its former course.

At Sarâî Badle, now a separate village, but once a quarter of the old town, is a large bâolî, built in A.H. 1137, with several temples, but no remains of the sarâî from which it takes its name.

According to tradition, the original name of Korâ was Karrâ, meaning "hard;" and, in fact, Alberûnî gives the name as Kuraha. Probably it was subsequently modified to Korâ in order to prevent confusion with the town of Karrâ on the Ganges in the Allahâbâd district.

- 22. Kôr, village in tahsîl Khakhrêrû, 32 miles S.-E. of Fathpûr, possesses, on the bank of the Jamnâ, the remains of an ancient fort destroyed by Alâ-ad-dîn Ghorî.
- 23. Kuṭilâ, village in tahsîl Khâgâ, 19 miles E. of Faṭhpûr, possesses the ruins of two forts on the bank of the Ganges, one said to have been built by Jayach-chhandra, and the other by an Afghân.
- 24. Kutiya, village in tahsil Kalyanpur, 11 miles N.-W. of Fathpur. It was conjectured by General Cunningham² that this might possibly be the Buddhist site mentioned by Hiuen Tsiang³ under the name of 'O-yu-t'o. The present village was moved about 100 years ago from a high cliff a little to the east, which is still

Hb.

Hb.

III.

III.

¹ Sachau, Alberúni's India, Vol. I, page 200.

¹ Archwological Reports, Vol. XI, page 56.

^{*} Beal, I.c., Vol. I, page 225.

III. called Barâgâon; and here under a nim tree are collected a few fragments of figure sculpture. One piece was subsequently converted to Musalmân uses, for it is engraved at the back with the endings of four lines of a Persian inscription in bold raised characters.

To the west of the village is another high bare cliff, which is called kôt, and, as the name would denote, may very possibly have been a fort. Here large bricks are found, and occasionally coins.

- 25. Malwa, village in tahsil Kalyanpür, 12 miles N.-W. of Fathpür, possesses a somewhat remarkable group of Musalman buildings, a masjid, an imambara, a range of rest-houses, and a karbala. The last-named is a massive square structure, with two round minarets, and consists of a vaulted corridor enclosing a domed centre. At a corner of the village lane may be seen a red sandstone pillar of the old Hindû pattern, said to have been brought from the site of the karbala, and doubtless dating from the 10th century.
- 26. Naubasta, hamlet of Bâigâon, in tahsîl Khâgâ, 28 miles E. of Faṭhpûr, Dossesses several small temples on the bank of the Ganges, at the west of the Khâgâ road, all dating apparently from the end of last century.
- The site of the old village, higher up the stream, is now almost entirely deserted.
 III. It is marked by a series of brick-strewn mounds, on which are collected several groups of stone sculpture, including a miniature temple cut out of a single block, all of early pre-Musalman character. There is also a stone elephant, about four and-a-half feet long, but half-buried in the ground, and so much mutilated as to retain but little of its original shape.
- 27. Râmpûr Thariaon, village in pargaṇa Haswâ of tahsil Fathpûr, 12 miles S.-E. of head-quarters, possesses at the head of a series of ponds, where it forms a picturesque feature, a temple tower in the old style, built four generations ago by Ålam Singh. It contains a small head of Buddha with crisp curling hair and long pendant ear-rings.

There is a railway station a mile distant, at Barhâm pûr, which may be the place quoted by Alberûni¹ under the name of Barhamshil, as a stage on the old road from Kanauj to Prayâga, half-way between Korâ and Aphûi, viz., eight farsakh from each.

28. Ren, village in tahsîl Ghâzîpûr, 18 miles 8.-W. of Faṭhpûr, was a large and important place in former times. It has an area of more than 3,000 bîghas. The hamlet of Kîrttikherâ is now a larger and more thriving place than the original village, which is a mile and-a-half away on the bank of the Jamnâ. Its houses are huddled together under a steep cliff, about 100 feet high, but much cut up by ravines, where once stood the old fort. The river, which runs immediately under it, has here taken a deep bend to the east, and in so doing is said to have submerged a large portion of the town. This would seem to be a fact, for on the other side, in what is now the Bândâ district, there are many traces of former habitations, and one of the main gates of the city is also said to have stood there. If so, the course of the river at that time must have been very far to the west. The village is one mass of debris, and for the greater part of the way to Kîrttikherâ the fields are strewn with bricks and dotted with mounds, where many pieces of stone sculpture have been collected.

Sachan*, Alberân* India*, Vol. I. page 200.

A few are cross-legged Jain figures; but the majority represent Brâhmanical divinities; and there are also many fragments of architectural decoration. They are of different dates, but some are executed with considerable spirit, and are possibly older than any other remains in the district.

A rival Raja is said to have had his fort at Benûn, a village about five miles to the east.

III. At Kirttikherâ are some carved stone panels from the sikhara of a temple at Ren of the 10th century.

IIb.

III.

IIb.

III.

IIb.

IIb.

In the village of Thawâî, on the opposite side of the high road, is a large stone lingam under a modern domed temple, which stands on a high mound approached by flights of masonry steps. Under a tree on the plain below is a smaller lingam inserted in a carved stone panel, which also was probably brought from the old Ren temple.

In December, 1888, a copperplate grant of Govindachandra Dêva of Kanauj, dated Samvat 1188, was found in the debris of a fallen high bank of the Jamna, close to the inhabited site of Ren, not far from the village of Lalauti. The village to which the grant refers is called Dosahali, undoubtedly the modern Dasauli on the Jamna. The original plate is now in the Lucknow Museum.

- Sah, large village in tahsil Ghazipur, seven miles W. of Fathpur, possesses an old fort.
- 30. Shiùrajpùr, village in tahsîl Kalyâṇpûr, on the right bank of the Ganges, possesses for nearly half a mile along the bank of the river a succession of temples and ghâts, none of antiquarian value or special architectural importance, but all in a more or less ruinous condition. The largest of the series has a picturesque group of towers and spires; but the details are all in a most debased style. Adjoining it is a large old three-storeyed house of effective design, but much out of repair, and disfigured by incongruous excrescences. The temples are all of brick and plaster, with one exception, which is of carved red sandstone of superior execution.

IV.-KANHPÜR DISTRICT.1

- Akbarpûr, tahsîl, 26 miles W. of Kânhpûr, was originally known as Gurai Kherâ. Four miles to the south-west of the tahsîlî, in the ravines of Kumbhî on the Saingur river, there is an ancient kherâ or village mound, called Lakrapûr.
- Akbarpür Bîrbal, village in tahsil Ghâtampûr on the left bank of the Jamnâ,
 miles S. of Kânhpûr, possesses an ancient temple, dedicated to Râdhâ Krishna.
- 3. Bazîdpûr, village in tahsîl Kânhpûr, six miles S. of head-quarters, possesses a masjid, built in A.H. 762, and the tomb of Makhdûm Shâh, built in A.H. 761, during the reign of Fîrûz Shâh.
- 4. Bhîtargâon,² or Bâharî-Bhîtarî, village in tahsil Narwal, 20 miles S. of Kâṇhpûr. Bhîtargâon means the "inner town," and the present village is said to have been in the heart of an ancient town, named Phulpûr, or "Flower-town." The village of Bâharîgâon, or "outer town," more than half a mile to the east, is pointed out as one of the ancient suburbs, and the whole of the land of these two villages is known by the general name of Bâharî-Bhîtarî. They stand in the midst of a group of villages, which in the rains are surrounded by the waters of the Arind river.

¹ North-Western Provinces Gazetteer, Vol. VI, pages 197-269.

² Cunningham. Archeological Reports, Vol. XI, page 40.

The large temple at Bhîtargâon, which is still standing on the east of the village. Ib. is called simply Deval or "the temple," and nothing whatever is known of its history. It is a square of 66 feet with the corners indented, and a projecting portico or entrance hall on the east. The walls are eight feet thick; altogether it is 47 feet long and 364 feet broad. It is built throughout of large, well-burnt bricks, 18" × 9" × 3", laid in mud mortar. A flight of six steps leads up to a small ante-room, eight feet by seven feet three inches, from which a passage, eight feet in length, opens into the main room. The two passages are roofed with semi-circular vaults, and the two rooms with pointed domes. These vaults are built after the Hindû fashion with the bricks placed edge to edge, instead of face to face. The outer semi-circular arch. which covered the entrance steps, has fallen down, but some of the bricks still remain to show that its construction was exactly the same as that of the semi-circular arch between the two rooms. Both the arches and the domes rise from imposts; this particular kind of arching seems to be peculiar to India. Above the main dome there is a second square chamber of similar size, which was also covered with a vault of the same construction. The interior of the temple is now only plain earth, the whole of the floor having been dug up. Exteriorly the temple is decorated with numerous figures in terra-cotta. In the lower part the figures are of large size, two feet six inches in height by two feet in breadth. These are placed in niches which are separated by bold ornamental pilasters four feet six inches in height. In the centre of the west face opposite the entrance there is a figure of the Varaha Avatara of Vishnu with the boar's head. On the north side there is a figure of Durgà with four arms, and on the south side a four-armed figure of Ganêsa. Many of the remaining figures appear to be only various forms of Vishnu and Siva and

At a distance of 530 feet nearly due south from the Devâl, there is a mound of ruins covered with large bricks and broken figures. According to the people, these are the remains of a temple called Jhijhi Nâga. In plan the Jhijhi temple was quite different from the Devâl, as there was only a single room $22\frac{1}{2}$ feet long by seven and-a-half feet broad, with walls four and-a-half feet thick, and a door in one of the long sides facing the east. In the back wall there were four niches. From the style and patterns of the moulded bricks, this temple was certainly of the same period.

their wives, as one of them has eight arms. Judging from the position of the Varâha incarnation at the back of the building, it seems highly probable that the temple must have been dedicated to Vishņu. The Bhîtargâon Devâl is one of the few specimens of ancient brick temples now standing in Northern India, and this style of building would appear to have prevailed very extensively for several centuries. The date of this building is not absolutely known, but judging from its style it cannot be placed later than the sixth or seventh century, and is probably even

The people of Bhitargaon say that there was once a brick temple at every kôs along the bank of the Arind river. There certainly is one at Parâuli, one at Simbhuâ, two at Râr, one at Bedâ-Bedaunâ, two at Khurdâ, one at Kanchlîpûr, and two at Sarhâr-Amaulî; but there are only four of them on the Arind, those at Râr, Bedâ-Bedaunâ, Kanchlîpûr, and Sarhâr-Amaulî being far away from the river.

II.

older.

The pretty little temple of Parâulî is unfortunately imperfect, about one-half Ib. of it having fallen down. But the standing half is in very good preservation, and is remarkable for the uniform and bright colour of its bricks. In plan, it is a polygon of 16 sides externally standing on a circular plinth, with a circular chamber six feet eight inches in diameter, and no portico. The walls are three feet four inches thick; the temple is therefore only 13 feet 4 inches in diameter, each of the 16 sides being two feet five inches. The chamber was covered with a pointed dome, built with bricks end to end after the Hindû fashion, and there was a second domed chamber above to lessen the weight on the walls. The door was on the west side, and on each of the other three sides there was a small niche only 111 inches high and 61 inches broad. Inside in the centre of the circle there is a lingam. Outside the whole surface of the walls is richly decorated with deeply cut arabesque ornament in perpendicular lines, the edges of each face being distinctly marked by sunken lines by the omission of brick in every alternate course. The effect is decidedly good, as the different faces are clearly defined.

III. The Simbhuâ temple is unfortunately thickly covered with plaster. On many places, however, where the plaster has fallen off, the same flowered ornament is visible as that of the other brick temples. The inner chamber is of carved stone and only eight feet three inches square.

Ib. Of the two small temples at Râr, one is built on the same plan as the Bhitar-gâon Devâl, and the other on the plan of the Jhijhi Nâga temple. The former has no name, and its exterior dimensions are only 10 feet three inches by nine feet six inches, with a portico projecting three feet on the north side. The chamber is only four and-a-half feet by four feet. The larger temple is dedicated to Chaṇḍikâ Dêvî. Its entrance is on the west through a passage eight feet long by two and-a-half feet wide, which leads into a chamber 10½ feet long by six feet broad, with the longer side facing the door. Externally it is 18½ feet long by 12½ feet broad, or with the portico 17 feet. Outside, this temple is decorated in the same style as that of Parâulî, the same flowered ornament being repeated from top to bottom. Here also nothing is known about the builders of the temples.

Ib.

IIa.

The brick temple at Bedâ-Bedaunâ is exteriorly covered with whitewash, but occasionally carved bricks and square beaded panels with hood mouldings are visible. In plan it is a square of 47 feet, with the corners indented, and two vaulted ante-chambers. The vaults rise from imposts, and are built with the bricks placed edge to edge. The cella is 20 feet long and 14 feet broad, and supported on eight tall and graceful columns, richly ornamented; the architraves and ceiling being decorated with leaf ornaments and alto-relievos. The most characteristic feature of this temple is the employment of the semi-circular arch between the two ante-chambers. Judging from its style, the temple cannot be placed later than the seventh or eighth century, and it is probably even older.

One-half of the temple at Khurdâ has fallen down; but the standing half is in very good preservation. In plan it is a square of 36 feet externally, with a chamber of 18 feet long and 12 feet broad, covered with a pointed dome. The lower part of the temple consists of plain bold mouldings, above which there is a series of panels, filled with groups in terra-cotta, and divided from each other by pilasters, supporting

16.

10.

IIb.

a richly carved cornice which runs continuously all round the building. Close to this temple are the ruins of another ancient brick structure, in plan a polygon of 16 sides with a circular chamber of 10 feet diameter,

Ib. The brick temple at Kanchlipür is built on the same plan as the Bâhari-Bhîtarî temple. Its entrance is on the west, through a passage six feet long by two feet wide, which leads into a chamber 12 feet long by six feet broad, with the longer side facing the door. Externally it is 18 feet long by 12 feet broad. Outside, the temple is decorated with moulded bricks of the leaf and flower pattern.

The village of Sarhar-Amauli possesses two brick temples, built on the same plan and in the same style of ornament and sculpture like those at Rar.

IIb. 5. BILHAUR, tahsîl, 34 miles N.-W. of Kânhpûr, possesses a masjid, built by Muhammad Razâ in A.H. 1110, during the time of Aurangzîb.

At the village of Subhanpûr there is a long Sanskrit inscription in the well of Gayadin Sakal.

The village of Pihani possesses the Masjid Gomți, built during the reign of Aurangzib, as stated in the Persian inscription.

- 6. Bithür, town in tahsil Kāṇhpūr, 12 miles N.-W. of head-quarters, possesses IIb. five large temples on the banks of the Ganges, and on a mound to the south of IIb. the town stands an old temple, dedicated to Kakapakshūśvara, or Rāma. Numbers of ancient metal arrow-points are found in the soil around Bithūr, said to be relics of the time of Rāmachandra. According to tradition, Brahmā is said to have celebrated his completion of creation by a horse-sacrifice at the Brahmāvartta-ghāţ of Bithūr. A nail of his shoe is still embedded in one of the steps of the landing-place, and is still the object of devout homage. The clusters of ghāṭs, temples, and dwelling-houses on the Ganges lend an imposing and picturesque appearance to that side of the town. There is also a spot on the bank of the Ganges, called Vālmīki-kī-kuṭī, where Vālmīki's hermitage is said to have been.
- IIb. 7. Kânhpûr, head-quarters of the district, lat. 26°-28′-15″ N., long. 80°-23′-45″ E., possesses 1,143 Hindû temples and 357 masjids; but few are of any architectural pretensions, and none of any antiquity.
 - CHARALÎ, village in tahsîl Narwal, 18 miles S. of Kânhpûr, possesses an old temple dedicated to Jvâlamukhî Dêvî, in which there is a Sanskrit inscription.
- 9. Derapür, tahsil, 35 miles W. of Kanhpür, contains the remains of several old masjids, a fine masonry tank called Sahaskund, and the ruins of a fort built in the time of the Maratha rule (1756—1762). It was once a place of considerable importance.

At the village of Bichhiâpûr, eight miles S.-W. of tahsîlî, there is an old tank near the tomb of Sandal Shâh, in which there is an inscribed Sanskrit slab.

- Пь. 10. Ghàтамрûв, tahsîl, 26 miles S.-W. of Kânhpûr, possesses an old temple dedicated to Kudhâ Dêvî, and to the south of the town a Gosâin temple built 300 years ago.
- 11. Jājmāt, village in tahsîl Kânhpûr, four miles E. of head-quarters, was anciently styled Siddhapuri, and still shows on the banks of the Ganges a ghât.

 IIb. and several temples dedicated to Siddhêsvara and Siddha Dêvî. It is also supposed to be the site of the capital of Yayâti, and to have derived its name from him.

 III. The high mound overhanging the river is known as the fort of the mythical Chandella

- IIb. Râjâ Chandravarman. The place is mentioned by Alberûnî¹ under the name of Jajjamau and as being 12 farsakh from Kanauj. To the south of the fort, in the IIb. village of Bâzîdpûr, rises the tomb of Makhdûm Shâh, built during the reign of Fîrûz Shâh in A.H. 761; and on the castle mound itself stands a masjid reared in the 17th century by Sultân Masîh-ad-din.
- 12. Kākūpūr, village in tahsīl Shiūrājpūr, 22 miles N.-W. of Kāṇhpūr. The existing remains of Kākūpūr consist of numerous foundations formed of large bricks, and more particularly of a connected set of walls of some large building, which the people call "the palace." General Cunningham² identifies Kākūpūr with the capital of 'O-yu-t'o (Ayodhyā), visited by Hiuen Tsiang³ in the seventh century. He, moreover, suspects it to be the same as the Bāgud or Vāgud of the Tibetan Buddhist books. According to Hiuen Tsiang there were at the capital of Ayodhyā about 100 Buddhist monasteries, 10 Hindū temples, and several stūpas containing relics of Buddha's hair and nails.
- 13. Khwāja Phūl, village in tahsîl Derâpûr, 48 miles W. of Kânhpûr, possesses III. the remains of a strong fort said to have been built in the reign of Shâh Jahân IIb. (1628—1658) by one Itimâd Khân. Close to the fort is the mausoleum of Itimâd Khân, a building of no architectural pretensions.
- 14. Makanpur, 4 village in tahsil Bilhaur, 48 miles N.-W. of Kanhpur. The holy shrine of Shah Madar has made the village of Makanpur famous throughout Пъ. India. The shrine is situated on the bank of the Isan river, 10 miles to the southwest of Kanauj and about two and-a-half miles north-east of the railway station of Araul. Half-way between Araul and Makanpûr there is an old Hindû village named Harapura, which possesses so many fragments of sculpture that it seems reasonable to suspect that Makanpûr itself may be an old site which was appropriated by the saint after the usual Musalman fashion. The saint was a native of Halab, or Aleppo, and came to Makanpur in A.H. 818, or A.D. 1415, during the reign of Ibrahîm Shah Sharqî of Jaunpûr. The tomb of the saint is a plain building, 314 feet square, with a low-roofed dome, the whole covered with numerous coats of white-wash. It stands in a court-yard about 70 feet square, called haram, or "the forbidden," within which no woman is allowed to enter, no lamps are lighted, no hymns are chanted, and no food is cooked. Altogether there are seven distinct courts, called the seven darbars, each of which has a separate name. These are: (1) Roza Mubaraq, the court-yard about 90 feet square, which surrounds the tomb itself; (2) Haram Darbar, an outer enclosure into which no woman is allowed to enter; (3) Sankar Darbar, or "Chain Darbar," is so named from a chain on its door; (4) Pâkar Darbâr, so named after a Pâkar (fig-tree) which stands in it; (5) Damalkhana is the court where the malangs, or mad faqirs, are allowed to play and sing songs; (6) Nakârkhâna contains the nakâras, or great metal drums, as well as the degs, or gigantic metal cooking-pots; (7) the Alamgir Masjid. The erection of the tomb is ascribed to Ibrâhîm Shâh Sharqi of Jaunpûr, who died in A.H. 844. There is no inscription on the tomb. There are two gateways with inscriptions, but

¹ Sachau, Alberdai's India, Vol. I. page 200.

¹ Archaelogical Reports, Vol. L. page 295.

³ Beal, Lc., Vol. I, page 225.

^{*} Cunningham, Archaelogical Reports, Vol. XVII, page 102.

IIa.

they are of later date. One of these, called the Chor-ka-darwaza, dates from the year A.H. 873 or A.D. 1468, as noted in the inscription. The second gate, called the Saudagar darwaza, or the "merchant's gate," bears the date A.H. 899. The people speak with pride of a visit paid to the shrine of Madar by the Emperor Aurangzib. The exact date is not known, although he built the masjid which still exists. Besides this there is another masjid built by Daulat Khan in A.H. 1022.

- Hb. 15. Mâwar, small village in tahsîl Bhognîpûr, 21 miles S.-W. of Kânhpûr, is remarkable for the tomb of Hazrat Mutahar, one of the four principal disciples of Madar Shah. The masjid is of no architectural pretensions and of no antiquarian merit.
- 16. Mûsanagar, town in tahsil Bhognipûr, on the left bank of the Jamna, 34 miles S.-W. of Kanhpur, possesses, near the Umargarh, the remains of an ancient III. Ia. fort built by the Ponwars in Samvat 1504. The Dêojâni tank is of some antiquarian and architectural interest. The ancient Mukhadêvî temple closely resem-16. bles, except that it is on a much smaller scale, the pre-Musalman portion of the A taladêvî Masjid at Jaunpûr, which are the remains of a Buddhist vihâra. Images and distinctive emblems of very old date have been dug up in the vicinity of this temple.
- 17. RASCLABAD, tahsíl, 40 miles N.-W. of Kanhpûr, possesses a fort built under Ia. Maratha rule (1756-1762), in which now the tahsili offices are located,
 - 18. Shiùrâjpûr, tahsîl, 21 miles N.-W. of Kânhpûr, possesses the ruins of a fort of the Chandella period.
- 19. Sikandra, town in tahsil Derâpûr, 45 miles W. of Kânhpûr, possesses numer-III. ous ruins which testify its former importance.

V.—Hamîrpûr District.1

- 1. Akona, village in tahsîl Kulpahar, eight miles S. of tahsîlî and 68 miles S.-W. of Hamirpur, possesses four groups of ruined Chandella temples, called Ha. Raj Math, Rani Math, Chamar Math, and Konchbhaor. Raj Math is a large group of temples and colonnades, the principal temple of which has fallen, whilst three smaller ones on the corners of the principal temple are still standing. Near the temple there is a life-size statue of an elephant, of which the trunk is gone. The Rani Math is in ruins. To the east of the village is the Châmar Math; it is a low-roofed hall without any dome or sanctum. Konchbhaor is a small masonry tank, on the bank of which there is a lingam temple in fair state Πa . of preservation. Many interesting sculptures are scattered about the place.
- The neighbouring village of Akonî has also a small Chandella temple. 2. DINAÎ,2 village in tahsîl Kulpahâr, seven miles W. of tahsîlî, and 63 miles Ib. S.-W. of Hamîrpûr, possesses on a hillock the ruins of a large lingam temple of the Chandella period, built in the usual form of a cross. The pillars are mostly plain, but the central ones are ornamented with four female statues each, and a few of the pillars are richly ornamented with other carvings. The peculiarity of the temple is that the roof does not appear to have been built in the usual style of intersecting squares or of overlapping stones, but by long stones laid across on the architraves, and

¹ North-Western Provinces Gazetteer, Vol. I, pages 361-601, sub voce.

² Conningham, Archaelogical Reports, Vol. VII, page 40.

entirely without ornaments of any kind. There are no traces of anything like a pyramidal roof over them, from which it is evident that this temple was flat-roofed. The basement mouldings of this temple are singularly beautiful, more so than those of the Mahobâ temples.

Ib. Close to the road below the hill there is a Jain temple with a colossal statue of Santinatha, inscribed Samvat 1194. This temple is an oblong externally, divided into a portice and sanctum. The statue of Santinatha is mutilated, having had the arms cut off, and the minor statues on either side of it are also mutilated. Inside the roof is formed of interesting squares supported by four engaged pillars at the corners of the cell. These pillars have the usual square block interposed, breaking up the height of the shaft into two portions. The outer pillars of the portice, however, are without the blocks. The roof is externally a flat cone, with a very slight bulge, exactly like the domes over the corners and central pillars in the Qutb cloisters. Close to the temple are the remains of cloisters; these consist of rows of pillars of small height supporting a flat roof formed by placing slabs over the architraves. Near this there is an inscribed slab, dated Sanvat 1676.

3. Garhauli, village in tabsil Jalalpur, 35 miles S.-W. of Hamirpur, has a large Chandella tank outside the village, but now nearly silted up, with the ruins of several large temples on its banks, which show that once it must have been of some importance.

4. GAURAHRÎ, village in tahsîl Kulpahâr, 50 miles S.-W. of Hamîrpûr, possesses a very fine temple of comparatively modern date.

Hamîrpûr, head-quarters of the district, lat. 25°-57'-30" N., long, 30°-11'-50"
 E., possesses the ruins of a fort built by Hammîra Dêva in the 11th century, and a few Musalmân tombs which are the only traces of antiquity.

Two miles to the west of Hamîrpûr lies the village of Badanpûr, which has a lill. kherâ showing the site of a deserted village. In the village itself there is under a nîm tree an image, inscribed Sanivat 1363.

About 11 miles to the south of Hamîrpûr there are the two small villages of Itârâ and Pachkhaurâ, standing on ancient kherâs, covered with broken bricks and sculptures. Old coins are said to be found in large quantities after the rains.

6. Ingothâ, village in tahsîl Hamîrpûr, 15 miles S. of head-quarters, possesses the ruins of a small fort close to the village site.

7. Jarreur, town in tahsil Kulpahar, 65 miles S.-W. of Hamirpur, possesses several modern temples, some still unfinished, and the remains of a fort which tradition ascribes to the Maratha period. Scattered about in the town are numberless dressed granite stones with carvings similar in design and execution to the carvings at Mahoba; they are undoubtedly ancient, most probably of the Chandella period. Innumerable similar stones are also built into the walls of the fort and of the buildings within it, rendering it impossible to doubt that there in former times must have existed many ancient structures of the same style and period as those at Mahoba.

Within a short distance of the town is the Bêlâ Tâl, or Sâgar Tâl, ascribed to the Chandellas. On the western edge of this large tank there runs a chain of several low hills, rocky and steep on the land side, but less so on the tank side. Along

III.

116.

III.

¹ Cunningham, Archeological Reports, Vol. VII, page 28.

- III. the crest of the northernmost of these is built a strong loopholed wall in the usual style of Indian rubble and mortar forts. This wall runs down at the northern end along a spur of the hill that juts into the tank; the spur, after jutting out of the hill into the tank, in a direction perpendicular to the line of the chain, for a distance of about 500 feet, turns back southwards, and runs in this new direction parallel to the main chain for about 800 feet, thus including on three sides a small sheet of water that forms, as it were, an arm from the tank. Along this ridge the fort walls run down to the lake, the end being formed into a massive tower rising sheer out of the water, but now in ruins. At the corners of the wall are other strong towers rising boldly out of the water. The spur that connects the main chain of hills with the small ridge in the tank running parallel to it, appears to be artificial. At the south end the walls run down the declivity of the first hill of the chain to the water ending in a ghât; this is the weakest point of the fort, and subsequently, judging from the style of construction, an extension was made on this side by the addition of a sort of outwork connected with the main fort at its south end and carried along the ridge of the next hill up to its summit. Hence it goes perpendicularly down towards the tank in a slight curve, forming at its southern end a figure like the nook at the northern end, but far smaller and far less decided. A massive tower rising sheer out of the water terminates it at this end as at the other. In the fort there are palaces and other buildings situated in the space between the walls and the edge of the tank. The buildings must have been very extensive, and subterranean passages from the mahal to the edge of and into the tank exist in several places to this day. From the style of buildings inside it is impossible to ascribe to this fort an age much prior to the Marâtha period; but it is certainly earlier than the usual run of Marâtha structures. It appears that the outwork noticed above was afterwards added, and, if one may judge by the Musalman tombs that occur in this portion alone of the fort. by the Musalmans, after they had probably proved the weakness of the south end of the main fort by capturing it themselves.
- 8. Jalâlpûr, town in tahsîl Maskarâ, 30 miles west of Hamîrpûr, possesses IIb. several masjids and Hindû temples of no archæological value. Outside the town there is a kherû, named K hândant.

In the village of Punian there are on the banks of the tank of Alha and Udal Ib. two images of black basalt, inscribed Samvat 1232, during the reign of Parmal.

- 9. JHALOKHAR, town in tahsîl Hamîrpûr, eight miles W. of head-quarters, IIb. possesses a temple dedicated to Dêvîjî Bhanyâ Râņî.
 - 10. Kabráfa, town in tahsíl Mahobá, 43 miles S. of Hamírpûr. The Brahm Tâl, a stone called Chakarî ya Dâî, several Chandella temples, the Dûdhû rock, and the Bhawânî-kâ-Pahâr are the only objects of archæological interest.

The Brahm Tâl is an extensive tank now much silted up; the embankment is in the form of a segment, and is faced in the usual Chandella style with immense stones which form steps to the water's edge. On this embankment are the ruins of III. a large Chandella temple. In the middle of the lake was a baithak; but that, too, has been completely thrown down, and only the basement is now visible. There is said to be an inscribed slab lying near the ruins of this baithak; there are also some sati monuments, apparently of no great date.

III. The Chakariya Dâi is a carving of a woman with a child in her arms; close by IIb. there is a small Chandella temple, hidden, however, by recent renovations. Not far IIb. from this temple there is another temple on the top of a rock, and votaries have to make their exit by a passage under the rock whence there is a fine view of the Brahm Tâl. There are numbers of Chandella stones lying about the village, some used for chabûtras, &c.

IIb.

IIb.

IIb.

IIb.

III.

III.

III.

III.

III.

III.

Ib.

IIb.

a fort.

The Dûdhû rock is near the lake, and on the top of it the ghost of a telî is said to reside. A little further on is the Bhavânî-kâ-Pahâr, on which there are some small temples dedicated to the goddess Bhavânî; but none of these are very old or in any way remarkable.

 Kharaila, town in tahsîl Maskarâ, 40 miles S.-W. of Hamîrpûr, possesses an old temple.

12. Kulpanâr, tahsîl, 60 miles S.-W. of Hamîrpûr, possesses several modern temples, îdgâhs, and masjids, and the ruins of a palace on a hill. The banks of the large tank south of the town are ornamented with numerous temples and houses; a stone ghât runs along the embankment with platforms and shrines at intervals. Close to the tank, on the opposite side, stands an isolated octagonal structure on a small mound, the tomb of some Musalmân; it must have once been very beautiful and is still picturesque, though ruined. No ancient remains, however, exist except an occasional fragment of a statue. On an eminence near the town are the ruins of

About four miles south-east of Kulpahâr lies the village of Râwâtpûr, with a large Chandella tank, on the embankment of which stands a large ruined granite temple of the earliest Chandella type. The sanctum has fallen, whilst the great hall is in a tottering condition. About 300 yards distant from the tank is another temple of a smaller scale, of which the dome has fallen.

Six miles to the west of Kulpahar are the villages of Charna and Patkari. The former has the ruins of two granite temples, the latter a large tank.

About five miles to the north-east of Kulpahâr is the village of Mohâri, with two ruined granite temples.

About six miles south-east of Kulpahar lies the village of Sahâţ Mahâţ, which possesses some large tanks, a fine old temple sacred to Vishņu, and a low-roofed Jain temple with *inscribed* statues of Samvat 1200 and 1213.

Close by is a large kherâ covered with broken bricks and sculptures, where Madanavarman, the Chandella ruler (A.D. 1129—1165) is said to have founded a town, called after him Madanapura.

Six miles south-east of Kulpahâr is the village of Karerâ, with a diminutive Ib. plain Chandella temple.

About 15 miles S.-W. of Kulpahâr are the villages of Telî Pahârî and IIb. Tewâh, possessing three small Chandella temples.

About 13 miles S.-W. of Kulpahâr is the village of Parãobâri, which has an old well with an inscription, dated Ashâdava di 5, Samvat 755.

Makārbāi, small village in tahsil Mahobā, 10 miles N.-E. of tahsili and
 48 miles S. of Hamîrpûr, possesses many remains; one, a large pillared hall, probably

¹ Cunningham, Archaeological Reports, Vol. VII, page 26.

Ib.

III.

III.

Ib.

Hb.

IIb.

Ib.

a Jain temple, now below the level of the adjacent country from accumulation of rubbish, is called Parmâl's baithak; fragments of innumerable statues and sculptures, but of no particular interest, abound in the place. It also possesses a large tank ascribed to the Chandella kings, and there is a small, but very beautiful, temple of a unique type, possessing three instead of one sanctum. An accumulation of fully six feet of rubbish hides the mouldings of the basement of this singular temple,

One mile to the north of Makârbâi there are the ruins of a large granite temple, more than double the size than that of Makârbâi.

About four miles E. of Makarbai lies the village of Barsi Talao, with an almost dry tank, on the embankment of which is a middle-sized temple of which the dome has fallen. Behind it there is a large low-roofed hall in a ruinous condition.

About six miles E. of Makarbai, near the village of Pahra, lies the hamlet of Sakara, which possesses a flat-roofed Jain temple in a nearly perfect state of preservation and a small Brahmanical temple of the Chandella period.

14. Манова, tahsil, lat. 25°-17′-40″ N., long. 79°-54′-40″ E., 54 miles S. of Hamîrpûr. Its name is a contraction of Mahôtsavanagara, or the "city of the great festival," which was celebrated there by Chandravarman, the founder of the Chandella dynasty. Mahobâ is divided into three distinct portions: (1) Mahobâ, or the city proper, to the north of a low granite hill; (2) Bhìtarì Qila, or the inner fort, on the top of the hill; and (3) Darìbâ, or the city to the south of the hill.

To the west of the city lies the great lake of Kirat Sâgar, about one and-a-half miles in circumference, constructed by Kîrttivarman (1063—1097). To the south is the Madan Sâgar, about three miles in circuit, constructed by Madanavarman (1129—1165). To the east is the small lake of Kalyân Sâgar, and beyond it lies the large deep lake of Vijaya Sâgar, constructed by Vijayapâla Dêva (1040—1050). The last is the largest of the Mahobâ lakes, being not less than four miles in circuit; but the most picturesque of all is the Madan Sâgar. On the west it is bounded by the singularly rugged granite hill of Gôkarna, on the north by ranges of ghâts and temples at the foot of the old fort, and on the south-east by three rocky promontories that jut boldly out into the middle of the lake. Near the north side there is a rocky island, now covered with ruined buildings, and towards the north-west corner there are two old granite temples of the Chandella princes, one altogether ruined, but the older still standing lofty and erect in the midst of the waters.

As Mahobâ was for some time the head-quarters of the early Musalmân governors, we could hardly expect to find that any Hindû buildings had escaped their furious
bigotry or their equally destructive cupidity. When the destruction of a Hindû
temple furnished the destroyer with the ready means of building a house for himself
on earth as well as in heaven, it is wonderful that so many temples should still be
standing in different parts of the country. It must be admitted, however, that in none
of the cities which the early Musalmâns occupied permanently have they left a
single temple standing, save this solitary temple at Mahobâ, which doubtless owed
its preservation solely to its secure position amid the deep waters of the Madan

¹ Cunningham, Archaeological Reports, Vol. II, pages 439—459; Vol. VII, pages 24—25; Vol. XXI, pages 70—74.

Sågar. In Mahobå all the other temples were utterly destroyed, and the only Hindû building now standing is part of the palace of Parmål, or Paramårdi-IIb. dåva, on the top of the hill fort which has been converted into a masjid. In 1843 General Cunningham found there an inscription of Paramårdidåva, built upside down in the wall of the fort just outside this masjid. It is dated in Samvat 1240, or A.D. 1183, only one year before the capture of Mahobå by Prithvîrâjâ, IIb. Chauhân of Dehlî. In the dargâh of Pîr Mubâraq Shâh and the adjacent burial-ground there are about 310 Hindû pillars of granite. A black stone bull is lying beside the road, and the argha of a lingam is fixed as a water spout in the terrace of the dargâh. These last must have belonged to a temple of Siva which was

lying beside the road, and the argha of a lingam is fixed as a water spout in the terrace of the dargâh. These last must have belonged to a temple of Siva which was probably built in the reign of Kîrttivarman, as a mutilated inscription of that prince was found, in 1865, built into the wall of one of the tombs. These are the earliest remains discovered at Mahobâ itself; but there seems no good reason to doubt the popular tradition of its foundation by the first Chandella Râjâ, Chandra-varman, as the story is at least as old as the time of the bard Chand, and is most probably much older.

Ib. The Kâkrâ Math stands on a rocky island in the north-west corner of the Madan Sâgar. In size it is equal to the largest of the Khajurâho temples, being 103 feet in length by 42 feet in breadth. It is built entirely of granite, and is therefore very much inferior to the Khajurâho temples in decoration; its architectural ornaments being limited to such small geometrical patterns as could be executed without much difficulty in hard granite. The general arrangement of five chambers is similar to that of most Hindû temples of the same period; but the size of the mahûmandapa, or transept, is greater than that of any of the Khajurâho temples. On each of the outer faces of the sanctum there are three niches for the reception of statues; but neither outside nor inside can be found even the fragment of a figure. The name Kâkrâ is said to refer to the worship of Siva.

On another rocky island, a few hundred feet to the north of Kakra Math, there is a large ruined temple now called Madari, which is a name of Krishna, one of III. the avataras of Vishnu. Only the foundations of the building are now standing, which show that this temple was even larger than the other, being 107 feet in length by 75 feet in width. Opposite the east end or entrance there are the foundations of another small temple, 16 feet square, which, judging from other examples, must once Ш. have enshrined a statue of the Varaha Avatara, or boar incarnation of Vishnu. But the most interesting remains of the ruined temple are five life-size elephant statues in sandstone. There is nothing left to show the original positions of these statues; but if we may be guided by the arrangement of the half-size elephant statues at Khajuraho, then these five enormous figures must have been projected in mid-air from the five disengaged faces of the two spires of the sanctum and transept. It is quite possible, however, that they may have been erected in pairs at each of the three entrances to the temple, that is, at the east or main entrance and at the two side entrances to the north and south.

On the north-east bank of Madan Sagar stands a colossal statue of Kali, hewn out of a solid granite rock, surrounded by several sati pillars of the Chandella period.

IIb. Dîpdân is the name of a single granite pillar standing on the north bank of the IIb. lake in front of the temple of Mânyadêvî. Its name is derived from the practice of placing a lamp or dîp on its summit on stated occasions. But this certainly could not have been the original purpose of the pillar, as it is crowned with a broad flattopped capital, and does not possess a single receptacle for a lamp. It is a single shaft 18 feet high and one and three-quarter feet square at the base. In the middle it is octagonal and in the upper part round. The two lower portions are quite plain, but the uppermost is ornamented with four chains and bells suspended from four lions' heads immediately beneath the capital. This column was most probably connected with the temple of Mânyadêvî, in front of which it now stands; but there is nothing to show its age, and the present temple is a common plaster building in the modern Musalmân style.

The old fort at Mahoba is situated on a low granite hill immediately to the north III. of the Madan Sagar. On the north side the walls crown the crest of the hill and on the east and west side they run down to the lake which forms the south boundary of the enclosure. It is 1,625 feet in length from the Bhainsâ Darwâza on the west to the Dariba Darwaza on the east; but is not more than 600 feet broad in the widest part. The wall is built exclusively of fragments of older structures, some plain, some carved, and some simply rubble. It is a place of no strength, and there is no record of its ever having been defended. The palace of Raja Paramardidêva, Ib. or Parmal, is situated on the top of the hill fort. The portion now standing is an open pillared hall, 80 by 25 feet, which was formerly converted into a masjid by the addition of a back wall to the west, in which basement mouldings and other carved stones are built up one over the other. The Musalman pulpit with its staircase is still standing against this west wall, in the middle of which there is a small arched recess that is common to all masjids. The pillars are massive blocks of granite upwards of two feet square and 12 feet in height, and are richly decorated with deep mouldings and bold geometrical figures. There are eight rows of pillars in the length and three in the breadth of the building, making seven openings for the front of the masjid.

In the south-east quarter of the city, called Darîbâ, there is a small stone pillar called Ålhâ-kâ-lâṭ, or Ålhâ-kâ-gili, or "Âlhâ's staff," or "Âlhâ's plaything." The stone lâṭ is nine and-a-half feet in height and 13 inches in diameter, and is placed loosely in a square hole cut in a large mass of granite. On another granite rock close to Âlhâ's gili there is a sunken tablet about two feet square containing the figure of a horseman called Chanda Matwâra.

In the west part of the town, just outside the Bhainsâ Darwâza of the fort there is a flat-roofed masjid on Hindû pillars which, according to an inscription over its doorway, was either erected or converted by Malik Tâj-ad-din Ahmad in the reign of Tughlaq Shâh, in A.H. 722, or A.D 1322. Most probably it is part of the original temple slightly altered, as its floor is considerably below the present level of the ground.

On the banks of the Kîrat Sâgar is a steep bare hill covered by ruins; these ruins must once have been temples, now a Musalmân grave of Mîra Tûlan occupies the site.

¹ Proceedings, Asiatic Society of Bengal, for 1873, pages 156 and 157.

Round Mahobâ at short distances are to be seen occasionally ruins and frag-III. ments of sculpture, some of the colonnades still standing, some mere mounds; they are all traditionally known as Parmâl's baithaks, or Âlhâ's baithaks.

It will be observed that all the existing ruins of Mahobâ are exclusively Bråhmanical. But the numerous broken Jain statues which lie about the city, including inscribed pedestals of Samvat 1169, 1203, 1211, 1213, 1219, 1220, and 1224, show that the sråvakas of former days must have possessed several rich temples, of which even the sites are now unknown. On the south-east bank of the Madan Sågar, on a hillock, there are 24 rock-hewn images of the Tirthankaras with several inscriptions, dated Samvat 1206.

The discovery also of a single pedestal *inscribed* with the Buddhist creed formula in characters of the 11th century is sufficient to prove that the Buddhist religion was still existing in Mahobâ at that late period.

About six miles S.-W. of Mahobâ lies the village of Sijhârî, which possesses Ib. a large tank on the embankment of which there is a low-roofed square temple which had about 12 conical domes of which seven now remain.

Ten miles south-west of Mahobâ is the village of Urwâra, possessing a large Ib. tank called Ratan Sâgar. Near the embankment stands a flat-roofed temple of the usual Chandella style.

About three miles S.-W. of Mahobâ lies the village of Râhilyâ, with a small tank, on the embankment of which stands a ruined large Chandella temple built in the form of a cross. The dome of the central hall has fallen, but the walls and cross lintels are still standing. The tank and temple were probably constructed by Râhilavarman (A.D. 875—900).

III. 15. Маириа, tahsil, 20 miles S. of Hamîrpûr, possesses the ruins of a stone fort, three masjids, three dargâhs, and five tanks, all of no great antiquity and of no architectural merit. Under a pipal tree on the Bândâ road, outside the village, there is a broken image of Pârsvanâtha, inscribed Samvat 1229.

16. Maskarā, or Maskharā, tahsil, 33 miles S.-W. of Hamîrpûr, is said to be a corruption of Mahêsa Kherā, or the mound of Mahêsa, whose temple is still extant.

17. Panwârî, town in tahsîl Kulpahâr, 64 miles S.-W. of Hamîrpûr, possesses IIb. the dargâhs of Bhâi Khân and Pîr Haqîm erected in the beginning of the 18th century.

In the village of Nanyaurâ, 20 miles S.-E. of Panwârî, were found, in 1872, two copper-plate grants¹ of the Chandella rulers, viz., one of Dhangadêva, dated Samvat 1055, and another of Dêvavarman Dêva, dated Samvat 1107.

18. Râțh, 2 tahsîl, lat. 25°-35′-35″ N., long. 79°-36′-55″ E., 50 miles S.-W. of Ib. Hamîrpûr, contains two ancient-looking bârakhambhâs, or twelve-pillared halls, both roofless, which the Musalmâns claim as theirs, while the Hindûs as stoutly maintain them to be Hindû. Of the pillars the bases, capitals, and shafts correspond and are apparently in their proper positions; but close examination shows that the capitals are not all of the same size. The remains of the brick dome which once crowned each of these show indisputable signs of having been built after the Musalmân con-

Ib.

¹ Indian Antiquary, Vol. XVI, pages 201-205; Jaurnal, Asiatic Society of Bengal, Vol. XLVII, Part I, pages 81-84.

Hb.

III.

Ш.

quest, and the existence of two carved stones, the lower sills of the entrances of Hindû temples, among the stones forming the present basement, proves that they are built out of older Hindû temples of the Chandella time. Râțh possesses a fine large lake, called Sâgar Tâl, besides several smaller ones, adorned with extensive ghâțs, the ruins of two forts, several modern Hindû temples, and a masjid and a well built in Aurangzîb's time.

About eight miles N.-W. of Rath lies the village of Kachhwa, with some III. mounds covered with broken statues and sculptures. Old coins and Buddhist beads are found after the rains.

About six miles S.-E. of Râth is the village of Rorâ, possessing a small mound with a small ruined temple on the summit. The temple is a square cell surmounted by a dome on low neck; the cell has stone pillars at the corners and at the centres of three sides, and the door-posts are also of stone. The dome rests on architraves, some carved in the peculiar Chandella style, and others plain. As it stands, the structure cannot be very old; but it is built of the materials of a more ancient one, and the statues inside are probably old.

- 19. Sayar, village in tahsîl Maudhâ, 18 miles S. of Hamîrpûr, possesses a mud fort outside the village site.
- 20. Śrónagar, village in tahsil Mahobâ, 65 miles S. of Hamirpūr, possesses the remains of a stone fort on the hill overlooking a part of the village, two fine tanks, one of which, called Barâ Tâl, has an island, in the middle of which are the ruins of a large Chandella temple.
- 21. Sumerfür, town in tahsîl Hamîrpûr, nine miles S. of head-quarters, possesses the ruins of two forts outside the village, several mounds covered with broken bricks, tiles, and sculptures, and three kherûs in the immediate neighbourhood, viz., Lakhanpûr, Mîrzâpûr, and Iţârâ. Glass bangles and earthenware remains are found in all these kherûs, and occasionally coins.
- 22. Sungrå, village in tahsîl Kulpahâr, 60 miles S.-W. of Hamîrpûr, possesses III. a fort with a large masonry well.
- 23. Sûpâ, village în tahsîl Kulpahâr, 55 miles S.-W. of Hamîrpûr, possesses III. the remains of a fort built in the beginning of last century.

VI.—JAUNPÜR DISTRICT.1

- 1. Jalalpür, or Jalalpür Sai and Jalalpür Bialsi, small village in Ib. tahsil Kararköt, possesses an old bridge over the Sai, built in 1510 A.D. by Jalal Khan, governor of Jaunpür, who wished to transfer to this place the capital of his government. This bridge is 58 years older than the famous bridge of Akbar over the Gümti at Jaunpür. It is built on nine pointed arches, and has a roadway of 245 feet.
 - Jaunpür,² head-quarters of the district, lat. 25°-44′-53″ N., long. 82°-43′-49″ E.
 For nearly a century (A.D. 1394—1493) the city of Jaunpür was the capital of an

¹ North-Western Provinces Gazetteer, Vol. XIV, Part III, pages 100-147, passin,

² Cunningham, Archaeological Reports, Vol. XI, pages 102—126; Journal, Asiatic Society of Bengal, Vol. III, page 617, seqq.; Vol. XLII, pages 160—163; Proceedings, Asiatic Society of Bengal, for 1873, pages 139 and 140; Führer and Smith, The Sharqi Architecture of Janupur, 4°, Calcutta, 1889, pages 1—63.

independent Musalmân kingdom, perhaps the richest in Northern India. The founder of the dynasty, K h w â j a J a h â n, was appointed to the government of the Eastern Provinces by M a h m û d T u g h l a q with the title of M a l i k - u s - S h a r q, and took up his residence at Jaunpûr. He was shortly after (A.D. 1399) succeeded by his adopted son, M u b â r a q S h â h, who declared his independence and assumed the title of Sulţân-us-Sharq, or "King of the East." Mubâraq died in A.D. 1400, and was succeeded by his brother, I b r â h î m, during whose long reign (A.D. 1400—1440) the sway of the Sharqî kings was firmly established over the fairest provinces of Northern India, from Kanauj to Bihâr and from Bahrâich to Iţâwah. During the period of their sway, covering nearly the whole of the ninth century of the Hejira, the architecture of Dehlî is represented only by the tomb of M u b â r a q S a î d at D e h l î and by those of A l â - a d - d î n l a m S h â h and his family at B a d â o n. But the kings of the East, who built such magnificent masjids, have left behind them no tombs, all of them being contented with plain graves in the open air.

The architecture of Jaunpur is confined almost entirely to these Musalman masjids, for the Sharqi kings who were such great builders were equally great destroyers, as every masjid was reared on the site of a Hindû temple. Even the old name of the place is lost, and we are left to conjecture whether the Musalman story that Firûz Shâh named the city after his cousin, Jûnân (Muhammad Tughlaq) is more probable than the rival statements of the Brahmans about Jamadagnipura and Yavanapura. One thing is quite certain, that no Hindû ever calls the place Jaunpûr, but always Jaman pûr, which seems to point to Yavanapura as the original name. As to the Musalman name, it seems to be only a slight alteration of the old name for the purpose of pleasing Firûz Shâh. Some one made the ingenious discovery that the letters of Shahr Jaunpur gave the number 772 (A.D. 1370), reckoned by the abjad, and as this was the date of Firûz Shâh's visit, the new form of the name was at once adopted. Indeed, the place is actually mentioned by name more than a century before the time of Firûz Shâh's alleged foundation of it. In A.H. 665, or A.D. 1266, during the reign of Balban, "the intercourse between Dehli and Bengal by the route of Jaunpur and Benaras" was interrupted. In this passage Ferishta has either adopted the later spelling of the name, or he may have found the name so written in the author from whom he quoted, as the early Musalmans always wrote Jun for Jamna, and would therefore have written Jonpur for Jamanpur. But whatever may have been the original name, it is quite certain that there was a city on this site long before the Musalman conquest. In fact, the conquerors themselves acknowledge this when they relate how all their masjids were built on the sites of Hindû temples which they had destroyed. That the site of Jaunpûr was occupied by the Hindûs at a much earlier period is evident from an inscription2 of the seventh century on the archway of the south gate of the Jami Masjid, which gives the name of Îsvaravarman, of the Maukhari dynasty.

According to the tradition of the people, the fort overhanging the river was called Kararkôt, after a demon named Karar, who was killed by Rama-

¹ Brigg, Ferishta, Vol. I. page 256.

² Corpus Inscriptionum Indicarum, Vol. III, page 228,

Ia.

III. chandra, and afterwards worshipped under the name of Karâr Bir. His shrine exists at the north-west side of the fort. The name of the old town is not known, but the part which lies immediately to the north-east of the fort is still called Karâra.

Ib. The oldest building in Jaunpur is the masjid of Ibrahîm Naib Barbak in the fort; it is a long narrow building of the early Bengâlî type, that is, a simple arcade supported on carved Hindû pillars, with three low domes in the middle. It has no minars, their place being taken by two stone pillars placed at a short distance in front of the masjid. The building is 130 feet four inches long by 22 feet broad outside. The interior is divided into three distinct portions, a centre room and two side rooms. The centre room is 37 feet four inches by 15 feet; it is spanned by two arches of 15 feet, which sub-divide it into three compartments covered by three domes. The side rooms are each 40 feet six inches by 15 feet, each presents five openings in front with a flat architrave supported on a double row of Hindû pillars, the outer row being square and the inner row round. Down the middle of each room there is a row of four round pillars, and against the back wall a row of square pilasters. The pillars have no bases and are made up of all kinds of shafts pieced together, some square, some round, some octagonal. Only one of the stone columns is now standing in front of the masjid; but the position of the second is marked by its broken plinth and pinnacle. The shaft is formed of two distinct pieces, the lower part being of reddish sandstone and the upper part of yellowish sandstone, both from the Chunâr quarries. The pillar is square below, with a side of one foot eight inches, octagonal in the middle of the shaft, and round in the upper part; the whole surmounted by a capital and pinnacle like the amalaka fruit and kalasa of a Hindû temple. On the octagonal portion there is a long inscription1 engraved in Tughra characters, recording the erection of this masjid in A.H. 778, or A.D. 1377 by Ibrahîm Nâib Barbak, the brother of Firûz Shah.

The Atala Masjid was the work of Ibrahim Shah during the early part of his reign. It was built on the site of the Hindû temple of Atala Dêvî, which is said to have been erected by Jayachchhandra Dêva (1175-1193), the last Râthor prince of Kanauj. Of all the masjids remaining at Jaunpûr, the Atala Masjid is the most ornate and the most beautiful. In plan it is a quadrangle surrounded by cloisters of two storeys on three sides, with the masjid itself on the west side. The whole block of building is 252 feet long from north to south, by 248 feet broad outside, the courtyard inside being 176 by 160 feet. The grand feature of the masjid is the highly decorated propylon or great central arch, with a smaller propylon on each side of it. The propylon is 75 feet high with a base of 54 feet seven inches, and a top breadth of 47 feet showing a batter in the walls of three feet nine inches on either side. The masjid proper is divided into five compartments: the central room covered by a dome 30 feet in diameter, one long room of a single storey 62 feet by 28 feet eight inches on either side, and two low rooms in two storeys in each corner. These corner rooms are cut off from the rest of the building by stone screen work, of which portions still exist. The arrangement of the central room is very peculiar. as it is oblong in shape, although covered by a hemispherical dome. The room is 35

Proceedings, Asiatic Society of Bengal, for 1875, page 14; Führer and Smith, i.e., page 26.

feet one inch in length by 29 feet six inches in breadth. This difference is rectified by projecting huge corbels from the four side piers and four corners, so as to make the space to be covered by the dome an exact square. The angles of the square are cut off in the usual way and an octagon formed, which in its turn is developed into a sixteen-sided figure, and upon this the cupola of the dome is carried. In the cloisters behind each smaller propylon there is a hexagonal opening covered by a dome. Here also is the curious departure from the hexagonal figure, as the space to be covered by the dome is 22 feet in the direction from north to south, but only 191 feet in the other two directions. The difference is corrected by the use of large projecting brackets from the north and south pillars, which reduce the space to be domed to the shape of a regular hexagon of six equal sides. In the middle of each of the other three sides of the quadrangle there is a gateway with an octagonal room in the cloisters in front of the northern and southern gates. Opposite each of these gates the cloisters have only one storey, in which the pillars are formed by two Hindû shafts placed one above the other to gain the necessary height. Outside the back walls of the cloisters there is a row of rooms facing outwards with a verandah beyond, supported on coupled square pillars. In the double-storeyed portion of the cloisters, the aisles are extended outwards over the verandahs, thus forming five lines of open aisles supported on pillars. In the lower storey all the pillars are square, but in the upper storey the four central rows of shafts are round, the two outer lines alone being square. The gateways are similar in design to the central part of the masjid, each presenting a lofty propylon outside with a dome completely hidden behind it. All the domes are panelled on the outside by perpendicular ribs, which give a rich play of light and shade to the hemispherical masses. As is proved by nine inscriptions.1 found in the Atala Masjid, Fîrûz Shâh commenced the appropriation of the Ataladêvî temple in A.D. 1376 and Ibrâhîm Shâh finished the Atala Masjid in A.D. 1408.

The next masjids in point of age are those which were built by order of Ibrâhîm Shâh on the sites of temples of Vijayachandra and Jayachchhandra, The Masjid Khâlis Mukhlis, also called Darîbâ, or Charangulî, was erected on the site of Vijayachandra's temple for the devotion of the pious Saîd Usmân of Shirâz, about A.H. 820, or A.D. 1417. Very little of this masjid now remains in its original condition except the great propylon, which is 67 feet 10 inches broad at base, with a broken arch of 25 feet span. The lower part up to a height of 30 feet is built of stone, above which all is made of large bricks; but there is no ornament to break or relieve the sombre massiveness of the building. Behind the propylon there is a square enclosure, 65 feet eight inches in depth, covered with a flat roof supported on 10 rows of Hindû pillars.

The masjid at Châchakpûr is more commonly known as the Jhanjhrî

Ia. Masjid, on account of the "chain-like" appearance of its ornamentation. Nothing now remains except the great propylon. The masjid was built by order of Ibrâ-hîm Shâh in honour of one Hazrat Saîd Sadr Jahân Ajmâlî on the site of a famous Hindû temple of Jayachchhandra, close to the Muktaghât on the Gûmtî. The masjid was much smaller than any of the others; but the front of the propylon yields to none of them in richness and beauty of ornamentation. The

Ib.

¹ Führer and Smith, Lc., pages 38-40.

base of the propylon is 35 feet seven inches in breadth, with an arch of 23 feet nine inches span. The style of decoration is similar to that of the Atala Masjid. Though very little known, it is well worthy of a visit, both on account of its past beauty and as showing now completely what in the Jaunpûr style seems an inner true arch is merely a part of the screen; for its voussoirs here—all carved with a long raised Arabic inscription, the only instance in Jaunpûr of such a decoration—are all loose, and but for the support of the pierced screen would fall. The eastern gate and the side walls of the masjid were destroyed by Sikandar Lodi, and other parts were afterwards thrown down by the inundations of the Gûmti. Many of the stones are said to have been used in building the great bridge during the reign of Akbar.

Ia.

The Jami Masjid is the largest masjid at Jaunpur; its erection was ordered for the convenience of Hazrat Khwaja Îsâ, who used to suffer much during his walk to the Khalis Mukhlis Masjid. The foundation was laid in A.H. 842, or A.D. 1438; it is said that the date of the completion of the masjid was found in the words Masjid Jami us sharq which were engraved on the front of the eastern gate. This would fix the date in A.H. 852 during the reign of Mahmûd Shâh Sharqî. According to some people, the inscription on the eastern gate was Al Masjid Jami us sharq, which would make the date A.H. 883, during the reign of Husain Shah. The plan of the Jami Masjid is essentially the same as that of the Atala Masjid; but there are many differences, of which the most remarked is the high platform on which it stands, all the other masjids being raised but little above the ground level. Another difference is the piling up the cloisters to the height of three storeys on each side of the gateway. The shafts of the pillars are all square and plain, and on many of them there are socket holes for iron cramps which tell their own tale of having been brought from some earlier Hindû temple. The masjid proper is 235 feet long by 59 feet broad. It is divided into five distinct compartments: a central room, 39 feet seven and-a-half inches by 39 feet eight and-a-half inches, and roofed by a dome (gumbaz); a low-pillared room (chhât) on each side, 25 feet four inches by 44 feet seven inches, over which is the zanàna gallery, and on each side of this again a lofty arched chamber (chhapra) 49 feet three inches in length by 39 feet seven inches in width. In front of the central room rises the great propylon to a height of 84 feet four inches, with a base of 76 feet 101 inches. The height of the arch alone is 72 feet two inches. This lofty entrance to the masjid stands on an elevated platform which has a staircase of 27 steps leading up to it from the street of the city. Altogether it rises to a height of more than 200 feet, and towers over the city, forming a more conspicuous object than the Fort itself. The flat-roofed compartments on each side of the central domed room have two storeys. The upper rooms are provided with trellises which look into the domed room in the centre and the vaulted rooms at the ends, and must therefore have been intended for the use of the ladies of the king's family. Access to these rooms is obtained by staircases in the massive piers of the great arch. The staircases are continued upwards to the roofs of the flat rooms, from which there is a continuous passage in the thickness of the wall all round the centre room with openings just below the spring of the dome. This dome is, according to Kittoe,2 "a

¹ Führer and Smith, Lc., page 42.

² Illustrations of Indian Architecture, Calcutta, 1838.

wonderful piece of workmanship, the exterior shell being many feet apart from that of the interior, and is formed by different segments of circles," and Major-General Cunningham¹ is of opinion that there must be some arrangement of this kind, as by his measurements the top of the dome outside is 67 feet three inches, whilst the inside is only 55 feet three inches, showing a difference of 12 feet, and as this is too much for the top thickness of a single dome, he concludes there are two thin domes, each about three feet in thickness at the top, and thus leaving an empty space of six feet in height. But the true height of the dome on the *inside* is 67 feet six inches, and not 55 feet three inches, and outside the height is 72 feet six inches to the top of the cap which supports the finial. The thickness of the wall, measured through the window openings in the drum of the dome, is three feet and three-quarter inches, not 12 feet, and therefore could hardly support a double dome; while at the vertex, including the cap, the whole thickness is only five feet. The diameter of the dome is 39 feet five inches.

The courtyard of the masjid is a square of 219 by 217 feet. In the middle of each side there is a large gateway, that on the east being 48 by 46 feet, and those on the north and south sides 43 by 41 feet. The eastern gateway is a complete ruin, having been purposely destroyed by Sikandar Lodî. The other two gates are much injured, but the domes and main walls are still standing. The whole ground covered by the quadrangle and gateways contains a space 320 feet in length from east to west by 307 feet from north to south. The cloisters to the north and south have 11 openings on each side of the gateway, with two aisles in two upper storeys, and a row of rooms facing outwards in the lowest storey. On each side of the gateways the cloisters are extended outwards by two more rows of pillars. To the north of the northern gateway, at a distance of 11 feet, lies the khângâh, or burial-ground of the Sharqî kings, 120 feet in length by 60 feet in breadth. Here are the tombs of Ibrâhîm Shâh and his son and grandson, Mahmûd Shâh and Husain Shâh.

The Masjid of Bibi Raji, or, as it is commonly called, the Lal Darwaza Masjid, stands near the village of Begamganj at some distance outside the city to the north-west. Bibî Râji, the founder of the masjid, was the queen of Mahmûd Shah, who reigned from A.H. 844-861, or A.D. 1440-1458. This masjid is the smallest of all the Jaunpur masjids, the outside dimensions of the quadrangle being only 190 by 171 feet, or less than one-half of the area covered by the Jâmi Masjid. The general design and style of the building are similar to those of the other masjids; but the walls are much thinner, and the whole building is on a lighter and less massive scale. The masjid proper measures 168 feet six inches by 35 feet four inches inside dimensions, with the usual propylon or pyramidal entrance, 48 feet six inches high from the floor of the entrance hall and 44 feet nine inches wide at the base, in front of the central dome. The dome itself is only 22 feet eight inches in diameter; but in front of it there is an entrance hall, which is wanting in the other masjids. The rooms on each side are four aisles in depth, and are formed entirely of pillars covered by architraves without a single arch. On each side of the propylon there are four openings into the court-yard and two into the north and south cloisters

16.

¹ Archwological Reports, Vol. XI, page 115.

of the quadrangle. The whole of the cloisters are only one storey in height, with the exception of two portions to the right and left of the centre room, which consist of two low storeys, and are separated from the rest by trellises. These rooms were doubtless intended for the ladies of the court. On the other three sides of the quadrangle the cloisters are two aisles in depth, with a row of rooms outside the walls. In the middle of each face there is a gateway of the same style as the propylon. The eastern gate is 25 feet four inches broad, and the other two gates 22 feet four inches. In the aisles of the masjid the pillars are all square with double capitals for the purpose of obtaining height. In the cloisters the shafts of the middle row of pillars are all round; most of the pillars, both square and round, have been plundered from Hindû temples. Bracket-capitals have been re-cut and adapted to smaller shafts, square shafts have been rounded, and several inscriptions1 have been partly cut away in these alterations. The Lâl Darwâza is more decidedly Hindû than any of the other masjids. The dome and great entrance and the three gates are the only arched constructions in the whole building.

The Fort of Jaunpur, the ancient Kararkôt, no longer exists except as a III. ruin, the walls having been quite needlessly thrown down at the end of the mutiny at the recommendation of some committee. The walls themselves had no special beauty; but along with the walls the Engineer, Lieutenant Malcolm, threw down the beetling palace of Chihal-sitûn, or "forty pillars," with its three retreating storeys. The principal gateway of the fort still remains, which was built by Munim Khân, Khân Khânân, the Governor of Jaunpûr under Akbar. The spandrils of the arch are filled with glazed tiles, and the walls are divided into panels with ornamental niches. Outside the fine gateway stands a lat with a Persian inscription. dated A.H. 1180.

The stone bridge over the Gumti is the only remaining building of any con-Ia. sequence at Jaunpur. It was commenced in A.H. 972 by Khan Khanan Munim Khân, and completed in A.H. 795, when seven inscriptions2 in verse were placed on the piers giving the date and name of the builder. The bridge consists of two distinct portions separated by an island, and is certainly one of the most picturesque structures in India. Its long line of arches and piers, all of the same size, is relieved by the light pillared rooms which crown the ends of the piers on both sides. The roadway is 26 feet in clear width, with a solid stone parapet of two feet three inches on each side. The whole length of the bridge is 654 feet three inches. The main bridge to the north consists of 10 pointed arches of 18 feet three inches span. resting on piers of 17 feet, with abutments of half the thickness. The smaller bridge to the south has only five arches of the same span as the others, and with similar piers and abutments. The island between the two is 125 feet six inches. On the side of the roadway crossing the island, there is a large stone figure of a gigantic lion, standing over a small elephant, which must have been brought from one of the Hindû temples.

There are many other interesting monuments in Jaunpûr, of which the following are the most important: the masjid of Haqîm Sultan Muhammad, a small vaulted building, erected in the reign of Akbar under the governorship of

IIb.

Führer and Smith, Lo., pages 49-51.

² Führer and Smith, Lc., pages 17-20.

Ma'sûm Khân, in A.H. 978 (A.D. 1570), on the northern bank of the Gûmtî close to the bridge; the masjid of Nawâb Mohsîn Khân in mahallâ Hanumân Darwâza, built in A.H. 975, or A.D. 1567; the masjid of Shâh Kabîr in mahallâ Partalâ, erected by Bâbâ Bîk, în A.H. 991, or A.D. 1583; the masjid of Zâhid Khân on the north bank of the Gûmtî, in Miyânpûr, built in A.H. 1150, or A.D. 1737; and the dargâh of Sulaimân Shâh, dated A.H. 867, or A.D. 1462.

3. Macchlishahr, or Ghiswâ, tahsîl, 18 miles south-west of Jaunpûr, possesses the ruins of an ancient fort, 17 masjids nearly all in ruins, of which the Jâmi Masjid, built by Husain Shâh Sharqî, the Karbalâ, built by Shaikh Kabûl Muhammad in the 13th century, and the Îdgâh built by Shaikh Muhammad IIb. Mangalî in the 16th century, are the most important. The town itself is surrounded by 17 tanks, one of them on the south side being very large, and another on the north side of fair size.

A copper-plate grant of Rājā Govindachandra Dêva of Kanauj, dated Samvat 1209, was found, in September, 1888, in a field close to a small village, seven miles north of Machhlishahr. The original plate is in the Lucknow Museum.

4. Mâî, small village in tahsîl Jaunpûr, 12 miles north-west from head-quarters, is the ancient Mayâ according to an inscription¹ of Samvat 1273, found in 1846 in a neighbouring field.

 Mariano, tahsîl, 12 miles south of head-quarters, possesses the Jâmi Masjid, the small masjid of Sâlâr Pîr, and an Îdgâh of no great antiquity or architectural merit.

6. Sikrârâ, village in tahsîl Jaunpûr, 10½ miles south-west of head-quarters, possesses a stone bridge, called Pul Gulzâr, over the Sâî, built by Munim Khân in A.H. 979, or A.D. 1569. Originally it consisted of eight 18-feet arches with piers of somewhat greater breadth; one or two arches had more than once been blown up by floods and repaired; but when a pier was again broken down in the rains of 1847, arrangements were made for remodelling the whole. Two arches were in each case thrown into one, to the great increase of beauty of the bridge and improvement in every way.

7. ZAFARĀBĀD,² village in tahsîl Jaunpûr, on the right bank of the Gûmtî, four miles south-west of head-quarters, possesses the walls of the old kankar fort of Jaya-chchhandra, which enclose a space of eight acres to the west of the town. Zafar Khân, the governor appointed by Fîrûz Shâh, is said to have founded a city here, and to have called it Shahr Anwâr, which would give as the date of its foundation A.H. 762, or A.D. 1366; but Shaikh Barhan's Masjid, on the other hand, is said to have been appropriated in A.H. 711, or A.D. 1311.

A very remarkable building is the masjid known as that of Shaikh Barhan, being a Buddhist temple with the pillars in situ, the form of worship alone being altered. The roof is flat and the interior is a hall 18 feet high, nine bays deep from east to west, and seven broad from north to south. The outer ranges of columns are double, and plain walls close the spaces between the outmost. The square pillars are somewhat irregularly placed towards the western sides; the aisle running from the

IIb.

Ia.

III.

Ib.

¹ Journal, Asiatic Society of Bengal, Vol. XIX, page 454.

Fuhrer and Smith, Le., pages 64-66.

door to the qibla is eight feet six inches broad, the others six feet six inches; the greater breadth of this centre side is the only thing about the place suggestive of Musalman interference in its construction, for the arch which once finished the front may have been, and probably was, added even after the Jaunpûr masjids were built. The substructure is of stone to above the level of the roof, and the arch has been of stone; but the upper half of the piers is of brick. The little remains of the spring of the arch do not seem to have any traces of the inner or recessed arch which frames the screens of the Jaunpur masjids; if it ever had this arch and screen, this masjid alone of all has lost it. The top of the piers is marked by a very steep stair running across the back of the arch, whereas had there been a screen, one would have expected a plan followed like that of the upper part of the Jami Masjid, which, carrying the stair across the screen, makes the ascent far easier and safer. It never had a dome, whilst it certainly had a large arch between two piers, giving a façade as lofty as that of the Atala Masjid. The stone on which Shaikh Barhan's dedication was carved, fell from the front and it is lost; but in a suit brought against Mr. Ommaney, a former Collector of Jaunpur, evidence was given to show that the inscription gave the date of the building as A.H. 711, or A.D. 1311, and Ala-ad-dîn Mahmûd Khiljî was said to have been the then ruler, whose accession dates one century and-a-half later. The date refers most probably to the reign of Alâ-ad-dîn Muhammad Shâh.

There are several curious old tombs scattered about Zafarâbâd, which most probably belong to the period of the Sharqi kings. The oldest and most curious of these Ib. is an open building said to be the resting-place of Said Murtaza, who fell in the religious invasion of Shahab-ad-din Ghori in A.D. 1194. In plan it is a square platform of 20 feet with 12 Hindû pillars supporting a low entablature, above which there is a small squat dome. There are two varieties of pillars, but their shafts agree in being octagonal below, sixteen-sided in the middle, and circular at top. They are four feet nine inches in height and from 15 inches to 16 inches in diameter. The capitals are all round, the upper part being like a tulip-shaped bowl. Above there are bracket-capitals, making the total height beneath the architraves seven feet seven inches. Many pillars of the same pattern are used up in Asar-ad-din and Makhdûm Shâh's dargâhs built by Zafar Khân during the reign of Firûz IIb. Shâh, in A.H. 781, or A.D. 1379, according to a Persian inscription1 over the entrance door of the dargah. Near the same place there are a couple of small octagonal tombs standing close together, which are commonly known as the "two sisters." These also are open buildings standing on Hindû pillars with octagonal shafts and finely-carved capitals surmounted by usual bracket-capitals. The superstructure is also eight-sided with openings on the alternate sides and a battlement above, from which springs a Pathan dome with rather steep sides and a flattish top. The whole neighbourhood of Zafarabad abounds with kheras, the remains of Hindu palaces and temples.

¹ Führer and Smith, Lc., page 65.

VII.—BANÂRAS DIVISION.

I.—AZAMGARH DISTRICT.1

 AMIA BAZAR, lat. 26°-10′ N., long. 83°-34′ E., village in pargana Ghosì of III. tahsil Sagri, 22 miles north-east of Azamgarh, possesses the ruins of a mud fort.

Ш.

IIb.

III.

III.

III.

44

 ATRAULIA, lat. 26°-20′ N., long. 82°-59′ E., town in tahsil Mahal, 26 miles to the north-west of Azamgarh, possesses to the north of the town a mud fort, built by Bujhawan Singh, a Palwar of Nariaon.

3. ÅZAMGARH, lat. 26°-33′ N., long. 83°-13′ E., capital of the district, derives its name from Âzam Khân, who founded it on the ruins of the village of Phulwarîâ, about A.D. 1665. The only antiquities in the town are a dilapidated fort, built by Âzam Khân, and a temple to Gaurî-Ŝańkara in mahallâ Asafganj, said to have been built about A.D. 1760 by a family priest of the local Râjâs.

In the town there is a Sanskrit inscription on a stone sugarcane press, dated Sanvat 1609, or A.D. 1553, in the time of Salîm Shâh Sûr.

Four miles to the south of Azamgarh, at the villages of Unchagaon and Harbanspar, there are the ruins of two large mud forts.

4. AZMATGARH, lat. 26°-9' N., long. 83°-24' E., village in tahsil Sagri, 14 miles north-east of Azamgarh, possesses the ruins of an old fort, built by Azmat, a Sikh sangat. Adjoining the village is the great Salonâ, or Azmatgarh Tâl.

5. Chiraîyakor, lat. 25°-52′ N., long. 83°-22′ E., village in tahsîl Muhammadâbâd, 16 miles south-east of head-quarters, is no doubt a place of great antiquity as many ancient punch-marked coins have been found there. It is a square-shaped mound of earth, measuring about 160 feet from north to south by about 150 feet from east to west, and situated in the middle of the village. There is an old tank to the north of the village, with a mound on the south side of it; this mound is higher than that in the village. There are two traditions accounting for the name of the place: one connects it with the Cherûs; another with a Hindû chief whose name was Chiraîya. More true it seems to have received the name of Mubâr-aqpûr, but this has long since dropped out of use.

IIb. On the outskirts of the town is the large mausoleum of Hâtim Khân, a Shaikh of Chiraîyakot who held office and acquired wealth at the imperial court of Dehlî during the earlier part of last century.

Six miles to the north of Chiraîyakoţ on the bank of a large jhîl close to the village of B h a tṛi, there is an ancient site, called Gâṛha-kâ-koṭ, or Râjbhâr-kâ-koṭ.² The entire extent of this site measures about 2,400 feet from north to south by about 1,500 feet from east to west; the whole ground is covered with fragments of bricks and pottery. On this, at a distance of about 1,300 feet from the northern limit of the traces of ruins, there is an old ruined fort, covered with jangal, which measures 600 feet from north to south by 500 feet from east to west. In the fort there is a ruined conical-shaped mound of bricks which has a circumference of about 100 feet and a perpendicular height of about 11 feet. It may possibly be a ruined stûpa.

¹ North-Western Provinces Gazetteer, Vol. XIII, Part I, pages 141-186, passim.

^{*} Cunningham, Archwological Reports, Vol. XXII, page 106.

III.

III.

Hb.

III.

Ia.

III.

6. Dabhaon, village in tahsil Dêogâon, 26 miles south of Âzamgarh. To the III. north-west of the village there is an old dry tank, called Hâthiyah-dâh, or the "elephant's tank," with an inscribed pillar standing in the middle of it. The pillar itself is called Hâthiyah-dâh-kî-lâţ, or the "pillar of the elephant's tank."

Ia. The name is derived from a large stone elephant, five feet six inches in length, and four feet 10 inches in height, which stands to the north-west of the pillar, at a distance of 138 feet. Both the pillar and the elephant are formed of a coarse grey sandstone, and they have accordingly suffered from exposure to the weather, and are now much worn. The pillar is a mere cylindrical block, apparently intended for the sole purpose of exhibiting the inscription; its shaft being 12 feet nine inches in height and one foot five inches in diameter, both at base and top. The capital is a flat circular slab, slightly rounded on the upper edge, and quite plain. The inscription occupies 10 lines; but as the letters are large and coarsely cut, it is not a long one. It records the excavation of the tank by several Thakkuras, of whom the chief is Bellan Thakkura, the treasurer of Gosalâ Dêvî, the queen of Govindachandra Dêva of Kanauj, on Thursday, the 5th of the waning moon of Âshâdha, in Sanivat 1201, and not Sanivat 1207 as General Cunningham reads.

To the west of the pillar there is a low mound of brick ruins, 170 feet in length from north to south and 25 feet broad. It is called S i w â r i-kâ-t î l â; most probably it has some reference to a temple of Siva which may have stood there in former days.

7. Deogaon, tahsil, lat. 25°-45′ N., long. 83°-1′ E., 28 miles south of Azamgarh, is an old place, though there are no remains about it to attest the fact. The legend respecting its name is that when Said Muhammad Baghdadi took possession of it after driving out a demon, he so far had mercy upon the latter that the name of the place was allowed to bear testimony to the demon's prior occupation of it.

Three miles to the north of Dêogâon, at the village of Râmgarh, there are the ruins of some stone temples.

 Dohríghát, town in tahsíl Sagri, 26 miles north-east of Ázamgath, possesses a large masjid, built by Jahán Khán, a Rájá of Ázamgath, at the end of last century.

9. Ghost, lat. 26°-6′ N., long. 83°-34′ E., town in tahsil Sagri, 24 miles east of Azamgarh, is doubtless an old place, and was probably once much larger than it is now. None of the architectural remains are, however, of any importance or great age, but the well-preserved ruins of a large mud fort give interest to the place.

Close to the town was discovered, in 1838, a mutilated Sanskrit inscription² of Rājā Dharaṇi Varāha, apparently belonging to a period not long anterior to the Musalman invasion.

At the village of Chakêśar there is a Persian inscription³ on a loose slab, dated A.H. 760, or A.D. 1359, in the time of Fîrûz Shâh, which had belonged to a Jâmi Masjid.

10. Kauriâ, village in tahsîl Mâhal, 14 miles north-west of Âzamgarh. Near the villages of Ariâ on Jahâniânpùr and Awank there are the ruins of two large mud forts; the first is ascribed to Ayodhyâ Râî, Râjbhâr, and the second is pointed out as Râjâ Parikshit's.

¹ Conningham, Archaelogical Reports, Vol. I, page 95.

² Journal, Asiatic Society of Bengal, Vol. VII, page 635.

Proceedings, Asiatic Society of Bengul, for 1877, page 100.

11. Korâ, village in tahsîl Muhammadâbâd, 25 miles east of Âzamgarh, owes its existence to Irâdat Khân, a Râjâ of Âzamgarh, who founded it about A.D. 1745, and named it Irâdatganj; but the name has since been changed. A strong mud fort was thrown up, which became a favourite residence of the Râjâs, and to the ruins of which the present representative of the family still clings.

The masjid of Mirzà Âtâ Bêg was built in A.H. 1195, as stated in an inscription.

There is a Hindî inscription on a stone that is built in over the door of a small Hindû temple, giving the date Sanivat 1529, or A.D. 1472.

12. Madhuban, village in pargaņa Nathûpûr of tahsîl Sagrî, 32 miles northeast of Azamgarh. In a field near this village was discovered, in January, 1888, by a cultivator's ploughshare a valuable copperplate inscription,1 recording in later Ia. Gupta characters the grant of the village Somakundika to two Brahmanas, the Sâmavedî Bhatta Vâtasvâmin, of the Sâvarnigotra, and the Rigvedî Bhatta Sivadêvisvâmin of the Vishņuvriddhagotra, by King Harshavardhana, of Sthânvîsvara, the modern Thânesar, for the spiritual welfare of his father, Prabhâkaravardhana; his mother, Yasomati Dêvî; and his elder brother, Rajyavardhana, on the sixth day of the dark fortnight of the month Margasirsha in (Harsha) Samvat 25, or A.D. 631. This grant is the more valuable as it is the only one as yet discovered of this famous King, and as its historical details confirm the genealogy of that king, given by Banabhatta in his biography of Harshavardhana. It gives the following ancestors of the Vaisya family of Sthanvisvara: (1) Naravardhana and Vajrinîdêvî; (2) Râjyavardhana I, and Apsarodêvî; (3) Âdityavardhana and Mahasenaguptadevi; (4) Prabhakaravardhana and Yasomati; (5) Rajyavardhana II, and (6) Harsha (brothers).

The original plate is now in the Lucknow Museum.

13. Mahārājganj, town in pargaņa Gopālpûr of tahsil Sagrî, 13 miles north of Azamgarh, possesses the famous old Hindû shrine of Bhairava, called Bhairo-kâ-âsthân, or Dêotârî. The village of Bishnpûr (Vishņupura), within the bounds of which the town stands, is doubtless an old place, whilst the name Mahârâjganj is of comparatively recent origin. The shrine of Bhairava is alleged by its attendant Brâhmanas to have been a gate of Ayodhyâ from which it is now 40 kos distant.

14. Mâhal, tahsil, lat. 26°-8′ N., long. 82°-52′ E., 25 miles west of Âzamgarh. At the village of Dêhduâr there are several old tanks and mounds attributed to the Râjbhâr chief Asaldêo.

There is a Persian inscription² on a slab in an old masjid at the ruined village of Qasbah Nigûn, dated A.H. 940, or A.D. 1533, in the reign of Humâyûn.

15. Mau Nathanjan, lat. 28°-57′ N., long. 83°-35′ E., town in tahsil Muhammadabad, 25 miles north-east of head-quarters, is a place of greater antiquity than Azamgarh, but when it was originally settled is not clear. One local tradition is that Malik Tahir, whose tomb is still preserved in the town, settled in it, and having exorcized a demon that troubled it, left a memorial of his deed in the name by which the place became known, Mau Nathhanjan, meaning "land of the expeller of the demon." The town is mentioned in the Ain-i-Akbari. During the reign of Shâh Jahân the pargaṇa was assigned to Jahânârâ Begam, the emperor's daughter,

1 Epigraphia Indica, Vol. I, page 67.

III.

IIb.

IIb.

III.

Hb.

IIb.

² Proceedings, Asiatic Soviety of Bengal, for 1877, page 100.

IIb.

ш.

III.

- III. and the town received the name of Jahânâbâd. A katrâ, or market-place, now falling to ruins, was erected by the Begam's order, and in her time as well as in the reign of Aurangzîb, the town seems to have enjoyed the special care of those in authority. It is said to have contained 84 mahallâs and 360 masjids.
 - 16. Минаммаравар Gohna, tahsil, lat. 26°-1′ N., long. 83°-25′ E., 12 miles east of head-quarters, has been held by the Musalmans from the early part of the 15th century, apparently as a dependency of Mau. It possesses, however, no buildings of any historical or architectural interest, excepting the dargah of Pîr Kashani. To the east of the town there is a large tank, known as Thâkurahî.
- At the villages of Indpûr Bhîra and Dêolâs are the stone remains of III. some old Hindû temples. The celebrated temple of Sûrya at Dêolâs is nothing more than a commonplace modern Śivâlâ.
- IIb. At the village of Ganjâhra there is the masjid of Muhammad Sâlih of the time of Ålamgîr, with a Persian inscription, dated A.H. 1099, or A.D. 1687.
 - 17. Nizâmâbân, town in tahsîl Âzamgarh, eight miles west of head-quarters, is no doubt an old town. It is said to have been a Hindû settlement previous to the Musalmân occupation. The local tradition respecting its present name is that it is derived from a certain Shaikh Nizâm-ad-dîn, a saint whose tomb is pointed out in the town, which bears a Persian inscription, dated A.H. 969, or A.D. 1561.
- IIb. At Kalandarpûr is the tomb of Kalandar Shâh, built by the wife of Asad Khân, minister of Aurangzîb, in A.H. 1118.
- 18. Powar, village in tahsil Mahal, 30 miles west of Azamgarh, possesses the III. ruins of a large mud fort.
 - 19. Sarái Mír, town in pargaṇa Nizâmâbâd of tahsîl Âzamgarh, 18 miles west of head-quarters, is said to have been founded under the auspices of Shâh Alî Âskikân in A.H. 943, or A.D. 1536, and named Murtazâbâd; but the name did not gain currency, and the place became known as Sarâi Mîr.
- IIb. On the outskirts of the town there is a large mausoleum, built partly of block kankar and partly of sandstone, in the Pathân style, known as the dargâh of Lâl Khân; but nothing is known of Lâl Khân, except that he and his brothers were residents in the neighbourhood about the time of Shâh Alî. The tomb of Shâh Alî still exists, and a mêlâ is held at it once a year.

II.—BÂLIYÂ DISTRICT.2

- 1. Båghaunch, village in tahsîl Bâliyâ, on the left bank of the Ganges, 11 miles west of head-quarters, possesses a large mound under a banyan tree which is said to have been raised in honour of a female deity, named Bâghaunch, from whom the village derives its name.
 - 2. Bâliyâ,³ head-quarters of the district, lat. 25°-43′ N., long. 84°-11′ E., on the left bank of the Ganges, is supposed to have derived its name by corruption from that of the Rishi Vâlmîki, who is said to have had his hermitage there, or to have dwelt on the spot for some time. Its ancient name may therefore perhaps have been Vâlmîkîyâ. The old town of Bâliyâ was almost entirely destroyed by the erosive

¹ Proceedings, Asiatic Society of Bengal, for 1877, page 99.

^{*} North-Western Provinces Gazetteer, Vol. XIII, Part III, pages 80-141, passim,

Cunningham, Archaeological Reports, Vol. XXII, pages 82-87.

action of the Ganges between 1873 and 1877; the old masjid, the old fort, and the whole of the better-built part of the town were swept away.

Notable for its religious, but in no way for its architectural, importance, is the IIb. temple known as Bhrigu-asrama, "the hermitage of Bhrigu." The changes in the course of the river have produced changes in the position of Bhrigu's temple, which was built on its present site 10 years ago, having formerly been much further south where the river now flows. Close to it there was a famous temple of Dêvi Bhavanî.

At the distance of about 450 feet to the north of the north-east corner of Baliya IIb. there is an ancient tank, which is called Dharmaranya Pokhara, and to the north and east of it there are traces of the former existence of an ancient jangal or scrubby forest, probably a remnant of the ancient Aranya.

III. There are mounds of ruins at a place called Beduwalî, about a mile to the north of Bâliyâ.

Near the village of Vazîrapûr, at a distance of about 4,000 feet to the south-III. east of Bâliyâ, there is a mound of ruins, with a small pond at its western side. This mound measures 165 feet in circumference, 73 feet in diameter from north to south, 67 from east to west, and about 14½ feet in height.

About 850 feet to the south-east from this mound, there is another mound of ruins, near a village called D h a r m a 0 1 i, probably a modern corruption of D h a r m a 1 a y a. This mound measures 283 feet in circumference, 109 feet in diameter from north to south, 43 feet in diameter from east to west, and a little less than 13 feet in height.

At a distance of 2,400 feet to the north-east from the Dharmaôlî mound, and near the village of Muhammadpûr, there is a still larger and much higher mound of ruins, which is situated on the north side of a large oval-shaped pond of water. This mound measures 299 feet in circumference, 72 feet in diameter from north to south, 81 feet in diameter from east to west, and about 24 feet in height. This mound most probably contains the ruins of a stûpa.

At a distance of about 500 feet to the east of this mound, there is a long narrowshaped mound, running eastwards, along the north side of a road, for over 500 feet to a temple which is situated on the eastern end of the mound.

There can be no doubt that the remains about Bâliyâ represent the site of the Buddhist Vihâra mentioned by Hiuen Tsiang¹ under the name of Aviddhakarņa, "ears not pierced," and by Fa Hian² under the name of Araṇya, or "desert."

- 3. Bânspîh, tahsîl, lat. 25°-53′ N., long. 84°-15′ E., 10 miles north of Bâliyâ, is clustered round high artificial mounds, called garh or fort. The town derives its chief interest from the fact of its being situated in the heart of the country formerly ruled over by the Cherûs. Bânsdîh itself has no remains or traditions of Cherû rule; but close by, in the deserted village of Dêori, are pointed out the ruins of the stronghold of Mahîpa Cherû, who is believed to have reigned over the country when the Râjpûts first invaded it.
- 4. BARMÂYAN,³ village in tahsîl Bâliyâ, six miles north of head-quarters, is an ancient site where there are abundant remains of a structural nature to testify to its

Ш.

III.

IIb.

III.

Beal, Le., Vol. II, page 62.

^{*} Beal, I.c., Vol. I, page LXVII. Compare also Beal, I.c., Vol. I, page 212, where Hinen Tsiang mentions a statue of Avalokité'svara Bodhisattva on a desert spot near the banks of the Ganges.

² Cunningham, Archaelogical Reports, Vol. XIX, pages 49—59.

III.

Ш.

III.

Hb.

Hb.

III.

former importance, and as some of these remains are of Buddhist origin, a very early

occupation of Barmâyan is proved.

III. Foremost among the antiquities is a ruined Buddhist monastery which lies to the north of the village, between Barmâyan and a remarkably large lake, called Sûrahâ Tâl. The old main walls of this vihâra cover an area of 100 feet from north to south by 67 feet from east to west; but the limits of the mound altogether extend from north to south over 160 feet and from east to west 110 feet. The bricks are very large, measuring 18"×9"×3", and many carved and ornamented specimens are lying about. These are the only traces left to us of the ornamental portion of this monastery, which must have been a building with considerable pretensions to architectural merit.

The other remains in the neighbourhood of Barmâyan and Hanumânganj consist of a large mound, called Mîra Dîh, covered with broken bricks and pottery of a dark hue. They are doubtless the remains of an ancient city.

5. Bhâlsand, or Bhârsand, village in tahsîl Bâliyâ, six miles east of head-quarters, is a place of great antiquity, said to have been founded by Râmadêva, the eighth Râjâ of Haldî, who, according to the pedigree in possession of the family, was installed in A.D. 1100. The name is said to be derived from Bharadvâja, a rishi whose permanent residence was at Prayâga, but who lived for some time at Bhâlsand.

6. Сни́ата, village in tahsil Bâliyâ, eight miles north of head-quarters, is a place of considerable antiquity, whose name is probably derived from the umbrella-like

(chhattra) appearance of a ruined stûpa close to the village.

7. Chit Fîrûzpûr, or Bâragâon, village in pargaṇa Kopâchît, east of tahsîl Bâliyâ, eight miles west of head-quarters, possesses a convent of the Bhîkha Shâhî sect and four dome-covered tombs of its departed spiritual guides. Adjacent to the village on either side of the high road are two large tanks of stone masonry work, which for size and beauty are the finest in the district.

At Pakkâ Kôţ, on the right bank of the Chhotî Sarjû, not very far from Bâragâon, there are extensive remains of brick-work and earthen embankments, which are referred to an ante-Hindû period, when the Cherûs ruled over this portion of the district.

 Garwar, village in pargana Kopachit, east of tahsil Baliya, 10 miles northwest of head-quarters, possesses a small mound which is said to be the débris of a Cherû stronghold.

9. Hald, village in tahsil Bâliyâ, on the left bank of the Ganges, 10 miles III. east of head-quarters. The ancient town of Haldi contained a celebrated fort, built by Râjâ Dhiradêva about A.D. 1643, which was long ago carried away by the Ganges. The modern town is in no way remarkable.

10. Husainabad, village in pargana Kharid of tahsil Bansdih, 12 miles northeast of Baliya, is said to have derived its name from Husain Shah Sharqi, and III. to whom is attributed the construction of a tank and masjid now in a dilapidated condition. The tradition is that the original name of the village was Kalasadih, and that the inhabitants incurred the displeasure of the king. In consequence of this, having caused all the male adults to be killed and the village to be destroyed, he built the masjid on the ruined site.

- KARNÂÎ, village in tahsîl Bâliyâ, six miles west of head-quarters, possesses
 a large mound, said to be the débris of a Cherû fort.
- 12. Kathaurā, village in pargaņa Sikandarpūr East of tahsīl Bānsdih, on the III. right bank of the Ghāgrā, 28 miles north of Bāliyā, possesses a mound which is said to be the ruins of a fort built in the time of Quṭb-ad-dîn Shāh of Bengal about A.D. 1203.
- 13. Kharîd, small village in pargana Sikandarpûr East of tahsîl Bânsdîh, 26 miles north of Bâliyâ, on the right bank of the Ghâgrâ. The only interest attaching III. to this place is the traditional account which makes it the site of a former large city, also named G h a z a n f â r â b â d. From the fact that mounds, apparently representing former inhabited sites, are found on both sides of the Ghâgrâ, it is evident that the old town may have been destroyed by the river.
- Ia. Kharîd is mentioned in a Tughrâ inscription¹ of A.H. 933, or A.D. 1527, found IIb. some years ago near the Ghâgrâ, and now fixed in the northern wall of the dargâh of Rukn-ad-din Rukn Âlam in Kharîd. According to this inscription a large masjid was built by Khân-i-Âzam Khân, Mukhtâr of Kharîd, during the reign of Nasrat Shâh, son of Husain Shâh, of Bengal, in the month of Rajab, A.H. 933, or the 29th April, 1527.
- 14. Lakhnesar Dîh, a deserted village site in the south-east corner of pargaṇa Lakhnesar in tahsîl Rasrâ, on the banks of the Sarjû, 18 miles west of head-quarters, contains immense piles of débris in which pieces of sculpture have occasionally been found. The tradition, which makes Lakshmaṇa, one of the heroes of the Rāmāyaṇa, visit this place and build here a temple in honor of Mahâdêva, tells us by implication that, even in those early times, it was a settled abode with a flourishing population.
- 15. Maniar, village in pargana Kharid of tahsil Bânsdih, on the right bank of the Ghâgrâ, 18 miles north of Bâliyâ, is clustered round high artificial mounds, formerly sites of the fortified residences of the principal zamindârs, but now waste and bare.
 - 16. Någrûnå, village in pargaṇa Lakhnêsar of tahsîl Rasrâ. On the left bank of the Chhotî Sarjû, 12 miles west of Bâliyâ, is a place of some antiquity and, like most of the villages in Lakhnêsar, has traditions relating to men of enormous strength and great sanctity in by-gone times. There is a temple to the celebrated Amarasimha, a deified hero of the Sengar tribe, who is worshipped under the designation of Nâtha Bâbâ.
 - 17. Nărâyanpûr, small village în pargaņa Doâba of tahsîl Bâliyâ, 24 miles east of head-quarters, îs situated about a mile to the north-east of Gaṅgâpûr and about the same distance off from the river. It is said that there was originally another village of the same name, situated somewhere on the old bank of the Ganges to the south of the former, but was washed away by an encroachment of the river a few years ago. There is also said to have been the ruins of an ancient temple here. Mr. Carlleyle² proposes to identify this site with the temple of Nârâyaṇa Dêva, visited by Hiuen Tsiang.³

IIb.

III.

¹ Journal, Asiatic Society of Rengal, Vol. XLII, page 296.

² Cunningham, Archaeological Reports, Vol. XXII, page 77.

³ Beal, Lc., Vol. II, page 64.

IIb.

III.

III.

Hb.

III. There is a mound of ruins at the village of Lakshmîpûr, which is an old site, about three and-a-half miles to the north-west of Gangapûr and Nârâyanpûr.

18. Rasrà, tahsil, lat. 25°-51′ N., long. 83°-53′ E., 21 miles north-west of Bâliyâ, possesses five large masonry masjids and 15 smaller ones, but all of no architectural or antiquarian interest. Adjoining the town is a large tank with several flights of steps not all completed, surrounded by a large umbrageous grove, the remains of primeval forest. At one side of the tank are some scores of earthen tombs quaintly dotted with red patches, the memorials of the self-immolation of widows (sati) committed here.

19. Sikandarpûr, town in pargaṇa Sikandarpûr East of tahsîl Bânsdîh, lat. 26°-2' N., long. 84°-5' E., 24 miles north of Bâliyâ. Its foundation is ascribed to an officer of Sikandar Lodi towards the end of the 15th century. The importance of the town in former times is attested not only by local tradition, but by the existence of ruins covering a large area. These ruins extend almost continuously to the village of Kharid on the Ghagra, and it may be inferred that at one time the suburbs of Sikandarpûr extended as far as the river. The site of a large fort is recognisable by scattered bricks and portions of the walls and gates still standing. There is a tradition regarding this fort to the effect that the first attempts to build it were unsuccessful. At length, by the advice of a local saint, two young girls were immured: one a Brâhmaoî near the western, and the other a Dusâdhîn near the eastern gate. A temple kept by a Brahmana, who receives the offerings of devotees. now marks the spot where the Brahmani was immured; but the place where her humbler sister suffered is known merely by a stone that is now and again reverently marked with sindur. This tradition points to Sikandar Lodi's well-known character as a fierce persecutor of Hindus.

 Turtîpâr, village în pargana Sikandarpûr West of tahsîl Rasrâ, on the right bank of the Ghâgrâ, 36 miles north-west from Bâliyâ.

III. Close to the north-west of Turtîpâr lies Khâirâ Dîh,¹ or Khâirâgarh, the ruined site of a very ancient city named Bhârgavapura. The fortified portion of the ancient city, enclosed by broken ramparts and ruined walls, measures 1,600 feet from north to south by 1,500 feet from east to west. The present village of Khâirâ is situated on the eastern rampart. Signs of ancient inhabitation, however, extend for some distance to the south and south-east, in the direction of Turtîpâr.

Khâîrâ Dîh is said to have been the residence of Rishi Jamadagni and the birth-place of his son, Paraŝurâma, the fabled destroyer of the Kshatriyas. It is said that Paraŝurâma, on leaving Khâîrâ, went to Sôhanâg, an ancient place in the Gôrakhpûr district, and there performed tapasyâ. Large numbers of coins, mostly of the Indo-Skythian period, are annually found at Khâirâ Dîh. The bricks found in the ruins are very large, and measure 2'×1' 6"×5".

About six miles to the west of Khâirâ Dih, in tahsîl Sagrî of the Azamgarh district, there is a large lake, called Raktôê, where it is said that Sahasrabâhu was killed by Parasurâma; and it is fabled that the blood which flowed from Sahasrabâhu formed a lake, and was therefore called Raktôê.

^{*} Cunningham, Archaeological Reports, Vol. XVI, page 131; Vol. XXII, page 107.

- 21. Wainā, village in tahsîl Bâliyâ, four miles west of head-quarters, contains extensive ruins, said to be those of a fort built by Râjâ Bhûbala Dêva of Haldî in the middle of last century; but they are more probably the remains of an ante-Hindû period, when the Cherûs ruled over the Ghâgrâ-Gangetic delta.
- 22. Zîrâbasrî, village in tahsil Bâliyâ, on the right bank of the Katehâr river, four miles west of head-quarters, possesses a large brick mound which is believed to be the débris of a Cherû fortress, founded by a chief, named Zîrâ.

III.—BANARAS DISTRICT.1

- 1. Baburî, large village in pargana Majhwâr of tahsîl Chandaulî, lat. 25°-10′ N., long. 83°-14′ E., 13 miles south-east from Banâras, possesses a brick fort said to have been built by Bhopat Sâh, some 400 years ago. The derivation of Baburî is crudely stated to be Babuesvara, a hypothetical name of Siva, a shrine of whom under this name is supposed to have been situated in the jangal where the bâzâr now stands.
 - 2. BAIRÂNT,² or Vairânta, village in pargana Bâra of tahsîl Chandaulî, 16 miles south-east of Banâras, is a very extensive ancient site, situated on the south bank of the Bân Gangâ, an ancient bed of the Ganges. The people claim it to be the ancient Vairâța where the Pândavas hid themselves during the last year of their enforced banishment.
- The old site of Bairant consists of a very ancient ruined fort on the eastern edge III. of the Ban Ganga, and of a former ancient town which is a high ground running from the fort for a long distance southwards along the bank of the old river. The old fort is of earth-work, but contains many ancient broken bricks. It is nearly a parallelogram measuring about 1,350 feet in length from north to south by about 900 feet from west to east. Its sides consist of ramparts from 70 to 100 feet in thickness, parts of which are still pretty high, while in some places they have been cut through by fluvial water channels. On the north-eastern, north-western, and south-eastern corners there are the remains of high earth-work bastions. The sites of ancient gateways can still be distinguished in the four sides of the fort, but especially in the northern and southern sides. More than a third of the southern part of the interior of the fort is low; the ground then rises northwards for about one-third more, and the northern part of the interior of the fort is still higher. Close inside of the north-eastern bastion there is the site of some large building. About the middle of the southern part of the interior of the fort, there is a small conical mound of ruins with a stone lingam on the top of it; there is another stone lingam on the summit of the middle of the western rampart. The old exterior ditch ne fort is quite plainly discernible on the northern and southern sides.

About 380 feet to the north of the fort, the present village of Bairant is situated; and there is an additional hamlet to the south-west of it, and only 270 feet from the fort. There is a long mound 150 feet to the north-east of the village.

Two thousand and fifty feet to the north of the village there is an old embanked tank, called Bhaktîn-kâ-Talâo, with a small temple on the west side of it.

Three hundred and twenty feet to the north of the tank there is a small mound of

¹ North Western Provinces Gazetteer, Vol. XIV, Part I, pages 119-170, passim.

³ Cunningham, Archwological Reports, Vol. XXII, pages 108-118,

III.

III.

IIb. ruins, and about 630 feet to the west of the tank, there is a temple called Râmśâla: about a quarter of a mile to the north of the Râmśâla lies the village of Râmgarh.

There is some high ground containing fragments of brick and pottery, about 650 feet to the north-east of the village Bairant. About 230 feet to the south-east of the village, there is a large statue of Hanuman, on a platform under a tree.

Two hundred and seventy feet to the south-west from the south-western corner of the ancient fort, and at the very edge of the old river, there is a small conical mound of ruins called Dêvî-kâ-sthân. About 450 feet to the south of the fort, there are the remains of a high ancient rampart, running east and west, like a long narrow ridge, for about 1,400 feet.

Close to the south of that, and on the high bank of the Bân Gangâ, but divided from the long rampart by a deep cut, there is a large rectangular-shaped mound, measuring about 800 feet from north to south by about 600 feet from east to west. The whole of the surrounding ground is full of fragments of ancient brick and pottery. The whole of this extent of ground, on the high eastern bank of the Bân Gangâ, thus far southwards from the fort, has evidently been the site of an ancient city; and fragments of old bricks, but principally of old pottery, are constantly being turned up by the plough.

The whole length of the site of the ancient city, independent of the fort, and counting from the fort southwards, is about 7,700 feet, or a little less than 1½ mile; but if we include the fort also, the total length of the entire ancient city is nearly two miles. The breadth of the site of the ancient town, from east to west, towards its northern end, appears to be about 2,000 feet, while towards its southern end it decreases to about 1,400 feet and 1,000 feet, and at its extreme southern termination to only about 800 feet.

From the preponderance of ancient punch-marked and Buddhist inscribed coins, found in these mounds, it is evident that Bairant must be a very old place. A Buddhist railing, numerous beads of agate, cornelian, onyx, and rock-crystal, fragments of copper vessels, worked flakes of black chert, stone hatchets, and ancient bricks inscribed in early Gupta characters were excavated by Mr. Carlleyle in these ruins.

- 3. Balûâ Sarâî, village in pargaṇa Mahwârî of tahsîl Chandaulî, on the right bank of the Ganges, 14 miles north-east of Banâras, is also called Paśchima-vâhinî, because the Ganges here commences to flow from east to west, whence the place has a peculiar sanctity. It is stated that Vâlmîki, the author of the Râmâyaṇa, resided here.
- 4. Banâras, lat. 25°-18′ N., long. 83°-3′ E., head-quarters of the district and division, is situated on the left bank of the Ganges, between the Barņâ Nadî, or Varaņâ on the east, and the Asî Nâlâ on the south-west. The points of junction of both streams with the Ganges are considered particularly holy, and accordingly temples have been erected both at Barñâ Sângam below the city and at Asî Sângam above the city. From the joint names of these two streams, which bound the city to the north and south, the Brâhmaṇas derive Vârâṇasî, one of the ancient names of Banâras. But the more usual derivation amongst the common people is from Râjâ

ш.

 Πb .

Sherring, The Sucred City of the Hindes, 1868, pages 1—363, passin; Beal, Lc., Vol. I, page LXVII; Vol. II, pages 44—61; Cunningham, Archeological Reports, Vol. XIX, page 60.

Banar, who is said to have re-built the city some 800 years ago. Another ancient name of Banâras is Kâsî, or Kâsikâ; and up to the present day devout Hindûs speak of coming to end their days in Kasi, for the sake of kasivah; i.e., the benefit presumed to be derived from dying in the holy city and the efficacy of funeral rites therein performed. The Hindûs believe that by the mere act of dying in Kâśî a man obtains eternal salvation, because Mahâdêva himself reads the târakam brahma to the dying man, a favour which no other place can claim.

At least since 120 years before our era, Vârâṇasî, as denoting a city, has been a name familiar to Brâhmanical literature. Convertible in later usage with Vârânasî is the designation Kasi or Kasi. Whence it arose, history has long forgotten; but conjecture may, possibly, unravel its etymology. Among the descendants of Âyus was Kāśa, whose son is noticed under the patronyms of Kāśeya, Kāśiya and Kāśi.1 The regal successors of Kāśi, and equally their subjects, were called Kāśis, Kāsvas, and Kāsikas. The term Kāsi, denominating, if not a city, a people and its chieftains, occurs repeatedly in Sanskrit works of all but the highest antiquity. Of Kasi, in whatever sense of the word, we cannot, however, collect from indigenous records materials from which to construct anything approaching history. The kingdom of the Kâsis and its rulers, as is evidenced by the frequency of reference to them, enjoyed from distant ages more or less of notoriety; and this is substantially all that the Hindû memorials teach us.

The Puranas specify but one dynasty of Kasi kings, beginning in the most authoritative of those works with the son of Kasa. To Kasa by a lapse of perhaps two centuries succeeded Divodâsa, in whose reign Buddhism seems to have been still acting on the aggressive. In this synchronism there is no discernible improbability, and with some likelihood it embodies an historical fact. A reflection of actual events may likewise be afforded in the story of the burning of Varanasi by the discus of Vishņu.2 Of the age of Ajātašatru as of other very early leaders of the Kāšis, none but most vague indications have as yet been discovered. At the time of the Musalman conquest Banaras and the surrounding country appertained to the throne of Kanauj.

Flagrant as is the exaggerating of the Hindus, it is surpassed by that of the Buddhists. The Devadatta who figures so largely in their sacred writings as king of Banaras very likely was not a myth; but there is no ground for crediting that Sakya Muni ever governed that city at all, notwithstanding that they represent him to have reigned there during 19 several states of existence. In a similar spirit they assert that at the same capital ruled in turn 84 thousand monarchs descended from Asoka.3 From these specimens it is manifest that the Buddhist scriptures are little to be trusted for throwing light on the history of Banaras.

Some relevant details, scant but interesting as far as they go, are derivable from the itinerary of Hiuen Tsiang, the Buddhist pilgrim from China, who visited India in the first half of the seventh century. At that date, he informs us,4 the kingdom of Varanasi had a circuit of about 4,000 li, or eight hundred miles, while its capital measured about 18 or 19 li in length and five or six li in breadth, or nearly four miles

Wilson, Vishnupurdna, Vol. IV, pages 30—32; Bhāgavatapurāņa, XVII, 4; Harīvania, 11, 1734.
 Vishnupurāņa, Book V, chapter 34.
 Jaurnal, Asiati: Society of Bengal, Vol. VII, page 927.
 Beal, Le., Vol. II, pages 44—46.

by somewhat more than one. The inhabitants of the kingdom were for the most part Hindûs; they were mostly worshippers of Siva (Mahêsvara), and among them were two classes of ascetics, viz., Nirgranthas and Pasupatas. Their temples amounted to a hundred with about 10,000 sectaries. The Buddhists, who are stated to have been much in the minority, kept up about 30 sangharamas, tenanted by 3,000 priests, all of the Sammatiya school. In the capital were 20 Hindû temples, the towers and halls of which were of sculptured stone and carved wood, and a copper statue of Siva, somewhat less than 100 feet in height. We are not apprised whether there were any sacred edifices of the pilgrim fellow-religionists in the capital itself; and the obvious inference is that there were none, or none worth commemorating. On the monasteries, stúpas, and lakes of the immediate neighbourhood at Sarnath, hallowed by Buddhist associations, Hiuen Tsiang dwells at great length.

That in very early days Banâras attained to prominent fame is a conclusion scarcely indicated by documentary evidence. And so it was during the period of the Buddhists. It was but natural for their founder in the course of his mission to take thought of the centres of population, and the spots which he and his disciples signalized by their teachings were reverently regarded in after-ages as consecrated grounds. These spots were, however, in the neighbourhood of cities,—as Buddha Gayâ, Mathurâ, Ayodhyâ, and Banâras—rather than in the cities themselves, and it was not till after Buddhism had passed its prime on Indian soil that these towns acquired the special repute which now attaches to them. As for Banâras, the attribution to it of peculiar sanctity seems to date from the period of the Purâṇas, and some of these compositions may unquestionably claim a very respectable antiquity.

To the early Arab and Persian travellers Gangetic India was an unexplored tract. Albirûnî, who wrote about A.D. 1030, had, however, heard of the holy fame of Banâras which he compares not inaptly to Makkâ. Mahmûd of Ghaznî is said, on doubtful warrant, to have advanced as far as Banâras and to have made a few converts there during his ninth incursion. In 1194 Shahâb-ad-dîn, after defeating Jayachchhan ar of Kanauj, marched on Banâras, where he is reported to have demolished near a thousand Hindû temples. The subsequent history of the place for many centuries is well nigh a blank. Its religious character was not in the eyes of its Islâmite masters a thing to recommend it, and commercial or political importance it had none. Even Akbar, with all his toleration of Hindûism and occasional partiality to it, did nothing to prop the sinking fortunes of Banâras. Its decline was uninterrupted, and under Aurangzîb, who changed its name to Muhammadâbâd, it reached at last the depth of its ignominy. At the command of that harsh bigot its principal temples were laid in ruins, and masjids constructed from their materials reared on their half-destroyed foundations.

The observatory built by Manasimha, Raja of Ambheri, about A.D. 1600, is the only noteworthy Hindû edifice of the city still entire. For nearly all that is striking in its architectural embellishment, Banaras is beholden to the Marathas, and to the zeal and enterprise of the same energetic race the resuscitation, in the decline of Hindûism, of much of its former influence is in large measure indebted.

Ib.

³ Sachau, Alberáni's India, Vol. II, pages 146 and 147.

The oldest monuments Banaras possesses are the remains of edifices of the Buddhist period; but we must not imagine that in any instance they are existing in their original integrity. On the contrary, they have been appropriated by Hindus and Musalmans, and principally by the latter, for their own purposes, and therefore they have become blended with other buildings from which they must be disintegrated. The use of numerous pillars in the cloisters of Buddhist monasteries, which were mostly on a uniform pattern, greatly aids the identification of the remains of this ancient period. A careful examination will reveal those portions of the city which contain buildings, or parts of buildings, or sculptured stones, or other objects of undeniable antiquity. Such ancient remains are for the most part only to be found in the northern division of the city and among the narrow streets on its eastern border running parallel with the Ganges.

Ha.

IIb.

In mahalla Alipar, in the north-west corner of the city, there are some undoubted Buddhist remains on the edge of a tank known as Bakariyâ Kund,1 measuring 550 feet in length by 275 feet in breadth. On the northern side of the tank there is a high mound, on the top of which lie several blocks of cut stone, broken statues, kalasas or topstones, nine feet in diameter, and many other remains. On the western bank there is a massive breastwork formed by large stones, bearing various masons' marks and names written in Gupta characters, some of which are similar to those inscribed on the stones at Sarnath, and sustaining a solid terrace which runs by the side of the kund to a great distance. This terrace is 20 feet above the tank and supports two others of smaller dimensions, one above the other, each of which is girded by a breastwork of huge stones. The lower terrace is 130 feet broad and 270 feet long on its western face, and 330 feet on its eastern face, overlooking the tank. It was originally held up by the wall of heavy stones just alluded to, but this wall is in many places much broken down, especially towards the kund, the great blocks lying in disorder at its ancient base. Nevertheless, extensive portions are still standing. On the terrace there is an old edifice, now occupied by Musalmans, one portion being partitioned off and used as a zanana. The beams and slabs constituting the roof are in some cases nine feet in length, and the roof is supported by three rows of thick stone columns, the capitals of which are cruciform. The cornice decorating the walls is 12 inches deep and is ornamented with carvings of various elegant designs. The outer wall on the western side is strengthened by a huge buttress of stone, 14 feet wide and 15 feet high. With pillars, breastwork, and buttress of such prodigious strength, it seems not improbable that formerly there were several storeys above this lower one. Moreover, it is not unlikely that other structures once existed along the border of the terrace throughout a considerable portion of its extent, not only on its western side, but also on its northern and eastern sides.

Directly in front of this ancient building are two other extensive elevations of the ground or terraces, one over the other. The lower elevation is 86 feet long by 62½ feet broad, and about four feet in height. The upper is 48½ feet by 24 feet, and is crowned with an ornamental cornice which runs in an unbroken band throughout a large portion of the circuit of the terrace. The breastworks of the two terraces by which the enclosed soil is sustained, although they have been evidently at times

¹ Journal, Asiatic Society of Bengal, Vol. XXXIV, pages 1-13; Vol. XLII, pages 163 and 164.

extensively repaired, nevertheless appear as ancient as the neighbouring building. Beyond the two upper terraces is another raised terrace which in all likelihood was originally connected with one of them, but is now isolated from them. On this probably stood a Buddhist shrine, connected by a cloister with a building on the main terrace. A short distance further on, are the foundations of probably another; but the traces of this are almost obliterated.

On the eastern side of the *kund* is a mound, 220 feet long by 90 feet broad, running parallel with it, which might be taken for a mud embankment thrown up from the tank, were it not for the circumstance that layers of large Buddhist bricks, lying in situ, crop out from its side, and that upon its summit and slopes are numerous blocks of sculptured stones, symbols of by-gone glory.

III.

To the east of the mound is a small round structure, called Jogi-bir, on the site of which, it is said, a devotee buried himself alive. It is made of earth, on the top is a hollow circular stone, the exterior surface of which is divided into sixteen equal sections, each of which exhibits the sculpture of a man, with one leg turned up and the hands apparently grasping a garland which encinctures and connects together all the figures.

To the south of the tank is a ghât, the stones of which are scattered about in great disorder, so that looking at it from a distance, it has the appearance of an utter ruin. Judging from the elaborate and finished carvings on many of these stones, it is evident that they have been contributions from fallen edifices in the neighbourhood.

At the south-west corner of the tank is a water-course, depressed considerably below the ground on either side. To the south of this water-course, overhanging the kund, is a huge breastwork of stone, on the top of which is a spacious court-yard and the dargâh of Fakhr-ad-dîn Alawî. By reason of the carved stones used in the foundations, the underlying mortar, and the evident frequent repairs, it is difficult to say whether any portion of this breastwork or of the buttress jutting out at its base, is really ancient, although some portions seem to be so. The buttress is continuous with the stone ghât, and merges into it.

 Πb .

IIb.

To the east of the dargah is a small masjid, 37 feet long by 191 feet broad, open to the east, and supported by three rows of pillars, five in each row. The pillars in the second row have deep scroll carvings on their sides, with ornamented corners, consisting of lotus seed-pods, one on another. Each pillar is seven feet nine inches high, including the capital, and the latter is two feet six inches in length and two feet four inches in width. The capitals of the outer pillars are somewhat larger than those of the inner, and are cruciform, the extremities being rounded off; while the upper surface of each limb exhibits a convex curve, the line of which rises higher in proportion as it recedes from the extremity. The architrave is about a foot in thickness, and on it rests the flat stone roof. Seven niches are placed at intervals round the three walls of the room. The entire building is of stone. The western wall on its outer side is strengthened by a buttress, at the base of which runs a beautifully carved band, 11 feet broad, which projects a couple of inches from the wall; and below it is a cornice, 10 inches in width and seven in depth, bearing on its front a broad band of elegant carving. While the building itself can hardly be regarded as original, there can be no doubt of the antiquity of the pillars, which belonged

probably to some Buddhist cloister. On one of the stone roof-beams of the masjid there is engraved a Persian inscription of the time of Firûz Shâh, which records that Ziâ Ahmad built or appropriated the masjid, with the dome over the vestibule, or outer entrance porch, the reception chamber (a small chamber subordinate to the masjid), the steps of the reservoir or tank, and the encircling wall of the dargâh of Saïd Fahkr-ad-dîn, in A.H. 777, or A.D. 1375. The inscription affords a fresh example of the Musalmân policy of appropriating Hindû temples, for which Banâras offered an unusually ample field.

A few steps off is an enclosure in the form of an irregular parallelogram, a wall being on either side and two small buildings at its extremities. That situated on the northern extremity is in some respects like the masjid just described. Its carvings, however, are not at all similar, and its ornamented band is of a very ancient type. There is a small building, used as a Rauza, attached to its north-west angle and sustained by ancient pillars and modern walls. The building is surmounted by a low cupola of primitive construction. It is not unlikely that originally there were cloisters on this bank of the kund, and that the three small buildings just described were all at one time connected together. The edifice at the southern extremity of the enclosure wall exemplifies the old Hindû and Buddhist method of making a roof by the imposition of stone beams, one upon another, cross-wise and corner-wise, until they meet in the middle. A second object of interest here is a cut stone screen which serves the purpose of a window.

Nearly 150 feet to the east of the last mentioned buildings is another, which has evidently been erected from old materials. It has four pillars, two outer and two inner, exclusive of others embedded in the walls, and has five recesses on its three sides. The carvings have been to some extent obliterated by the whitewash with

which the masjid is besmeared.

IIb.

IIb.

IIb.

IIb.

Ib.

Still further eastwards, at a distance of 75 feet, is a terrace walled round by a stone breastwork, 48 feet long by 36 feet broad, on which stand four profusely carved columns supporting an ancient roof, the remains probably of a chaitya, or of its innermost shrine. The columns are seven feet seven inches in height including the base, and are elaborately ornamented. The four sides of the base display an elegant carving of a vase with flowers drooping low over the brim. The well-known representation of a face with a floriated scroll streaming forth from the mouth, eyes, and moustache is repeated four times on each column, and above it runs a band of beads, each of which is nearly an inch in diameter. An arc of the sun's disc rests upon this band, and higher up the column becomes octagonal. It then becomes quadrilateral again, and on each side is a chaste design, exceedingly well executed, of an overflowing vase. The pillar is crowned with a capital, beneath which is a broad double moulding. The cornice above the architrave is also beautifully cut; but the ceiling of this shrine, consisting of overlapping stones, is its most striking feature. Each stone is richly carved and was originally coloured, while representations of suns and lotuses are depicted upon them in bold relief. Taking it altogether, this little remnant of antiquity is as a work of art a striking proof of the delicacy in taste and expertness in chiselling of the architects of those times, and also of the degeneracy of their successors.

¹ Thomas, Puthan Kings of Delhi, page 286; Proceedings, Asiatic Society of Bengal, for 1874, page 104.

16.

This chaitya seems to have been the eastern extremity of the range of ancient buildings under notice. Leaving it, the boundary line took a southerly direction, and probably included several buildings of the same character as those on the northern side, but only very faint traces of their foundations are at most visible. The boundary line, however, on the southern side, takes in a remarkable structure, consisting of a massive stone breastwork, 130 feet long, 90 feet wide, and five feet four inches high, sustaining a terrace now used as a Musalman cemetery. The breastwork is in some places in decay, yet to a great extent it is in good condition. Its stones, especially where exposed in the foundations, have masons' marks upon them, and some as many as three symbols in a row. It is surmounted by a cornice, six inches deep. Ascending the terrace, no buildings besides Musalman tombs are visible; but it is probable that an extensive Buddhist edifice stood on this spacious area. On the

gregated for religious purposes. An inspection of the Atala and Jami Masjids at Jaunpûr, formerly Buddhist monasteries, confirms this view.

western side, exactly in the centre, is a projecting buttress, originally the simhâsanam, or throne of Buddha, round which the moulding also runs. On this spot may have stood a gigantic figure of Buddha, visible to every one entering the court. Indeed the large terraces may all have been cloistered courts where disciples and devotees con-

The most remarkable of these ruins, however, is a Buddhist temple, 550 feet distant from the chaitya, mentioned above. The Musalmans have appropriated this edifice as a mausoleum, and capped it with a dome. It stands on 42 pillars, all of which are in good order, with the exception of one in the southern portico, which has been twisted by the falling of a large tree upon it. Formerly there were evidently two pillars more than there are at present, upholding the heavy entablature of the southern portico, so that the whole number of pillars was originally 44. Of these, 32 supported the temple proper and four the roof of each of the northern, southern, and eastern porticos. To the west there is no portico, but simply a sort of projecting buttress or simhasanam on which probably the chief image stood, and was, therefore, at once seen by persons coming in through the main entrance to the east. The northern and southern porticos are 15 feet long by 10 feet wide, while the eastern is only 12 feet by 10 feet. The inner part of the temple is 18 feet square. Round the whole of the exterior of the temple, above the capitals of the columns and supported by their external limb, runs an eavestone nearly three feet in width, and, as at the Atala and Jami Masjids at Jaunpur, this eavestone has been made to imitate wood. Each column is eight and-a-quarter feet in height, of which the quadrilateral shaft between the capital and the plinth is four and-a-half feet. The capital is in the form of a cross, each limb consisting of two portions, the lower bellshaped with an ornament in the corners. The columns in the temple proper stand two or four together, and the abacus or square stone upon them, between the capital and architrave, is 13 inches deep and beautifully carved. The architrave has a rich double band sculptured upon it, which passes all around the temple including the porticos. Above this is a flat stone and above the stone a row of niches, which are probably of Musalman origin.

Viewing the temple from outside, a practised eye soon distinguishes between the ancient portion and that added by the Musalmans. Above the portico, all below the octagonal breastwork, is evidently of Bauddha workmanship, and the remainder of Musalmân; but the Musalmâns, there is reason to suppose, availed themselves of old materials. At the termination of the breastwork at each corner rests a small kalasa, about two-thirds of the circular disc of which is exposed, the remainder being inserted in the wall. Although so many ages have elapsed since this temple was erected, and although it has been exposed alternately to the ruthlessness of Hindâ and Musalmân fanaticism, yet with such singular skill have its proportions been designed and its blocks of stone been joined together, though without cement of any kind, that at the present moment it seems almost, if not quite, as durable as on the day on which it was finished. The simplicity, combined with the great strength, of its parts and the symmetrical arrangement of the whole give to the building, not-withstanding the general scantiness of its ornamentation, an appearance which the most fastidious must pronounce to be of no mean order of beauty. A small cloister was originally connected with the south-west corner of the temple, as is shown by the continuation of the ancient basement moulding; some of its walls are still visible.

Ia.

The remains of a Buddhist Vihara are to be found in the interior of the Fort at Rajghat, in the outskirts of the city on its northern boundary. The Fort is a small tongue of high land, about 50 feet above the plain below, extending to the junction of the Ganges and Barna. According to the tradition of the people, this elevated tract was first fortified by Raja Banar, who had his chief residence there. A short distance to the right of the main road leading into the Fort may be seen the remains of the Buddhist Vihara, which next to the Buddhist temple at Bakariya kund are the most complete, and certainly are the most beautiful, of any ancient remains yet discovered in Banaras. They consist of two cloisters in a continuous line, each being sustained by a quadrangle colonnade, but differing both in height and length. The smaller cloister is 66 feet long and the larger 84 feet, and therefore the entire façade is 150 feet in length, whilst the breadth of both is uniform, and is 25 feet. There are eight columns in each row in the one room, or 32 in all, and in the other there are 10 in each row, or 40 in all, so that the number of stone pillars standing in the entire building is 72. Those in the smaller cloister are barely nine feet high and are all square and of a uniform pattern, a slight difference only being traceable in the capitals which are of the old cruciform shape. There is not much ornamentation on these pillars, but the chess-board and serrated patterns are abundantly carved upon the architraves. The pillars in the larger cloister, including the capital and base, are 10 feet in height, but the architraves above the capitals are of the same height as those in the smaller cloister, namely one foot. These pillars differ greatly both in shape and ornamentation from those in the smaller cloister. Some of them are covered with profuse carving cut deeply into the stone, which in many instances is so sharp and well-defined as to give the appearance of having been recently executed. The lotus plant-pod, leaf, blossom, and stem-forms a conspicuous object in many of the designs, all of which are striking, but some are exquisitely chaste and elegant. The sacred goose is represented in various attitudes on the noble scroll-work extending along the square sides of several shafts from the base to the capitals. These scroll bas-reliefs equal the carvings on the Sanchi

¹ Journal, Asiatic Society of Bengal, Vol. XXXV, pages 59-87.

pillars in richness, whilst the designs are much more free in their conception. The pillars are regularly arranged with regard to the *simhāsanam*, and the finest pillars are in the centre of the cloister, in the direction of its depth; and above them, near the inner wall, the stone ceiling in two divisions of the roof is singularly carved, being covered with lotus blossoms carved in relief.

There is not the smallest doubt that these cloisters have been much altered from their original condition, and that principally by the Musalmans who transformed them into a masjid by placing two mihrabs and a mimbar, constructed out of a sinhasanam, within the Vihara. The two mihrabs are inscribed with appropriate verses from the Quran. On closely examining the columns, architraves, and ceilings, it is plain that not only has there been a good deal of shifting of places, but new pillars carved in recent times have been added to the old, and some of the old have been cut up for repairs, and their separated portions have been scattered amongst several pillars and joined on to them. The inner massive stone wall running along the entire length of the building is evidently unconnected with the original structure, as is also the present stone floor which is a foot and upwards higher than the old. A trench having been dug on the east side, it was discovered that the bases of many of the columns were embedded deep below the modern stone pavement, while in front of the smaller cloister, at a depth of about a foot, the outer moulding of the ancient floor could be traced continuously from one end to the other. Notwithstanding all these extensive alterations which the building has undergone from time to time at the hands of Hindus and Musalmans, we cannot but think that many of the columns are standing on their proper sites, and that the edifice, although greatly changed, is still in its main features a Buddhist structure.

There is reason to believe that a third cloister, corresponding to the smaller, formerly existed at the southern extremity of the larger cloister. And this supposition is greatly strengthened by the circumstance of a sinhâsanam being still standing by the wall in the centre of the latter, but altered from its original form, having been used as a mimbâr. This mimbâr as well as the two mihrâbs are of an exceedingly hard dark porphyry, in some places having the peculiar characteristics of jade. The vihâra, when complete, was in all likelihood a square, each side being at least the length of these three cloisters, and the principal statue of Buddha was exactly opposite the centre of the square.

A few hundred yards north from the old gateway leading into the Råjghåt Fort is a mound of circumscribed extent, now used as a Musalmân burial-ground, on the summit of which are the remains of an old Buddhist chaitya. They consist of four pillars, richly carved with scroll-work, sustaining an ancient roof. At the corners of the shafts is the ordinary ornamentation resembling a chain of lotus seed-pods. The capitals are cruciform and the bases are square with embellished faces. The ceiling is very beautifully sculptured, and is composed of slabs overlapping one another with the centre stone crowning the whole, according to the primitive mode of Indian roof-building. This latter stone exhibits the outspread petals of a lotus blossom, while eight out of the 12 triangular spaces formed by the intersection of the slabs are freely carved with the scroll-pattern.

In mahallâ Badâon near the Râjghât Fort, a short distance south of the high road, there is a small masjid in an enclosure, made up to a great extent of ancient

Ib.

IIb. remains. The building seems to have been curtailed from its original dimensions, leaving a ruined portion still standing on its southern side. This entire structure contains 17 stone pillars, eight of which exhibit ornamental carvings, and probably belonged to a Buddhist chaitya.

IIb.

Ib.

Ha.

Hb.

From the Barna near its confluence, is running an ancient mound or ridge into mahalla Ådhampûr, which was, no doubt, the old boundary of the city in the early period of its history. The ridge is in one part formed of three terraces, the uppermost being 30 feet above the land, upon which elevated spot is the dargâh of Mîra Sâhib. On the south side of the ridge, in sight of Mîra Sâhib's tomb, is an Imâmbara, a modern edifice, and a few paces distant from it are two small structures, one in front of the other, which are partly composed of old materials. Each building possesses four ancient pillars, and lying about in various places are four pillars more, five kalasas, two architraves, and seven bases, one of the latter being richly carved. All these are the spoils of some ancient temple.

The Buddhist ruins at Tiliya Nala, now forming part of a deserted masjid. are immediately above the Nala on the high ground of its left bank, a very short distance only from the point where it runs into the Ganges, and close to the main street under which the stream flows. The ruins not only overhang the brook, but there is no doubt that at one time they must have extended nearly, if not entirely. across its present bed. They consist of 17 massive square columns in three rows, namely four double columns in the front row, four single ones in the second, and five in the third or innermost row. Between the third and fourth pillars of the last row is a simhasanam, an immense slab of stone, nine feet three inches in length and five anda-half feet in breadth, retreating beyond the boundary wall behind, into which all the pillars of this row are inserted. There can be no doubt that the simhisanam was in the centre of the building, so that as there are three pillars to the right of it, there were as many to the left, in each of the three rows, the front row being of double pillars throughout. Re-constructing the edifice as it originally stood, therefore, there were one row of six double pillars, and two rows of six single pillars, or 24 pillars in all. Each capital is ornamented with the bell pendant, of which the Buddhists were so passionately fond. The double columns are surmounted by one huge capital, five and-a-half feet in breadth, each of which possesses a long arm for eavestone. Over the two inner rows are two domes, one of which is above the simhasanam, and is more ornamented than the other. There must have been originally a third dome to the left of the central dome, corresponding to that on the right. Outside the building there is a fine basement moulding, which doubtless belonged to the primitive structure. Estimating the building as it once stood, it was fully 54 feet in length and about 24 feet in breadth. The Musalmans may have altered it considerably in transforming it into a masjid; but we apprehend that not a little of the old temple still remains.

Makhdûm Sâhib is a square enclosure in mahallâ Gulzâr, near to Tiliyâ Nâlâ, used by the Musalmâns as a cemetery. On its northern and western sides are cloistered pillars with portions of ancient stone eaves overhanging their capitals, presenting on their upper surface imitations of wood carving. There are 25 pillars on the western, and 32 on the northern, side. Several of the pillars are carved; while some of the capitals are ornamented, some are double. There are also hand-somely-carved stone brackets for the support of the eaves. The eastern wall bound-

ing the enclosure is composed to some extent of cut stones of an ancient date. The entire court is 100 feet long from east to west and 60 feet broad from north to south,

At the junction of the old Ghazipar road with the Rajghat road, to the north of the latter and about a mile from the Fort, is a large square tank on the left bank of IIb. which, as on a terrace, stands a lat, which gives the name of Lat Bhairava to the spot. It is now only a few feet high, and is covered with copper sheeting. The IIb. original stone column, of which the concealed pillar is doubtless a small fragment, was about 40 feet high, and, it is said, was covered with ancient carvings which were most probably inscriptions. It was thrown down by the Musalmans during a terrible conflict with the Hindûs in the early part of the present century. The pillar once stood in the courtyard of a temple which was destroyed by Aurangzib, and on its site a masjid was erected, the courtyard of which enclosed the pillar. On examining the terrace where the lat stands, it is exceedingly manifest that the upper portion has been thrown up in modern times, and that the ancient level was some six or eight feet lower than what it now is, and indeed was even with the soil of the Musalman cemetery close by, in the midst of which are a few Buddhist remains in the shape of pillars and architraves made up into a dargâh. What this so-called temple was, admits of very little question, inasmuch as the boundary walls of the terrace and of the neighbouring cemetery and garden exhibit a considerable variety of isolated carved remains, sufficient to afford abundant attestation to the supposition that formerly a large Buddhist structure stood on this site, covering the whole extent of the ground elevated above the tank on its northern side.

Below the upper terrace on which the *lât* stands, is a Musalmân cemetery with a Hauza in the middle. This building rests upon 16 pillars, each being eight feet two inches in height, and the architraves between their capitals being one foot two inches in thickness. In addition, there are five pillars in the verandah to the south. Some of the pillars are ornamented with scroll-work and the lotus plant, while their four corners are deeply cut with representations of the lotus seed-pod. One pillar is eight-sided in its lowest division and sixteen-sided in its upper, and has also a band of four grinning faces connected together, and under them a row of beaded garlands. The pillar is covered with a round stone projecting two inches, on the face of which is a curious assemblage of 32 grotesque faces all round the edge of the stone, with beaded garlands and tassels depending, issuing from their mouths.

About a third of a mile to the east of the Bakariyâ kuṇḍ remains is a beautiful IIb. little structure, called battîs khambhâ, or "thirty-two pillars." It is a very picturesque object, and consists of a dome sustained by 24 square pillars standing in pairs at intervals all round. Formerly each corner had four pillars, thus increasing the present number by eight; but two from each corner have been removed, leaving the spaces occupied by them empty. All the upper part of the building is Musalmân, while all the lower part is indisputably Buddhist in its style of architecture. On the western side is an abutment for the simhâsanam. The pillars stand upon a platform raised above the ground, and in the interior of the building is a Musalmân tomb.

IIb. Between this dargâh and Bakarîyâ kuṇḍ is a small building standing by the road side, in which are several pillars of the ancient type inserted into the containing walls. The building has an unpretending appearance.

IIb. The Arhai Kangara Masjid, a handsome structure and one of the finest masjids in the whole city, is situated in the mahalla bearing its own name. Its magnificent and lofty dome, as well as various parts of the masjid itself, unquestionably exhibit a Musalman style of architecture; but by far the greater portion of the building, and certainly five-sixths of its materials, belong to an epoch far more distant than the Musalman invasion. The numerous square columns with their cruciform capitals, and also the screens between some of them in the upper storey, are of Buddhist workmanship; but it is evident that both Buddhists and Hindûs have made use of the same materials in different eras, and that in fact the masjid is a mixture of three styles, namely Bauddha, Hindû, and Musalman. The first edifice was most probably a vihâra with one or more temples attached. Certain leading characteristics of the first structure are perpetuated by the Hindûs in the matha which they raised on the expulsion of the Buddhists from Banaras. In the roof of the second storey of the masjid a slab was discovered, bearing a long Sanskrit inscription, dated Sanvat 1248, or A.D. 1190, recording the erection of certain tanks, temples, and mathas in and

III. Near the temple of Vriddhakâla, one of the very few Hindû temples of the earlier Musalmân period still standing in Banâras, and not appropriated by the III. Musalmâns, and a few paces from the well-known shrine of Ratnêsvara, is a masjid known as Âlamgîrî Masjid, which was erected in A.H. 1077, during the III. reign of Aurangzîb or Âlamgîr. The masjid is built, as tradition states, from the materials of the Hindû temple of Kîrttî Vîsvêsvara, and has three rows of lofty stone pillars, eight in each row; the pillars at both extremities are not single, but threefold. The capitals are large and massive, and cruciform in shape. In the centre of each shaft, upon all the four sides, is the boss ornamentation, each boss being fully a foot in diameter.

about Banaras.

Attached to the masjid is a corridor, built in A.H. 1096, as stated in a Persian inscription on the inner wall.

The long Chaukhambha street in the city of Banaras takes the name from

The masjid and corridor adjoining it are supported by 24 pillars, of which six are double. The capitals are of the simple cruciform pattern, and their outer limbs are decorated with the dwarf bell ornamentation. To the south of the building is a staircase leading up to the roof, built of heavy stones. Most of the pillars are in situ, and originally formed part of a Buddhist structure.

 Πb . The masjid built by Aurangzib on the foundations of what is commonly regarded, though erroneously, as the old or original Visvêsvara temple, is of interest not for its own sake-for notwithstanding its lofty appearance, it is a structure without any striking beauty-but for the sake of the ancient buildings with which it is associated, and with the materials of which it has been largely constructed. The courtyard consists of a terrace raised some five feet above the level of the temple quadrangle, in the centre of which it is situated, and occupying a large portion of the area. On walking round the quadrangle and examining the retaining wall of the terrace, one's attention is arrested by peculiar openings or niches in the wall, in which architraves, capitals, and parts of pillars on which they rest are visible. Proceeding from west to east, the ground gradually declines, until after descending four steps and arriving opposite a large stone bull or Nandi, the opening in the terrace becomes clear, and a cloister, such as surrounds a Buddhist Vihâra, comes into view and reveals the character of the entire series. It consists of a number of small chambers, supported by genuine Buddhist pillars, simple in their type and without doubt of great antiquity. Formerly a succession of such cloisters encompassed not less than three sides of the existing terrace, which consequently dates from the same epoch.

The series of cloisters formed the lowermost storey of a large Buddhist monastery which once enclosed the entire space occupied by the terrace, and rose to the height of probably two or three storeys above it. On the southern side stood the chief chaitya which, on the suppression of Buddhism, passed into the hands of the Hindûs, who transformed it according to their own tastes. The masjid on this side is altogether composed of the remains of an ancient temple of large dimensions and of very elaborate workmanship. The high pillars, moreover, on its northern face have been abstracted from the same spacious building. These remains are partly Hindû, and it is unquestionable that the edifice, which was destroyed in order to make way for the masjid, was an old temple of Viśvéśvara. Thus, the masjid with its terrace exhibits a singular architectural anomaly, and presents us with no less than three styles, namely, Bauddha, Hindû, and Musalmân.

Aldi-Visvêsvara¹ is the name of a lofty temple situated a short distance from Aurangzib's masjid; it is held to be the original or most ancient temple of this deity. The derivation of its name only bears out this supposition, for the temple itself, from the pinnacle to the base, has nothing really ancient about it. On the eastern side of the enclosure the ground takes a sudden rise of 18 feet, forming a terrace manifestly of artificial construction. On this side there is a retaining wall of stone masonry which is wanting on the southern side of the terrace, where there is only an earthen bank. The other two sides of the terrace are covered with buildings which prevent the exact ascertainment of its boundary in these directions. On that flank which is 11b. contiguous to the Adi-Višvėšvara enclosure stands a masjid erected some hundred years ago; it was built of stones found on the spot. The terrace existed before, with the buttress, and is evidently of ancient construction.

The building is in two divisions, each of which is 23½ feet in length, connected together by a massive wall 5½ feet thick, composed of large blocks of stone. This

A temple of this name is mentioned in an invertible, dated Samvat 1353, engraved on a pillar in the north-west cloister of the Lal Darwaza Masjid at Jaunpur, see Archeological Survey Reports (New Series), Vol. I. page 51.

wall projects considerably beyond the building into the courtyard to the east, and has the appearance of a huge buttress. Possibly the buttress is pierced with a staircase that led formerly to an upper storey which the buttress supported, and the Musalman architects, not caring to remove the massive prop, have retained it in the masjid. They appear, moreover, to have confined themselves chiefly to materials lying upon the spot, as in three places carved pillars, similar to those sustaining the centre aisle, have been adopted as architraves. There are 14 columns in the interior of the masjid which are peculiarly but not extensively carved, and are crowned with ornamented capitals. The western wall is strengthened externally by three rounded buttresses of the Pathan style; they did not exist in the Buddhist period, and were added as much for ornament as for strength.

There is no doubt that the Âdi-Viśvêśvara temple stood on this site, and was destroyed by the Musalmâns who, as usual, transferred its stones to their own masjid. The modern temple bearing this name the Hindûs built, with the connivance of the Musalmâns, for the purpose of perpetuating the worship of the old image of Âdi-Viśvêśvara. Yet, while allowing that the edifice standing on the site of the present masjid when the Musalmâns took possession of it, was the temple of Âdi-Viśvêśvara, it is equally certain that the primitive building was a Buddhist monastery, but later in date by several hundred years than the Vihâra erected on the opposite terrace. It was probably a quadrangle encompassing the four sides of the terrace. Nothing remains of it except the massive transverse wall, with the buttress and the lower portion of the retaining wall. The amount of stone material expended on the present comparatively small building is exorbitantly great, and furnishes a proof that an edifice of much larger dimensions formerly stood here.

Between the city of Banâras and the Buddhist remains at 8 å r n å t h there is a tank, called 8 o n å - k å - ta l å o, "or golden tank," 300 feet by 140 feet, situated on the opposite side of the Baraâ, near the Pañchkosî road. The tank is approached by a strong and well-built ghât, on which are several Buddhist figures. In the midst of it is a round pillar, 18 feet high and upwards of nine in circumference, composed of great blocks of stone cut in quadrants and put together without mortar. The pillar bears neither an inscription nor masons' marks.

The lands lying on the bank of the Ganges to the north-east of the Barnâ are strewn with brick and stone débris for about five miles. In many places the rubbish lies thick upon the ground, choking up the soil, and to a large extent the deposit can be traced continuously. Here and there small bits of sculptured stone are visible, and occasionally, where the broken bricks and stones are in very great abundance, they have been collected into ridges or small mounds. This is especially manifest at the termination of the deposit at a spot called Patharâ-kâ Siwân, where in ancient times doubtless stood a large fort, of which the foundations may even now be partially traced. Although the fields beyond this point seem to be clear of rubbish, yet further on, at Muskâbâd, at a distance of a mile, it re-commences and becomes as thick as in any other place. Perhaps this latter was the site of an outlying town.

These remains lie immediately on the banks of the Ganges, and never extend from it more than three quarters of a mile. It is very evident that all the way from the mouth of the Barna this bank has been, in the lapse of centuries, considerably cut

ш.

Ib.

III.

IIb.

away; indeed, as much as a quarter of a mile may have fallen into the river. In all probability, therefore, the space covered by débris was much broader than it is at present. There can be no question, however, that here a great city once stood. Judging from the great scantiness of ancient structural remains in the present city of Banaras, dating from even the Buddhist period, not to speak of the pre-Buddhist epoch when, as we know from historical records, Banaras was in existence, the original city of the pre-Buddhist and early Buddhist epochs for the most part must have occupied this site. Beyond the northern extremity of the remains of the earlier city is a series of mounds, also covered with debris, tending in a north-westerly direction, where formerly forts or fortified towns existed. It is not unlikely that in a far distant age the connexion of the primitive city of Banâras with Sârnâth was along the course of these mounds. Sârnâth is spoken of, in the Ceylon records, as though it may have been a city of itself; and there is no doubt that it is referred to, in ancient documents, as a part of Banâras. Now, modern Banâras is nearly half a mile to the south of the Barna, whereas Sarnath is out in the country, about three miles to the north of that stream. If we suppose, however, that Banaras in its most remote period was mainly on the north side of the Barna, and if such supposition is corroborated by extensive remains of ancient buildings in the shape of brick and stone débris stretching over several miles of country and terminating in mounds lying in the direction of Sarnath, the proof approaches to demonstration that at that early epoch a union, more or less intimate, existed between Sârnâth and Banâras, as stated by historical records.

If these observations respecting the site of the early city be correct, it must follow that the derivation of the word Vârâṇasî, as the city "lying between the Barṇâ and the Asî," is utterly absurd as applied to the most ancient city. That it may be taken to explain the word as denoting the city of modern times, even as far back as the Gupta period and perhaps somewhat further, is historically unobjectionable. It seems indeed probable that the Buddhists were the first people to occupy to any extent the southern side of the Barṇâ, and such a notion is remarkably substantiated by the existence of various Buddhist remains there, as described above; but none of them date from earlier than the Gupta period. The Pañchkôsi road, or sacred boundary of modern Banâras, regarded by Hindûs as of immense antiquity, is no older than the city which it encompasses, and must also be assigned to a comparatively recent date.

Besides the ancient Buddhist remains mentioned above, Banâras boasts of 1,454 Hindû temples and 272 masjids and dargâhs.

Of the Hindû temples only one has remained unchanged since the mediæval Brâhmaṇical period, namely, the temple of Vṛiddhakâla on the northern side of the city. It formerly possessed 12 separate courts, but now only seven are in existence, and several of these are fast falling into ruins. The site of the other five courts and of the gardens once attached to the temple is occupied by dwelling-houses. When this shrine was in its glory, it must have been a place of some magnificence. The legends connected with this temple ascribe to it a hoary antiquity, and attribute to it the power of healing diseases and prolonging life. The actual date of its erection is unknown, but it belongs evidently to the 13th or 14th century.

The smallness and insignificance, from an architectural point of view, of most of the existing Hindû shrines is the result of the destruction of all important Hindû fanes by Aurangzîb, and of the difficulties put in the way of devout Hindûs who wished to erect temples to their deities during the reign of Musalmân rulers. It was when the power of Musalmân rule in India was beginning to wane that the present shrines were built, or re-built from old materials. All of these lay claim to be erected on spots famed for some deed of one of the numerous deities of the Hindû pantheon.

- IIb. Besides the temples, many ghâts and wells are accredited with great sanctity, and there are also several sacred tanks to which pilgrims flock to bathe. The legends connected with these relate to incidents said to have happened many centuries ago; but none of the ghâts are very old, the destructive action of the Ganges being constantly at work, so that no ghât lasts for more than a few generations at most.
- The Naga Kûpa, or "Serpents' well," situated in the Nag Kûan mahalla, 16. in the north-western part of the city, bears marks of considerable antiquity, and must be regarded as one of the oldest historical places the present city possesses. Steep stone stairs in the form of a square lead down to the well, and a broad wall of good masonry, seven feet thick, surrounds them at their summit, rising to a height of five feet above the ground. Each of the four series of stairs has an entrance of its own. Their junction below forms a small square, in the centre of which is the well. Descending 12 stone steps, the water is reached, which is stagnant and foul. Beneath the water is a sheet of iron which constitutes the door leading to a still lower well, which may be the old well in its original state. The stairs are apparently of no great date. On the inside of those to the east is a Sanskrit inscription to the effect that in Samvat 1825 the well was extensively repaired. Many of the slabs of stone of which the stairs are composed display carvings on their external surface, some of which bear unmistakable marks of considerable antiquity. These slabs were doubtless taken from dilapidated buildings in the neighbourhood.
- IIb. The Manikarnikâ Kund, or Chakrapushkarini Tîrtha, a tank of great antiquity, was repaired by Narenu, a dependant of King Vâsudêva, in Samvat 1680, according to a Sanskrit inscription. The flight of steps was repaired by Nârâyanadâsa Gupta for the service of Sivâ in the same year.
- IIb. The Pańchagańgâ Ghât was consecrated by Raghunâtha of the Țandana family in Samvat 1637, as stated in a Sanskrit inscription on the mathi, or domed temple, of Sheśâi close by.
- IIb. The Draupadi Kund at Sivapura, a village three miles from the city of Banâras, was built by Govindadâsa under orders of Todaramalla, the famous minister of Akbar, in Samvat 1646, according to a Sanskrit inscription. This document is of some importance, as it records the name of the family of Ţodaramalla-Ţandana, which had hitherto been doubtful.

Two copperplate grants of Govindachandra Dêva² of Kanauj, issued at Banâras in Samvat 1181 and 1185 respectively, are of considerable historical value.

¹ Proceedings, Asiatic Society of Bengal, for 1875, pages 82-84.

¹ Journal, Asiatic Society of Bengal, Vol. LVI, pages 113-123.

IIb.

- Of the masjids and dargâhs, the most important ones have already been menIIb. tioned. The tomb of Lâl Khân, erected in A.H. 1182, as stated in a Persian
 inscription over the entrance door, near the western gate of the Râjghât Fort, is a
 good specimen of decorated Moslîm architecture. It occupies the centre of an
 extensive quadrangle, which is ornamented with four towers, one at each corner.
 The tomb itself consists of a massive tower, rising high above the rest, and is crowned
 with a dome, from the middle of which a spire emerges. A large portion of its outer
 surface is still bright with the colours, chiefly blue, with which it was originally
 embellished. Within the building are three tombs, and on the platform outside are
 four more.
- Baragaon, village in pargana Kôl Aslâ of tahsîl Banaras, 12 miles northwest of head-quarters, possesses a ruined brick fort, built by Kripâ Nath Simha in A.D. 1737.
- 6. Basnî, village în pargana Kôl Aslâ of tahsîl Banâras, 12 miles north-west of head-quarters, possesses a ruined fort, seven Hindû temples, and four masjids, of no architectural or archæological value.
 - Chandauli, tahsil, lat. 25°-15′ N., long. 83°-19′ E., 20 miles east-south-east of Banaras, possesses the ruins of a brick fort.
- Banaras, possesses the ruins of a brick fort.
 8. Chandrauti (Chandravati), old village in pargana Katehar of tahsil
 Banaras, 14 miles north-east from head-quarters, possesses the remains of a fine massive brick fort, erected by Domana Dêva Râjâ on the left bank of the Ganges some
 300 years ago, three plain Jain temples of no great age, and one masjid.
 - Dândupûr, village în pargana Pandrahâ of tahsîl Banâras, 16 miles westnorth-west of head-quarters, contains two masjids of no great merit.
- 10. Dumri, village in pargana Râlhûpûr of tahsîl Chandauli, four miles east IIb. of Banâras, possesses a masjid, a sati temple, and a spacious dharmsâlâ, built in the beginning of this century.
- 11. Jalhurur, village in tahsîl Banâras, 10 miles north-east of head-quarters, contains the remains of an old Rajpût fort and two Hindû temples.
- 12. Katthî, village in pargaņa Katehâr of tahsîl Banâras, 16 miles north-east of Hib. head-quarters, contains several Hindû temples, said to be about 200 years old.
- 13. Moghal Sarai, or Moghal Chauk, village in pargana Dhûs of tahsîl III. Chandaulî, 10 miles east-south-east of Banaras, possesses a ruined brick fort, built by Abdhût Simh, a servant of Balwant Simh.
- 14. Naubatpür, village in pargaņa Narwân of tahsil Chandauli, 26 miles eastsouth-east of Banâras, possesses a Hindû temple and a masonry sarâi, built by Biśrâm Sinh, a tahsildâr of Bâlwant Sinh.
- III. Near the present site is a kherâ covered with débris, which evidences the existence of some pretentious building there formerly. Tradition says that one Nabî Khân, the âmil of the Dehlî Emperor, used to reside there, and that the place which then extended from the hill to the present bâzâr was called after him Nabînagar.
 Ib. On the top of the mound is a fine masonry well.
- PINDRÂH, village in pargana Kôl Aslâ of tahsîl Banâras, 14 miles north west of head-quarters, is commanded by a massive brick fort, the residence in the

¹ Cunningham, Archaeological Reports, Vol. XXII, page 105.

middle of last century of Thâkur Kripâ Nâth Simh and Thâkur Bariâr Simh, father of Rânî Gulâb Kunwâr, the wife of Bâlwant Simh.

III. Half a mile from Pindrah is the small village of Asla. A ruined palace and the traditions held by the inhabitants show that this now insignificant village was once a place of importance, having been the residence of a deputy of the Dehli

- Emperor in the time of Shah Jahan. Near the ruined palace is a grave said to be that of Mir Muhammad, the local Governor. There is a Persian inscription, dated
- Ib. A.H. 1039, carved on a loose slab, measuring 36 by 24 inches, which is called tilak bir, i.e., a thing to take an oath on. The inscribed stone is held in high reverence by the inhabitants of the neighbourhood. The inscription is simply an evidence of the insecurity of private property even so late as Shâh Jahân's reign. It threatens the destroyer of the building it is designed to protect with such punishment, if a Musalmân, as would be the due of one who killed a pig in a masjid, and if a Hindû, of one who killed a cow in Jagannâth's temple.
- 16. Râmnagar, large town in pargaṇa Râlhûpûr of tahsîl Chandaulî, is situated on the right bank of the Ganges, four miles south-east of Banâras. In A.D. 1750 IIb. Bâlwant Simh selected it for his residence, and built a massive brick fort, ever since the palace of his descendants. The structure rises loftily on the banks of the IIb. Ganges, and is the picture of a feudal castle. It encloses a temple dedicated to Vyâsa. Bâlwant Simh's successor, Chait Simh, embellished the town, and amongst IIb. the monuments of his taste remaining are a most lovely tank and a richly-adorned temple at a garden residence just beyond the bâzâr.
 - 17. Sakaldîhâ, town in pargaņa Barhaul of tahsil Chandauli, 20 miles east of Banâras, possesses the ruins a brick fort, built in the middle of last century by Achchhail Simh, two masjids and four Hindû temples.
 - Near the present site of Sakaldihâ is a kherâ which represents the ancient Suklapura.

Two miles off at Chaturbhujpûr is the Sakaldíhâ station of the East Indian Railway, near which is a temple of Kolésvara Nâtha, built by Achchhail Simh.

18. Sårnåth,¹ the site of the great Buddhist establishment described both by Fa Hian² and Hiuen Tsiang,³ lies three and-a-half miles to the north of the city of Banåras. The name, though usually applied to the great Buddhist tower of which the real name is D h a mek, properly belongs to a small Bråhmanical temple situated on the west bank of the Sårañg Tâl. Sårnåth is generally explained to mean "great lord," a title applied to Mahådeva, but General Cunningham interprets it to be an abbreviation of Sårañganâtha, or the "lord of the deer." This title, while it would be applicable to Siva, would also be singularly appropriate for Buddha, who in a former existence is fabled to have roamed the woods (mrigadâva) in this very spot as the king of a herd of deer.

Of the ruins found at Sarnath some date from the sixth or seventh century of our era, while others belong to a period several centuries before. The remains

Hb.

III.

IIb.

III.

IIb.

¹ Journal, Asiatic Society of Bengul, Vol. IV, page 712, seqq.; Vol. XXIII, page 469, seqq.; Proceedings, Asiatic Society of Bengul, for 1878, page 66; Cunningham, Archeological Reports, Vol. I, pages 103—130; Sherring, The Sacred City of the Hindris, pages 230—270.

^{*} Beal. Le., Vol. I., pages LXVII and LXVIII.

Beal, I.c., Vol. II, pages 44-58.

Ia.

Ia. consist of two large towers, one of stone (Dhamek) and the other of brick (Chaukandi), separated from one another by a distance of half a mile. Between

III. them lies an extensive mound consisting of brick and stone ruins of other buildings.

The extent of this mound is half a mile by a quarter of a mile, and its surface is strewn with broken bricks and here and there a mutilated statue. On the east of the

IIb. mound lies the Narokâr, or Sârang Tâl, 3,000 feet long by 1,000 feet broad; it communicates on the north-east with the Chandokâr or Chandra Tâl, a tank of much the same size, which in turn communicates to the north with a long narrow sheet of water, half a mile in length, called Nayâ Tâl. The surroundings of the ruins are the village of Barâhî, the ancient Vajravarâhî, on the north-east, IIb. Gurônpûr on the west, and a fine wood lying between the brick tower, Chau-

Gurônpûr on the west, and a fine wood lying between the brick tower, Chaukandi, and the great stone tower, Dhamek, which no doubt is the site of the ancient Mrigadâva, or "Deer Park." To the south-west of the great tower of Dhamek

IIb. the Jains have erected a modern temple of Pârsvanâtha.

The name Dhamek is derived by General Cunningham from Dharmopadesaka, or "preacher of the law," and the stûpa to which it is applied is described by him as a round solid tower, 93 feet in diameter at the base and 110 feet in height above the surrounding ruins, but 128 feet above the general level of the country. The foundation or basement, which is made of very large bricks, has a depth of 28 feet below the level of the ruins, but it is sunk only 10 feet below the surface of the country. The lower part of the tower, to a height of 43 feet, is built entirely of stone from one of the Chunar quarries, and with the exception of the upper five courses, the whole of this part of the building is a solid mass of stone, and each stone, even in the very heart of the mass, is secured to its neighbours by iron cramps. The upper part of the tower is built entirely of large bricks, and General Cunningham considers that it was originally plastered over and not encased in stone. The lower part of the monument has eight projecting faces, each 21 feet six inches in width, with intervals of 15 feet between them. In each of the faces, at a height of 24 feet above the ground, there is a semi-circular headed niche, five and-a-half feet in width and the same in height. In each niche there is a pedestal; but the statues which are conjectured by General Cunningham to have been life-size figures of Buddha, the Teacher, are all wanting. Around the niches seven of the faces are more or less richly decorated with a profusion of flower foliage. The carving on some of the faces has been completed, on others it is little more than half finished, while the southern face is altogether plain. About nine feet below the niches there is a triple band of ornament which encircles the entire building. The central band, which is the broadest, is formed entirely of various geometrical figures, the main lines being deeply cut and the intervening spaces being filled with various ornaments; the upper band, which is the narrowest, is a scroll of the lotus plant with leaves and buds only, while the lower band, which is also a lotus scroll, contains the full blown flowers as well as the buds. On the south-south-west side of it occur the only forms of animal life that are depicted; these consist of a human figure seated on a lotus flower and holding two branches of the lotus in his hands, of several pairs of the chakua, or Brahmani goose, seated in different positions among the lotus plants, and of a frog. The attitudes of the birds are all good, and even that of the human figure is easy, although

formal. The lotus scroll with its flowing lines of graceful stalk, mingled with tender buds and full-blown flowers and delicate leaves, is very rich and very beautiful. Below the ornamental borders are three plain projecting bands.

The shape of the structure, which is a tall, round tower surrounded by a dome, seems to indicate that it belongs to the latest period of Buddhist architecture.

About 140 yards to the west of the tower Dhamek is an excavated chamber, in which a large number of images and other relics have been found. The chamber is circular and about 12 feet below the level of the ground. Its diameter is 57 feet four inches at three feet above the ground, and it is enclosed by a wall 161 feet thick, built of bricks. The lower portion of the wall appears to be older than the upper part, and is built in a more solid and lasting way. The excavations carried on at this ruin have been too often made with a view of despoiling it rather than of assisting antiquarian research. This was notably the case with those made by Bâbâ Jagat Simh, the diwan of Raja Chait Simh of Banaras, in 1794. The materials taken from the ruin were carted away in order to build Jagatganj. His workmen found in this chamber 27 feet below the surface two boxes of stone and marble, one inside the other; the inner vessel, according to Duncan's account,1 contained a few human bones, some decayed pearls, gold leaves, and other jewels of no value. The second box, which in 1794 was again committed to the ground, was re-discovered in 1835 by General Cunningham through the agency of one of the workmen who had been employed in 1794. At the time that these relic boxes were discovered in 1794, a statue of Buddha, bearing an inscription2 dated Samvat 1083, was found. The statue was recovered in a mutilated state by Major Kittoe in Jagatganj; the inscription, however, was intact. It records that Mahipâla, Râjâ of Gaudâ,3 caused to be erected in Kasi hundreds of lamp-pillars (isanam) and ornamental bells (chitraghanta), and that Sthirapala and his younger brother, Vasantapala, raised this tower with an inner chamber and eight large niches. General Cunningham is of opinion that the original relic stûpa became ruinous, and was repaired by the brothers Sthirapâla and Vasantapâla in A.D. 1026.

Due south from the great tower of Dhamek, and at a distance of 2,500 feet, there is a lofty ruined mound of solid brickwork, surmounted by an octagonal building. The mound, called Chaukandî, or Lorî-ki-kûdan, is 74 feet in height to the floor of the octagonal building, which rises 23 feet eight inches higher, making a total height of 97 feet eight inches. An inscription over one of the doorways of the building records that it was built in the reign of Humâyûn as a memorial of the Emperor's ascent of the mound. Examination of it has shown that the building was not a relic tower, and it is conjectured by General Cunningham that it is the ruin of a stûpa described by Hiuen Tsiang as lying to the south-west of the monastery and rising to no less than 300 feet in height.⁴

Excavations made at different times by General Cunningham, Major Kittoe, and Mr. E. Thomas⁵ have established the fact that the walls and foundations lying on the

Ia.

Ib.

¹ Asiatic Researches, Vol. V, page 131.

^{*} Asiatic Researches, Vol. IX, page 204; Journal, Asiatic Society of Bengal, Vol. IV, pages 211, seqq.

^{*} The country to the north of the Ghaghra, the present district of Gonda,

⁴ Beal, Le., Vol. II, page 51.

^{*} Journal, Asiatic Society of Bengal, Vol. XXIII, pages 469, seqq.

III.

TIb.

III.

III.

Hb. III.

mound between the towers Dhamek and Chaukandi are all that remains of what was once a large monastery. The investigations go further to prove that this monastery III. was built on the remains of a still earlier building. A great number of sculptured images and bas-reliefs, some of which are inscribed in characters of the fifth and sixth centuries, have been found among these ruins, representing in many instances Buddha turning the wheel of the law (the preacher). Another interesting relic is the chaitya, a small vessel of baked clay, flat below, and ending in a blunt point above. When the bottom is removed, a clay seal containing a confession of the Buddhist creed, written mostly in characters of the sixth century, is discovered.

There are numerous signs to show that this monastery (samgharama) must have been destroyed by fire when the Buddhists were expelled from India in the 11th century. The heaps of ashes found among the ruins, the concealed images, the uncooked food, and the melted remains of the cooking-vessels of the monks, are all speaking evidence of the theory that the monastery was fired by the persecuting followers of another creed, and that its destruction was not the work of an accident. The existence of so many sacred buildings at Sârnâth, a considerable number of them built between the visit of Fa Hian, A.D. 400, and of Hiuen Tsiang two centuries later, testifies to the fact that Buddhism, though sensibly on the decline at the latter period, still retained a considerable amount of innate vigour. The fact that the sacred buildings at Sârnâth were largely added to in this interval may be evidence of an expiring effort on the part of Buddhism to regain the position from which it had been slowly, but surely, receding.

19. Saîdrājā, or Kalyāņ pûr, village in pargaņa Narwân of tahsîl Chandaulî, 24 miles east-south-east of Banaras, was founded some 400 years ago by Said Raja Ahmad of Karrâ. He made it over to Kalyân Tiwârî, whence the name Kalyânpûr. The massiveness of the ruins scattered about the place show that some imposing buildings formerly existed here. Said Raja Ahmad's dargah is still preserved, and is the object of some veneration; there also remain a masonry sarái and a well built by him. There was till lately an inscription on the well, but it has now crumbled away.

Connected with Said Raja is the village of Sivapûr, which is also called Baijnathganj and Harnathpûr. It was founded 140 years ago by Baijnath Simh of Karauna, a courtier of Raja Balwant Simh, who built a fort and bazar which he called Baijnathganj. The bazar passed into the hands of Harnath and Siva Simh, who both sought to perpetuate their names to it, whence the names Harnathpur and Sivapûr. The latter built a second fort.

20. Tari, village in pargana Pandraha of tahsil Banaras, 14 miles north-east of head-quarters, is said to be named after Târêsvara, or Târakêsvara, whose shrine is supposed to have existed there from time immemorial. It contains a few Hindû temples, amongst them that of Tarakêsvara (Siva), three masjids, an imambara and a fort, built by Qâzî Zahûr Muhammad, the âmil of the Dehlî Emperor, in the middle of last century.

IV.-BASTÎ DISTRICT.1

1. Aмоrнà, village in tahsîl Harâiyâ, 23 miles south-west of Bastî, possesses the remains of a long winding canal, extending to Rupnagar, eight miles in length 1 North-Western Provinces Gazetteer, Vol. VI, pages 731-797, passim. III.

by 30 yards in width, and bearing marks of high antiquity. Along its banks are several kheras, the ruins of ancient brick buildings, in one of which a life-size statue of Buddha was found some years ago. Nothing is known as to the history of these ruined III. mounds. The villagers, as a rule, ascribe them to the forest tribe of Tharûs; but this ascription is evidently incorrect, and due to the fact that when the ancestors of the present inhabitants immigrated, they found the country, so far as it was peopled at all, in the possession of the Tharûs. The immigrants knew nothing of an earlier and vanished civilization, and naturally ascribed all ruins to the people whom they found in occupation of the country.

In the south-west of the Basti district the Rajpat and other mediæval settlers displaced Bhars. In parts of Gorakhpûr and Basti the Pôms or Pôm Kaţţars were the ruling tribe, which had to give way before the immigrants from the west. Consequently in some places ruined mounds will be ascribed to Bhârs and Dôms instead of Thârûs; but nowhere is there any trace of genuine continuous tradition handed down from the times of Buddhist ascendancy and civilization. So far as appears, the Gôrakhpûr and Basti districts lapsed into jangal during the disturbances which accompanied the extinction of Buddhism, and remained for centuries unoccupied by settled or civilized inhabitants.

The thread of tradition was thus broken, and nothing can be learned of the past history of the country except from coins and such other fragments of antiquity as may have survived.

- 2. Bakhirâ Dîh, deserted ancient site in pargaṇa Maghar of tahsîl Khalîlâbâd, 28 miles east-north-east of Basti, is situated to the south-east of the great lake, called Bakhirâ Tâl. The lake itself is said to have been the site of an ancient city, which was destroyed and overwhelmed on account of its wickedness. The ancient name of the lake is said to have been Lakshmisarovara, or Lakshmisara. It has also been called the Badani Tal.
- 3. Banst, tahsil, 32 miles north-north-east of Basti, possesses on the right bank of the Râptî the remains of a large brick fort, perched on a high kherâ, in the south-east corner of the town; a Hindû temple and a masjid of no great age. III. 11b.
 - 4. Baran Chuetra² (Varâhakshetra), deserted ancient site in pargaṇa Basti West of tahsil Harâiyâ, eight miles north-north-west of head-quarters, is situated in the retreating angle of an extraordinary bend of the Kûanî river. It is evidently the site of an ancient city which had pleasure-gardens and tanks surrounding it; but all that remains of the traces of that city now are fragments of broken bricks and bits of old pottery, scattered here and there. The greatest monument of the ancient city is the banking-in of the Kûânî river like a canal opposite to its

The Brahmanas claim this to be the real place where the Varaha Avatara of Vishņu was manifested. According to the Purāṇas it occurred at a place called Vyaghrapuri, which is no doubt identical with the Vyaghrapura or Kôlî, of the Buddhist chronicles, where there was the residence of Raja Suprabuddha, the father of Mâyâ Dêvî, the mother of Śākyamuni.

IIb.

¹ Cunningham, Archaelogical Reports, Vol. XXII, page 71.

^{*} Cunningham; Archæviogical Reports, Vol. XII, pages 211-215.

Hb.

Ш.

Ha.

IIb.

Ш.

III.

III.

IIb. The kund and temple of the Varâha Avatâra are situated at the inner southern angle of the bend of the river, and at the south-eastern angle of the embankment. On the top of the bank on the north side of the kund there are the traces of the foundations of some ancient building composed of large ancient bricks. On this there now stands a small, square, roofless, ruined shrine, which contains a small lingam.

To the south of the tank, there is a plain, modern brick temple.

Further to the southwards, there is a high, square, deserted mud fort, overgrown with jangal, which is said to have been constructed by a Râjâ of Basti, called Lâl Sâhib. Further to the westwards, there are several fine tanks, on the banks of which are three sati monuments. This spot may have been the site of a pleasure-garden in former times, which belonged to the ancient city of Vyâghrapura.

5. Basrî, tahsîl and capital of district, lat. 26°-49′ N., long. 82°-44′ E., consists chiefly of an old entrenched village whose citadel was the still existing castle (kôt) of the Râjâ. The latter stands, highly-raised and strongly-built, on the ancient mound which it adorns, covering about four acres of ground. The building has a picturesque frontage with a steep entrance-way rising to the main-gate.

About a quarter of a mile south of old Bastî, at the village of Manhan, there is a kherâ, about 200 yards in diameter, irregular in form and surface, and without any trace of ditch. Tradition says that its summit was once crowned with a lingam temple. Here was found, in 1887, a hoard of eleven gold coins of Chandragupta II.

Some three-quarters of a mile north-east of old Bastî, at the village of LakhIII. naurâ, rises another kherû of 300 yards in diameter and of no great elevation.
About 1,000 yards beyond this, in the village of Barwâ, is another ruined mound;
III. its diameter is smaller, but its elevation more considerable. On its summit stands a lingam, very much decayed. About two miles beyond this, north-east, is another ruined mound, called Arel. It is about 300 yards in diameter, but is higher than that of Lakhnaurâ. Some deep and large excavations have been made into it, probably in search of bricks.

Six miles south of Bastî, there is an old ghât at the Kûânî river, which is called Deôrâmghât (Dêvarâma); near which there is a mound of brick ruins.

6. Bhūìla Dîh, deserted ancient site in pargaṇa Basti West of tahsil Harâiyâ, 15 miles north-west of head-quarters, has been identified by Mr. Carlleyle² with Kapi-lavastu, the birth-place of Buddha, as described by Fa Hian³ and Hiuen Tsiang.⁴

The principal mound of ruins is situated on the north-western bank of the Bhûîla Tâl. On the eastern bank of the lake are situated the villages of Amâ, Râṇîpûr, and Parâs Dîh, and on its southern bank the village of Dabhâ; about half a mile to the south-south-west from the last place, there are the villages of Bâwarpâra, Bhankarî, and Parsâ, at all of which there are mounds of ruins, and at the latter the remains of a brick stûpa. About 800 feet from the western bank of the lake there is the old village of Jaitapûr; between this village and the lake there are the remains of a large brick stûpa, 70 feet in diameter and 18 feet in height, which

¹ Proceedings, Asiatic Society of Bengal, for 1887, page 221.

Conningham, Archaeological Reports, Vol. XII, pages 108-228.

³ Beal, Le., Vol. I, pages XLIX and L,

⁴ Beal, I.c., Vol. II, pages 13-25.

may perhaps mark the spot where Buddha competed in archery with the Sâkyas. About 350 feet to the north-north-west of Jaitapûr there is a deep, circular-shaped tank, about 120 feet in breadth, called the Hâthîkuṇḍ, which probably represents the hastigarta of the Buddhist traditions, where an elephant is supposed to have fallen, which Buddha is said to have thrown across the ditch of the city. About 300 feet to the north of the Hâthîkuṇḍ there is a channel which towards the eastern end is both deep and broad, but becomes narrow and shallow towards its western end. This ditch runs from a small lake, called Nâka Tâl, eastwards until it joins the Bhûîla Tâl, the distance between the two being about 1,000 feet. On the southern side of the ditch there is a conical mound, probably the remains of a stûpa. Immediately on the northern side of the ditch there are two mounds close together and united by a low and narrow ridge. To the north of the last there are two broad, flat mounds of ruins, which are probably the sites of ancient Vihâras, referred to by Hiuen Tsiang.

The great mound of ruins, which was probably the site of the citadel and palaces, is situated about 650 feet to the north of the ditch. This mound measures about 1,090 feet from north to south by about 1,020 from east to west. What Hiuen Tsiang calls the remains of a palace appears to be the remains of a fortified citadel which contained numerous buildings of various kinds and adapted to various purposes. Two nearly effaced and broken lines, one lower than and outside the other, run round the outer face of the great plateau of ruins, showing the site of ancient inner and outer lines of fortifications. There are eight depressions at the sides, showing the positions of former gateways. Mr. Carlleyle notices four mounds outside the gates corresponding with the sites of four Vihâras, each of which contained a statue of one of the four predictive signs, viz., of an old man, a diseased man, a dead man, and a **sramana*, i.e., the sights which met Sâkyamuni's gaze when he left the city on his excursion.

About 700 feet to the north of Bhûila Dih, there is a kherû about 210 feet in length by 100 feet in breadth; beyond it there is a large square tank, on the northern and eastern banks of which the ground is strewn with fragments of brick and pottery.

About 800 feet to the west-south-west of the great mound of Bhûîla there is a large shallow lake called Aghiâ Tâl, on the western bank of which are the ruins of an irregular quadrilateral-shaped brick mound.

On the north-eastern side of the Bhûîla Tâl, and exactly opposite to the great dîh of Bhûîla, there is a small brick mound, evidently the remains of a stûpa. For some distance around this the ground is high and strewn with fragments of brick and pottery, from which it is evident that this must have been the site of a portion of the ancient city.

About 2,000 feet to the north-north-west of Bhûila Dîh there is a square tank, on the northern bank of which there is a slightly elevated piece of ground, called Râghupûr Dîh. This is bounded on the north-west by a small lake; close beyond this, to the north-west, there is the large village of Mâhûâ Dâbar. To the east-north-east of this village there is a very small lake, on the north-east bank of which there is a series of ruined mounds which go by the name of Atrohâ. These mounds are divided into two portions, one of which lies to the south-western side of the ancient village of Koţwâ, and the other lies a little

III.

further to the north-west, a short distance to the west of the village of Râmpûr. A very small lake lies between these two portions of the mounds. The southernmost of these two sites consists of a raised piece of ground, about 1,300 feet in length from north to south by about 700 feet in breadth from east to west. On the southern portion of this site there are the remains of three small brick stupas, forming the figure of a nearly equilateral triangle. The second portion of the Atrohâ mounds, called Garha Dih, is situated about 270 feet to the north-west from the former across a very small lake. The area of ground covered by these ruins is about 630 feet from north to south by about 800 feet from east to west. This ruined site, with its assemblage of detached mounds, must evidently anciently have constituted the most northerly extension of the city of Kapilavastu.

There can be no doubt that the ancient city of Kapilavastu, with its attached suburbs, extended from Atrohâ Dih on the north to Bawârpâra Dih and Parsâ Dih on the south, a distance of two miles and a third, and from Aghia Dih on the west to Rânîpûr Dîh and Parâs Dîh on the east, a distance of one mile and a third.

The most distinct, striking, and imposing of the more outlying ruined sites, in the vicinity of Bhûila Dih, are the following:-

About a mile and a third to the south-east of Bhaila Tal there is an ancient mound III. of ruins, called Pindari Dih; it is only one-third less in size than the great mound of Bhuila. The most important fact connected with this site is that coins of the Mittra as well as of the Indo-Skythian dynasty are frequently found on the mound during the rains.

About four and-a-half miles to the north of Bhûila Dîh, there is a high mass of solid brick ruins, which are the remains of an ancient fortress of great strength, called Kôt; it is only about two-thirds of the size of the great mound of Bhûila. but it is much higher. The fort of Kôt is quadrangular, and measures about 740 feet from north to south by about 520 feet from east to west. There are high, massive bastions of brick at the four angles and at the four sides; the ramparts are high, broad, and solid. Close to the south of the fort outside there is a pond, and from this a ditch originally ran round the whole outer circuit of the fort on the other three sides.

To the east of the fort, the large village of Kôt is situated on a ridge of ruins which is evidently the site of an ancient town.

There is another mound of ruins and also the remains of a small stupa, at the village of Sentûâ, about a mile and three-quarters to the north-north-west of Bhûila Dîh: and another mound of ruins, called Morêr Dîh, lies about three-quarters of a mile to the north-north-east from Sentûâ, or about half way between Bhûîla and Kôţ.

At the village of Sikhiri, two and-a-half miles to the north-east of Bhûila, there is a large and important mound of ruins, the remains of a small stupa, which Mr. Carlleyle believes to be the spot where Buddha sat down to watch the labourers in the field.

At a place, called Bhata or Kosahra, a mile and-a-half to the north-west of Bhûila Dih, there is a collection of ruins, apparently of small stûpas, which, according to Mr. Carlleyle, mark the spot where a number of Sakyas were massacred, in an attack made upon Kapilavastu by Virûdhaka, Râjâ of Srâvastî, after he had dethroned his father, Prasenajita, who had been a friend of the Sakya family.

III.

Ш. III.

III.

About seven and-a-half miles to the north-west of Bhûîla Tâl, and about three-quarters of a mile to the south of the village of Bîrpûr, there is an old village, called Nagara, situated on the eastern end of a very large and pretty high mound of ruins, which is the site of an ancient city. On the southern part of this *kherâ* are the remains of a ruined brick stûpa which, according to Mr. Carlleyle, marks the spot where Krakuchchhandra, the fourth Buddha, was born. About 800 feet to the east-south-east of Nagara Dih there is a fine large brick stûpa, 56 feet in diameter at the base and 25 feet in height.

III.

III.

III.

About 14 miles to the west-north-west of Bhûila Dîh, and about eight miles to the west-south-west of Nagara Dih, there is the old village of Khemrâjpûr, whose mounds are probably the remains of a suburb of the ancient city of Kshemavati, the capital of Râjâ Kshema of Mekhala. The principal part of the ancient city was situated between the villages of Pâir and Asojpûr, a mile and-a-half to the north-east of Khemrâjpûr.

About six miles west of Bhûîla Dîh, and about four and-a-half miles south of Nagara Dîh, there is the old village of Kanakpûr, and only three quarters of a mile to the south-south-east of Kanakpûr, there is a large ancient mound of ruins, called Khopôâ Dîh, which Mr. Carlleyle identifies with Sobhâvatînagara, the birth-place of Kanakamuni Buddha.

About four and-a-half miles to the south-south-east of Bhûila Dîh there is the village of Sarkuhîyâ, with the remains of a stûpa, which marks the spot where the arrow of Buddha struck the ground, causing a clear spring of water to flow forth, commonly called Sarakûpa, or "arrow fountain."

About five miles to the east-south-east of Bhûila Dîh, there is the old village of Buddhapâra, to the west of which lies a mound of ruins, the remains of stûpas, which, according to Mr. Carlleyle, represent the spot where Buddha was born under a sûl tree in the Lumbini garden.

About 700 feet to the south of Buddhapâra Dîh lies the Bairâhwa Tâl from which issues the Gadî Nâlâ which is the upper portion of the Majhâra Nadî, a corrupted form of Mrakshavaranâ, or "the river of oil," running past the birth-place of Buddha.

About 1,500 feet to the south-west of Buddhapara Dih there is the old village of Hardiya, where there are several mounds of ruins, the remains of stupas, and an ancient kund with an old well on the edge of it, which place Mr. Carlleyle identifies with the tank in which the infant Buddha was washed by two dragons (Nagas).

About three quarters of a mile to the south-south-east of Buddhapâra Dîh, there are some conspicuous mounds of brick ruins, called Bûâ Dîh, on the eastern bank of the Bûâ Tâl. The first and most conspicuous of these is a brick stûpa, about 50 feet in diameter and eight feet in height, which, according to Mr. Carlleyle, marks the spot where Indra is said to have taken the infant Buddha in his arms.

At the distance of about 850 feet to the south of Bûâ Dîh, there is a large and extensive mound of ruins, occupied by the modern village of Kurdâ. This kherâ is probably the site of some large Buddhist monastery.

About one mile and-a-quarter to the west of Buddhapâra Dîh, and about three miles to the east of Bhûîla Dîh, there is a small mound of ruins, called Kapilî

III.

III.

III.

Dih, which Mr. Carlleyle believes to be the hermitage of Kapila Rishi, from whom the name of Kapilavastu is said to have been derived.

At the west side of the village of Barâ Dâr, on the Dochûâ Nâlâ, there is a lowish mound of ruins, which is situated at the distance of about 1,100 feet to the north-north-east of Buddhapâra Dîh.

At the west of the village of Kesarâî, about a mile and-a-quarter to the north-

III. west of Buddhapara, there is a low mound of ruins.

The village of Majhâwan is situated at the distance of 3,500 feet to the west of Buddhapara Dih. Mr. Carlleyle believes this to be a corruption of Mokshavana, "or garden of beatitude," another name of the Lumbini garden.

At the village of Piprâ, about a mile and-a-quarter to the west-south-west of Buddhapâra, there is a dih, and two ancient tanks which are said originally to have been bâoli wells.

At the village of Åîn pûr, on the south side of the Åîla Tîl, and about a mile and-a-half to the south-west of Buddhapâra, there is a large and high mound of ruins.

The village of Tilchhûan is situated on the Tilchhûan Sohî, or Gadî Nalâ, about 6,900 feet to the east-north-east of Buddhapara. This village is partly situated on a mound of ruins; and a short distance to the east of the village there is a small mound of ruins, composed of ancient bricks.

The large village of Šivapûr is situated about a mile to the north of Tilchhûân.

Close to the north side of this village there is a large mound of ruins.

After a careful inspection of all the places identified by Mr. Carlleyle, I come to the conclusion, as I have shown elsewhere, that Bhûîla Dîh cannot be the Kapilavastu of Fa Hian and Hiuen Tsiang on the following grounds:—

(1) Hiuen Tsiang states "that the country of Buddha's birth is about 4,000 li in circuit," whilst the tract of land lying between the Ghagra and the Gandaka, from Ayodhya to the confluence of these rivers, gives a circuit of 550 miles, which would represent upwards of 600 miles by road.

(2) The places excavated and identified by Mr. Carlleyle as the principal palace of Râjâ Śuddhodana, the bed-chamber of Mahâmâyâ, and the stûpa of Asita, the Rishi, are so insignificant that they cannot be the remains of the ruins mentioned

by Hiuen Tsiang.

- (3) The circular tank about 340 feet to the south of Bhûila Tâl and still called, according to Mr. Carlleyle, Hâṭhîkuṇḍ, was identified by him with the hastigarta or "fallen elephant ditch" of Hiuen Tsiang, and General Cunningham is perfectly convinced that this is the spot indicated in the Chinese text. The chaukidâr and the inhabitants of the neighbouring village Nyagrodhâ, however, state that the name of Hâthîkuṇḍ was given to the tank by Mr. Carlleyle himself, and that this name was utterly unknown in that part of the country before the arrival of Mr. Carlleyle.
- (4) Mr. Carlleyle indicates Krakuchchhandra Buddha's fabled birth-place at Nagara, seven and-a-half miles to the south-west of Kapilavastu, whilst it must be sought eight miles to the south-east of that place, as Fa Hian² visiting this place after leaving Śrâvasti, went north about eight miles, then east eight miles to Kapilavastu.

Archaelogical Reports, New Series, Vol. I, page 69.

Beal, Le., Vol. I, page XLIX.

From this it is evident that Bhûila Dih is not the ancient site of Kapilavastu. Our knowledge about the position of Kapilavastu may at present be reduced to this: that it lay on the route, from the Buddhist cities of eastern Gôrakhpûr to the Buddhist Śrâvastî, the Saheţ-Maheţ of the Goṇḍâ district, and that route probably passed between the Ghâghrâ and Râptî rivers.

7. Bhàrî, village in pargaṇa Rasûlpûr, of tahsîl Domariâganj, 28 miles northwest of Bastî, has an old tank, which is celebrated as one of Krishṇa's favourite bathing-places. Close to the tank there is a large mound of brick ruins, rising to a height of some 18 feet above the surrounding plain, apparently the débris of some temple or vihâra. Around the kherâ are several smaller tanks and the foundations of a building, extending some 400 yards from north to south and some 350 from east to west. The ancient name of this kherâ is said to have been Bharatabhârî.

IIb.

III.

III.

III.

III.

III.

III.

IIb.

Ш.

III.

At the neighbouring village of Hathisari, or Hastisanda, there is a large khera, covered with bricks and fragments of pottery.

At the village of Pauriya, there are the ruins of a temple, called Samayasthana.

8. Katahlâ, small village in pargaṇa Bânsî West of tahsîl Domariâganj, 46 miles north of Bastî, is situated on the southern bank of the Buḍhî Râptî, and possesses many small kherâs, scattered at irregular distances over a great extent of ground. The place seems to have been a town with many brick buildings and small tanks, but no traces of fortification, and to have extended more than a mile each way. On the banks of a tank are the foundations of two small stone temples, near which many fragments of dressed stone are lying.

At the deserted village of Sanauli, three miles west of Katahlâ in the forest, there is a large mud fort with a deep and wide ditch and a strong rampart, but with no considerable buildings within the walls.

The village of Sarayat, two miles to the east of Katahlâ, stands on the south side of a large brick mound. Two small modern temples, consisting of a cubical chamber surmounted by a dome, are perched on the ruins of a large stone temple, the foundations of which in some places are still a few feet high. Many fragments of pillars, ceiling stones, etc., are scattered about.

Close to the village of Mahâdêva, eight miles east of Katahlâ, are two brick mounds, apparently the ruins of temples. The top of each mound is crowned with a lingam, which evidently belonged to the old temples.

Two miles to the east of Mahadêva, at the village of Musharûa, there are the ruins of a large brick fort.

9. Khirnipûr, small village in pargana Bastî West of tahsîl Harâiyâ, five miles north-west-west of Bastî, possesses on the east bank of the Kûânî river the ruins of a brick stûpa, which, according to Mr. Carlleyle, marks the very spot where Buddha, as prince Siddhârtha, crossed the first river he met in his course, after he left Kapilavastu, in order to enter upon the life of an ascetic. This ruined stûpa is nearly three miles to the south-east of Barâh Chhetra and a little to the south-east of the Sidhâonî Ghât, which is one of the most ancient ghâts on the Kûânî river.

¹ Cunningham, Archaelogical Reports, Vol. XVIII, pages 1 and 2.

IIa.

Ha.

III.

Ш.

IIb.

IIb.

III.

About a quarter of a mile to the north of Sidhâonî Ghât, on the left bank of the Kûânî river, there is an ancient site called Chimrâwa Dîh, covered with frag-III. ments of brick and pottery, the ruins of an ancient city.

About one and-a-half mile to the east-south-east of Khirnipûr, there is a large ancient tank, called Bhainsâ Pokharâ, at the north-west corner of which there

are the ruins of a brick stupa. III.

About a quarter of a mile to the west of Bhainsa Pokhara there is a small brick temple, entirely enclosed within the roots of a huge pipal tree.

Two miles to the east of Sidhaoni Ghat there is a mound of ruins, called

Baheriya Dih. III.

About four miles to the north-east of Sidhaoni Ghat, and to the east of the village of Barawa, there are the ruins of a stone temple.

About three miles to the north-east of Sidhaoni Ghat, at the village of Laksh-

manpûr there is a mound of ruins. III.

About five miles to the north-east of Sidhâoni Ghât, there is a large ruined site,

called Kaili Dih. III.

About eight and-a-half miles east-north-east of Sidhâonî Ghât, at the village of

Hatha, there is a large mound of ruins. III.

10. Maghar, village in tahsîl Khalîlâbâd, 27 miles south-east of Bastî, is an ancient site, though its remains at present visible do not appear to be of very ancient date. It is, however, reputed to have been the seat of Buddhist hierarchs for some time after Kapilavastu was destroyed.

To the east of the town, on the right bank of the Âmî river, there is the cenotaph (rauza) of the famous reformer Kabîr Dâs, or Kabîr Shâh, erected in A.D. 1450 by Bijli Khân and restored in A.D. 1567 by Nawâb Fidâi Khân. A little further stands another shrine, dedicated to Kabîr Dâs, and frequented by Hindûs only, and a masjid; but neither is architecturally striking, neither impressively large.

In the town itself stands the tomb of Qazî Khalil-ur-Rahman, a governor of Hb. Maghar in the 17th century. Westward may be traced the remains of a castle which III. is said to have been the stronghold of the Maghar Rajas. The fortifications cover some 16 acres, and are in the usual style of a quadrangle defended by a ditch and an earthen rampart. Around the castle itself and thence through the town to Kabir's rauza may be seen several mounds covered with brick and pottery.

About two and-a-half miles to the west-south-west of Maghar there is an extensive ruined site, called the Mahasthan Dih, near the eastern bank of a lake, called the Sirsara Tal. The village of Sirsarao is situated on a mound of ruins, and at the distance of about 400 feet to the east of the village there are the remains of a brick stupa which, according to Mr. Carlleyle,2 marks the spot where Buddha cut off his hair. About 300 feet to the north-east of the Sirsarao stupa there is a massive circular mound of bricks, about 50 feet in diameter, probably the remains of the great stupa of Asoka, where Buddha parted with his servant Chandaka and his horse.3 About 370 feet to the north of this ruin there is a large round-topped mound of bricks, probably the remains of a stûpa, which marks the spot where Buddha

Conninghum, Archicological Reports, Vol. XXII. page 72.

Cunningham, Archaelegical Reports, Vol. XVIII, pages 27-31; Vol. XXII, pages 5 and 6.

Beal, Le., Vol. II, page 30.

put off his royal garments and exchanged them for those of a hunter, supposed to be Brahma. About 550 feet to the south-east of this mound there is a smaller, longish, ridge-shaped mound of solid brick, called Paithana Dih. The whole of the extensive open space lying between these mounds of ruins is covered with fragments of brick and pottery, and betokens a very extensive ruined site, which probably comprises the ruins of various vihâras, besides the stûpas mentioned.

About six miles north of Maghar, at the village of Kôpa, there is a large mound of brick ruins, about a third of a mile in diameter and very irregular in shape.

IIb. A little way to the east of the kherâ stands the modern temple of Śiva, called Kôpêśvara.

11. Манолі, the ancient Mahuliya, village in tahsil Khalilabad, near the right bank of the Katnaya, 18 miles south-east of Basti, possesses the ruins of a brick fort, built on an ancient khera, the ruins of a Buddhist vihara.

12. Nagar Khâs,¹ or Aurangâbâd Nagar, village in tahsîl Bastî, six miles south-west of head-quarters, is situated at the east end of a large lake, called Chando Tâl. Adjoining it is the comparatively modern fort of the late Râjâs. To the west of the modern village of Nagar Khâs, there is a large, long-shaped mound, about half a mile in length, covered with fragments of large bricks and ancient pottery.

About a mile to the south of Nagar Khâs, on the bank of the eastern end of the Chando Tâl, there is an isolated, circular-shaped mound, probably the remains of a stûpa.

Near the village of Pokhrâ there is a small kherâ, probably the ruins of a Buddhist vihâra. About a mile to the west of Pokhrâ there is another small mound.

The great mound near Nagar Khâs may very probably be the site of some ancient city, perhaps one of the "ten deserted towns" which are stated by Hiuen Tsiang² to have existed in the dominions of the Śâkyas.

13. Râmpûr Dhorîvâ, village in pargaṇa Mâholî West of tahsîl Bastî, 11 miles south-east of head-quarters, situated near the head of a great lake called Marawâ Tâl, has been identified by Mr. Carlleyle³ with the Râmagrâma of Fa Hian⁴ and Hiuen Tsiang.⁵

III. The village of Râmpûr is situated on a considerably large mound of ruins which is of greater extent than the present village. And at the north-west corner of the village there is a large elevated bare space of ruined mound, composed of solid bricks which was apparently occupied by some large building in ancient times, probably the Vihâra mentioned by Hiuen Tsiang as existing at Râmagrâma. There are six tanks at Râmpûr, of which four surround the village; of these five are ancient and one is said to be modern. The furthest north-eastern tank is the most ancient of all, and close to the south-west of it there is a ruined stûpa of about 20 feet perpendi-

IIa. cular height. It stands upon the ruined remains of a brick platform which projects somewhat beyond the base of the ruined stûpa. The sloping side of it is about 50 feet, and the diameter at base about 85 feet. The top of the ruined stûpa is sur-

III.

III.

¹ Cunningham, Archaelegical Reports, Vol. XII, pages 83-89.

^{*} Beal, Lc., Vol. II, page 14.

² Cunningham, Archaelogical Reports, Vol. XVIII, pages 3-10; Vol. XXII, page 2.

^{*} Beal, Le., Vol. I, page L.

^{*} Beal, Lc., Vol. II, pages 26-31.

mounted by a stone lingam which stands in the centre of the ruined foundations of a small square building. Fragments of Bauddha and Vaishnava sculptures are scattered about. There can be no doubt that this conical mound is the remains of a stupa, as the circular courses of brick are clearly visible in many places. A sloping mass of brick, about 80 feet in length, runs down from the north-east front of the stupa to the ancient tank, most probably a ghât leading from the stupa to the tank. Mr. Carlleyle believes that in this tank the Någas lived who guarded the stupa, and who assumed the form of men during the day, but resumed the shapes of Någas at night.

About 13 miles to the south of Râmpûr, the village of Koron or Korâwa,¹ is situated at the eastern end of an extensive mound of ruins, which is larger than the great dîh at Bhûîla, and which has once been the site of an ancient town (Śubha-maṇinagara), upwards of a mile in circuit. The great mound of ruins measures about 2,100 feet in length from east to west, by about 1,400 feet in breadth from north to south. There are no remains now on the Korâwa Dîh, except three ancient wells; but to the west there are two small mounds named Piprâwâ Mahâdêva and Barewâ Mahâdêva, which are the ruins of Brâhmaṇical temples. A great mass of ruins lies to the south of the Rasârhî Nâlâ, on the northern bank of the Harnâyâ Tâl, and one quarter of a mile to the east of the village of Chandûâ. These remains are known by the general name of Bithâ or "mounds," and extend for about 400 feet in length by 150 feet in breadth. The principal ruin is a mound of 10 feet in height with the remains of walls 120 feet apart, probably the remains of a temple or vihâra. Numerous carved bricks and a broken statue of Sûrya are lying about the place.

14. Tama, small village in pargaṇa Maghar East of tahsîl Khalîlâbâd, 25 miles south-east of Bastî. Close to the village there is a very large and extensive mound of ruins, on which there is a modern temple, called Tamêsvara Nâtha, which kherû has been identified by Mr. Carlleyle² as the site of the ancient town of Mânêya, mentioned in the Buddhist chronicles.

The main mass of ruins at Tamésvara Dîh consists of an elevated flat-topped plateau, about a mile in length from north to south, and which is entirely composed of brick ruins. The breadth of this mass of ruins from east to west is îrregular, it being in some places broad and in other places narrow. In the northern end of these ruins there is a large tank, called Sâgar, on the north-west corner of which there is a ruined cone-shaped brick stûpa which is fully 30 feet in height. There are also many other detached ruins scattered here and there, round about. About a mile to the north there is a village, called Mênhîya, a modern corruption of the ancient Mânêyanagara.

About a mile to the north of Tamêsvara Dîh, and about half a mile to the east of Mênhîya, and about a quarter of a mile from the west bank of the Kûdawâ Nadî, in the midst of dense jangal, there are the traces of a circular brick ruin, the remains of a stûpa which, according to Mr. Carlleyle, marks the spot where Buddha leaped across the Anomâ with his horse, which river he identifies with the Kûdawâ Nadî,³ or "the river of the leap."

1 Cunningham, Archaelogical Reports, Vol. XI, page 101; Vol XII, pages 217-219.

* Cunningham, Archeological Reports, Vol. XII, pages 223—226; Vol. XVIII, pages 22—27; Vol. XXII, pages 2 and 3,

² Cunningham, Archicelogical Reports, Vol. XII, page 224; Vol. XVIII, pages 13—22; Vol. XXII, pages 3—5,

Ш.

III.

III.

About two miles to the north of Tamesvar Dih, at the village of Seasara, there is said to be a copperplate inscription in the possession of one Kishan Bhat.

III. WARÂÎ, small village in tahsîl Bastî, five and-a-half miles to the south-east of head-quarters, possesses to the north a large mound of ruins at the south-eastern end of a lake, called Barka Tâl, and about half a mile to the south of a village, named Baisukhiyâ. The dîh, or great mound of ruins, measures about 1,500 feet in length from north to south by about 700 feet in breadth from east to west. On the top of this mound there is a large, octagonal-shaped well. There are also several smaller mounds of ruins a short distance to the west. These extensive ruins show that Warâi Dih must have been the site of an ancient town of some size and importance.

V.—GHÂZÎPÛR DISTRICT.2

- 1. Âonrîhâr, small village in tahsil Saidpûr, 26 miles west of Ghâzîpûr, is built on a large kherâ, the ruined site of an ancient city. The whole ground is covered with fragments of bricks and stones, and every few yards masonry walls occur. In the village itself large carved stones are scattered about, and pieces of fine sculptures are utilized as common building stones. To the north-west of Âonrîhâr the remains of masonry walls may still be traced running in the direction of the enormous mound known as Masâon Dîh. Dr. Oldham³ identifies these remains as the ruins of a monastery founded by Asoka to the north-west of the capital of the kingdom of Chen-chu, and visited by Hiuen Tsiang. See, however, article on Ghâzipûr.
- Bahadurganj, town in pargaņa Zahūrābād of tahsil Korantādih, 20 miles north of Ghāzipūr, possesses on its western outskirts a neat masjid and idgāh.
- 3. Bâra, old village in tahsîl Zamânîyâ, 18 miles south-east of Ghâzîpûr, possesses a pyramidal-shaped mound. About a mile to the west of Bâra, there is a large mound of ruins, probably those of an ancient kôţ. This is about two and-a-half miles to the north-east of a place named Gahmar in the maps; but the correct spelling of which is Gehmur or "abode of Mura," the name of a demon fabled to have been destroyed by Krishna, who, in consequence of this feat, obtained the name Murâri, or "the foe of Mura."
- 4. Barhanpur, village in tahsîl Saîdpûr, 14 miles south-west of Ghâzîpûr, III. possesses an old ruined fort, overgrown with jangal.
- About a mile to the north-east of Barhanpur, there is a small conical mound III. close to the north-west of Nandganj, and there is another mound about a mile to the south of that place.
- III. About two miles to the south of Nandganj there are two mounds of ruins near a village called Sabûwâ, on the south bank of the Gângî Nadi.
- III. There is another mound of ruins to the west of Meharâuli, one and-a-quarter miles to the north-east of Chochakpûr Ghâţ.
- 5. Bharaulí Gangarír, village in pargana Garha of tahsil Korantadíh, possesses III. on the road to Narhí a banyan grove of great antiquity, in which there are traces
 - I Cunningham, Archaelogical Reports, Vol. XII, pages 221 and 222.
 - North-Western Provinces Gazetteer, Vol. XIII, Part II, pages 51—56 and 105—147; Dr. W. Oldham, Historical and Statistical Memoir of the Gházipúr District: Allahabad, 1870, Part I, pages 15—40.
 - Memoir, Vol. I, page 37.

Ш

Пъ.

* Beal, Lc., Vol. II, page 61.

of ancient buildings. The place has been identified by Dr. Oldham¹ as the site of the "temple of the vast solitude," visited by Fa Hian² and Hiuen Tsiang.³ See, how-

ever, article on Bâliyâ.

6. Bhîtarî, village in tahsîl Saîdpûr, 20 miles west of Ghâzîpûr, situated on the left bank of the Gångi Nadi, contains the most important archæological remains in the district. Its appearance in the distance is that of a long low mound which on nearer approach displays a reddish hue on account of the large quantity of brick rubbish entering into its composition. In form it is nearly rectangular, and the only deviation from that form is caused by an eminence or spur running from the south-west corner, which has evidently been crowned by some imposing edifice. A mound rises at each corner, and another half-way along each face, and many more are within the enclosure itself. The general aspect of the site is that of a fort with projecting towers at the corners, connected together by a low embankment or wall, whilst the debris scattered about in every direction and the numerous mounds would seem to indicate that formerly extensive buildings existed upon it. On the spur is a recently-erected imâmbâra, under the foundations of which a hole has been made into the mound on which it stands, revealing the original foundations of a very ancient edifice lying in situ. The bricks are of exceedingly large dimensions, some being 19" × 12" × 3". Excavations made, in 1863, by Mr. C. Horne into several mounds in the immediate neighbourhood of the inhabited portion of Bhîtarî, yielded nothing of importance, as only vast masses of earth, pottery, brick, and other rubbish were discovered. It by no means follows, however, that because no ancient relics were brought to light in those kheras which were then laid open, that a further and more complete investigation would be fruitless. It is only natural that the changes which have taken place through many generations among the buildings which the successive inhabitants of Bhitari have erected, having recourse to the ancient structures for their materials from century to century, rather than to materials of their own manufacture, should have occasioned the formation of some. perhaps of many, of the existing mounds. It is the opinion of General Cunningham that the Bhîtari ruins date from the Gupta period, and that they are amongst the oldest Brâhmanical remains known to us. He is wrong, however, in the implied supposition that they are altogether of Brahmanical origin, as there can be no doubt that during the Buddhist period several temples and one or two monasteries flourished in Bhitari.

In a masjid in the village, of modern erection, are 30 stone pillars, seven of them being elaborately carved. These must have been taken from buildings situated here in ancient times, for they present similar characteristics to the columns of Buddhist shrines and monasteries, of which remains are still found at Banâras and elsewhere. In a small uncovered brick enclosure are several old sculptures, among them a rude statue of Buddha in excellent preservation. Of the other sculptured stones found at

statue of Buddha in excellent preservation. Of the other sculptured stones found at this spot, one exhibits the figure of a man seated on a prancing ram, which may possibly be intended to illustrate one of the signs of the zodiac. Portions of cloister

27.1

IIb.

III.

IIb.

Ha.

Memoir, Vol. I, page 32. Beal, Le., Vol. I, page LXVII.

Beal, Le., Vol. 11, page 62.
 Cunningham, Archeological Reports, Vol. I. pages 96—103; Journal. Axiatic Society of Bengal, Vol. XXXIV, pages 82—89; Dr. Oldham, Memoir, Vol. I, pages 16—21.

pillars, square below and octagonal above, may be here and there seen. These were manifestly first cut down and rounded by the Hindûs, to serve as lingams, and when the Musalmâns became dominant, were then used by them as head-stones for their graves. Some of the massive stones of the masjid now used as architraves and pillars were evidently taken from ancient edifices; and it is not difficult to trace roofing stones of old cloisters in some of the stones in the pavement and in the covering stones of the graves. It seems evident, therefore, that the ancient remains at Bhîtari are both of Buddhist and of Brâhmaṇical origin, though it is hard to say precisely which preceded the other. The twofold character of the discovered remains tends to show that ancient Bhîtarî was alternately in the hands of Buddhist and Brâhmaṇical monarchs during the Gupta period, who severally embellished it, according to their distinctive religious views.

Ib. Judging from the tombs and masjids dispersed over the village and its suburbs, Bhîtarî must have been a place of some importance during the Musalmân period. The bridge over the Gângî below the village was erected by the Musalmâns at least three centuries ago, and the original structure, General Cunningham considers, "consisted of only two small arches," to which two others have subsequently been added. The bridge has been altogether built with cut stones taken from other buildings, and in one place a figure of a non-descript animal, such as supports the brackets, in the Ataladêvî Masjid at Jaunpûr, is inserted into the wall. Although in a dilapidated condition, the bridge nevertheless possesses considerable strength, and its thorough repair which is very desirable might be effected at a comparatively small cost.

The most noticeable object inside the ruined fort enclosure is undoubtedly the famous lât with an inscription of Skandagupta upon it. The column consists of Ib. a single block of reddish sandstone, 281 feet in height, and stands upon a rough stone, seven or eight feet below the present level of the soil. For the first 10 feet two inches it is square, and at the top of the square part is the inscription, facing east. The upper part, including the capital, is circular. At its junction with the square part its diameter is two feet three inches, and the same thickness is preserved in its whole length. The capital is about three feet in height, bell-shaped and reeded like the capitals of the Asoka pillars. From this capital on the western side a slice has been broken off, exposing a deep narrow socket which may have held a metal spike. The shaft of the pillar is split to a depth of about two feet from the top, a fact attributed on the spot to lightning, but is more probably due to the destructive bigotry of the Musalman invaders. The statue of a lion may have topped the column, and the treatment such objects received during the early Musalman period is sufficiently notorious to warrant this suspicion. The inscription itself consists of 19 lines of well-shaped characters of the Gupta period; but, unfortunately, the letters are much weather-worn and the stone has peeled off in several places. It chiefly refers to the reign of Skandagupta, closing with his death and the accession of his son, Kumaragupta Mahandra, and records the erection of a sacred image of Vishnu, and the allotment, to the image, of the village in which the column stands.

Journal, Bombay Branch, Royal Asiatic Society, Vol. X, page 59; Vol. XVI, page 349; Journal, Asiatic Society of Bengal, Vol. VI, page 1 seqq.; Prinsep, Indian Antiquities, Vol. I, pages 240—245; Corpus Inscriptionum Indicarum, Vol. III, page 52.

III.

III.

To this monarch General Cunninghan attributes the persecution of the Buddhists mentioned by Hiuen Tsiang.

At the foot of the *lât* several large bricks have been excavated, inscribed with the name of Śri Kumāragupta. An oval silver plate with an *inscription* of Kumāragupta was discovered, in 1885, amongst the ruins close to the *lât*; but it has as yet not been published. Besides, several hoards of Gupta gold, silver, and copper coins have been unearthed at Bhitarî.

- 7. Bîrpûr, village in pargaņa Muhammadâbâd of tahsîl Korantâdîh, on the left bank of the Ganges, 22 miles east of Ghâzîpûr, was once a place of some importance, as coins of the Gupta period and ancient sculptures have been discovered near the village.
- 8. Dhânapûr,¹ village in pargaṇa Mahâich of tahsîl Zamânîyâ, 16 miles southwest of Ghâzipûr, is said to have been founded by Râjâ Dhâna Dêva, belonging to a tribe called Sûriyân (probably the Śabaras). To the south-west of the village lies an ancient kôţ, overgrown with jangal; and about half a mile to the north-east of the village there is a large mound of brick ruins.
- About two and a-half miles south-west of Dhânapûr there is the village of Hingotâr, possessing a small ruined fort, close to the south of the village. The fort is surrounded by a ditch; within it there are ruins both of brick and stone. The fort has been added to or rebuilt upon while in the hands of the Musalmâns, and there are several blocks of stone bearing carvings of Musalmân workmanship; but there are also several sculptured pillars, some standing and some fallen, which are decidedly of Hindû workmanship. Inside the fort are the fallen ruins of a masjid which was no doubt partly built out of Hindû materials; and there is a fragmentary Persian inscription on a block of stone which must have belonged to the doorway of the building. In the village there is still partly standing, on an elevated platform of stone, a small flat-roofed structure, built of large and richly carved stones and supported on 16 massive square pillars.
- 9. DILDÂRNAGAR,2 village in tahsîl Zamânîyâ, 12 miles south of Ghâzîpûr, derives its name from a Pathân named Dildâr Khân who settled here in the reign of Aurangzib, after having destroyed the ancient Hindû town of Akhandhâ, the ruins of which are represented by a large khera lying between the railway station and the Ш. village of Dildarnagar. The whole mound of ruins is about 300 feet long by 250 feet broad, on the top of which the remains of temples and other buildings occupy symmetrical positions. Exactly in the middle are the foundations of two temples, of which one was certainly dedicated to Siva, as it still contains a lingam of black stone in situ, although one-half of the argha is gone. The entrance was to the east, with a water-spout to the north. The external dimensions of this small temple are only 17 feet six inches by 15 feet 8 inches. The external dimensions of the second temple are almost the same. Between the two temples there is a broken figure of Durga seated on a lion in black basalt. On the east side of the mound there are the remains of a large temple which was most probably dedicated to Lakshmi-Narayana, as in the centre of the lower lintel there is a seated figure of Lakshmi being anointed by

¹ Cunningham, Archwological Reports, Vol. XXII, pages 118 and 119.

² Cunningham, Archwelegical Reports, Vol. 111, pages 63 and 64; Vol. XIX, page 23.

two elephants, with Vishņu over the right jamb and Siva over the left. The left jamb is divided into panels with various figures, and the sill is ornamented with a row of musicians, the whole being surrounded with a rich leaf border. Altogether, these remains are fine specimens of Hindû work. Richly ornamented pillars and pilasters, apparently belonging to this fine temple, are lying about near the foot of the mound. To the west of the kherû there is a large lake, called Rûṇî Sûgar, attributed to Nala's wife, Damayantî.

- 10. Ghâuspūr, village in pargaṇa Muhammadâbâd of tahsil Korantâdîh, seven miles east of Ghâzipūr, is a place of considerable archæological interest. Large masses of dressed stone and quantities of brick have been from time to time discovered; the upper half of a finely-carved female figure, dug out of a tank, is now an object of religious veneration. In a sivâla near by, the lower half of this figure, and another unbroken female statue, and a remarkably fine sculpture of a lion, four feet long and three feet high, resembling those found as capitals of ancient pillars, have been collected. A very fine sculpture representing the Narasimha Avatâra of Vishṇu was discovered in a tank in the village, and is now set up in a temple as an object of worship. Dr. Oldham¹ identifies the place as the site of the Buddhist "monastery of those whose ears are not pierced," visited by Hiuen Tsiang.² See, however, article on Balîyâ.
- 11. Ghâzîpûr, lat. 25°-35′ N., long. 83°-38′ E., capital of the district, on the left bank of the Ganges, is said to have been founded in A.H. 730 by Mâlik-us-Sâ'dât Masa'ûd Ghâzî, who conquered the district in the reign of Muhammad bin Tugh-laq. According to Hindû tradition the ancient name of the city was either Gâdhi-pura or Gâjpura; and there is some suspicion shown upon this by the fact that the Hindûs generally pronounce the present name of the place as Gâjipûr. There can be no doubt that the spot which the native town of Ghâzîpûr occupies is an old site. On examining an exposed section of the high river bank on which the town of Ghâzîpûr stands, one can see that the soil contains many fragments of old brick and pottery. General Cunningham³ proposes to identify this ancient site with the capital of the kingdom of Chen-chu, or "the lord of battles," visited and described by Hiuen Tsiang, and he proposes Garjapatipura as the Sanskrit equivalent for the Chinese rendering of the name.
- IIb. The only ancient buildings worthy of notice are the perfectly plain tombs of the founder of the city and his son, built in the usual Pathân style; the fine masonry tank and tomb of Pahâr Khân, faujdâr of the city in A.D. 1580; a masjid and imâmbâra, built by Nawâb Shaikh Abdullâ, a former governor of the Ghâzîpûr sarkâr under the Nawâb Vazîr of Audh; the large garden, tank, and tomb, known as Nawâb-kî-châr-IIa. Diwârî, built by the same governor and his son, Fazl Alî Khân; and his palace C h i h a l Sa t û n or "forty pillars," now in ruins. The handsome gateway of this picturesque building still remains in a tolerably perfect condition. Near the tomb of Mâlik-us-Sâ'dât Masa'ûd Ghâzî there is a small neat masjid, which was without doubt formerly III. a Hindâ building. There are also the remains of a mud fort overlooking the river.

¹ Momoir, Vol. I, page 37.

³ Beal, Lc., Vol. II, page 62.

³ Ancient Geography of India, pages 438-440.

⁴ Beal, Lc., Vol. II, pages 61-66.

III.

III.

III.

Ia.

Ia. The only remarkable building in the civil station is the Cornwallis monument. This is a heavy structure with a domed roof supported by 12 Doric columns. The floor is raised some twelve feet from the ground, and is of handsome grey marble. In the centre stands a cenotaph of white marble, bearing on the south side a medallion bust of Lord Cornwallis, who died at Ghâzîpûr in 1805, between the figures of a Brâhman and a Musalmân, and on the north side the figures of a European and native soldier in attitudes of sorrow. The cenotaph is from the chisel of Flaxman.

Three miles to the west of the native town of Ghâzîpûr, there is an ancient site near two villages, called Hêmpûr and Atraulî, where a copperplate is said to have been found in 1878; but which apparently has never been published.

About six miles to the south-west of Ghâzîpûr, there is a dîh, or mound of ruins, called Suîrî-kâ-Râj, near the south bank of the Gângî Nadî, to the south-east of a village called Permit. The name applied to these ruins seems to indicate the site of an ancient town which was founded by the Sûirs, or Śabaras.

12. Jalâlâbâd, village in pargaṇa Sâdîâbâd of tahsîl Ghâzîpûr, 20 miles northwest of head-quarters, possesses the remains of a brick fort constructed by Nawâb Shaikh Abdullâ, who in 1738 A.D. was governor of Ghâzîpûr.

13. Kasimabad, or Sonbarsa, village in pargana Zaharabad of tahsal Korantadih, possesses the ruins of a brick fort built by Nawab Shaikh Abdulla, who named the village after his father. The fort is built on an elevated mound to the west of the village, surrounded by a moat, now dry. The four corners were defended by round towers; part of one of these is still standing, and forms a picturesque feature in the landscape.

14. LâŢīvâ,1 small village in tahsîl Zamânîyâ, 131 miles south of Ghâzîpûr, receives its name from a stone lat, standing on the western end of a mound of brick ruins, about 500 feet long by 200 feet broad, which is surrounded on all but the east side by a shallow sheet of water. The pillar is a single circular shaft of polished sandstone, one foot eight and-a-half inches in diameter, where it springs from the square base, and 20 feet in height. The square portion now stands two feet six inches out of the ground, but only one foot six inches of this portion is properly smoothed. On the top of the shaft there is a bell-shaped capital, two feet in height, surmounted by an upper capital formed by eight lions facing outwards. The capital was once crowned by two half-length female figures back to back, resting on a circle of lotus leaves. This stone, which is now lying on the ground, has a socket hole nine inches deep. The total height of the pillar was, therefore, just 30 feet. The pillar is about 18 inches out of the perpendicular; but it is firmly fixed in the ground by four large upright stones, one at each side. The actual depth of the column itself below ground is only four feet seven and-a-half inches; but as long as the four upright stones retain their position, the column is perfectly safe. There is no inscription, and not even a single letter upon any part of the pillar. From the shape of the bell-capital and the medium size of the bricks in the mound, 14"×9"×21", General Cunningham judges the pillar to belong to the Gupta period. Dr. Oldham2 regards it as a sister column to the Pahladpar lat. Nothing trustworthy is known by the

3 Memoir, Vol. I, page 24.

¹ Cunningham, Archwological Reports, Vol. III, pages 61-63.

people either about the monolith or the place. It stands only about one mile and-a-half east of the Ganges and of the town of Zamaniya, to which all the stories refer. See article on Zamaniya.

15. Masâon Dîh,¹ deserted site on the north bank of the Ganges in tahsîl Saîd-pûr, 24 miles west of Ghâzipûr, is the ancient Krelulendrapura according to an inscribed statue found by Mr. Carlleyle in the ruins of an old temple which formerly stood near this spot. The great mound measures about 1,500 feet in length from east to west, by about 1,000 feet in breadth from north to south at the west end, and about 600 feet in breadth at the east end. The highest point of the mound rises to a height of about 50 feet above the surrounding fields, while the height of the rest of the mound varies from 20 to 30 feet. On parts of the mound, mostly near the edge, there are narrow circular wells lined with cylinders of earthenware measuring two and-a-half feet in diameter. The whole of this great mound is entirely waste and unoccupied, and covered with jangal.

A short distance to the north of the great khera, there is a tank called Kal-wari-ka-Pokhra, with high embankments on both sides.

To the south, west, and south-east of Masaon Dih are traces of an ancient river bed, probably an ancient branch of the Ganges.

About a mile to the south of Masaon Dih and close to the village of Budhû-pûr, there is a village called Joharganj. This place is said to have been formerly called Bânjhulâwan from a mound of ruins close to the west of Joharganj, where robbers laid in wait for travellers. This mound was excavated by Mr. Carlleyle, who found several coins of the Buddhist period with legends in the Maurya alphabet, the kalasa of an old temple, fragments of statues of Sûrya, clay beads, ivory armlets, agate beads of various shapes, and stone celts.

About 1,000 feet to the south-east of this mound, there is another high kherû on the bank of the Ganges; and close to the west of that mound, there are some lower mounds of ruins and several broken statues of Hindû deities lying on the ground. The precipitous face of the river bank, opposite this spot, is full of ancient broken bricks and fragments of pottery. The ancient name of this ruined site is said to have been Dhanâwar, or Dhanapura; which assertion is corroborated by the fact that a copper coin of Dhanadêva, inscribed in Maurya characters, was found in these ruins.

16. Nârâyaṇpûr, village in pargaṇa Muhammadâbâd of tahsîl Korantâdîh, 24 miles east of Ghâzipûr, on the north bank of the Ganges, is a place of some archæological interest, as ancient coins and sculptures have been found here. Dr. Oldham² identifies it as the site of the temple of Nârâyaṇa Dêva visited by Hiuen Tsiang.³ See, however, article on Nârâyaṇapûr of the Bâliyâ district.

About a mile to the east of Narayanpur on the north bank of the Ganges, there is a place called Mathiya; and half a mile to the south of Narayanpur there is a village called Kotwa. The whole of these places occupy an ancient site covered with the ruins of many temples.

III.

Hb.

III.

¹ Cunningham, Archaelogical Reports, Vol. XXII, pages 96—105,

² Memoir, Vol. I, page 37.

Beal, Le., Vol. II, page 64.

- About five miles to the south-west of Narayanpûr, on the north bank of the III. Ganges, there are two groups of kherûs called Chetiyâ and Ambi Kôt, or Ambirikh. The mounds of Ambi Kôt consist of the remains of an ancient fort which is said to have been constructed by Ambika Rishi. The place is also said to have belonged to the Chêrû-kâ-Râj. A portion of this ancient site has been cut away by the Ganges, leaving a high perpendicular cliff overhanging the river; in this exposed section numerous bricks and fragments of ancient pottery are visible.
- 17. Pahladpür, or Pâllâțpûr, village in pargaņa Mahâîch of tahsîl Zamânîyâ, 14 miles south-west of Ghâzîpûr, is remarkable on account of a lât of red sandstone, about 30 feet high and two feet thick, having been found here. The monolith was removed, many years ago, by order of Mr. Thomason, when Lieutenant-Governor, to the Queen's College at Banâras, where it now stands. It bears a short Sanskrit inscription¹ of Śiśupâla in Gupta characters, of which a good fac-simile and transcript is given in Corpus Inscriptionum Indicarum, Volume III, page 250.
- 18. Sâdîâbâd, village in tahsîl Ghâzîpûr, 14 miles north-west of head-quarters, derives its name from Sâdî, the servant of Mâlik Mardân, brother of Mâlik Bahrî, who first conquered this part of the country. The tombs of Mâlik Mardân and Sâdî are still venerated. That of Mâlik Mardân is said by Dr. Oldham² to be really an ancient Hindû structure, transformed by the addition of five domes into a Musalmân dargâh.
- 19. Skippûr, 3 tahsîl, 24 miles west of Ghâzîpûr, possesses many ancient remains of great interest and importance. In the town itself there are two Musalman dargahs, which are of undoubted antiquity. The first is a small domed building sustained by Hb. four stone pillars, the bases of which rest on a platform 12 feet square, raised a few inches above the ground. The shafts of the pillars are square and the capitals are cruciform, each limb being one foot 10 inches in length and having the usual Buddhist bell ornamentation. The pillars on the north and east quarters exhibit a groove which evidently once contained a pierced stone railing. The eave-stones above are apparently original, and have a projection of 15 inches. These eaves are strikingly characteristic of the architecture of the early period to which this building must be assigned, and are often of great size and solidity. In ancient Buddhist structures both in Banaras and in Jaunpur, as well as in this instance, they are cut on the upper surface to resemble woodwork. Some persons will be reminded by this circumstance of Akbar's stone roof at Fathpur Sikri, cut in imitation of tiles, and of the carved beams in the caves at Elephanta.

The second building is 26½ feet long by 23 feet broad, and is upheld by at least 34 columns disposed in the following remarkable order, viz., six at each of the northeast and south-east corners, nine couples at intervals in the circumference, and four single pillars in the centre forming a square. The two clusters of six pillars have been united by stone slabs into two thick ones, each 2½ feet square. This curious amalgamation is in all probability the work of the Musalmans, though from what motive it is hard to conjecture. The building was already strongly supported, and the alteration con-

¹ Journal, Asiatic Society of Bongal, Vol. VII., page 1055; Dr. Oldham, Memoir, Vol. I, page 24.

² Memoir, Vol. I, page 39.

^{*} Journal, Asiatic Society of Bengal, Vol. XXXIV, pages 80-82.

siderably detracts from its simplicity. The space between the side pillars is five feet nine inches, between the side and centre pillars six feet four inches, and between the centre pillars themselves five feet one inch. The height of each column is six feet 11 inches, of which the base is nine inches; the shaft four feet eight inches, the stone upon it 10 inches, and the capital one foot eight inches. The innermost line of columns is built into a wall of solid masonry composed of ancient stones, and is of more recent date than other parts of the edifice. The roof is of long slabs, but in its centre is a primitive Buddhist ceiling consisting of four stones placed diagonally upon the architraves and crowned by a flat stone ornamented with a lotus blossom. Each corner stone also exhibits this flower in relief. The existence of the original eavestones on portions of three sides of this structure, is sufficient proof that it could not have been any larger than it is at present; but the great strength of the supports above alluded to, would appear to indicate that it once possessed a second or even third storey. Upon the roof is a diminutive chamber of comparatively modern construction, sustained by four ancient pillars. The shafts are octagonal, and the capitals and rounded bases are richly carved with the bell and leaf pattern. These pillars have been doubtless taken from old buildings which were formerly situated in this neighbourhood.

There can be no doubt that these two edifices were separate *chaityas* attached to a Buddhist Vihâra, traces of which are still visible. The preservation of these interesting remains is to be attributed to the circumstance of a Musalmân faqîr, named Shaikh Samman, having taken up his abode in one of them, and having been buried in it at his death, in A.H. 1003, as stated in a Persian *inscription* on a pillar close by. The second *chaitya* contains the tomb of one Makhdûm Shâh. Many of the Musalmân tombs, which abound in this locality, have been constructed with stone taken from the usual Musalmân quarries of Brâhmanical and Buddhist remains.

About three quarters of a mile from Saidpur, on the high road, is the small village of Zaharganj, between which and the Ganges is a mound regarded by the people III. as the remains of an old fort. Bricks are cropping out of its sides, and for some distance along the banks of the river round to the main road beyond the village, the soil is strewn with broken brick, showing that formerly buildings of this material were standing here. To the north of the road, but almost close to it, is a mound called Ram Tawakku, rising abruptly from the plain, on which are also numerous frag-III. ments of broken brick. To the north, about a mile from the public road, is an immense terrace raised from 30 to 40 feet high above the surrounding country; its length is 420 paces and its breadth 190. The terrace is thickly covered with broken brick, and at one corner there are likewise fragments of stone. This enormous mound is of irregular shape. There is little doubt that extensive buildings lie buried here, which, judging from the quantity of brick rubbish found above, are for the most part probably of this material. Close by are two other kheras and further off, in the Khân pûr pargana, on the banks of the Gumti, are many more which III. contain masonry wells and débris of brick.

About half a mile beyond Zahûrganj, a few steps from the road, is a stone plat-Ib. form on which are two statues, one representing the Varâha Avatâra, and the other Krishna with the gôpîs. Both are old and in excellent preservation. III.

Dr. Oldham1 identifies the country round Saldpur as having been the site of the capital of the kingdom of Chen-chu visited by Hiuen Tsiang. See, however, articles

on Ghâzîpûr and Udharanpûr.

20. Shaikhanpûr, village in pargana Zahûrâbâd of tahsil Korantâdîh, 12 miles north-east of Ghâzîpûr, is a place of some antiquity, as ancient remains have often III. been found by the villagers. Dr. Oldham2 found here during an excavation a small, but finely-carved, stone head and an extensive brick building, now buried beneath earth and débris.

21. Udharanpûr, small village in tahsîl Zamânîyâ, six miles south-east of Ghâzîpûr, situated on an ancient bed of the Ganges, possesses extensive mounds of ruins. Mr. Carlleyle3 thinks the name of Udharanpûr might be a modern corruption of Yuddharanapura, the Sanskrit equivalent of Chen-chu, or the capital of "the

lord of battles," visited by Hiuen Tsiang.

22. Zamânîyâ,4 tahsîl, 10 miles south of Ghâzîpûr, on the right bank of the Ganges, is a place of some historical interest. According to the Hindûs, Jamadagni Rishi and his wife lived in a hut on the bank of the Ganges close to the present town, whence it received its name of Jamadagniya, which they say is the true form of the present name. The wife of Jamadagni was a sister of the queen of Raja Madana, who lived in the town. One day when Raja Madana and his wife were passing by the Rishi's hut, on a visit to his father-in-law, Râjâ Gâdhi of Gâdhipura, the sage's wife wished to entertain her sister and brother-in-law. The Rishi gave his consent very reluctantly. The Raja was accordingly treated with the dignity due to his rank, the whole of the entertainment having been supplied by the never-failing cow Kâmadhênu. The Râjâ was surprised, but instead of being thankful, he carried off Kâmadhênu by force. Râjâ Madana was afterwards overcome in fight by Parašurâma, son of Jamadagni, and Kâmadhênu was recovered.

The Raja was humbled, and offered a sacrifice in satisfaction of his sin. No less than 11 padams of rûpîs were expended on an asvamêdha by Râjâ Madana. About 60 years ago a copperplate inscription giving an account of Raja Madana's sacrifice was found at Zamaniya by a Musalman. It was enclosed in a pewter box inside a stone box. The copperplate was thrown either into the Ganges or into the Makna tank owing to a quarrel which arose on the Tiwari Brahmans of the place asserting that it recorded a grant of land made to their ancestor by Raja Madana.

After the sacrifice the Raja erected a temple to Madanesvara at Latiya, one mile east of Zamaniya, and set up the lat on the mound where it now stands, as a memorial that he wished to build a city on the site of Jamadagniya, which was to be called Banaras. But the Brahmans considered the site not sufficiently auspicious, and the design was abandoned. Jâmadagnîyâ was then called Madana Banaras, "the desired or intended Banâras," a name which is mentioned in the Ain-i-Akbarî.5

Such is the story which is now in everybody's mouth, the whole of which General Cunningham believes to have been invented within the last three centuries by the

Memoir, Vol. I, page 37.

^{*} Memoir, Vol. I, page 26.

Cunningham, Archaelogical Reports, Vol. XXII, page 94.

^{*} Cunningham, Archaelogical Reports, Vol. III, page 62,

Blochman, 'Ain-i-Akbari, page 320.

fertile mendacity of the Brâhmans. The place was originally called Madana Banâras; but the whole story about Jamadagni has been invented to account for the name of Jamânîyâ, as they pronounce it, but which is correctly speaking Zamânîyâ, as the town was founded in A.D. 1560 by Khân Zamân, governor of Jaunpûr, in the early part of Akbar's reign. Two hundred years after its foundation, the town was burnt down by Fazl Alî Khân, and remained for some years deserted till the âmil of the pargaṇa, Chaudhrî Muhammad Ajmâl, rebuilt it.

In the northern portion of the town, near the Ganges, there is an extensive kôt from which massive carved stones have been frequently excavated. They are to be found in numbers scattered about the mound, and also in the walls of dwelling-houses, masjids, and other buildings in the vicinity.

VI.—Gôrakhpür District.1

Anaûlâ, or Sangrâm pûr, village in tahsîl Bânsgâon, 13 miles south-south-west of Gôrakhpûr, is built on an ancient kherâ, covered with fragments of brick and pottery; a good many old brick wells may be found in its neighbourhood.

III.

Ш.

IIb.

A memorial of ancient woodland survives in tappâ Bankatâ, "forest-clearing," to the west of Anâûlâ.

- Bairâûnâ Khâs, village in pargaņa Salîmpûr of tahsîl Dêorîyâ, 37 miles southeast of Gôrakhpûr, contains the ruins of an ancient fort attributed to the Bhârs.
- III. 3. Bânsgâon, tahsîl, 19 miles south of Gôrakhpûr, is perched on an old dîh, the highest eminence of which is called Barâban, or "the great forest." It possesses two Hindû temples, erected on old temple mounds, and a masjid of no great architectural pretensions.
- 4. Barhaj, town in pargaņa Salîmpûr of tahsîl Dêorîyâ, 41 miles south-east of Gôrakhpûr, possesses near the banks of the Râptî the ruins of a fort said to have been built by Kuâr Dhîr Sâhi. This stronghold is believed to have been stormed and destroyed by Musalmâns about 200 years ago. The town contains five modern Hindû temples, dedicated to Siva, and a good-looking masjid.

Legend derives the name of Barhaj from one Barahan or Barhaji, a Brâhman hermit who turned Musalman; his supposed tomb is still an object of veneration.

- 5. Barhalganj, small town in pargaṇa Chillûpûr of tahsîl Bânsgâon, 36 miles south-south-east of Gôrakhpûr, possesses a famous temple sacred to Siva as Jaleś-varanâtha Mahâdêva, anda Vaishṇava temple, known as Charaṇapâduka.
- 6. Barhî, village în pargaṇa Havelî of Sadr tahsîl, 13 miles south-east of Gôrakh-pûr, is situated on the left bank of the Râptî. A short distance east of Barhî, in the villages of Updhāolîyâ and Râjdhâni, are the extensive remains of a very large ancient city, which has been identified by Mr. Carlleyle² with Môri yanagara, the city of the Môriyas in the Nyagrôdha forest, where the charcoal ashes of Buddha's funeral pyre were enshrined in a stûpa.

This ancient city appears to have extended from the Rapti river eastwards to the Pharen river, or for a distance of fully four miles from west to east, with a varying breadth of about a mile from north to south. The ruins commence near Dih Ghât

¹ North-Western Provinces Gazetteer, Vol. VI, pages 459-550, passim.

² Gunningham, Archaeological Reports, Vol. XVIII, pages 31—41; and Vol. XXII, pages 7 and 8.

III.

III.

III.

on the eastern bank of the Rapti, a series of detached mounds of brick ruins extending thence to the Gorrâ river. Next, on the eastern bank of the Gorrâ river, there is a very large mound of ruins, called Updhaoliya Dih, which is about a mile in length from north to south by about 1,600 feet in breadth from west to east. On the western part of the dih there is a conical ruined brick stupa, which is still nearly 30 feet in perpendicular height. These are probably the remains of the famous Ashes stupa, visited by Fa Hian1 and Hiuen Tsiang.2 At the south-eastern corner of the dih there is another ruined stupa, about 17 feet in height. At the distance of about three-quarters of a mile to the north-east of Updhaoliya Dih there is the village of Rajdhani, which is situated on part of a wide flattish mound of ruins, the rest of which is covered with jangal. About one and-a-quarter mile to the north-east of Râjdhâni, there is an ancient brick enclosure, called Sâhankôt, which is situated in the midst of a dense forest of bar, sal, and jaman trees, and at the distance of about half a mile from the banks of the Pharên river. This square brick enclosure measures about 1,900 feet in length from west to east, by about 1,300 feet in breadth from north to south. But traces of brick ruins already commence in the jangal halfway between the village of Rajdhani and Sahankôt. This brick enclosure is most probably the large saingharama, or monastery, mentioned by Fa Hian and Hiuen Tsiang, which appears to have been situated to the north-east of the city of the Môriyas.

Five miles to the south-east of Râjdhâni lies the ancient village of Mithabel³

III. which is situated on a broad mound of ruins in the midst of a dense forest of banyan trees, which are apparently the remains of the ancient Nyagrôdha forest mentioned by Hiuen Tsiang. To the north side of Mithabel, there is a large tank and a lib. sivala. About one mile to the south of Mithabel, and in the middle of the bar forest, there is a small temple of modern age, containing ancient statues of Narâyana and Lakshmî. Close to the west side of the temple there is a double-topped mound of brick ruins which appear like the ruins of twin stûpas. About a quarter of a mile to the north of the last there are three conical-shaped mounds of brick ruins, probably the ruins of stûpas; the ground all around is strewn with fragments of brick for some distance.

Six miles to the north of Mithabel lies the village of Châorâ, and half a mile to the north-west of Châorâ there is an old village called Bhôpâ, which is situated on a flattish mound of brick ruins, and many fragments of old bricks are strewn about the southern side of the village. Immediately to the north of the high road, exactly opposite to Bhôpâ, there are three high conical mounds of bricks, which are evidently the ruins of stûpas. About half a mile to the south-west of these mounds there is a considerably extensive mass of ruins, including also some high conical mounds of brick, in a grove of high trees and jangal. About two miles to the west-north-west of these ruins, in the middle of a forest, and near the left bank of the Pharênd river, there is a smallish mound of ruins, on which there is an âsthâna of Dêvî, called Tarkulaki-kî-Dêvî-kî-thân, where a great melû is held every year.

Beal, Le., Vol. I, page XLI.

Beal, Le., Vol. II, page 31.

^{*} Cunningham, Archaeological Reports, Vol. XVIII, pages 52 and 53; Vol. XXII, page 13.

^{*} Cunningham, Archaelogical Reports, Vol. XVIII, page 54; Vol. XXII, page 15.

 Bhágalpûr,¹ village in pargana Salîmpûr of tahsîl Dêoriyâ, on the left bank of the Ghâgrâ, 52 miles south-east of Gôrakhpûr, was evidently the site of an ancient city, said to have been named Bhargavapura. Apparently the ruins at Khairâgarh, near Turtipâr, which are now on the Bâliyâ bank of the river, were once conterminous with Bhagalpur, and have been separated from it by a change in the course of the Ghagra. The ancient buildings on the Gorakhpur side have almost Ia. all disappeared, and only the inscribed monolith of rough grey sandstone remains, which stands about half a mile to the east of Bhagalpur, and quite close to the river banks. The total height of the pillar is about 17 feet, with a circumference of about five feet; it had a square base below, but the whole shaft is round. The capital is merely a circular slab supporting a cone. The inscription is on the east face of the pillar, and consists of 21 lines written in so-called Kutila characters of the 10th century. Unfortunately, the inscribed portion is much injured and defaced, as a large piece on the right side has been broken out of the pillar. About the top of the Kutila inscription is a short record of a Hindû yogî, engraved in large modern Dêvanâgarî letters. The people call the lât the club (gadâ) of Parasurâma.

About three miles east of Bhâgalpûr, at the village of Sahiyâ, there is a modern Hb. temple, called Chaturbhûjî Nârâyanî, standing on a mound of brick ruins, apparently the site of a Buddhist monastery, as several Buddhist statues have been recovered from this kherâ.

- 8. Bhâuâpâr, village in tahsîl Bânsgâon, eight miles south of Gôrakhpûr, possesses III. the ruins of a large castle on the highland overlooking the Râptî, and in the neighbourhood numerous mounds, the sites of ancient forts or villages, attributed as usual to the Thârûs.
- 9. Chetiyaon, small village in pargana Sidhuâ Jobnâ of tahsîl Parâûnâ, 47 miles south-east of Gôrakhpûr, contains the extensive ruins of an ancient city which has III. been identified by Mr. Carlleyle2 with Pâ wâ, at or near which Buddha is said to have rested and drank water and bathed, before proceeding on to Kusinagara on his last journey, the course of which was from Vaisali (the modern Besarh in the Muzaffarpûr district of Bangâl) to Kusinagara (the modern Kasiâ of the Gôrakhpûr district). Afterwards, on the death of Buddha, Mahâkasyapa, his chief disciple, also halted at Pawa, on his way to Kusinagara. Here, also, was a great stupa in which one of the original eight portions of the relics of Buddha was enshrined. In the Ceylonese Buddhist chronicles, Pawa is said to have been situated at the distance of about 12 miles from Kusinagara in the direction of the Gandak river, that is evidently somewhere to the east or south-east of Kusinagara and on the old road which people travelled between Vaisali and Kusinagara. The Ceylonese chronicles also mention that between Pawa and Kusinagara there was a small river, called the Kukuttha, at which Buddha stopped to bathe and drink; but in the Burmese version the stream is called Kakukhâ.3 This is probably the present Ghagi river, which runs at a distance of nearly six miles to the east-south-east of Kasia.

Cunningham, Archeological Reports, Vol. XVI, page 130; Vol. XXII, page 60; Journal, Asiatic Society of Bengal, Vol. VII, page 34.

^{*} Cunningham, Archaelogical Reports, Vol. XVIII, pages 101 to 116; Vol. XXII, pages 29 to 35.

² Cunningham, Ancient Geography of India, page 435,

Ш.

Ш.

III.

III.

Ш.

Ш

III. The remains at Chetiyâon consist mostly of a large dih, the north-eastern corner of which is situated at the distance of less than half a mile to the south-west of the village of Fâjila or Fâzilnagar. The greatest length of this mound of ruins is 1,900 feet from north to south, whilst the greatest breadth is 900 feet from east to west. There is a large pond of water, about 1,200 feet in length by 550 feet in breadth, close to the western side of the Chetiyâon Dih. At the distance of about 650 feet to the south-west of the great dih and in the middle of the fields, there is a gradually-sloping somewhat circular-shaped mound, about 270 feet in diameter, the remains of a stûpa. Besides these, there are several other mounds and large ancient tanks in the neighbourhood of the great dih. The bricks composing the ruins of this ancient city are of a large size, $18" \times 10" \times 2"$.

Less than half a mile to the north-east from the north-eastern corner of the great dih of Chetiyaon lies the village of Fajila, or Fazilnagar, perched on the narrow northern extension of a great mound of moderate elevation containing traces of brick ruins. On the very top of this mound are the ruins of a large stapa which stands upon a great oblong-shaped quadrangular platform of masonry, measuring 270 feet from east to west by 157 feet from north to south. The circumference of the ruined stapa at its base, above the plinth, was about 400 feet, giving a diameter of about 127 feet. The present perpendicular height of the ruined stapa appears to be about 35 feet above the plinth; but if the stapa was originally hemispherical, its original height must have been about 63½ feet. This ruined stapa is probably the famous stapa of Pawa, which contained one of the eight portions of the relics of Buddha.

On the top of the long eastern extension of the great platform, and about 40 feet to the north-east of the stûpa, there is a mound, the circumference of which measures about 170 feet, and which contains the ruins of an oblong-shaped building, the remains of walls of which crop out at the top of the mound. This building, apparently a temple, appears to have been about 30 feet in length from east to west by 21 feet in breadth.

Three miles to the north-north-west of Chetiyaon Dih, on the west bank of the Sarêya Tal, lies a mound of ruins, called Sarêya.

About three and-a-half miles to the north-west of Chetiyâon, and near the junction of the Ghâgi and Bândî rivers, is the village of Kukkurpati. The place is only remarkable from its name, which might possibly be connected with that of the Kukuttha river of the Ceylonese Buddhist chronicles.

About three miles to the west-south-west of Chetiyaon is a mound of ruins, called Nandwa.

About three and-a-half miles to the south-west of Chetiyaon lies a mound of ruins called Danaha.

At the distance of three and-a-half miles due south of Chetiyâon is a very large mound of brick ruins, called Asmânpûr Dîh.

About four miles to the south-east of Chetiyâon lies the village of Mîr Bihâr, at which there is a small conical-shaped mound of brick ruins. The name Bihâr is apparently derived from some former Buddhist vihâra.

About three and two-thirds miles to the north-east of Chetiyaon is a large flattopped mound of ruins, named Jharmatiya. About three and-a-quarter miles due north of Chetiyaon is the village of Gangi
III. Tikar. Close to the south of it there is a large mound of ruins, covered with bar
trees, which is called Gangi Dih.

10. Chūatarīyā,¹ small village in pargaņa Vināyakpār of tahsîl Mahārājganj, near the Nepāl border, 52 miles north of Gôrakhpūr, is only remarkable on account of two copperplate grants, dated Samvat 1836 and 1845, and written in the Bhôjpurì

dialect of Hindi, having been found there in 1877.

11. Deoriva, tahsil, 33 miles to the north-west of Gorakhpûr, is built on an old kherâ. About a mile north, at the village of Bharâulî, is a great kherâ beside the Karnâ watercourse, on the top of which there is an ancient statue of Siva and the foundations of a temple. In the village of Bâhmnî, south of the Karnâ, there are more extensive ruins, in which a lingam and a statue of Pârvatî have been discovered, besides the moulded foundations of two temples. West of these temples is an ancient tank about 40 yards square, and up to the temples there are the remains of a flight of masonry ghâts. At the other side of the Karnâ are the remains of a mud fort, the moat of which is still clearly traceable. On the top of the fort is the tomb of some Shahîd.

About five miles south-south-west of Dêorîyâ, at the village of Saraulî, are the remains of an extensive fort, overgrown with jangal and covering an area of about 22 acres. Within are three large masonry wells and the remains of a bâolî. Traces of a surrounding ditch are still visible.

12. Dhuriàpar, village in tahsil Bânsgâon, 26 miles south-south-west of Gôrakhpûr, contains the ruins of an enormous fort on the left bank of the Kuânâ river, which is traditionally assigned to the Bhârs or Thârûs.

About eight miles to the north of Dhuriâpâr, at the village of Barhiâpûr or Bhadâr Khâs, is a series of enormous mounds, evidently marking the site of a

very extensive ancient city.

III.

III.

III.

13. Gagahâ,² small village in pargaṇa Bhâuâpâr of tahsîl Bânsgâon, 26 miles south of Gôrakhpûr, is an ancient site, covered with mounds of brick ruins and possessing a very ancient masonry well. In one of these mounds were found, in 1877, two copperplates³ constituting one grant of Râjyapâla, son of Govindachandra Dêva of Kanauj, dated Samvat 1199, or A.D. 1142. In the inscription, Râjyapâla is simply called mahârâjaputra, so that he was not reigning.

Three miles to the north-east of Gagahâ lies the village of Kôt wâ, perched on an old dih on the left bank of the Râptî. A hoard of 16 gold coins of the Gupta dynasty was found loose under some bricks, in 1887, by some chamârs when digging in a field adjoining a high kherâ close to the village. This hoard is remarkable for its variety, as no less than seven distinct types are comprised in this small batch of coins. They all belong to the reigns of Chandragupta II and Kumâragupta Mahêndra, and are now deposited in the Lucknow Museum Coin Cabinet.

Two miles north of Kôṭwâ lies the village of G aj p û r, possessing a ruinous kôt on the left bank of the Râptî.

¹ Cunningham, Archeological Reports, Vol. XXII, page 61.

^{*} Cunningham, Archaelogical Reports, Vol. XXII, page 59.

³ Indian Antiquary, Vol. XVIII, page 20.

^{*} Proceedings, Asiatic Society of Bengal, for 1887, pages 182-185.

 Gôpálpúr, village in pargana Dhuriápár of tahsíl Bánsgáon, 33 miles south IIb. of Gôrakhpûr, possesses a fine brick castle, still used, and to the west of the village an III. extensive mound, apparently the site of an ancient city.

15. Gôrakhpûr, head-quarters of the district, lat. 26°-42' N., long 83°-23' E., possesses very few buildings of any real mark, and these are of rather modern date. The masonry saraî stands in mahalla Basantpûr on the rising ground overlooking the stretch of alluvion which intervenes between the city and the Rapti. Its high and turreted enclosing wall is entered by a great gateway; within there is a small masjid.

IIb. The imambara, an imposing structure, was built by Raushan Ali in the time of Asaf-116. ad-daula, Nawab of Oudh (A.D. 1775-1797). The Khudai Masjid, a plain and rather heavy-looking structure, was erected by Qazi Khalil-ur-Rahman of Maghar under orders of Prince Mu'azîm, afterwards Emperor Bahâdur Shâh of Delhî. in whose honour Gôrakhpûr was for a short time called Mu'azîmâbâd. The Jail marks the site of the old fort above the Rapti built by Raja Basant Singh of Satasi; the site is raised about 10 feet above the general level of the town.

The temple of Gorakhanatha is more remarkable for the strange legends told of Gorakhnath in whose honour it was founded than for any architectural merit.

About one and-a-half miles to the north-west of Gôrakhpûr, close to the junction of the Rôhinî with the Râpti, is a large and high mound, the ruins of the ancient Dômangarh,1 said to have been founded by, and to have received its name from, a ruling tribe called Dom-kattar. The bricks which compose the interior or oldest portion of the ruins of Dômangarh are very large and thick, and of a square shape.

During the construction of the Bengal and North-West Railway, in 1884, a relic casket was discovered near this kherà containing an amulet of thin plate gold, representing Yasôdharâ and Râhula, the wife and son of prince Siddhartha, as well as the ornaments of a child. The relics are deposited in Lucknow Provincial Museum.

About a mile to the north-north-east of Gôrakhpûr, at the village of Jattâî. there is an ancient tank, called Asuran-ka-pokhara, and popularly ascribed 116. to Râjâ Srî Pâla.

Besides these, there are several other mounds of ruins in the neighbourhood of Gôrakhpûr, viz.:-Râmgarh, two and three-quarters miles to the east of Gôrakhpûr, Ш. on the east bank of the Râmgarh Tâl, and on the south side of the road to Kasia.

Bhêriyâgarh, two and-a-half miles to the north-east of Gôrakhpûr, and on the south side of the road to Pipraich.

Baitalgarh, about four and-a-half miles to the north-east of Gorakhpur and to the south side of the road to Pipraich.

Mãola Kôl and Patara, eight miles to the north-east of Gôrakhpûr and on the road to Pipraich.

Jakahî Dîh, on the west bank of the Jakahî Tâl, seven and-a-quarter miles to the north-west of Gôrakhpûr. One mile to the east of this mound there is an old dih, called Sakhui.

Bhîti, nine and-a-half miles to the north-north-west of Gôrakhpûr.

Râjâ Bârî, on the east bank of the Râpti, 11 miles to the north-north-west of Gôrakhpûr.

Hb.

Пь.

¹ Cunningham, Archivological Reports, Vol. XXII, pages 65-72.

Kanapâr Gangâpâr, 11½ miles to the north-north-west of Gôrakhpûr.

Khâkukhûrî, 16 miles to the north-north-west of Gôrakhpûr.

Sarahrî Dîh, on a lake close to the east bank of the Rôhiṇi, 11 miles due north of Gôrakhpûr. Two miles to the east-north-east of this kherû there is a mound of ruins near the village of Tekriyâ.

Narkatahâ Dîh, on the Rôhiṇi, 14½ miles north of Gôrakhpûr. Matihaniyâ, about 20 miles to the west-north-west of Gôrakhpûr. Barâichâ and Matkopâ, 30 miles north-east of Gôrakhpûr.

IIb.

Ш.

IIb.

Ib.

16. Itava, hamlet in pargana Haveli of Sadr tahsil, eight miles north-east of Gôrakhpûr, possesses the dargâh of Abdûl Qâdir Hazrat, an object of pilgrimage.

17. Kahaon, small village in pargana Salimpur of tahsil Dêoriyâ, 46 miles south-east of Gôrakhpûr, is the ancient Kakubha, or Kakubhagrâma built on a low but extensive mound of brick ruins. Although the kherâ is of rather irregular outline on the east side, it may be best described as a square of nearly 800 yards. The village occupies the south-eastern quarter of the square, and contains some fine old wells built of very large bricks, which are a sure sign of antiquity. The other ancient remains at Kahâon consist of an inscribed stone pillar, two ruined temples, and several tanks. The tanks, which would seem to have been connected with the old buildings, are all called gar, probably another form of gaḍhā or gaḍhāiyā. These are the Purênagar, to the north of the village; the Karhāhîgar to the north-west angle of the ruins; and the Askāminî, or Akāskāminīgar to the east of the village.

The pillar, popularly known as Bhimsena's lât, is a single block of coarse grey sandstone, 24 feet three inches in height from the ground to the metal spike on the top. The existence of this spike shows that the pillar has once been crowned by a pinnacle of some sort, perhaps by a statue of a lion; but its height could not have exceeded two and-a-half or three feet. The total height of the column, therefore, must have been about 27 feet. The lower part of the shaft, to a height of four and-ahalf feet, is a square of one foot 10 inches; above this, for a height of six feet three inches, it is octagonal; then sixteen-sided for a height of five feet 101 inches, and then circular for a height of two feet one and-a-half inches. Above this, for a height of nine inches, the pillar becomes square with a side of 18 inches, and then circular again for a height of four and-a-half inches, making the total height of the shaft 19 feet 10½ inches. The height of the capital, in its present incomplete state, is four feet four and-a-half inches. The lower portion, which is two and-a-half feet high, is bell-shaped, with circular bands of moulding both above and below. The bell itself is reeded after the fashion of the Asoka pillars. Above this the capital is square, with a small niche on each side holding a naked standing Jain figure. The square top slopes backward on all sides, and is surmounted by a low circular band in which is fixed the metal spike.

On the western face of the square base there is a niche holding a naked standing figure, with very long arms reaching to his knees. Behind there is a large snake folded in horizontal coils, one above the other, and with its seven heads forming a canopy over the image, which represents the Jain Tirthamkara Pârsvanâtha. Two

¹ Cunningham, Archaelogical Reports, Vol. 1, pages 91-95; Vol. XVI, page 129.

small figures, male and female, are kneeling at the feet and looking up to the Tir-thankara with offerings in their hands.

On the three northern faces of the octagonal portion of the *lât*, there is an *inscription*¹ of 12 lines in Gupta characters, recording the dedication of five stone images of Âdikartṛis, or Tirthamkaras by one Madra in Gupta Samvat 141 during the reign of Skandagupta.

Immediately to the north of the pillar, and on the highest point of the mound, there are traces of the brick walls of two temples. General Cunningham presumes that the pillar must have been placed opposite the entrance of the temple in which the five Jain images were enshrined. It is probable that there were several temples and other buildings crowded around the pillar, otherwise it will be difficult to account for the great size of the mound, which, though not more than six feet above the fields, extends from west to east upwards of 1,200 feet, with an average breadth of 400 feet.

18. Kasîâ, village in pargaṇa Sidhuâ Jobnâ of tahsîl Parâûnâ, 37 miles east of Gôrakhpûr, has been identified by General Cunningham² with the celebrated Kuśi-nagara, which, as the scene of Buddha's death, was famous throughout India. This sacred spot was visited both by Fa Hian³ and Hiuen Tsiang,⁴ and the latter has left a detailed account of the various stûpas which still existed in his time. Most of these have now disappeared, owing partly to the removal of bricks by the villagers, but chiefly to the inundations of the little Gandak river, which at some former period must have flowed close by the sacred buildings of Kuśinagara, as there are several old channels between the two principal masses of ruins which are still occasionally filled during the rainy season.

The existing remains lie south-west of the village near the Khânuâ Nadî, and consist of a lofty mound of solid brick-work, called Devîsthân, or Râmabhâr Bhavânî; an oblong mound, called the fort of Mâṭhâ Kuâr, which is covered with broken bricks and jangal, and on which stands a much-ruined brick stûpa; a large statue of Buddha, the ascetic; a colossal statue representing Buddha's Nirvâṇa;

a low square mound covered with broken bricks near the village of Anirudhwâ, and a number of low earthen mounds like barrows, which are scattered over the plain to the north and east of the great mound.

The mound, called Devîsthân, or Râmabhâr Tîlâ, is the ruin of a large ancient stûpa of solid brickwork which is still 49 feet in height above the fields. It is situated somewhat less than one mile to the south-west of Kasiâ. On the top, under a fine old banyan tree, was once the shrine of Dêvî or Bhavânî; there is neither statue nor building, but only some votive figures în baked clay, the offerings of the poor people to their favourite Dêvî. The goddess is also called Râmabhâr Bhavânî, because the mound is situated on the western bank of the Râmabhâr Jhîl, a large sheet of water, which forms part of the bed of the Chakdawâ Nâlâ, one of the old channels of the little Gandak. As the mound is also called Râmabhâr Tîlâ, it is possible that this name may have originally belonged to the stûpa. The mound has been

Ш

¹ Journal, Asiatic Society of Bengal, Vol. VII. pages 36 to 38; Prinsep, Indian Antiquities, edited by E. Thomas, Vol. I, page 250; Corpus Inscriptionum Indicarum, Vol. III, page 65.

² Archaelogical Reports, Vol. I, pages 76 to 85; Vol. XVI, pages 120 to 125; Vol. XVIII, pages 55 to 101; Vol. XXII, pages 16 to 29.

³ Beal, Lc., Vol. 1, page LI.

^{*} Beal, Lc., Vol. II, pages 31 to 47.

thoroughly excavated, but nothing was found except a few lac seals. At the southeastern foot of the great stûpa are the remains of a small stûpa, formed of very large wedge-shaped bricks with a diameter of only 16½ feet.

The large mound, called Mâṭhâ-kuâr-kâ-kôṭ, or "the fort of the dead prince," i.e., Buddha, is situated nearly 1,600 yards to the west-north-west of Râma-bhâr Tîlâ, and is 600 feet in length from north-west to south-east, and from 200 to 300 feet in breadth. Towards the eastern end of the mound, at its highest point, which is 30 feet three inches in height above the plain, the kherâ is formed entirely of solid brick-work, the remains of a Buddhist relic stûpa of the usual type, viz., a round brick tower with a spherical roof. General Cunningham concludes that this tower was built between 200 and 600 A.D., on the débris of some older buildings. Its original diameter, now somewhat reduced, was about 27½ feet, and its original height would, according to the usual proportion, have been about 55 feet.

III.

Close to the west side of this great stupa, Mr. Carlleyle, during his excavations, discovered the famous Nirvâna statue of Buddha, just as it was described by the Chinese Ib. pilgrim, Hiuen Tsiang. It is quite certain that this statue is the same that was seen by the pilgrim, as there is an inscription2 on the pedestal of the mourning figure. beside the simhasanam, of two lines in early Gupta characters, recording it to be the meritorious gift of Haribala, the great master of the vihâra. The figure is colossal, 20 feet in length, and is represented lying on the right side with the right hand under the head, and facing to the west precisely as described by Hiuen Tsiang. The statue was enshrined in a vaulted temple, the inner chamber of which was 30 feet in length by 12 feet in breadth, the vault being constructed in the old Hindû fashion, such as is found in the great temple of Mahabodhi at Buddha Gaya. In this construction the radiating voussoirs are placed edge to edge, instead of face to face. The thickness of the walls of the temple, on a level with the floor, was nearly 10 feet, and the dimensions of the temple exteriorly, along the foot of the walls outside. were about 47 feet eight inches by 32 feet. But there was, besides, also an antechamber on the west side, which was about 35 feet 10 inches in length by about 15 feet in breadth outside, with walls about five feet thick, the dimensions of the interior being about 26 feet by 10 feet six inches.

This great vihâra has been roofed in and repaired by Mr. Carlleyle at his own expense and according to his own taste, to afford shelter for the colossal statue of Buddha's Nirvâṇa discovered by him on the mound in A.D. 1875. But the vihâra, which Mr. Carlleyle repaired, was not the original or most ancient temple, or at least not the only temple that had been built on the same site; for he discovered that the present temple was closely surrounded on three sides by the ruined remains of the base of another brick wall which extended from the front along the sides to within six feet of the back of the present temple, while it extended about 10 feet beyond the front of the present temple. The exterior outline of this low ruined wall presented a series of horizontal step-like ins and outs, the four corners being thus frittered off by a series of angular recessions. The dimensions of this outer building would appear to have been about 85 feet from north to south by about 50 feet from

¹ Cunningham, Archaelogical Reports, Vol. XVIII, pages 55 to 101; Vol. XXII, pages 16 to 29.

² Corpus Inscriptionum Indicarum, Vol. 111, page 272.

east to west. There were ancient steps running down from the west side of the base of the ancient temple. These ancient steps were lower than, and about 10 feet distant to, the west of the steps of the present temple; and the ancient steps probably originally reached down to the same level as the base of the lower plinth of the great stûpa.

The circular tower of the great stupa stands at the distance of only 13 feet to the east of the back wall of the vihâra. The vihâra and stûpa stand on one and the same plinth; for the plinth of the stupa is carried on westwards, as it continues to be visible along the southern and northern sides of the vihâra, and it terminates close to west or front of the temple. The original total length of the grand plinth from east to west was thus probably about 150 feet, the breadth of the plinth at its base from north to south being about 92 feet.

Close adjoining to the east side of the base of the lower plinth of the stûpa, Mr. Carlleyle excavated a row of five small stûpas of various diameters, viz., nine feet one inch, eight feet four inches, seven feet eight inches, six feet, and three feet 10 inches. Adjoining the south side of the basement of the great stûpa, he discovered another small stûpa, six feet in diameter, and in a very perfect condition; and in the course of his general excavations he found a numerous assemblage of small brick stûpas scattered over the eastern half of the great mound.

To the west-north-west of the great temple, Mr. Carlleyle uncovered a portion of the walls of two sides of some large building, which appears to have been probably a great monastery. The greatest length of this building from south to north appears to be about 120 feet, whilst the length of the building from east to west, as far as the excavation was carried, was only about 80 feet; but as the excavation at this side was not complete, it is probable that this side of the building was equally as long as the other, namely about 120 feet. It is not impossible that this building was a great equilateral quadrangle, with a court in the centre, surrounded by a series of chambers on all four sides.

During his excavations round the plinth of the great stûpa, Mr. Carlleyle found the following objects of interest:-a terra-cotta figure of Buddha, the teacher; a small sitting figure of Mâyâdêvî; two fragments of a canopy of a small statue, which from a fragment of a Kutila inscription on the back of one of the fragments would appear to have been a statue of Sâriputra, the most famous of Buddha's disciples; a small copperplate, four and-a-half inches by one inch, with the Buddhist creed formula inscribed in characters of the fifth century of our era; upwards of 20 burnt clay seals, with the Buddhist creed formula impressed upon them in characters of the eighth century; a statue of Buddha, sitting in meditation, with the Buddhist creed formula inscribed on the back in Kutila characters; a four-armed figure of Ganesa, and a broken statue of Vishnu. The scarcity of Brahmanical figures discovered in the various mounds, seems to show that Kusinagara boasted of very few Hindû temples.

About 400 yards to the south-west of the great stûpa there is a large statue1 of Buddha, known as Matha Kuar; it is of the dark blue stone of Gaya, split into two pieces from top to bottom, and otherwise much injured. The short Kutila inscription on its pedestal has been almost worn out by the villagers in sharpening

Ib.

¹ Journal, Asiatic Society of Bengul, Vol. VII, pages 477-479.

their tools. The figure itself represents Buddha Bikshu, seated under the Bodhi tree at Buddha Gaya. The whole sculpture is 101 feet in height by four and threequarter feet in breadth. The height of Buddha alone is five feet four and-a-half inches, the breadth across the shoulders being three feet eight and-a-half inches and across the knees four feet five inches. Close to the east side of the statue there is a low square mound, containing the base of a small square temple, about 23 feet exteriorly and about 10 feet square interiorly, in which the image was formerly enshrined. On excavating round about the walls outside, Mr. Carlleyle found a large slab of blue stone, with a mutilated Kutila inscription, measuring two feet 11 inches by 18 inches, lying near the wall on the south side of the doorway.

III.

Between the Mâțhâ Kuâr-kâ-kôt and the Râmabhâr Tîlâ there is a low mound of brick ruins about 500 feet square, which is said to have been a kôt, and to which no name is given; but as it lies close to the village of Anirudhwâ, on the north-east, it may be called the Anirudhwa Khera. There is nothing now left to show the nature of the buildings which once stood on this site; but from the square shape of the ruins, it may be conjectured with some probability that they must be the remains of a large palace. The adjacent village clearly derives its name from Anirudha, the cousin and disciple of Buddha; it is situated on a low mound of irregular shape which is mainly composed of the debris of ruins. General Cunningham identifies the mound and village of Anirudhwâ as the site of the ancient Buddhist city, in the middle of which the palace of the Malla nobles was standing, where Buddha's cremation took place.

About 1,400 yards westwards from the village of Anirudhwa and on the west bank of the Khanûâ Nâlâ, there is a small village called Râmnagar, situated on

III. a low mound.

Three thousand feet to the north-east of the great vihâra on the Mâthâ Kuârkâ-kôt, there is an ancient tank called the Kusmî Pokharâ; close to the south side of Kusmî Pokharâ there is a small village called Binâoliyâ, situated on a low broad-shaped mound of ruins.

III.

Ш.

On the plain lying between the Mâțhâ Kuâr-kâ-kôt and the Kusmî Pokharâ as well as on the plain lying between the Matha Kuar-ka-kat and the Ramabhar Tila, there are about 50 small mounds or barrows, from three to six feet in height and from 12 to 25 feet in diameter. These mounds are called bhimawat, or "fearsome spots" by the natives of the neighbouring villages; they are probably sepulchral. Megasthenes (300 B.C.) describes the Indian sepulchres as plain tumuli of low earth. But neither General Cunningham's nor Mr. Carlleyle's excavations of some of these mounds did result in any discovery, except a small quantity of a pale powdery substance resembling bone-ashes and a few minute dark-coloured particles resembling charcoal.

19. Khakhundû, village in pargana Salimpûr of tahsîl Dêorîyâ, 44 miles southeast of Gôrakhpûr, is said to be the ancient Kishkindapura, so called from Kishkinda, a mountain in Southern India, famous in the history of Râma. General Cunningham1 believes it to be the large village described by Hiuen Tsiang,2 in which a rich Brâhmana had spent his wealth in the magnificent decoration of a Buddhist monastery; whilst Mr. Carlleyle3 places this spot at the ancient town of Rudrapûr.

¹ Cunningham, Archaeological Reports, Vol. I, pages 85—91; Vol. XVI, pages 127—129.

³ Beal, Le., Vol. II, page 42,

Cunningham, Archeological Reports, Vol. XVIII, page 41.

Ib.

The extensive remains at Khakhundû consist of a few large tanks and of about 30 low mounds covered with broken brick and thick jangal. The ruins which lie III. scattered about over the plain and amongst the fields to the south of Khakhundû cover nearly one square mile of ground. All the larger mounds are square in form and are beyond all doubt the ruins of Brahmanical and Jain temples, whose overthrow General Cunningham attributes to the destructive power of the roots of lofty trees growing on the summits of these mounds. Only three of them have special names, the rest being simply called deora. The greatest mound is 120 feet square at base and 18 feet in height.

On the tops of the mounds many ancient and interesting objects are even now visible. There are four-armed figures of Vishau in blue stone, and representations of the same god under five of his ten avatâras; there are lingam and yoni of blue stone, and statues of Siva, Parvati, and Ganêsa. But there are also the stone foundations of several lingam temples, and fragments of moulded bricks, with flower ornaments.

In some cases the remains, whether sculpture or masonry, are distinctly Jain in character. There are statues of Adinatha, Santinatha, Parsvanatha, and Mahavira-16. nâtha, the statue of the latter being called by the people Jugbir, or Yugavira. There is also one good piece of sculpture representing two seated figures, entirely naked with the exception of some ornaments, male and female, the latter with a child in her arms. A tree rises behind them, and with its branches forms a canopy over their heads. The figures represent Naya and Trisala, the father and mother of Mahaviranâtha, or Vardhamana Nâyaputta, the 24th and last Tirthamkara of the Jainas, or Niganthas.

Though it now contains no Jain residents, Khakhundû has still a Jain temple; this is a modern structure, square, flat-roofed, and brick-built. Inside, squatting IIb. beneath a triple umbrella, is a large image in blue stone, of Vrishabhanatha, the first Tirthamkara. The temple is often visited by Baniyas and Agarwala Saraugis of Gôrakhpûr and Patnâ.

III. On a long low mound of ruins, to the south-west of Khakhundu, General Cunningham discovered the remains of an octagonal building of 14 feet across, with projections on the four sides facing the cardinal points, which he is inclined to believe a Buddhist stûpa.

20. Lâr, village in pargaṇa Salîmpûr of tahsîl Dêorîyâ, 52 miles south-east of Gôrakhpûr, possesses a Hindû temple, whose foundation is ascribed to Vasishtha, three Пъ. masjids, and an imâmbâra, which in design and workmanship is the best modern Muslim building in the district.

21. Majhaulî, village in pargaņa Salîmpûr of tahsil Dêoriyâ, 53 miles southeast of Gôrakhpûr, on the left bank of the Chota Gandak, possesses four Saiva temples, IIb. and a castle, the residence of the Majhauli Rajas, which is a block of commonplace brick buildings on a sandy bluff overlooking the Chota Gandak.

On the opposite bank of the river lies Salimpûr, which possesses two masjids. Hb. Two miles south-east of Majhauli, at the village of Kunara, also called III. Kundilpûr, are the ruins of a brick fort.

22. Motirâm-kâ-ADDâ, or Addâ Motirâm, a police outpost on the Dêorîyâ

road, eight miles south-east of Gôrakhpûr, is also known as Châh Shikasta, or

- the broken well; the bâoli being a large masonry structure in the dense sâl forest Ib. close by.
- 23. NICHLAVAL, an ancient village in pargana Tîlpûr of tahsîl Mahârâjganj, 51 miles north-north-east of Gôrakhpûr, contains the ruins of a large brick fort. III.
 - 24. PADARÂUNÂ, or Parâunâ, tahsil, 49 miles north-north-east of Gôrakhpûr, has been identified by General Cunningham1 with the ancient Pawa, both on account of its situation and the similarity of names, taking the name of the village to be merely another reading of Padaravana, which might have been shortened to Parban and Pâwâ. See, however, article on Chetiyâon.
- The remains to the south of Padarauna consist of a large mound covered with Ш broken brick and a few statues. The mound is 220 feet in length from west to east, 120 feet in breadth from north to south, and 14 feet in height at the western end above the fields. General Cunningham made an excavation on the highest part of the mound, and concludes that the mound must have been the site of a large Buddhist monastery, about 100 feet square, with cells on each side for the accommodation of the monks. In the centre of the courtyard, whose entrance was seemingly on the eastern side, stood probably a relic stûpa, as wedge-shaped bricks and bricks with rounded edges of two sizes as well as the base of a grey sandstone pillar were unearthed during the excavation.

In a small roofless brick building at a short distance to the north of this mound there are a few old sculptures. The temple is dedicated to Hathi Bhavani, most probably to Pârvati as mother of Ganêsa. The principal image, however, from which the temple derives its name, is not that of a Hindû goddess, but of some naked Jain Tirthamkara, squatting under a triple umbrella.

- IIb. About four miles east of Padarauna is the tomb of Barhan Shahid, said to have been one of Salar-i-Masaud's principal officers. The tomb of a martyr so called is also shown at Badaon.
- 25. Rânîghâr, village in pargaṇa Salimpûr of tahsil Dêorîyâ, 46 miles southeast of Gôrakhpûr, possesses on the banks of the Chotâ Gandak the remains of a very III. large brick fort.
 - 26. RUDRAPÜR, town in pargaṇa Silhat of tahsil Hâtâ on the eastern bank of the Mânjhuê river, 27 miles south-south-east of Gôrakhpûr, has been identified by Mr. Carlleyle2 with the large village where a hospitable Brahmana lived, who was devoted to Buddhism, and which was visited by Hiuen Tsiang3 on his way from Kusinagara, the modern Kasia, to Banaras. Its ancient name is said to have been Hamsakshetra.
- The ruins are situated mostly to the north, but also extend to the east and west of the town of Rudrapur. The great fort, called Sahankôt or Nathnagar, is III. situated about three-quarters of a mile to the north of the town. This great ancient fort is a quadrangle of which the sides are not equal. According to Mr. Carlleyle's measurements, the northern side is 2,500 feet in length, the eastern side 2,300 feet, the southern side 2,200 feet, and the western side 2,015 feet. There is also a sort of outer and lower enclosure to the south of the former, which measures 2,300 feet from

Beal, Lc., Vol. II, page 42.

¹ Archieological Reports, Vol. I, pages 74 and 75; Vol. XVI, pages 118 and 119.

² Cunningham, Archeeological Reports, Vol. XVIII, pages 41—52; Vol. XXII, pages 9 to 13.

III.

Ib.

III.

north to south by 3,700 feet from east to west; this was probably some outer shahr panah. The ramparts of the great fort are very high and broad, and vary in height from 15 to 25 feet.

IIb. Outside the fort and near the eastern side of it, there is the temple of Dûdhnâth (Śiva), which is much more modern than the ruins surrounding it. The original temple of Dûdhnâth appears to have been a plain square stone building, without any ornament, but the lower part of which has been encased within a modern closed-in brick verandah. The temple is surrounded by a broad round-topped octagonal dome which has a sort of small cupola on the top of it. There is nothing in the temple except a small lingam. The temple is surrounded by a walled-in court. Along the sides of the enclosure there are some four smaller modern shrines which are surmounted by tall pointed spires. There are several broken statues of various Brâhmaṇical divinities, as well as a small Jain figure within the enclosure.

III. There are about 25 isolated mounds of ruins round about Rudrapûr, which are nearly all the ruins of lingam temples, many with enormous black stone lingams still standing embedded in the tops of them. There are only four mounds that have even the outward appearance of stûpa mounds, and of these four two are oblong-shaped and huge lingams embedded in their tops, surrounded by traces of straight walls of a former temple.

There is, however, a conical stûpa-shaped mound, at a village called A m â o n î, about two miles to the north of Rudrapûr. On the top of this conical mound there is an enormous black stone lingam, which is encircled by three great rings of stone, the uppermost of which is an argha.

There is a long statue of Vishņu, about 11 feet in height, standing under a tree, to the east of Rudrapûr.

On a high square-shaped mound, close to the west of Rudrapur, Mr. Carlleyle found a broken Jain statue, with a partly defaced inscription in Kutila characters, dated Samvat 1161.

The whole extent of all the ruins, taken together, is about two miles from north to south, by from one and-a-half to two miles from east to west.

About six and-a-half miles to the south of Rudrapûr, there are some ancient ruins of considerable extent near two places called Barâon and Samôgar.

27. Sōнanāg, hamlet in pargaṇa Salîmpûr of tahsîl Dêorîyā, 50 miles southeast of Gōrakhpûr and three miles south-west of Salîmpûr, is remarkable as containing an ancient tank, 27½ bîghas in length from north to south, and a large mass of ruins and sculptures, apparently dating from the later Buddhist period. To the west of the tank and along its entire length rises a mound of large brick ruins, the extreme elevation of which is about 50 feet and the breadth in the widest part about 100 feet. The highest part was probably a relic stûpa, and the lower portion, which shows traces of a quadrangular building, a Buddhist vihâra.

On the highest top of the mound is a small ruined brick enclosure, containing a modern Hindû temple of the common type dedicated to Parasurâma. In this shrine are four Buddhist sculptures, locally known as Chaturbhuj Nârâyaṇa, Parasurâma, Kuvera Bhaṇḍâri, and Ranchhôr Tikam. In the same enclosure are some ruined Buddhist cloisters and the remains of a small lingam temple, with a black stone lingam,

known as Mahârudranâtha. Close by there is a ruinous temple, containing a small black stone image representing a man with a woman in his lap, known as Gauri Śańkara. At the base of the mound is a small ruinous temple containing a lingam, called Jhârkandi Mahâdêva, and two Buddhist black stone images in excellent preservation, said to represent Paraśurâma's parents, Jamadagni and Rêṇukâ. On the edge of the tank are the remains of an ancient stone ghât, and under an adjoining pîpal tree is a small Buddhist figure known as Laukus. The name seems to have been compounded from those of both Râma's sons, viz., Lava and Kuśa, that son of Râmachandra who was miraculously formed out of a handful of kuśa grass. Most of the statues discovered at Sôhanâg are of Buddhist origin, and have been appropriated by the Brâhmanical cultus.

The ancient name of Sôhanag is said to have been Nagapura, where Parasurama did penance to recover his divinity.

On the whole Sôhanâg is very interesting, and offers a good field for archæological exploration, as it seems never to have been excavated. It was probably one of a line of Buddhist cities extending from Bhâgalpûr Ghât on the Ghâgrâ to Kuŝinagara; the intermediate stages being perhaps Kahâon, Sôhanâg, Khakhundû, Dêorîyâ, and Târakulwâ, in all of which Buddhist remains exist.

28. Tărakulwâ, large village în pargana Shâhjahânpûr of tahsîl Hâtâ, 40 miles south-south-east of Gôrakhpûr, is situated on a great low mound of brick ruins, on which small Buddhist coins are frequently found in the rainy season. A short distance westwards there is a much higher dîh, apparently the remains of a Buddhist stûpa.

VII.-Mîrzâpûr District.2

1. Adhlésar, hill in tappå Upraudh, pargana Kantit of tahsil Mirzapur, 48 miles south-west of head-quarters, is a lofty, flat-topped peak, some 800 feet in height. It stands on the left side of the road leading from Mirzapur through Haliya and Dibhor into Rewa. It is said that there are several caves in the precipitous sandstone cliff near the top of the hill, but the lower slopes are so densely covered with jangal that none of the Kôl population ever attempt to ascend it. It is believed, however, that one of the Bijaypur Rajas managed to reach one of the caves by means of ladders, and that he found an image of Parvati.

The Adhésar Hill seems to be similar in its formation to the hill forts of Kå-lañjar and Ajaygarh, the lower three-fourths being comparatively easy slopes of granite, thickly covered with jangal, and the upper fourth being a bare bluff of sandstone. The hill itself is an isolated offshoot of the Kaimår Range, immediately facing the most easterly peaks of the Vindhya Tange on the opposite bank of the Adhwâriver. It is possible that there may have been some connection originally between the name of the river and that of the hill. The latter was probably named after the former, as the "hill of the Adhwâriver," which, after the adoption of the lingam stone by the Brâhmans, would naturally have been changed to the hill of Adhésar.

III.

¹ Cunningham, Archaeological Reports, Vol. XVI, page 125.

^{*} North-Western Provinces Gazetteer, Vol. XIV, Part II, pages 146-229, passim.

Cunningham, Archaeological Reports, Vol. XXI, page 125.

IIb.

Ia.

2. Agôrî Khás, village in tahsîl Robertsganj, 62 miles south-east of Mîrzâpûr, at the confluence of the Rehand and Sôn rivers, contains many ruins which testify to the III. former existence of a very large town, said to be the city of the Baland Rajas, which, according to tradition, was as large as Banaras. The only remains, however,

now standing are the fort and a few temples at Gothani.

The fort is picturesquely situated on a hill on the right bank of the Sôn. At the III. entrance some carved stones are embedded in the masonry, and the present fort was probably erected on the site of an older structure. The oldest portion of the present building is a gloomy, but admirably built, suite of rooms in the north-east corner. The stones are carefully hewn and fitted, and the roof has at first sight the appearance of being arched, as the stone beams of the roof have been placed on curved supports. This portion of the fort was built in A.H. 1026, or A.D. 1616, by Raja Madho Singh, the brother of Râjâ Madan Shâh, as is shown by a Persian inscription. In contrast to this part of the fort is the crumbling portion to the west, the clumsily rubble masonry of which dates as clearly from the Bâlwant Singh period (1745-81) as the similarly ill-executed and ill-preserved additions in the fort of Bijaygarh. Tradition, however, makes the fort the seat of the Bâland Râjâs, and would therefore throw back the date of its erection by seven centuries. But it is the custom in the neighbourhood to ascribe all great works to the Balands who are said to have retained Asuras, probably Bhars, as architects, and to have constructed the forts of Bijaygarh and Bardî in the Rewâ territory, and the large tanks at Pûr and Koradih.

The few temples at Gôt hânî, dedicated to Sobhnáth (Siva), are commonplace buildings, and neither of archæological nor architectural interest.

3. Ahraurā, town in tahsîl Chunâr, 32 miles east-south-east of Mîrzâpûr, lies near the foot of the Sukrit Pass in the Vindhya Range. At the back of the town is a

fine, flat-topped hill said to have once been the site of a Kôl fort.

III. About three miles to the south, in the gorge of the Sukrit Pass, is the ruined stone fort of Latifpür. It is of rectangular shape, enclosing a considerable area, two III. sides being protected by the precipitous banks of a deep stream, and the other two by a solid stone rampart and ditch. The buildings which are now but a shapeless, though picturesque, mass of jangal-clad ruins, are said to have displayed considerable signs of architectural taste. In some passes leading towards this fort, there are some small stone garhis or redoubts, built for the protection of outposts.

The great number of old forts and castles scattered along the outskirts of the Vindhya Range is a very striking indication of the insecurity of person and property

in former times; but all are now deserted and in ruins.

At the village of Rasûlpûr, close to Ahraurâ, is the tomb of a quasi-shahîd IIb. Said Ashraf Ali, an object of pilgrimage from the surrounding districts.

About one and-a-half miles to the south of Ahraurâ is the small village of Belkhâra;1 lying in a field near it there is a stone pillar, 11 feet seven inches long and 15 inches in diameter, with two inscriptions. Above there is a small figure of Ganêsa, with a few letters, and between the two inscriptions there is a bird and a still ruder horse. The upper inscription is a record of Raja Lakhana Dêva of

³ Cunningham, Archeological Reports, Vol. XI, pages 128 and 129.

Kanauj, dated Samvat 1253, or A.D. 1196. This document is interesting from its date, which is just three years after the final defeat and death of Jayachchhandra, the last Rathôr king of Kanauj. It must have been close about this very date of A.D. 1196 that Muhammad Bakhtiyâr Khiljî received the two districts of Bhâgwât and Bhûîlî in fief together with Patîla and Kuntilâ, I all of which places are in the neighbourhood of Chunar. But the inscription takes no notice whatever of the Musalmân conquest, and speaks of the Hindû kingdom of Kanauj as if it were still in existence.

About nine miles to the east of Ahraurâ, at the village of Hetunpûr, are about 21 pieces of at least 15 square stone obelisks collected near a modern temple, the largest being 13 inches square and five feet seven and-a-half inches high. It is divided into seven compartments on each face, each containing a small sculpture. There are men and women dancing; a single woman dancing and playing on an instrument; a man killing an animal; a man standing near a house; a man sitting over a prostrate body with a fish's tail; a large fish; and several scenes representing the Varâha and Narasimha Avatâras. The top of the obelisk is crowned with a low pinnacle like that of a temple. Amongst the smaller obelisks General Cunningham noticed several other objects: such as a sow with six small pigs; a woman lying on a bed; two women with swords and shields; a woman and child churning butter; a man and a horse; a woman seated and kissing her child. Along with these there is a large figure of Hanumân treading on a kneeling figure; he has a small sword resting on the right hip, his right hand being placed above his head and the forefinger of his left hand upraised.

Apparently General Cunningham is right in attributing these monuments to the aboriginal races, especially to the Sûîrs, or Śabaras of Sanskrit writers. Amongst them the principal objects of worship are Hanuman and Bhainsasuri, the great buffalokilling goddess.

There are similar-shaped obelisks at Bhûîlî, Mangraur, and Chayanpûr in the Mîrzâpûr district, at Baijnâth and Daraulî in the Shâhâbâd district of Bangâl, at Patharî in Mâlwâ, and at Mârkandâ in the Chânda district of the Central Provinces.

4. Ahugî,³ old village in tappâ Upraudh, pargaṇa Kaṇṭit of tahsîl Mîrzâpûr, 38 miles south-west of head-quarters, is situated on the road between Haliyâ and Dibhôr at the point where it divides into two branches, one going direct to Dibhôr and Bhopâri (Rewâ), and the other to the east of the Adhêsar Hill to Bardî (Rewâ) on the Sôn river. The houses of the village are scattered along both banks of the Adhwâ river, which here flows in a deep channel with plenty of water. Its favourable situation amongst fine old trees on the banks of a running stream must have led at an early date to the selection of Ahugî as a halting-ground for the Banjâra merchants, and afterwards to its occupation by the Brâhmaṇs as a pleasant site for their temples. There are, however, no temples now standing, but there are many ruins of stone temples both to the north and to the west of the village, beside numerous statues.

Ib.

¹ Raverty, Tubakāt-i-Nāsiri, pages 549 and 550,

^{*} Cunningham, Archeological Reports, Vol. XI, page 131.

² Cunningham, Archaeological Reports, Vol. XXI, page 126.

Hb.

Hb.

III.

 Πb .

III. On a low mound to the west of the village, there are the ruins of a Saiva temple, of which the sill, one jamb, and the lintel of the entrance to the sanctum still remain on the ground. The lintel has a figure of Siva, four-armed, seated in the middle, with Brahmâ to his right and Vishņu to his left. There is a single pilaster, five feet five inches in height, and a standing figure of Sûrya, three feet two inches high, with Aruṇa on the pedestal, and five horses.

III. To the north of the village there are the remains of three small lingam temples. The first temple is facing the west, the interior being only three feet nine inches by three feet, while the walls are formed of single upright slabs only four and-a-half inches thick. The entrance of the second temple is to the east; the interior is only four and-a-half feet by four and-a-quarter feet, and the walls are formed of single slabs containing figures in panels, amongst which Ganesa, Bhainsasuri Dêvi, and Durga are chiefly represented. On a long flat slab a few letters are still visible, which are sufficient to show that the temples belonged to the mediæval period of about 1000 A.D. The third temple is similar to the east, but is much more broken.

5. Аконнî, village în tappâ Upraudh, pargaṇa Kaṇṭit of tahsil Mîrzâpûr, 11 miles west of head-quarters, possesses several temples of some local repute, on the banks of the Pahârl Nadi, but none of any architectural pretensions.

6. Ashtabhuja, eight miles south-west of Mîrzâpûr, and two and-a-half miles south-east of Bindhachal, is a noted place of pilgrimage on the most northern The name of the place is derived from the tutelar spur of the Vindhya table-land. deity, Ashtabhuja Dêvî, one of the numerous titles of Parvatî. The pilgrimage hither is usually an adjunct to the worship at Bindhachal. The pilgrims proceed by the old Mirzâpûr and Allâhâbâd road to the foot of the hill, where there is a tank, fed by a perennial spring, known as Sîtâkund. Thence two flights of steps lead to the brow of the hill, one old and comparatively deserted, and the other lined with shrines of great sanctity, but of no architectural pretensions. Arrived at the summit, the pilgrims pass across the plateau to the opposite declivity, about a mile distant, where another handsome staircase leads to the Kali Khô, the cave of Kali, with a halfruined temple. Thence the route leads back, directly across the plain, to Bindhâchal. Below the first ascent is a large and ancient mango grove; and the slopes being similarly wooded, the temples have a pleasing and picturesque effect from a distance, which their squalid surroundings somewhat dispel on closer inspection.

7. Baraint, village in talûka Majhwâ of tahsîl Mîrzâpûr, nine miles north-east of head-quarters, on the north bank of the Ganges, possesses a large stone temple, a conspicuous object in the landscape, and a three-storeyed satî monument, still the object of considerable veneration.

8. Bhadohì, ancient capital of the pargaṇa of the same name, in tahsil Family Domains of the Mahârâjâ of Banâras, 21 miles north of Mîrzâpûr, is now much decayed, and retains little of its former importance. The first settlements on the spot seem to date from a period anterior to the Musalmân conquest, and to have been made by the Râj pûts shortly after the expulsion of the Bhârs; but it is to its Musalmân rulers that it owes whatever it has of importance. It is said that Saïd Ibâd-ullâh, one of Shahâb-ad-dîn Ghorî's officers, reduced this part of the country. The first regular settlement of Musalmâns, however, in this part of the country seems

to have been in the time of the Sharqî dynasty of Jaunpûr. The ancestors of the still resident Qâzî family claim to have come in the time of Bâhlôl Lodî, when Abd-ul-Mulk was appointed Khalîfa of the pargaṇa; Abd-al-Karim was appointed Qâzî in the reign of Shêr Shâh. Akbar confirmed the Qâzî in his appointment, and appointed Nawâb Shêr Khân as governor, who built a fort, now utterly in ruins, around which the town grew up. None of the present masjids is of any note. At Marjâd patti close by is a dargâh copied from the tomb of Saïd Sâlâr Ghâzî at Bahrâich, where a melâ is held every year.

III.

IIb.

Ha.

III.

III.

Ib.

The pargaņa is almost entirely destitute of architectural monuments. The only building worthy of notice is an old Saiva temple in a magnificent grove of tamarind trees at Samradh on the banks of the Ganges. This temple which is now partially sunk in the ground, is solidly built of stone, in a simple and massive style, almost without any ornament. The forts of the Môna occupants of the pargaṇa were constructed of mud, and are now mere shapeless mounds; the ruins of their stronghold at Suriânwân, however, are still to be traced, and there are two fine tanks, the larger of which is 30 acres in extent. The earlier strongholds along the banks of the Barṇâ, known as Bhâr dîhs, apparently the ruined sites of Buddhist cities, evidently had within their circuit large brick buildings; but of these nothing but the foundations, the neighbouring tanks, and heaps of broken moulded bricks remain. Nothing bearing upon early history has been discovered, but the pargaṇa has never been the scene of a systematic archæological survey.

9. Bhữtht, village in tahsil Chunar, 30 miles east of Mîrzapûr, contains a ruined fort on the hill above the village. The derivation of the name is not known, but General Cunningham suspects it to be connected with the great tribe of Bhûias, and that it may be only a slightly altered form of Bhûiala.

The Bhûias are by far the most numerous class in the Mîrzâpûr district, they are evidently the aborigines or old inhabitants of the country, the proper application being bhûmyâs, or autochthones, a title given to them by the Brâhmans. They generally call themselves Musahar, which points to some connection with the Saharîyas, or Śabaras. One great branch amongst them takes the title of Rikhiâsan, and claims to be descended from Rishyasringa.

Of the few objects discovered, an inscription of Qutb-ad-dîn Mubâraq Khiljî (A.H. 716—720), of five double lines, let into the lower wall of a masjid in Dakhin Tôlâ, is of some interest; unfortunately, however, it is much injured. At the same place also there are three Hindû pillars and a bracket capital.

IIb. In the hill to the south there is a cave dargâh of Makhdûm Sâhib Chirâgh-î-Hind. It is whitewashed inside, and no inscriptions are visible; it is only a small room of eight feet by six feet and six feet high. There is also a rock shelter called Chilam marfia, 15 feet by 12 feet and six and-a-quarter feet high. Near it there is a curious natural monolith, five and-a-half feet in height, or with its base and pinnacle, nine and-a-half feet. It is reckoned a curiosity, as the shaft is considerably curved.

A little further there is another cave, called khō, containing two early Kuṭila inscriptions cut on the rock inside; one of them is quite illegible, and the other is a short record of a pilgrim. The cave is simply an enclosure made of three walls under

¹ Canningham, Archaelogical Reports, Vol. XI, pages 130 and 131; Vol. XXI, page 130.

an overhanging rock, with the rock for the back wall; the room is nine feet seven inches long by seven feet nine inches broad.

- In the neighbourhood there are some square stone obelisks, with curious carvings Ib. on all four faces, attributed to the Sûîrs, or Śabaras. The scenes sculptured on them are either ordinary occurrences of life, such as a woman suckling a child, or monstrous ones, such as a man astride on a serpent. A figure often repeated seems to represent a man in the act of killing a buffalo.
- Πa . 10. Bijayagarh, hill fort in tahsil Robertsganj, 60 miles south-east of Mîrzâpûr. lat. 24°-34′ N., long. 83°-13′ E., is 2,017 feet above the sea-level and about 800 feet above the table-land from which it rises. The position is one of great natural strength, the hill being steeply scarped all round and accessible only by two difficult paths. The approach to the fort from Robertsganj is by a massive and evidently ancient bridge Ib. over the Gaghar Nadi. This bridge bears a Sanskrit inscription, recording its erection by Bâlwant Singh, in Samvat 1829; but for "erection" we should read "restoration," as the body of the work is evidently much older, and probably dates from the time of Shêr Shâh. The bridge consists of 11 arches, small in width, and with massive piers between. It has a fortified gateway, and is further protected by a square fort on a small eminence close by, connected with the bridge by a curtain wall. From the bridge the path to the fort rises some distance by an easy slope; along which at intervals are the remains of ancient outworks. It then suddenly rises by an abrupt ascent of some hundreds of feet through close jangal to the entrance of the fort, which is by a triple gateway, apparently of Pathan architecture, but with much later and more flimsy restoration. Within there is an area of nearly three miles in circumference, surrounded with a continuous masonry rampart with circular bastions at irregular intervals and pierced for fifteen guns.

Near the gateway is a tomb said to be that of Said Zâin-al-Abdin, the Mîra Sâhib of local fame. Here again is one of Bâlwant Singh's tablets with the date Samvat 1829; there is said to be another inscribed stone close by with the date Samvat 1300. Near the tomb of Mîra Sâhib is a tank known as Mîra Sâgar, and beyond this another known as Râma Sâgar; both are hewn out of the solid rock and never run dry even in the hottest seasons. Between the two tanks is the Rang Mahal of Bâlwant Singh, and beyond the Râma Sâgar another palace, called Shish Mahal; but neither of these buildings is in any way noteworthy, and both are rapidly falling into decay. There is little else within the enceinte deserving notice.

The fort, like most of the strongholds which crown the natural fastnesses of the Kaimūr Range, is of uncertain foundation. It seems to have been a stronghold of the Kôls or of some other aboriginal race, and is attributed to Asuras, or demon architects. Two hostile demons, as the story runs, vowed to each other that whichever first built a fort should be the conqueror, and that the losing party should forfeit his life. They commenced their labours in the evening, one on the Bijayagarh hill and the other on the top of Kandâkât, a hill of similar shape about 12 miles to the west in pargana Barhar. The demon of Bijayagarh having lost his tools in the dark, struck a light to find them. His adversary, imagining that the fort was completed and that instant death awaited him, fled precipitately, while the Bijayagarh fort was completed during the night. The fort is next found as a fortress of the Bâland Râjâs, and it

passed with their kingdom into the hands of the Chandellas of Agôrî-Barhar; but the local tradition, with every show of probability, assigns the design and completion of the present works, excluding the later and flimsier work of Bâlwant Singh, to 8hêr Shâh. Indeed, there is an extravagant legend of a subterranean passage connecting Bijayagarh with Rohtâs garh in the Shâhâbâd district of Bangâl. On the dissolution of Shêr Shâh's empire, the Chandellas appear to have regained possession and held the fort till it was seized by Bâlwant Singh; since the expulsion of Chait Singh, it has remained nazûl of British Government.

11. BINDHÂCHAL, large village in tappâ Chhiânave, pargaṇa Kaṇṭit of tahsil Mirzâpûr, seven miles south-west of head-quarters, is celebrated throughout a great part of India for its temple of the goddess Vindhyêśvarî, which is, however, an ugly square building with no attempt at embellishment of any kind. The ancient town of Bindhâchal, or Vindhyâchala, famous in the Purâṇas, is said to have been included within the circuit of the ancient city of Pampâpura.

IIb.

III.

IIb.

ш.

IIb.

To the east of Bindhâchal are the remains of a fort, from which spot, in a westerly direction, ancient remains are found in great abundance, broken bricks and stone débris lying scattered over the fields for several miles. From its size and the substantial nature of the buildings which, judging from the relics it contained, this ancient city must have been of sufficient importance to be the capital of the country. Tradition says that the city once possessed 150 temples, all of which were destroyed by Aurangzîb. This is perhaps an exaggeration; but there is little reason to doubt that there were formerly many magnificent temples on this spot.

About three-quarters of a mile to the south-east of Bindhachal is the village of Kantit, possessing an old masjid, now entirely modernised, and the extensive debris of a fort, probably originally the citadel of ancient Pampapura. Of this only the mud ramparts and ditch and a few scattered fragments of masonry walls remain.

About one and-a-half mile to the west of Kantît lies the village of Sêopûr.1 In former days it possessed a very large temple, of which the ruins now lie scattered about. The present temple of Ramesvara Natha contains many large capitals, and III. there are numerous broken sculptures and other remains in the neighbourhood. The most striking object is a life-size female figure seated on a throne with a child in her lap; the sculpture is five feet two inches high by three feet eight inches broad, and one foot eight inches deep. The face is gone, but a small figure of a Buddha or Tirthamkara still remains on the top of the head. The right arm is broken at the elbow, and the left arm supports the child. The left knee is bent, and the leg is resting on the ground at the foot of the throne. At the back of the figure there is a large tree with foliage and flowers. At the foot of the throne under the left leg there is a lion. There are seven attendants on each side, two flying and five standing. The statue is now called Sankațâ Dêvî, and General Cunningham believes it to be a representation of Shashtî, the goddess of Fecundity; but it is more likely a representation of Trisala, the mother of Mahaviranatha.

12. Chakia, village in pargaṇa Kêra Mangraur of tahsîl Family Domains of the Mahârâjâ of Banâras, 44 miles east of Mîrzâpûr, possesses above the falls of the Karamnâsâ in a very picturesque situation the mausoleum of Latîf Shâh, a celebrated

¹ Cunningham, Archaeological Reports, Vol. XXI, page 130.

local saint, but the architecture of the monument is hardly commensurate with its sanctity.

formed his devotions. In November, 1888, the Military Works Department found a 1b. so-called cave temple during the progress of a retaining wall for No. 2 Battery, in the south-west corner of the fort. It contains sculptures of Siva, Pârvatî, and Bhairavâ beautifully cut on the rocks, bearing short dedicatory inscriptions in characters of the sixth century A.D. As the fort is still used as a fortress, no further description of it can with propriety be given; it has contained a State Prison since A.D. 1815.

The fancied resemblance of the ground-plan of the whole upper surface of the rock to a gigantic footstep, with the toes and ball of the foot projecting into the river and the heel towards the land side, has apparently given Chunâr its name, which is an abbreviation of Charanâdri, or footstep hill. Of course, tradition says that it is the real foot-print of some divine being of the *Dvâpara yuga* who, in stepping from the Himâlayas to Cape Komorin, rested his foot upon this hill, and impressed it with his mark.

The ancient history of the fort is obscure. We are told that Bhartṛinâtha, the younger brother of the famous Vikramâditya of Ujjayinî, having embraced the life and profession of a yogi, selected as his place of retirement the rock of Chunâr. Vikramâditya is said to have discovered the hiding-place of his brother and to have visited Chunâr and built for his brother a residence, the present temple of Bhartṛinâtha. The next name in the legend is that of Pṛithvîrâjâ, who is reported to have effected a settlement in this part of the country. After his death the country was taken from his successors by Khair-ad-dîn Subaktgîn. It appears, however, from a mutilated Sanskṛit inscription,¹ dated Samvat 1390, or A.D. 1333, over the gateway of the fort, that the place was again recovered by Svâmî Râjâ, who put up the stone to commemorate the event. The fort was finally acquired by the Musalmâns through the skill of Mâlik Shahâb-ad-dîn, one of Muhammad Shâh's generals.

Shêr Khân Sûr, the great opponent of Hûmâyûn, obtained possession of Chunâr by marriage with the daughter of a local chieftain, into whose power it had

Journal, Asiatic Society of Bengal, Vol. V, pages 341 to 347.

fallen during the disorders antecedent to the consolidation of the empire of the house of Taimur.

In A.D. 1536 Humâyûn besieged the fort and took it after a siege of six months, conducted under the direction of his General, Rûmî Khân. Humâyûn then continued his advance on Bangâl, but Shêr Shâh shortly afterwards retook Chunâr, and thus cut off Humâyûn's communications, and intercepting him on his return, utterly destroyed his army.

It was not until 1575 A.D. that the fort was recovered for the Moghals by the armies of Akbar, whose conquest of Bangâl and Bihâr, of which Chunâr was the key, was facilitated by the miserable condition into which the debased and effeminate successors of Shêr Shâh had by their misrule brought these provinces.

At the disruption of the empire, Chunâr fell into the hands of the Nawâb Vazîr of Audh; and through all the subsequent aggressions and intrigues, it remained the one place which Bâlwant Singh was not able or did not dare to reduce into his possession. In 1764 Chunâr was beseiged by a British force under Major Munro, and in 1772 the fort was formally ceded by treaty to the East India Company.

About a mile from the fort is the dargah of Shah Kasim Sulaimani, a building of considerable architectural pretensions, situated in the south-west corner of the town. The saint whose remains are here interred is said to have been an Afghan by birth, and to have lived in the reigns of Akbar and Jahangir. Losing parents, wife, and child at the age of 27, he betook himself to a holy life, and set out to visit the sacred places at Makkâ and Madînâ. The prestige gained by his pilgrimage procured him on his return a considerable following of disciples, and he unfortunately excited the anger of the usually tolerant Akbar by declining to subscribe to that monarch's peculiar view on religion. During Akbar's reign he was not molested further than having his place of residence fixed at Lahor; but on the accession of Jahangir, his enemies represented to that Emperor the danger of allowing Shâh Kâsim to attract so large a number of followers. At first, Jahângîr appears to have contemplated punishing the faqir with death, as he had done in the case of many others in Lahor who were suspected of favouring the claims of Sultan Khuzrů. Better councils prevailing, Shâh Sulaimânî was sent a prisoner to Chunâr in A.H. 1015, or A.D. 1606, where he died the following year. His disciples erected the mausoleum in A.H. 1016 as recorded in an Arabic inscription on the principal entrance gate, the Nakkashî darwaza, and his two sons were installed as chief attendants. Even Jahangir recognized the sanctity of the shrine by a grant to the saints' sons of 30 bighas of land in the adjacent village of Tikor. One of these sons, Shah Kabir Bala, himself became a saint, and his disciples erected a mausoleum to his memory at Kanauj. Another son, Muhammad Wasit, and two grandsons, Muhammad Afzal and Muhammad Haqim, were honoured with tombs near to that of Shah Kasim, built in A.H. 1028, or A.D. 1618. Other buildings attached to the dargâhs are, a small masjid, the Fawâra Sâwan Bhâdon, or the fountain of the rainy season, and the Rang Mahal, on the corner walls of which are engraved the first six couplets of the beginning of Jami's Yusuf-o-Zulaikhâ, with the date A.H. 1028. The buildings and the grove within which they stand are very solemn and striking; the carving of the principal gateway, and of the stone lattice

IIb.

IIb.

IIb.

Ш.

Ib.

Ib.

III.

with which the garden is enclosed, is more like embroidery than the work of the chisel. The dargâh is said to have suggested to Shâh Jahân the design of the Tâj at Âgrâ.

About half a mile up a narrow ravine to the south-south-west of the railway station at Chunar is a perennial pool, called Durga kund. On the north side of the ravine stands the temple of Kâmâkshî Dêvî, and just below it a small old temple without name. The ravine or Jhirna Nala, is spanned by a bridge, which leads to a row of three dâlâns or cloisters, formed by building against the face of the rock. Against the back wall there is a low platform, or seat, 15 inches high and 16 inches broad, which was probably intended for the reception of statues. Sculptured on the rock there are several figures of lions, horses, and elephants in outline. The face of the rock is five feet three inches high, above which the required height was obtained by building up. The beams and pillars of the present arcade are quite new. The whole back wall is literally covered with short inscriptions of all ages from the Gupta period downwards. There is nothing amongst these records of any interest, except perhaps the juxtaposition of the names of Chandra and Samudra. As they are in old Gupta characters, similar to those used upon the coins, it is possible that the names may refer to the two kings, Chandragupta and his son, Samudragupta. Most of the names appear to be those of the quarrymen or stone-cutters, who occupied the rock shelter which has been turned into a long arcade.

Similar records are also cut in the rock of the Durgâ khô, or Durgâ's cave, a little further up the ravine, near which an annual melâ is held on the ninth day of the Durgâpûja festival. The cave itself is simply an old quarry, which has been turned into a dwelling by building up two pillars under the edge of the overhanging rock in front so as to form a room. The inscriptions are of considerable antiquity, several of them being of the Gupta period, and are chiefly the personal records of pilgrims who have visited the cave of Durgâ, where she is said to have sprung out of the rock.

14. Dтвнов,² hamlet in a narrow valley of the Vindhya Hills in tappå Upraudh, pargaņa Kaṇṭit of tahsil Mirzāpūr, 43 miles south-south-west of head-quarters, possesses a small temple of the modern Mirzāpūr type, only 10 feet nine inches square. There is a long Sanskrit inscription of 22 lines of raised letters in the verandah of the temple, describing its erection by Śrimân Nâyak Mân Môr in Saṁvat 1881, or A.D. 1825. Close to the temple there is a fine tank, 430 feet in length from north to south by 352 feet in breadth, with steps all round.

About two and-a-half miles to the north-east of Dibhôra, and close to the Rewâ village of South Lohâri, there is a perennial spring, called Turâ, near the top of the hill. Close by the spring there is a rude stone cell that was formerly occupied by a sâdhû. The people call the cell a cave, but it is simply an irregularly-shaped room built of rough stones; it is only six feet long by four feet broad, covered with a flat roof. Formerly there was a second room, six feet square on the east side, but it has now fallen in. The cave, or cell, is approached by a flight of steps on the east

¹ Cunningham, Archaelogical Reports, Vol. XI, page 126; Vol. XXI, page 128.

^{*} Cunningham, Archaelogical Reports, Vol. XXI, page 126.

² Cunningham, Archeological Reports, Vol. XXI, page 121.

side. The spring flows out from beneath, the cave and its course is marked by a green truck right down to the foot of the hill. There is no inscription in the cave.

15. Halívá, village in tappá Upraudh, pargaṇa Kaṇṭit of tahsil Mirzâpûr, 31 miles south-west of head-quarters, is situated on the right bank of the Adhwa. It possesses an old mud fort, once doubtless of use as commanding the ford of the Adhwa Ш close to the village. The place was formerly of much importance as a haltingplace on the old route of the Dakhin trade which passed through Haliyâ to Mîrzâpûr from the Dibhôr and Kerâhi passes; but it has lost most of its importance since the new road by the Katrâ Pass from Mîrzâpûr to Rewâ was completed. Ia.

On the bank of the river, on a high point above the road, there is a large flat slab, seven feet eight inches high by four feet six inches broad, with two long inscriptions in English and Hindî, describing the capture of the fort of Bhopâri (Rewâ) on the Sôn river on 18th April, A.D. 1811, by a regiment of native infantry. Both inscriptions are rather roughly cut.

16. Karsorā, small village in pargaņa Barhar of tahsîl Robertsganj, 30 miles south of Mirzâpûr, possesses a large irrigation tank, formed by a massive masonry dam III. thrown across the head of a shallow valley. The work is referred by the people vaguely to the Bhars, but is probably the work of the Baland Rajas of Agori.

17. KERA MANGRAUR, pargana of tahsil Family Domains of the Mahârâjâ of Banâras, lies along the eastern border of the Mîrzâpûr district, and stretches from the Ganges southwards to about the centre of the Vindhya Range. It possesses very few.

At Bhikampûr and Sikandarpûr are the scanty remnants of ancient forts dating from Gaharwar times; but these are now little more than heaps of stone.

On the precipitous cliff overhanging the great fall of the Chandraprabhâ, there is a large enclosure, surrounded by a high wall of dressed stones. This is called by the people the kôt of Râja Pûrva, and the fall is in consequence known as Pûrvadarî. The enclosure contains no buildings, and was probably meant solely as a place of refuge in troublesome times.

At Muzaffarpûr on the Chandraprabhâ, shortly after it issues from the hills, and where the dam which diverts its waters in the Bahachandra canal is erected, are the remains of a Chandella temple built of large dressed stones put together without

In the north-eastern extremity of talûka Naugarh there is a very singular dell, called Amchuhā. It is a deep cleft in the mountain, formed by the bed of a small torrent, dry in the hot weather. A reservoir excavated in the solid rock remains constantly full of delicious fresh water, being fed apparently by percolation from the rock. The descent to the dell is exceedingly steep, and beneath a projecting rock, which overhangs the reservoir, is a deep cavern which presents the beau ideal of a sadhii's cell.

More than one of the hill tops of the Vindhya Range bear the half-obliterated signs of fortifications, which the people, probably with correctness, attribute to the

18. Koradin, small village in pargaṇa Bhagwat of tahsil Chunar, 28 miles southeast of Mîrzâpûr, is situated on the banks of a large artificial lake, similar to the one at Ш

III.

III.

III.

¹ Cunningham, Archaological Reports, Vol. XXI, page 121.

Hb.

IIb.

Ш.

IIb.

III.

III.

Karsota. It is said to have been constructed in the time of the Baland Rajas. Within a range of 10 miles there are two other lakes larger than this referred to the same era.

19. Mîrzîpür, capital of the district, lat 25°-9′ N., long. 82°-38′ E., being of modern origin, affords little scope for antiquarian research. No buildings of considerable size or boldness of outline rise from the banks of the Ganges; the ghâts, though numbering more than a score, great and small, are with four exceptions small in size and feeble in design; and many, from the insecurity of their foundations, are in various stages of ruin and decay. But the clusters of temples at Bariâghât and Nârghât, and the graceful arcades, massive piers, and broad stairways of the Pakkâ and Tirmohâni ghâts are worthy of more than passing notice. Many of these temples, however, enshrine ancient statues and decorative pieces of sculpture of apparently ancient date. The temple of Vindhyavâsinî at Bariâghât claims a hoary antiquity; but the present building is comparatively modern, having been erected in succession to one which the Ganges swept away, the ruins of which are still visible when the river is at its lowest. The finest site along the whole line, that whose name, the kôt, recalls the memory of an entirely obliterated and forgotten fort, is occupied

In the town itself are few buildings of note, the only ones whose towers break the sky-line being a couple of modern masjids of no great pretensions, the largest of which the town owes to Ganga Bibi.

by the dismal ruins of immense warehouses.

- 20. Patīta, village in pargaņa Bhāgwat of tahsîl Chunâr, 32 miles south-east of Mîrzāpūr, possesses a large mud fort, once one of the principal strongholds of the Musalmān zamindārs of the pargaṇa in the last century.
- 21. Pûr, village in pargaṇa Barhar of tahsîl Robertsganj, 34 miles south-east of Mîrzâpûr, is remarkable for a large masonry tank, attributed to a certain Arjan, a Râjâ of the Gadaria caste; but the work is similar to the other monuments of Bâland supremacy in these parts, and may probably be referred to that dynasty.
- 22. Saktîsgarh, small village in pargaņa Kaņţît of tahsîl Chunâr, 22 miles south of Mîrzâpûr, is only interesting from its connection with the fort, erected by Sakat Singh, to control the Kôls in the reign of Akbar. This stronghold is situated just at the mouth of the gorge by which the Jirgo river debouches from the hills. It consists of a small, plain, rectangular building of stone, with flanking towers at the corners, enclosing a two-storeyed building, the decorations of which in glass mosaic have obtained for it the name of the Shîsh Mahal. Around the fort there is a considerable enceinte enclosed on two sides by projecting hills, and towards the plain by a rampart and ditch, which must have formed a place of refuge for the neighbourhood in times of invasion. Inside this area there are the foundations of a small temple.

VIII.—LAKHNÂÛ DIVISION.1

I.—BARA BANKÎ DISTRICT.

- 1. Alîâbân, town in pargaņa Rudaulî of tahsîl Râmsanehî Ghâț, lat. 26°-56' N., long. 81°-41' E., 30 miles east of Bara Bankî, is supposed to be about five hundred years old. The size and number of the now dilapidated buildings attest III. its former importance.
- 2. Baddê Sarâî, village in tahsîl Fathpûr, lat. 27° N., long. 81°-30' E., 20 miles north-east of head-quarters, said to have been founded some 500 years ago by Baddû Shâh, a faqîr, possesses the dargâh of Malâmat Shâh, which is considered a place of great sanctity in the neighbourhood. $\Pi b.$
- At a distance of four miles east-south-east of the village is the temple of Jagannâtha Dâsa, with a fine brick tank in front. Πb .
- 3. Bara Banki, or Nawabganj, tahsil and head-quarters of district, lat. 26°-55' N., long. 81°-15' E., situated on a high bare kherâ, is a place of great antiquity, and was known before the Musalman conquest as Jasnaul,-from Jas, a ш. Raja of the Bhar tribe, who is said to have founded it some nine hundred years
- ago. The masjid in Bîch-kî-sarâi, built by Sirâj-ad-daulah, and two Hindû temples are the only buildings of any interest, and even these are of very little IIb. historical or architectural value.

At the village of Sarthrâ, five miles south-west of tahsili, there is a well with a Persian inscription of A.H. 1166.

- The village of Sarâi Akbarâbâd, three miles south of tahsili, possesses a masjid near Pul Mînâ, built by Akbar in A.H. 987, according to a Persian III. IIb. inscription.
- At the village of Dalvi, nine miles north of tahsili, there is the ruined masjid of Qazi Mahmad, built by Malik Tuti in A.H. 718, according to a Persian III. inscription in Kûfî characters, now deposited in the house of Shâh Fazl Husain.
- 4. Daryabad, village in tahsil Râmsanehî Ghât, lat. 26°-53' N., long. 81°-36' E., 24 miles east of head-quarters, was founded by Darya Khan, a subahdar of Muhammad Ibrâhîm Sharqî. III.
- A copperplate grant of Raja Govindachandra Dêva of Kanauj, dated Samvat 1208, was found in December 1887, in a field near the village of Bangâ-Ia. wan in this pargana. The original plate is now in the Lucknow Museum.
 - 5. Dhwa, town in tahsil Nawabganj, lat. 27°-5′ N., long. 81°-21′ E., eight miles north of the Sadr station, was once an old Hindû head-quarters town, and is a Musalman town of very old standing, but no remains are now visible. In the centre of the town is a high khera, which was formerly crowned by a brick fort, as mentioned in the Ain-i-Akbari. On the west was a handsome saral of red brick, built by a former chakladår, Afzal Khân, but now disused.
- 6. FATHPÜR, tahsil, lat. 27°-10' N., long. 81°-15' E., 15 miles north-north-east of head-quarters, said to have been founded about A.D. 1321 by Fath Muham-IIb.

¹ Oudh Gazetteer, Vols. I-III, sub voce, passin.

III.

IIb.

III.

Hb.

III.

mad Khan, one of the Dehli princes, possesses a common-place masjid of Abul Fazl, called sâtburjî, and built between A.H. 1083-1093, as stated in an Arabic inscription. The most imposing structure is an imâmbâra, built by Maulavî Karâmat Alî, an officer of high rank at the court of Nasîr-ad-dîn Haidar of Lakhnâû.

7. Haidargarh, tahsil, 25 miles east of head-quarters, possesses in its neighbourhood several mounds, covered with bricks and fragments of statues, which are III.

ascribed to the Bhars.

At the village of Ahrwâ-Bhavânî, four miles south-east of tahsîlî, are several good sculptures of Pârvatî, Nârâyana reclining on Ananta, etc.

8. Kursî, town in tahsil Fathpûr, lat. 27°-8' N., long. 81°-9' E., 16 miles westnorth-west from head-quarters, is perched on a high dih, the site of an old fort, III. said to have been called Kesrigarh. The only objects of interest are the masjid IIb. of Sirāj-ad-dîn, built during the reign of Shāh Jahān in A.H. 1063; a masjid in Qâzî tôlâ, built during the reign of Âlamgîr, and the masjid of Sa'âdat Alî Khân, erected in A.H. 1193, as is apparent from the Persian inscriptions inside these buildings.

About two miles to the north of Kursî lies the village of Mansar, or Mahsand, on a very high brick-covered dih of great extent, and below it on the north is a huge well built of slabs of kankar, and ascribed to the Bhars. The tomb of

Sa'îd Nûr Alî Shâh, who is revered as a shahîd, is a common-place building.

At the neighbouring village of Ghugtîr there is another large brick-strewn mound.

9. Rudaulî, town in tahsîl Râmsanehî Ghât, lat. 26°-45' N., long. 81°-46' E., 37 miles east-south-east of head-quarters, possesses the dargâh of Shâh Ahmad, a local saint, and the tomb of Zohra Bibî, the daughter of the Sa'id Râṇi of Rudaulî.

10. Satrikh, old Hindû town in tahsîl Nawâbganj, lat. 26°-51' N., long. IIb. 81°-14' E., five miles south-east of head-quarters, possesses a dargâh of Sâlâr Sâhû, the brother-in-law of Mahmûd Ghaznavî.

11. SIDDHAUR, village in tahsil Haidargarh, lat. 26°-46' N., long. 81°-26' E., 16 miles west of head-quarters, is said to be the ancient Siddhapura. The old IIb. temple of Siddhêśvara Mahâdêva, the dargâh of Qâzi Quṭb, and the masjid near Machhî Mahal, erected in A.H. 1156, are the only buildings of any interest.

12. Subeha, village in tahsîl Haidargarh, lat. 26°-38' N., long. 81°-34' E., 30 III. miles east of head-quarters, is built on an ancient khera, ascribed to the Bhars. It possesses a brick fort built by Mirza Quli in the reign of Asaf-ad-daulah of Lakhnaû.

II.—LAKHNÂÛ DISTRICT.

1. Amerui, or Amethi Dingur, town in tahsil Mohanlalganj, 17 miles east-south-east of head-quarters, is perched on a Bhâr dih, and possesses numerous III. masjids and tombs, amongst which the most noteworthy are those of Jûgan Shahîd, Hb. Sêj-ad-dîn Gada Shahîd, Hazrat Bandagî Miyan, Shaikh Baha-al-Haq, and Shah Yûsuf Qalandari Faqîr, built during the time of Akbar.

About three miles south-west of Amethi lies the village of Gosainganj, possessing the somewhat extensive remains of an old mud fort. The small walls

of the fort are still standing surrounded by a deep moat, now almost fallen in and overgrown with grass and bushes. The fort was built on a deserted village site, one of the old Bhar dihs of the country, and is elevated enough to command an extended view of the country lying round. An old statue of Vishnu is worshipped III. as Chaturbhujî Devî in a modern temple, and a heap of stones on the old dih as Râjâ Bir.

A few miles south-east, at the village of Kanhûpûr, are several wellexecuted kankar statues, representing the saptamâtris, the Vâmana-Avatâra, and

Sûrya; the saptamâtrîs are worshipped as sâtbahinis.

III.

116.

III. III.

III.

IIb.

Hb.

 Bîjnôr, town in tahsîl Lakhnâû, lat. 26°-44′ N., long. 80°-56′ E., 10 miles south of head-quarters, possesses to the south the ruins of an old brick fort, and on the west side the extensive remains of brick tombs built over the Musalmans who III. fell in battle against the Hindûs. The place is called the Ganj Shahîdân, or martyrs' gathering-place. Close to the Ganj Shahidan is a tomb of immense size, ascribed to Malik Ambar, who, according to tradition, was killed with Salar IIb. Masaûd at Bahrâich, but wandered back on his horse, a headless corpse, to Bijnôr.

The town is said to have been founded by, and to take its name from Bijli Raja, a Pasi, who built the great fort of Nathawan, about a mile to the north of Bijnôr; an elevated mound of considerable extent and striking appearance from Ш. the wide plains in which it is situated still marks its site. This Raja is said to have possessed 12 forts, amongst which were Kâlî Pachchhim, Mâtî, Parwâr Pûrab, lying to the east of pargana Bijnôr, and others whose names are forgotten, but which extended up to Sarsawan and the Gumti in a north-eastern direction.

 Kâkorî, town in tahsîl Lakhnâû, lat. 26°-12′ N., long. 80°-57′ E., nine miles west of head-quarters, is probably of considerable antiquity. It is said to have been inhabited by Bhars, whose fort was known as Kakorgarh. A little below the fort to the south are three old tombs, one erected to Shah Bhikhan and two to his disciples, Sultan Gulrat of the Imperial family of Dehlî, and his foster-brother Shams-ad-din. According to the Persian inscriptions on the tombs, they were built in A.H. 988 and 1037 respectively. Further on to the outside of the town on the south-east are two other dargahs raised to Makhdûm Shah, Muhammad Kazim, and IIb. Makhdûm Shâh Turâb.

 Kasmandî Kalân, village in tahsîl Maliyâbâd, lat. 26°-55′ N., long. 80°-45′ E., 19 miles west of Lakhnâû, is chiefly worthy of notice as the seat of Râjâ Ka in sa, who fell in battle against Said Salar Masaiad. Outside the village are numerous dargâhs, and two especially are pointed out as the tombs of Saids Hashim and Qasim,

At the village of Kaithauli, close by, is a small mound of broken bricks

which is pointed out as ranakhambha, or battle-pillar.

 LAKHNÂÛ, the capital of Audh, lat. 26°-52' N., long. 81° E., is said to be the ancient Lakshmanavatî, founded by Lakshmana, the brother of Râmachandra of Ayodhya. To this mythical period is ascribed the Lachhman Tila, the high ground situated within the defences of the dismantled Machhi Bhawan Fort, which is now surmounted by a small masjid, erected during Aurangzib's reign.

Lakhnâû, viewed from a distance, and not too closely scrutinized, is one of the most beautiful and picturesque large cities of India. There are two noble masjids, one Imâmbâra of imperial dimensions, four tombs of regal splendour—those of Sa'âdat Alî Khân, Murshîd Zâdî, Muhammad Alî Shâh, and Ghâzî-ad-din Haidar; there are two great palaces, or rather collections of palaces, the Chhatar Manzil and the Qaisar Bâgh; besides a host of garden-houses, pavilions, town mansions, masjids karbalâs and danashe all created deciments the latest and danashe all created deciments.

and the Qaisar Bâgh; besides a host of garden-houses, pavilions, town mansions, masjids, karbalâs, and dargâhs—all erected during the last one hundred years by a number of wealthy, prodigal kings, and their equally lavish courtiers. But nowhere can we see more markedly the influence of a depraved oriental court and its politics upon art and architecture than in Lakhnâû. Whilst some of the tombs, masjids, and portals, erected by Asaf-ad-daulah and Ghâzî-ad-dîn Haidar, though detestable in detail, are still grand in outline, and have a strong smack of the old solemn sepulchres of a better age, and whilst especially one building, the great Imâmbâra, is the architectural glory of Audh, the more modern buildings of Nasîr-ad-dîn Haidar and Wâjid Alî Shâh are the most debased examples of architecture to be found in India.

IIb. The great I mambara cannot, it is true, compare with the pure examples of Moghal architecture which adorn Agra and Dehli; but taken along with the adjoining masjid, the Husainabad Imambara, and the Rûmî Darwaza, it forms a group of buildings whose dimensions and picturesque splendour render it one of the most imposing in India. According to Fergusson1 the principal hall is 162 feet long by 53 feet six inches wide. On the two sides are verandahs, respectively 26 feet six inches and 27 feet three inches wide, and at each end an octagonal apartment, 53 feet in diameter; the whole interior dimensions being thus 263 feet by 145. This immense building is covered with vaults of very simple form and still simpler construction, being of a rubble or coarse concrete several feet in thickness, which is laid on a rude mould or centering of bricks and mud, and allowed to stand a year or two to dry and set. The centering is then removed, and the vault, being in one piece, stands without abutment or thrust, apparently a better and more durable form of roof than our most scientific Gothic vaulting; certainly far cheaper and far more easily made, since it is literally cast on a mud form which may be moulded into any shape the fancy of the architect may dictate. The building is as solid as it is graceful, built from very deep foundations, and no woodwork is used throughout. It was erected by Asaf-ad-daulah in A.D. 1784 according to the plan of the architect Kifayat-ullah, and at his death he was buried in it. IIb.

IIb. The Rûmî Darwâza is a magnificent gateway that still leads out of the Machhî Bhawân Fort. Though standing almost alone, yet the abutments are so contrived as to remove all appearance of heaviness; it is almost 60 feet high to the apex of the arch, which indeed is rather an alcove than an arch. The gateway is but the half of a huge dome, cut down perpendicularly, and the passage is a comparatively small square doorway in the base.

Ib. The plans of Asaf-ad-daulah's bridge, fort, masjids, and towers are simple and grand. The arches are the finest features; constructively they have little to be desired, except a better material. His fort, noticeable for its round earthen bastions and famous for its strength, was demolished some years ago for strategic reasons.

¹ History of Indian and Eastern Architecture, page 605.

Ia.

The Residency, standing on a considerable elevation about 300 yards from the right bank of the Gûmtî, was another of the works completed by Asaf-ad-daulah. It is, however, far too famous a place and too generally known to require a detailed description.

III.

The remaining buildings of a later period, whose style was avowedly and openly copied from debased European models, are unfit to be spoken of in the same chapter as the earlier buildings. All the mongrel vulgarities which were applied in Vauxhall, Rosherville, and the Surrey Gardens, took refuge in the Qaisar Bagh and Chhatar Manzil when expelled from thence, as, for instance, Corinthian pilasters under Moslim domes, false venetian blinds, imitation marbles, pea-green mermaids sprawling over a blue sky above a yellow entablature, etc.

Hb.

III.

П.

III.

The oldest epigraphic monument in the town is the tomb of Shaikh Mina, the patron saint of Lakhnau, who induced the Shaikhs to colonise Lakhnau, on the esplanade of the Machhi Bhawan Fort. According to the inscription Shaikh Mina would have died in A.H. 884, or A.D. 1479; whilst the biographical works on Musalman saints mention A.H. 870, or A.D. 1465, as the year of his death. Shaikh Mina's real name was Shaikh Muhammad; he was born at Lakhnau, and was brought up by Shaikh Qiwan-ad-din, a dervish of repute.

There are, besides, some common-place masjids of the time of Akbar and Shâh Jahân. Shêr Shâh and Akbar struck copper coins at the Lakhnâû Mint, and the later Moghals coined silver here. Humây ûn visited Lakhnâû in

1530.

About four miles to the north of Lakhnâû lies the village of Maṇḍigâon, or Maṇiaon. The village is said to derive its name from Maṇḍala Rishi, who here in the centre of a large forest performed his solitary devotions to Siva. It possesses the dargâh of Naugajâ Pir, and the remains of the old cantonments of Sa'adat Ali Ķhân.

6. Mahona, village in tahsil Maliyabad, lat. 27°-5' N., long. 80°-55' E., 15

miles north of Lakhnau, possesses the ruins of a brick fort.

At the neighbouring villages of Arjunpür and Rukhāra are old mounds of considerable extent, with the usual broken bricks scattered about, which are ascribed to the Bhārs.

At the villages of Mal and Ant is a huge masonry well and the foundation of a large brick building.

7. Maliyâbâd, tahsîl, lat. 26°-55′ N., long 80°-45′ E., 15 miles west of Lakhnâû,

possesses the ruins of an old brick fort.

8. Mohanlalganj, tahsil, 14 miles south of Lakhnau, is built on the land of the old village of Chorhan-ka-Mau, which, however, is devoid of any remains; but the pargana of Mohanlalganj abounds in about 20 old dihs which are sometimes of great elevation and extent. They are quite deserted, and the only signs of the ancient habitations are the broken bricks which lie scattered over the mounds, and occasionally a hut on the summit devoted to some deified hero, who is worshipped under the title of Bir. These mounds are usually ascribed to the Bhars; but they are in fact the deserted sites of Buddhist towns and forts. The greatest of these mounds are at Paharnagar Tikuria, Siris, and Nagram.

1 Proceedings, Asiatic Society of Bengal, for 1873, page 11.

- Nagram, the ancient Nalagrama, possesses the ruins of a large fort, the site III. of which, a high mound in the centre of the village, still exists. It seems to have IIb.
- fallen in the track of Sa'id Salar's invasion; for on the mound of the fort are the dargahs of Munawwar and Anwar Shahids, and outside the tomb of Piran Hājî Bard, and a Ganj Shahîdân. A very interesting kankar image, representing Siva and Pârvati, has lately been dug out of the fort mound, and has been placed in the Lucknow Museum.
- 9. Nīgohān, town in tahsil Mohânlâlganj, 23 miles south of Lakhnâû, said to III. have been founded by Râjâ Naghusha of Ayodhyâ, is built on a Bhâr dih.

III.-Unão District.1

- 1. AJGAON, large village in tahsîl Mohân, 24 miles north of Unão, possesses an III. extensive dih in the centre of the village. The masses of broken brick that cover it speak of a different people or different circumstances and customs than those of
- About four miles south of Ajgaon, lies the town of Asiwan, which possesses a masjid built in A.H. 1040, or A.D. 1631, as stated in a Persian inscription. This Hb. is, however, not the original date of the settlement, as the Musalmans of Asiwan III.
- are an offshoot from Safipûr, the inhabitants of which place found there the tombs of those followers of Salar Masa'ûd who had been killed in the fight of Bârithâna, a village close by.
- 2. Asoнà, village in tahsil Pūrwā, 32 miles east of Unão, is said to have been founded by Asvatthaman of the Mahabharata; but it contains no ancient III. remains of any importance, except a small modern shrine in honor of the eponymous hero of the village. See also article on Asothâr in the Fathpur district.

In November, 1874, a large hoard of ancient Buddhist silver coins, exhibiting the dharmachakra, the bodhi-tree, and the chaitya-emblem, were discovered in the village of Simri, near the banks of the river Sai, in the immediate neighbourhood

- 3. Barsar Ghât,2 village in tahsîl Pûrwâ, 32 miles south-east of Unão, is a very holy place on the Ganges which received its name Vakasrama from the demon Vaka, who was killed by Krishna. He is also said to have founded the temple IIb.
- About four miles west of Baksar Ghât lies Daundiâ Kherâ, a dilapidated III. fort of the Bais Rájpûts, perched on a bold projecting point of the river bank, 385 feet square, and about 50 feet high at its highest point, with the walls of two buildings which are called the Raja's and the Rani's palaces. The neighbouring
- village of Samgrampar possesses seven temples, but they are comparatively Hb. modern. The bricks are all small, the sculptures are all modern, and there is nothing now to be seen save the lofty mound that would suggest an antiquity of

General Cunningham,3 in 1862, placed at this place the capital of the kingdom of 'O-ye-mu-khi (Hayamukha), visited by Hiuen Tsiang.4 But as there

¹ A. Eliott, The Chronicles of Undo, Allahabad, 1862, passim.

² Cunningham, Archeological Reports, Vol. XI, page 57.

³ Archaelogical Reports, Vol. I, page 296.

^{*} Beal, I.c., Vol. I, page 229.

are no remains of any buildings which can be identified with the monuments described by Hiuen Tsiang, he changed his opinion in 1878, and identified Tusâ-rân Bihâr in the Pratâpgarh district and Singraur in the Allahâbâd district with that ancient Buddhist place.

4. Bângarmât, town in tahsil Safipûr, 31 miles north-west of Unão, built on the high bank of the old course of the Ganges, is the earliest Musalmân settlement in the Unão district. The name of the place is significant: "the fort on the Bângar," or highland beyond the danger of fluvial action, as opposed to Kachâr, or lowland subject to inundation when a river rises in the rainy season. It is a ruinous town now; but there are many roomy masonry houses which are the remnants of past prosperity and importance. The present homestead covers but a trifling part of the rising ground which marks the site and extent of the original town and fort. Traces of old buildings are to be seen cropping up here and there at some distance from the habitations now occupied, and a few old shrines still stand in the outskirts of the town.

There are two ancient monuments of the early Musalman incursions or settleIIb. ments existing at Bangarmaa. The earlier of these is a dargah erected to the
memory of Sa'id Ala-ad-din Ali, son of Qataim Samsaa, who died in A.H. 702, or
A.D. 1302, as stated in two Arabic inscriptions on the building, written in Khatt-iSuls characters. The courtyard of the dargah is paved with large bricks, 15 by 10
inches, stamped with four finger marks, and the verandah contains twelve Hindu
pillars, and lying round about there are many blocks of kankar, of red sandstone,
and of a dirty yellowish stone; there are also several capitals of pillars in red
sandstone. The tombs are on a high mound, which was no doubt the site of some
old Hindu building.

Close by is another tomb which memorializes an historical fact, viz., the erection of the dargâh by Firûz Shâh Tughlaq in A.H. 784, as stated in two Persian inscriptions. The occupants of the tomb are Sa'îd Muzaffar-ad-dîn and Jalâl Khusrû of Bângarmâû, who accompanied Malik Sulţân Shâh Khushdil, one of Firûz Shâh's generals, who was murdered in A.H. 792. A third inscription records the date A.H. 782.

Close by, about two miles to the north-west of Bångarmåû, on the bank of the Pachnåi Nålå and on the high bank of the old course of the Ganges which is now called Kalyåni Nadi, is a very extensive mound of ruins covering some 15 acres, known as Nawal. Local tradition claims for it that it was a city prior to the rise of Bångarmåû, that in fact it was the fall of Nawal which led to the rise of Bångarmåû. This tradition is supported by the fact that although old coins prior to the Musalmån era are found at Nawal, none are found at Bångarmåû.

There is, however, a tradition linking the overthrow of Nawal and the foundation of Bångarmåû with Sa'îd Alâ-ad-dîn Alî, who died in A.H. 702. They say that Nawal was the capital of a Hindû sovereign when this Musalmån worthy, whom they locally speak of as Mîran Sâhib, came and settled in a jangal of någphanni, or prickly pear, on the elevated ground, where now stands Bångarmåû. The washer-

IIb.

Ib.

¹ Archeological Reports, Vol. XI, page 68.

^{*} Samsat is a town on the Euphrates, celebrated for its learned men.

man, who washed Mîran Sâhib's clothes, lived in Nawal and was named Bângâ. He also washed for the king. On one occasion when the dhobî washed the venerable Moslîm's drawers and the king's clothes at the same time, the royal garments became pervaded by a sweet odour, and no sooner did they reach the palace than every chamber became fragrant. This excited the king's curiosity, and he enquired and found that the scent came from the clothes. He sent for the dhobî and demanded the secret; the washerman explained his inability to explain the origin of the perfume. The king threatened to kill him next day unless he disclosed the secret. The unfortunate Bângâ went to Mîran Sâhib and told him everything. He told the dhobî to return to Nawal and shout in every street:—"To-morrow shall Nawal be overturned." The dhobî did so, but the inhabitants thought him mad. Next morning the saint overturned (lautâ) the city of Nawal, and then a new town was founded and called Bângarmâû after the dhobî Bângâ. To this day Bângarmâû and Nawal are collectively called Lautâ Shahr.

This tradition bears obviously the traces of Musalman embellishment and is a figment, but from it we gather that Nawal was a capital at one time prior to Musalman invasion and to the rise of Bangarman. It was quite in keeping with the general character of the Moslim advance to raze a Hindû capital and erect another centre of government near it. Besides, the position of Bangarman and Nawal lying on the line which connects three great ancient cities, viz., Mathura, Kanyakubja and Ayodhya, must not be lost sight of. This line was and is a highway of communication, and there are not less than six ferries connecting Kanauj with Audh, and all within easy range of Bangarman and Nawal. The chief of these is the Nanaman Ghat, due west of Bangarman. An old unmetalled road leads from the ghat to the town, and the distance is 10 miles. There is no doubt that the latter kings of Kanauj held sway over the part of Audh opposite their capital, and when the earlier Musalman sovereigns of Dehlî established themselves at Kanauj, they entered Audh by Bangarman and Nawal.

The ruins of Nawal have been identified by General Cunningham¹ with the Na-po-ti-po-ku-lo, or Navadevakula, of Hiuen Tsiang.² The word means "the community of the new god;" but it is natural to suppose the word navakula, "the new sect," equally applicable to the eponymous community, and the transition from Navakula to Nawal is obviously easy.

The ancient remains at Nawal consist of five mounds, viz., Deorâ dîh, Sîtalâ dîh, Dânothêro, Mahâdêva, and Phûlwârî; with traces of walls, carved bricks, broken statues, and terra-cottas, both Brâhmanical and Buddhist, including also Buddhist coins and beads. The village itself stands on a mound, and is undoubtedly an old place, being a vast ruin, undulating, uncultivated, a concrete of ruined houses smoothed down by the wear of ages, with a few prominences, and with one or two shrines still crowning its heights.

In comparing Hiuen Tsiang's account of the buildings at Navadevakula with the remains now existing at Nawal and Bângarmâû, it is necessary to remember that although the extreme points of the two places are about two miles apart, yet the

Archæological Reports, Vol. XI, pages 47-53.

⁹ Beal, I.c., Vol. I, page 223.

distance between the village of Nawal and the high mounds of Bângarmâû is only one mile. There can be no doubt, therefore, that the old buildings which once stood on the mounds of Bângarmâû must have belonged to the larger town of Navadevakula, which Hiuen Tsiang describes as being 20 li, or upwards of three miles in circuit.

According to Dr. Hörnle, the modern Nawal is identical with the forest of \hat{A} -lo, mentioned by Fa Hian. It is stated that on his way from Kanauj to Sha-chi (see Sañchânkôț in the Unâo district), Fa Hian met that forest on the eastern side of the Ganges. He stayed and preached there; and there were also stûpas there. It is clear, therefore, that it cannot have been a mere forest, but that there was an inhabited place (\hat{A} lavî) in or near it. Dr. Hörnle is of opinion that the town named \hat{A} lavî in Pâli books and existing in Buddha's time is the same as the town called \hat{A} labhî or \hat{A} labhiyâ in Jain books, and which lay within that comparatively narrow circle within which Mahâvîra made his missionary peregrinations. Compare, also, notes on \hat{A} ir wâ in the Iţâwah district.

It is interesting to note that, in 1876, several rectangular Chinese silver coins were found close to the river Ganges in a dîh at Alâ-ad-dîn pûr, about six miles west of Bângarmâû.

About five miles north-east of Bångarmâû lies Jogîkôţ, perched on a large ancient kherâ. A statue of Pârvatî, locally called Phûlmatî Devi, bears a short dedicatory inscription in characters of the fifth century.

5. Bihar, old decayed town in tahsîl Pûrwâ, 28 miles south-east of Unão, is usually called Patan-Bihar, by joining to it the name of Patan, a small town in the neighbourhood, in order to distinguish it from other places of the same name. The present town of Bihar is not more than about 300 years old; but the site of the large ruined fort to the south-east is said to be very ancient. It is rather more than III. a quarter of a mile long from north to south, by 1,000 feet in breadth at the northern and 750 feet at the southern end. The whole is built of mud, with round towers and a broad deep ditch, which widens into a large sheet of water on the north side. In the middle of the fort there is a square mound of brick ruins, of which the walls have been dug out. The remains of rooms are still marked by the straight lines of excavation. There are fragments of very large thick bricks of the olden time, mixed with the thin bricks of a later date; but the old bricks are said to have been nearly all carried away to build the houses of the present town. There are also large bricks in the foundations of a dargah and idgah close to the fort. IIb.

General Cunningham³ conjectures that this might possibly be the Buddhist site mentioned by Hiuen Tsiang⁴ under the name of O'-yu-t'o. In favour of Bihâr, according to his opinion, there is its eminently Buddhist name, and the remains of a square building in the middle of the fort which answers to the samphārāma of Vasubandhu Bodhisattva inside the town. See, however, article on Jagatpûr in the Râi Barêli district.

III.

¹ The Urdsagadasão, Appendix III, page 51.

Beal, I.c., Vol. I, page XLIII.

³ Archaelogical Reports, Vol. XI, page 55.

^{*} Beal, Lc., Vol. I, page 224.

III.

III.

III.

Hb.

The neighbouring town of Patan is perched on an extensive dih, crowned with III. a small modern temple where ancient statues of Vishņu, Nârâyaṇa, Pârvatî, etc., are collected. The tomb of Mahabat Shah, a celebrated faqir, who died in the time IIb. of Asaf-ad-daulah of Audh, is a common-place structure.

6. HARHA, village in tahsil Unao, eight miles south-east of head-quarters, possesses the ruins of a large brick fort, ascribed to Mahmûd of Ghazni, and a

dargah of Sa'id Magbûl-î-Alam, inside the fort, of the same period.

Ib. In the neighbouring village Badarqa Harbans there is a large dwellinghonse erected in A.H. 1052 by Râjâ Harbans Kâyath, an officer of the court of Shah Jahan. The walls of this fine building are of kankar blocks to a height of about 15 feet, then rises a brick turreted wall; over the gateway is an elaborate frieze of red sandstone in which appear alternately pairs of geese and pairs of elephants. A large hall of audience supported on carved pillars formerly stood inside the building; but Asaf-ad-daulah of Audh took these away to help in building his great Imâmbâra at Lakhnâû. This structure is very picturesque and massive; from its strength of construction it would seem to defy the hand of time, which has only as yet clipped off the coigns and pinnacles, and here and there planted a pipal tree on its loftiest towers.

7. Kursat, village in tahsîl Safîpûr, 28 miles north-west of Unão, possesses the remains of a brick fort. The village is said to have been founded by Quds-ad-din III. in the time of Babar, and named after him Qudsat, now changed to Kursat.

8. Mawâî, village in pargaṇa Maurâwân of tahsîl Pûrwâ, 32 miles south-east

of Unão, stands on an old khera, said to be the ruins of a Bhar fort.

9. Mohan, tahsîl, 24 miles north-east of Unão, a Musalman town of considerable size and importance, stands on a high dih, the deserted site of some ancient III. Hindû town. A well has been sunk through the centre of the kherâ, and at several places on its steep side may be seen the remains of pipes in a good state of preservation, through which water was apparently drawn from a reservoir supplied from the river Sai. The workmanship of the piping is of no mean order, and the separate pipes are some 20 inches in diameter, four inches in depth, and curved to enable one to lap over the other.

About two miles south-west of Mohan lies the Musalman village Neotini, perched on an ancient dih, and possessing some old ruined masjids. According to tradition, the place was formerly called Khudâdâd, which would give, according to abjad, A.H. 614 as the year of its foundation.

10. Pariar, village in tahsil Unão, 14 miles north-west of head-quarters, is a sacred bathing-place of the Hindûs on the left bank of the Ganges. Tradition relates that there was formerly a dense jangal here, and that Sita, the wife of Râmachandra of Ayodhya, was turned out on this land, when divorced by her husband; hence the name of the village from the Sanskrit parihara, "abandoning, deserting," afterwards corrupted into Pariar. The great jhil, which almost surrounds Pariar, is called Mahna, said to be a corruption from maharana, "the great fight," in which Lava and Kusa, the sons of Râmachandra, unaided, vanquished the mighty armies sent by their father. In the temple of Somêsvara Mahâdêva on the banks of the jhil are collected a large number of metal arrow-heads said to have

been used by the contending armies; they are also occasionally picked up in the bed of the jhil and of the Ganges. See, also, note on Bithûr in the Kânhpûr district, which is on the opposite bank of the river.

III. The temples on the bank of the Ganges are all modern and of no interest. The ruins of a large brick fort, erected in the time of Vazir Mîr Almâs Alî Khân, are very picturesquely situated on a high cliff overlooking the Ganges.

11. Parsandan, village in tahsil Mohân, 14 miles north-east of Unâô, is believed to have taken its name from having been the residence of Parasurâma, who performed his penances here. There are, however, no ancient remains now visible, with the exception of the ruins of an old brick fort.

12. Pûrwâ, tahsîl, lat. 26°-32′ N., long. 80°-52′ E., 20 miles south-east of Unâo, possesses a noted lingam, called Bilêsvara Mahâdêva, in a common-place temple. A large masonry tank, with zanâna ghâts for women, in front of the temple, is called Trivedî-kâ-talâo; fragments of ancient sculptures are built into the IIb. walls of the tank. The tombs of Mînâ Sâhib, Niyâmat Shâh, and Hîra Shâh are of little or no interest.

III.

Hb.

The village of Maurâwân, six miles east of tahsîlî, is said to have been founded by Mayûradhvaja, who, according to tradition, celebrated the asvamedha simultaneously with the Pâṇḍavas at Hastinâpura. It possesses two masjids and nine Hindû temples of no interest.

At the village of Panhan, five miles south of tahsîlî, are the remains of an old brick fort, ascribed to the Bhârs, on the summit of which stands a noted lingam, called Achalêsvara Mahâdêva. The dargâh of Faqîr Muhammad Shâh is a common-place building.

About six miles north-east of Pûrwâ lies the ancient village Sarwan, where king Dasaratha of Ayodhyâ is said to have killed the holy rishi Sarwan, who, being on a pilgrimage, was carrying his blind parents in a kanwar, slung over his shoulders. An ancient stone figure of Sarwan Bâbâ is still lying under a tree near the banks of the village tank.

13. RASÜLÂBÂD, town in tahsîl Mohân, 14 miles north of Unão, possesses the ruins of a brick fort and a masjid erected by Mujâhid Alî Khân, during the reign of Alamgîr, in A.H. 1085, according to a Persian inscription.

14. Sapîpûr, or Sâîpûr, tahsîl, lat. 26°-50′ N., long. 80°-24′ E., 17 miles north-west of Unão, is one of the earliest Musalmân settlements in the Unão district. At the time of the conquest, the country belonged to five Râjâs of the Sakal tribe of Brâhmaņs, who had forts at the five villages of Arâî, Sakhân, Palînd, Pîkhî, and Sâîpûr. In A.H. 818, or A.D. 1414, a dervish named Maulânā Shâh Akrâm came from Bakkar in Sindh to Jaunpûr, at the invitation of Ibrâhîm Shâh Sharqî. On his journey, he stopped at the Suhora tank, near Sâîpûr, to sound the azân, on which occasion he was insulted by Râjâ Sâi Śakal of Sâipûr. The dervish then went to Jaunpûr and made his complaint to Ibrâhîm Shâh Sharqî. At that time the whole of Audh was subject to Jaunpûr, and Kanauj was the boundary between Jaunpûr and Dehlî, and was the scene of constant battles between the forces of the rival monarchies. Ibrâhîm at once sent troops to redress the injury done to the dervish. The leaders of the force were Sa'id Bahâ-ad-din Arzânî, Akrâm Khel,

III.

III.

III.

Sa'id Alâ-ad-dîn Wasti, Sa'id Mîr, and Shaikh Quţb-ad-dîn. In A.H. 819 they crossed the Ganges near Bithûr, attacked and slew the Brâhman Râjâs, and destroyed their five forts, the ruins of which are still to be seen at the villages of Arâi, Sakhân, IIb. Palind, Pîkhî, and Sâîpûr. In the battle Sa'îd Alâ-ad-dîn was killed, and his tomb still exists in Safîpûr; a peculiar sanctity attaches to it, and many miracles are said to have been wrought at the shrine of this shahîd. The great grandson of Shâh Akrâm was the celebrated dervish, Shâh Safî, who gave his name to the town, which instead of Sâîpûr was henceforth called Safipûr; but in the district throughout IIb. the epithet of Sâipûr is still more common.

The present town of Safipûr possesses 14 masjids and six Hindû temples, all of which are neither of archæological nor architectural value. The only remains of antiquarian interest are the dargâhs of five noted dervishes, viz., of Shâh Safi. Qudrat-ullâ, Fâmi-ullâ, Hâfiz-ullâ, and Abdullâ, in the construction of which fragments of ancient Hindû sculptures of superior workmanship have been utilized.

III. The temples of Râmasvâmî Mahâdêva in the village of Vakarma and of Pârvatî at Balirâj Atâha claim a hoary antiquity; but they are common-place structures of the last century.

About four miles north-west of the tahsîlî lies the village of U g û, perched on III. an ancient *kherû*, where the foundations of large brick temples, palaces, and courthouses are still traceable.

IIb. The village of Q â z î p û r possesses a neat masjid, built by Qâzî Abul Hasan, in A.H. 1072, according to an Arabic inscription.

15. Sanchankôţ,¹ or Sujānkôţ, old village in pargaṇa Bângarmâû of tahsîl Safîpûr, 34 miles north-west of Unâo, on the right bank of the river Saî, is perched on a great mound, about half-way between Bângarmâû and Sandilâ. The place is marked Râmkôţ in the maps, but if any one were to ask a villager for 10 miles round for Râmkôţ, he would be met with a vacant gaze of ignorance and surprise.

The position of the great mound of Sanchânkôţ reminds one much of that of

Śrâvastî (Sâheţ-Mâheţ in the Goṇḍâ district), standing as it does in the general form of an elongated irregular semicircle with its diameter facing the river Sâî. The view to be had across the Sâî from any high point in the breast facing the river is incomparably finer than that from any similar position in the ruins of Śrâvastî. The river Sâî makes a bend and washes two faces of the mound which is generally known as qilâ or the "fort." This was always a favourite position with the Hindûs, and as the place is on the high road between the ancient cities of Kan-yâkubja and Ayodhyâ, there can be no doubt that it was occupied at a very early date. The fort is nearly half a mile square, with two suburbs outside: one to the north-west, which is deserted; and the other to the south-east, on which stands the present village. To the south of the village, and close to the high road leading to Sandîlâ, there is another mound with a large pit in the middle, from which bricks of a stûpa have been dug out by the villagers. The stûpa was only 18½ feet in diameter, but it stood on a lofty terrace, 60 feet square and 15 feet above the fields, with a wall six feet thick all round. It was built entirely of very large wedge-shaped

bricks, which must have been made for the purpose, as they are slightly curved

¹ Cunningham, Archaeological Reports, Vol. XI, page 53.

outside. Perfect specimens of these bricks measured 18½ inches in length on the outer face, and 17½ inches on the inner face, with a breadth of 11½ inches, and a thickness of four inches. General Cunningham found that six bricks laid together touching each other formed exactly one-sixth of the circumference, or nine feet 1½ inch. As this was also the radius of the circle, the diameter of the stûpa must have been 18 feet three inches.

The place is unquestionably a field of great promise, for the buildings, though covered, are becoming exposed by the action of the rains, and a thorough exploration would not be difficult. Large hoards of ancient Hindû coins, comprising Buddhist punch-marked and cast silver bits, Indo-Baktrian, Indo-Skythian, and Gupta copper, silver, and gold coins, are constantly dug out by the villagers during their search for bricks. Interesting fragments of stone statues and terra-cotta figures, both Buddhist and Brâhmaṇical, are scattered about over all the mounds.

The position of this great mound on the highway between ancient Kanauj and Ayodhyâ has its bearings on the identification of Sañchânkôţ with the capital of the Sha-chi¹ (Sâketam), visited by Fa Hian.² This identification is placed beyond doubt by the existence of a stûpa on the south-east of the opening which seems to mark the south gate of the city, and four other marked eminences in other places.

It is quite clear that Fa Hian and Hiuen Tsiang both took the same route after leaving Kanauj; but while Fa Hian says he visited the capital of the country of the Sha-chi, Hiuen Tsiang names Navadevakula (Nawal near Bângarmâû). The distances they give differ, and the places they describe differ; thus it is fair to conclude they visited two different places.

The distance from Kanauj to Sañchânkôt is 35 miles viâ Nânâ mâû Ghât; but we must note that the Ganges has been subject to many variations of course in the past fourteen hundred years, and that it is also possible that Fa Hian may have crossed by some other ghât which is lower down the river, and this would add very much to the distance. Again we must remember that the river Ganges touched Kanauj in the pilgrim's time, and that the Kalyânî Nadî has since then been directed into its present channel. If the pilgrim visited the sacred place he refers to on the north bank of the Ganges, and thus came down to Nânâmâû Ghât, we will have another distance longer than that covered by the route direct viâ Nânâmâû Ghât. This is stated to show that the shortest route from Kanauj to Sañchânkôt, and the most usually taken, is 35 miles, and there are other routes which would be much longer and may have been adopted by the pilgrim.

16. Sâtan, village in pargana Harhâ of tahsil Unâo, 14 miles south-east of head-quarters, possesses an old temple of Sîtalâ Devî, with a square well, built of blocks of kankar, in its compound.

17. Unão, tahsîl and head-quarters of district, lat. 26°-34′ N., long. 80°-22′ E., was conquered from the Bais Râjâ, in 1450 A.D., by Sa'id Bahâ-ad-dîn, son of Sa'id Alâ-ad-dîn, who was killed in the taking of Safîpûr. The present town possesses

70

IIb.

¹ General Cunningham, Bhilsa Topes, page 180, wrongly identifies Sanchi in the Bhopal territory with the capital of the Sha-chi. Archicological Reports. Vol. I, page 318, he tries to show that Fa Hian's Sha-chi is the same as Hiuen Tsiang's Visakha, and that both are identical with Saketam or Ayodhya.

^{*} Beal, &c., Vol. I, page XLIII.

III.

III. the ruins of the old Hindû fort, some uninteresting though picturesque mounds, several old dargâhs with glazed tiles on the domes, 10 masjids, and 14 Hindû temples of no particular interest. Innumerable fragments of ancient sculptures are scattered about the town, and have been utilized either as isolated posts or as door-steps.

About five miles north-west of Unão lies the village of Thâna, perched on an ancient kherâ, and possessing the ruins of a brick fort.

Two miles further north, at the ancient village of Rão Karņa, are several III. high kherûs—the ruins of an old fortified city—on one of which, under a large banyan tree, is still standing a noted lingam of great antiquity.

IX.—SÎTÂPÛR DIVISION.

I.—HARDÔÎ DISTRICT.

- ÂLAMNAGAR, village in tahsîl Shâhâbâd, 24 miles north of Hardôi, possesses,
 close by the village lands, the ruins of the deserted town of Bâhlolpûr, which are locally called Raho, "the last left."
 - Barwan, village in tahsil Hardôî, 13 miles west of head-quarters, possesses the ruins of a large brick fort.
- III. Within its area of 53 square miles, the pargana of Barwan contains 21 dihs, or deserted village sites, which are believed to be of Thathêra origin.

III.

III.

IIb.

IIb.

- 3. Bāwān, village in tahsîl Hardôî, six miles west of head-quarters, is traditionally believed to have been the ancient Mahâbalipura, the capital of the well-known daitya Mahâbali, from whom Vishņu, in his Vâmanâvatâra, took away the two worlds (heaven and earth) by two steps; but in consideration of his virtues left the lower regions still in his dominion. The present village is perched on a large kherâ, and contains some interesting fragments of Brâhmanical sculptures of superior workmanship. At the Sûrâjkuṇḍ, a large ancient tank with pakkâ ghâṭs, a melâ is annually held in honor of Darsanî Devî (Durgâ). The dargâh of Makhdûm Sâhib Abul Qâsim, a contemporary of Sa'îd Sâlâr Masa'ûd, is of no special interest.
- III. There are eleven dils in the pargana of Bâwân, all of which are ascribed to the Thathêras. The most imposing of these mounds is called Kalhaur, or Kilho, and said to be the ruins of the chief stronghold of the Thathêras in this part of Audh. That it was of considerable size is shown by the height and extent of its debris which cover several acres in the heart of the jangals of Dânyalganj. The remains of a huge masonry well, 15 feet in diameter, and a ruinous tank, called Râmakuṇḍ, are still visible.
- 4. BILGRAM, tahsil, 15 miles south of Hardôl, is built on and round a lofty tila, said to be ruins of the ancient Hindu town of Srinagara, whose correct III. name, however, was most probably Bhillagrama. The tild seems to have been originally a high bluff on the edge of the old left bank of the Ganges, whose natural height has been increased by successive strata of debris of the habitations of Bhills, Thatheras, Raikwars, Shaikhs, and Sa'ids. The older portion of the town abounds with fragments of carved bas-reliefs, pillars, surcapitals of old Hindû temples, and huge blocks of hewn kankar, the remains of palaces and temples of the past. The best of these sculptural relics are collected in the small modern temple of Gudar Nath, in Lamkania tola, the Brahmans' quarter, IIb. lying to the north of the lofty tila, round a khera attributed to the Thatheras, on which traces of their smelting-houses are still to be seen. There is every reason to believe that these stones are the remains of the old Hindû town of Bhillagrama, its fort, temples, and tank, called Sagar. Some 20 years ago, on the traditional site of the tank Sågar, in the Haidaråbåd mahallå, a flight of hewn kankar steps was found under a deposit of mud and rubbish; but these blocks were speedily used

up for building purposes. Everywhere such blocks are to be traced in the foundations and lower courses of masjids, dargâhs, and houses, in wells, and at door-steps; many of them are grooved, showing that they have been taken from some older building. This tank Sâgar gives its name to a portion of the town lying at the foot of the high mound, or tîlâ, on which stood the old Hindû fort, and between it and mahallâ Maidânpura. This quarter seems to have been founded on a flat piece of land (maidân) left by the recession of the Ganges. Along the ridge that separates the Haidarâbâd and Maidânpura mahallâs remnants of boats are found from time to time in sinking wells.

The ancient Hindû town of Bhillagrâma could, however, not have grown into a town of much importance by the time of Sulṭân Mahmûd's campaign to Kanauj, in A.D. 1018; otherwise from its vicinity (11 miles north-west) to Kanauj, it would have been noticed by the contemporary historians, and by the author of the Mirâṭ-i-Masa'ûdî in his mention of the places to which Sa'id Sâlâr despatched detachments

from Satrikh in his Audh campaign, in A.D. 1032.

The campaign of Shahāb-ad-dîn Ghorî, in A.D. 1193, and the fall of Kanauj must have shattered the power of the petty Hindâ Râjās on the Hardôi bank of the Ganges, so that when, a generation later, in A.D. 1217, Shams-ad-dîn Iltitimish poured in his troops to complete the subjugation of the country, only a feeble resistance can have been made, and Shaikh Muhammad Faqîh of Irâq and Sa'îd Muhammad Sughra seem to have reduced Bhillagrâma and the country round it. Since the Musalmân conquest, Bilgrâm is notorious for the learning of her men. Several works on history and philosophy, as well as poems, have been produced here.

The present town possesses several old masonry wells, the following inscribed IIb. dargâhs and masjids:—The dargâh of Qâzî Yûsuf, dated A.H. 608; masjid in mahallâ Sa'îdwalla, dated 627; the Chauhath masjid, dated A.H. 882; the dargâh of Pîr Abdulla, dated A.H. 909; the masjid of Maulavi Pîr Baksh, dated A.H. 956; the masjid of Qâzî Mahmûd, dated A.H. 1011; the masjid of Muhammad Zâhid, dated A.H. 1042; the îdgâh in mahallâ Katrâ, dated A.H. 1059; and the masjid of Alî Hasan, dated A.H. 1118.

IIb. The village of Bojhar, north of Bilgrâm, contains the dargâh of Sa'id Sughra in the garden of Sa'id Mubâraq, dated A.H. 614; the tomb of Hâjî Afzal-ullâ, dated A.H. 980; and the Turvi well built in Akbar's time, according to a Persian inscription.

IIb. At the village of Naumalikpur there is a masonry well with a Sanskrit inscription, dated Samvat 1680.

The village of Mahmûdnagar, south of tahsîlî, possesses the dargâh of Qâzî Buddha, erected in A.H. 1022, according to a Persian inscription.

IIb. The village of Nazratnagar possesses a ruined masjid near Khajuâ tâlâb, erected in A.H. 1011, according to a Persian inscription, and a masonry well of the same date.

At the villages of Shiampar, Baragaon, Maron, Nagraura, Sala, Tendaapar, Boraa, and Biblapar in pargana Katiari, there are dihs, or deserted sites of fortified villages, ascribed to the Thatheras.

III. 5. Gôpamât, ancient Hindû town in tahsîl Hardôî, 14 miles north-east of head-quarters, is said to have been founded towards the end of the 10th century by Râjâ Gôpa on or near the site of an old Thathêra clearing in the forest known then as Mawwa Sarâî, or Mawwa Châchar. Among the scanty III. relies of that time, two rude stone images, called Kaurehru Dêo and Bâdal Dêo, are still venerated as having been the gods of the departed Thathêras.

In A.D. 1032, Sa'îd Sâlâr Masa'ûd, whilst staying at Satrikh, sent out an army under Mîr Sa'id Azîz-ad-dîn, celebrated now as Lâl Pîr, to conquer Gôpamâû. A terrible battle is said to have been fought, and Lâl Pir was buried by his victorious army in the shrine of Gôpînâtha, said to have been a large stone temple, with three doors facing to the north, In 1232, Khwajah Taj-ad-din Husain, Chhishti Shaikh, was posted at Gôpamâû by Sultân Iltitimish, who threw up an earthwork and built an unenclosed masjid, now ruined. At the suggestion of his spiritual preceptor, Khwajah Quth-ad-dîn, he built the dargah of Lal Pîr, which, however, in its present form was repaired in 1795 by Nawab Muhammad Ali Khan Wâla Jâh, subâhdâr of Arkôt. The chief development of the town took place in the time of Humâyûn, of whom there still exists, in mahallâ Sa'îdpura, a masjid, with a well attached to it, called Gondnî-kâ-kûân, built by Sa'id Kamâl, as stated in a Persian inscription. Up to a height of nearly seven feet from the ground this masjid is built of large slabs of kankar, measuring 46 feet by 10 inches. Similar blocks are to be seen in the doorway and steps of Lal Pir's dargah and in a baradari, built by Maulavi Ghulâm Rasûl, Qâzî of Trichinopoly, in the beginning of this century. These kankar blocks have no doubt been taken from the desecrated temple of Gopinâtha, or some other ancient Hindû fane.

III.

Hb.

IIb.

IIb.

IIb.

IIb.

III.

III.

III.

The Jâmi Masjid, measuring 62 by 26 feet, an îdgâh and well were built in the reign of Akbar, under the auspices of Khwâjah Habîb-ullâ, in A.H. 978 and 979, as is apparent from three Persian inscriptions. The Jâmi Masjid and îdgâh, which had been damaged by an earthquake, were repaired in A.D. 1786 by Nawâb Muhammad Alî Khân Wâla Jâh, subâhdâr of Arkôţ.

To Nawâb Anwar-ad-dîn Khân the town owes a curious square well, called chaukhantha, and a masjid.

Hb. The present temple of Gôpînâtha, with its fine tank, was built by Nauniddha Râî in A.D. 1699, during the reign of Aurangzîb, as stated in a short Sanskrit inscription inside the temple. The renowned lingam of black stone, known as Gopînâtha, and several fragments of sculptured bas-reliefs representing Ganêsa, are the only remnants saved from the original ancient temple.

6. Gandwa, village in tabsil Sandila, 34 miles south-east of Hardoi, possesses a ruined masonry fort, and near the villages of Bibi Khera and Bharaiya-Kharauli, on the road to Atrauli, immense brick mounds locally called Bhankargarh, crowned with the ruins of an ancient Naga temple and tank.

7. Hardôf, tahsîl and head-quarters of the district, lat. 27°-26′ N., long. 80°-10′ E., possesses no ancient buildings of any interest. To the south-west of the present town there is a high irregular *kherâ* of about 16 acres, covered with broken bricks and fragments of ancient sculpture, said to be the ruins of the ancient Haradohî. Many of the houses of the modern town are built of large ancient bricks dug out of the mound, and traces of brick temples and palaces are continually cropping up here and there on the mound.

III.

III.

IIb.

Hb.

Ha.

IIb.

III.

About six miles east of Hardoi, at the village of Nîr, there is a high brick III. kherâ, said to be the ruins of the Thathêra stronghold Basohrâ.

Six miles further south-east, at the village of Gauda Khera in pargana Bangar, there is a large dih, ascribed to the Thatheras.

8. Kalyanmal, village in tahsîl Sandilâ, 28 miles south-east of Hardôî, possesses the ruins of a brick fort built in the time of Alamgîr, who stationed an âmil here.

The ancient name of the present village is said to be Rathâulî, which is traced to the staying of Râmachandra's chariot (ratha) at this spot on his return from Lankâ. Here he halted and visited the sacred tank at Hattiâ Haran (hatyaharana), that he might wash away the sin of slaying the demon Râvaṇa. This sacred spot, also called panchachhattra, seems to have been one of the ancient Brâhmanical hermitages described in the Râmâyaṇa.

IIb. The present village of Kalyânmal possesses in a small modern temple a noted lingam, called Panchabgir Mahâdêva, and believed to have been set up by Râjâ Yudhishthira of Hastinâpura.

III. Close to the village are two deserted sites, viz., Wairî Dîh, the remains of the ancient fort of Rathâulî, and Kaimgarh Dîh, with the ruins of an ancient shrine of Kâlkadevi.

9. Mallawan, town in tahsîl Bilgrâm, lat. 27°-3′ N., long. 80°-11′ E., 21 miles south of Hardôî, contains four masjids, a dargâh of Makhdûm Shâh (Misbâh-al-Ashiqîn), two imâmbâras, several ruined brick buildings of some architectural beauty, 15 Hindû temples, and 24 old masonry wells.

As at Bilgram, many of the brick buildings and masjids, dating from the time of Akbar and Shah Jahan, are faced with large hewn blocks of kankar to a height of about three feet from the ground. The dargah of Makhdum Shah, and the masjid of his pupil Qazi Bhikhari, are thus faced throughout, the kankar slabs being relieved here and there with red sandstone. The dargah is crowned with a plain Pathan dome, supported on eight slender Hindû pillars, richly ornamented; its style resembles that of Sadr Jahan's dargah at Pihani. Close by there is a fine well of the same period, also lined with blocks of the same material. The blocks thus used in the ruined Jami Masjid, of Akbar's time, have evidently been taken from some older building, but apparently at the restoration of the masjid, not at its original construction. Undoubtedly these kankar blocks have been taken from ancient Brahmanical, Jain, or Buddhist shrines, of which the only relics now to be found are such fragments, built into Musalman structures, and the broken sculptures that one sees so frequently grouped under some old pipal trees. The Asa Devî, in a modern Hindû temple at Mallâwân, is a relic of some such shrine; its seven-headed naga-hood sheltering a female figure points to a Buddhist or Jain origin.

Six miles north-east of Mallawan, at the village of Bansa, there is a large dih covered with broken bricks and pottery, on the summit of which stands a small ruined temple of the 10th century, with an image of Parvati, locally called Bansadevi. The ancient coins which are found here in considerable numbers during the rains show that the place must have been inhabited long before the Indo-Skythian period.

10. Pali, old town in tahsîl Shâhâbâd, lat. 27°-30' N., long. 79°-44' E., 20 miles north-west from Hardôi, was founded, according to local tradition, at the close of

the 12th century, shortly after the downfall of the Râthor dynasty of Kanauj. The name may, however, in all probability be connected with the Pâla dynasty of Kanauj, from which place Pâli is distant 34 miles. To the west of the present town there is a large ruined site, called Sâṇḍi Kherâ, which is ascribed to the Thathêras.

IIIb. The town contains two modern masjids, one of which is a very showy florid structure, and a modern Hindû temple of no interest.

III.

III.

Hb.

III.

III.

III.

III.

Ш.

11. Pihânî, town in tahsîl Shâhâbâd, lat. 27°-38′ N., long. 80°-14′ E., 18 miles north-east of Hardôî, is said to have been founded on the ruins of a Thathêra stronghold, during the reign of Humâyûn, by Abdul Maqtadi, a younger brother of Sa'id Abdul Ghafûr, who was Qâzî of Kanauj in A.D. 1540. The oldest portion of the town is called Barî Pihânî; it is close to the kherâ, which marks the ruins of the first Sa'îd settlement in the time of Humâyûn. The oldest building in it is the dargâh of Abdul Ghafûr, whose date stone has been lost. The Sa'id settlers seem to have obliterated all traces of the earlier occupants. No ruined temple is to be seen, only the remains of a huge masonry well.

Barî Pihânî was deserted when Sa'id Nizâm Murtaza Khân founded the nearer adjacent town of Nizâm pûr, or Chhotî Pihânî. The western gateway, with its huge shafts of red sandstone, the bastions of the high enclosing wall, brick-faced, with blocks of kankar: the remains of Murtaza Khân's fort, show many a scene of picturesque ruin. But the gem of the whole place is the grand masjid and tomb of Mîrân Sadr Jahân, Akbar's celebrated chancellor, and of his son, Mîr Badri-Âlam.

IIb. The dargâh is a building of much beauty. A double dome, poised on red sand-stone pillars, rises from a pavement of brick, cased with carved slabs of stone, and shaded by tamarind trees of enormous girth. Lightness, symmetry, grace, delicate colour, and rich but not florid ornamentation, are its characteristics. According to its Persian inscription the building was commenced in A.H. 1057 and completed in A.H. 1067.

About five miles south-west of Pihânî lies the small village of Mansûrna-gar, whose original name was Nagar. Murîd Khân, the grandson of Mîrân Sadr Jahân, built a brick fort here, which was rebuilt in A.D. 1702, by Ibâdullâ Khân, who named the place Mansûrnagar after Nawâb Mansûr Alî Khân (Safdar Jang).

Three miles north of Mansûrnagar, at the village of Simaurgarh, are the vast ruins of a Thathêra stronghold. During the reign of Akbar, the Gaur Râjâ Lakshmîsêna removed his head-quarters from Kalhaur to Simaurgarh and built there on the ruins of the old Thathêra castle a large and lofty fort, the outer enclosure of which measured a mile each way.

12. Sâṇpî, town in tahsîl Bilgrâm, lat. 27°-17′ N., long. 80° E., 12 miles southwest of Hardôi, takes its name from Sântannagar, or Sântankherâ, the fortified head-quarters of Râjâ Sântan Singh, a Sombansi Chhattri, the ruins of which are lying a short distance to the north of the present town of Sâṇḍî.

The Musalman conquerors, in A.D. 1398, abandoned Santankhera, and founded a new town about a mile and-a-half to the south-east, and named it Fathpûr Islamabad. But pestilence broke out 22 years later and caused the abandonment

- III. of the new town. The village of Chandîâpûr stands near the deserted site which is now known as Fatihan Kherâ. In compliance with the wishes of the inhabitants the old town was re-peopled, and the Musalmâns gave it the name of Ashrafâbâd; but the new title did not survive, and Sântan dîh, contracted into Sândî, became its name.
- III. The ruined fort of Râjâ Sântan Singh, now called Unchâtîlâ, has been built on one of those isolated bluffs where soil harder than usual has withstood the river floods of ages, and has left a natural fortress commanding the adjacent basin of the river Garrâ. Here, layer upon layer, are piled the vestiges of the Ârakhs,
- III. Thatheras, Sombansis, and Sa'ids of the past, crowned with the remains of an earthwork thrown up during the reign of Shuja-ad-daulah.
- IIb. To the east of the town are the dargâhs of Shâh Allah Baksh Darwesh, also called Zinda Pîr, and of Maulâna Khâlis, faqîrs of great local renown, and claimed by tradition as companions in arms of Sa'id Sâlâr Masa'âd. These tombs seem to have been built about the end of the 14th century. One of them has evidently been chiefly erected out of the ruins of an ancient Hindû temple, being constructed almost entirely of large blocks of kankar of different sizes. At the edge and in front of the raised platform are two large blocks, of which the upper surface has been hewn into the segment of a large circle. In their present position these stones are without use or meaning; they have apparently been originally a part of the doorway of a Hindû temple.

Other fragments of pillars and bas-reliefs, belonging probably to the same building, are collected at the shrines of Mangala Devi and Gobardhani Devi, to the east of Maratganj. Close by is the Phûlmatî, a bas-relief representing a chaitya-like structure, rising over a seated central figure with attendants, of apparently Buddhist origin.

The town possesses two masjids, one built in A.H. 1013, and the other in IIb. A.H. 1113, and the tomb of Alî Raza, erected in A.H. 1144, as is apparent from their Ib. Persian inscriptions. In Munshiganj there is a large masonry well, called mitha kûâ, said to be of a date prior to the Sombansi occupation of Sândî under Râjâ Sântan Singh.

A mile from the town, in Adampûr, at the edge of the great Sandî lake Dâhar, a little spring wells up and trickles into it. The spot is called Brah-IIb. mâvarta, and is regarded with peculiar veneration by the Hindûs of the neighbourhood.

- 13. Sandîlâ, tahsîl, 27°-4′ N., long. 80°-34′ E., 34 miles south-east of Hardôî, possesses a ruined masjid built in A.H. 769, during the reign of Fîrûz Shâh, another built in A.H. 962, during the reign of Akbar, and a third one built in Hb.
 1121, as stated in their Persian inscriptions. In the garden enclosing the bârakham-bhâ, or hall of 12 pillars, there is a tomb, dated A.H. 971.
- The village of Manjhgaon, 14 miles north of Sandila, possesses the ruins of a large brick fort, with a fragmentary Sanskrit inscription of the 12th century.
 - 14. Sârâ, small village in tahsîl Hardôî, 14 miles north of head-quarters, is devoid of antiquities; but the pargaṇa of Sârâ contains the following twelve villages

- III. which contain dils, ascribed to the Thathêras, viz., Rûhi, Hariâon, Kurselî, Bîjgâon, Uttar, Ariâri, Bargâon, Toḍarpûr, Dhanwâr, Râmpûr, Sa'âdatnagar, and Kamâlpûr.
- 15. Shāhābād, tahsîl, lat. 27°-38′ N., long. 79°-59′ E., 24 miles north of Hardôî, III. is built on an extensive dih, the débris of a large Hindû town, ascribed to the Thathêras. In 1677 A.D., Nawâb Dilêr Khân, a distinguished officer of Shâh Jahân, founded the present town of Shâhâbâd, and in the centre of the mound
- III. raised a spacious fortified brick-palace, known as the Barî Dêorhî, of which
- III. two large gateways are still standing. He erected a fine Jâmi Masjid and his own maqbara, built of large dressed kankar blocks. The latter is in a ruinous condition, and its dome has fallen; the walls on the upper storey contain bands of florid decorations on red sandstone after the manner of those on the Tâj at Âgrâ. Frag-

About six miles south of Shâhâbâd, at the village of Saromannagar, are III. the ruins of a large brick fort, erected in A.D. 1708 by Râi Saroman Dâs of Sândî.

ments of Brahmanical statues are lying on the banks of the old Raitauha tank.

II.-KHERT DISTRICT.

- Aurangâbâd, town in tahsil Muhamdî, lat. 27°-47′ N., long. 83°-27′ E., 32
 miles south-west of Kherî, possesses the ruins of a large brick fort and palace, built by Nawâb Sa'id Khurram in the time of Aurangzib.
- 2. Balmiar-Barkhar, old village in tahsîl Muhamdî, 44 miles south-west of III. Kherî, is perched on the top of an extensive brick mound. Barkhar, or Barîkhar is said to be a corruption of Bariyakherâ, or Vairāṭakherâ, and its foundation is attributed to king Virāṭa in the time of the Pāṇḍavas.

According to General Cunningham,1 the ruined mound is 1,000 feet in length at

top from east to west by 600 feet in breadth, and from 16 to 20 feet in height. But the dimensions at the base are much more, as the slope is very gentle, being 200 feet in length on the north side. This would make the base of the mound about 1,400 by 1,000 feet, which agrees with the size of 50 bighas, or 1,400,000 square feet, which is popularly attributed to it by the villagers themselves. But the fields are strewn with broken bricks for upwards of 1,000 feet to the northward, and for 500 or 600 feet to the eastward, where there are the remains of several brick temples. The area actually covered by ruins is not less than 2,000 feet square, or upwards of one and-a-half miles in circuit, which shows that Barkhâr must once have been a good-sized town; but the story of the Brâhmaṇas, which attributes its foundations to Virâța, must be rejected. Virâța's capital, where the five Pâṇḍavas spent their thirteenth year of exile, as described in the Mahâbhârata, has been correctly identified by General Cunningham² with Bairâțnagar, an ancient town in the Alwar State of Râjputâna.

IIb. The present village of Barkhar possesses a small Hindû temple of no interest, where some broken sculptures of good workmanship are collected, amongst which there is a lingam with a fragmentary Kuţila inscription of the 10th century A.D.

¹ Archaeological Reports, Vol. I, page 351.

² Archaeological Reports, Vol. II, pages 241-249.

III.

IIb.

- 3. Barwar, town in tahsîl Muhamdî, lat, 27°-50′ N., long. 80°-24′ E., 34 miles south-west of Kherî, possesses the ruins of a brick fort, built by Nawâb Maqtadi Khân, great-grandson of Mîrân Sadr Jahân.
 - 4. Bhûr, village in tahsîl Lakhîmpûr, 16 miles north-west of Kherî, is devoid of objects of antiquarian interest; but all along the edge of the great sûl forest in pargaṇa Bhûr, and near the banks of the river Ûl, there are found numerous brick-strewn mounds, or dîhs, and occasionally the remains of large masonry wells. These mounds have never been touched; and as some of them are certainly Buddhist stûpas, they are worthy of a careful exploration.
- The villages of Aliganj, Shahpur, Barheya Khera, and Jagdispur III. contain the ruins of large brick forts and tanks, ascribed to the mythical King Bên, or Vêna.
- Close to Alîganj, at the village of Kâmp, are several old wells, the ruins of a large mediæval Hindû temple and of a brick fort, the latter having been erected by Chhîpi Khân, a famous Bâchhil Chief in Shâh Jahân's time. All these ruins are perched on a high bluff overlooking the Chaukâ river, buried in dense overgrowth and overshaded by lofty pipal trees.
- 5. Dhaurahrâ, town in tahsil Nighâsan, lat. 28° N., long. 81°9′ Е., 20 miles IIb. N.-Е. of Kherî, possesses three Hindû temples and a masjid of no interest. The town is said to derive its name from dêora, a small ruined temple, also called mâtâsthân, outside the city walls.
- The pargana possesses few antiquities worthy of the name. There is a small brick fort at Godurîâ, and a brick-strewn mound at the villages of Unchâgâon and Râmîâ-Bihâr.
- Ten miles south-east of Dhaurahrâ lies the fortified village of Îsanagar, and six miles further Fîrûzâbâd, which was founded by Fîrûz Shâh Khiljî in A.D. 1330. At both places there are ruined brick forts.
 - 6. Golâ-Gôkarnnâth, large village in pargana Haidarâbâd of tahsîl Muhamdî, 24 miles north-west of Kherî, a famous place of Hindû pilgrimage, is very picturesquely situated at the base of a semicircle of small hills, covered with sâl trees. There are four Hindû temples, a large masonry tank, four masjids, and numerous ruined Musalmân tombs, which crown the surrounding heights.
- of ordinary construction, having a square pediment of about 10 feet, an octagonal shaft and a circular roof. The lingam, which the temple enshrines, is the shaft of a round pillar, bearing the mark of a heavy blow with an iron mace—most likely one of those so common round Buddhist stûpas. The present temple is apparently not older than the time of Aurangzîb, and was most probably built on the ruins of a Buddhist stûpa. There is a tradition that Alamgîr endeavoured when visiting the place to drag out of the earth the great stone pillar which represents Mahâdeva; that the elephants harnessed to chains could not move it, although excavations had been made all round, and when the Emperor approached to discover the cause, tongues of flame darted from the bottom of the pillar towards him. The dismayed monarch is said to have retired, and endowed the shrine with extensive rent-free lands.

The temple is believed to be the central spot of a large area of sacred ground. There are four gates on the borders of this holy land, supposed to be at equal distances, 12 kôs from the centre; viz., Mâtî in the Shâhjahânpûr district to the west, Shâh pûr in pargaṇa Bhûr to the north, Dêokâlî near Kherî to the east, and Barkhâr in pargaṇa Muhamdî to the south. Through these four gates all pilgrims are compelled to pass before approaching the shrine. There is also a via sacra, with four shrines, round the temple at a distance of two kôs from it, viz., Badar Kuṇḍ to the east, Panâha to the north, Kirṇagaṛh to the south, and Mâin Kuṇḍ in Ahmadnagar to the west.

IIb.

Hb.

III.

III.

III.

IIb.

Ia.

The lesser shrines and the tombs of the Mahants are of the same construction, and are simply enlarged copies of the Buddhist votive stûpas. Buddhist bas-reliefs still appearing in the recesses of the walls sufficiently prove the truth of this theory. In the close neighbourhood several Buddhist terra-cotta images of the purest type have been dug up.

About eight miles east of Golâ-Gôkarnnâth lies the village of Bhetvâ, or III. Mosâîm, possessing the extensive ruins of an ancient city, now imbedded in dense jangal. Two of the most prominent mounds, called Faqîr-kî-Maṭhî and Telenîâ-bîjna, are covered with fragments of large bricks and broken statues of Vishnu and Mahisha Mardinî, or Durgâ. In many places the walls of buildings, constructed of bricks measuring 18"×12"×4", are still rising up some 20 feet above the ground, and several large octagonal wells, built of large kankar blocks, attest the high antiquity of the place.

7. Haidarábád, village in tahsíl Muhamdí, 28 miles north-west of Kherí, possesses, to the south, near the banks of the Kháwá river, the ruins of the jangal-clad fort of Muhammadâbâd, erected by the Sa'ids of Pihání.

Ahmadnagar, Siâthû and Âtwâ Piparîâ contain the ruins of large brick forts, overgrown with dense jangal.

8. Khairigarh, town in tahsil Nighāsan, lat. 28°-26' N., long. 80°-41' E., 32 miles north of Kherî, possesses, on the banks of the Sarjû river, a large ruined square fort, known by the name of Shahâb-ad-dîn Ghorî, the conqueror of Prithvî-râja, who is said to have been confined here after his defeat. The walls and bastions are built of huge blocks of dressed kankar below, and above of bricks of very large size; the interior now lies waste and is infested with wild beasts. The fort was one of the best in India, as recorded in the Âîn-î-Akbarî, and was visited by Fîrûz Shâh of Delhî in A.D. 1355. Outside the fort are lying about in the jangal fragments of ancient sculpture, mostly representing the different Avatâras of Vishņu, and in the construction of the walls of the neighbouring dargâh of Pîr Sa'âdat Alî carved kankar blocks have been utilized. These fragments, no doubt, belonged to some ancient Hindû fane in the neighbourhood.

The modern town of Khairigarh is two miles north-east of the great fort, the intervening space being covered with broken bricks and fragments of statues, and overgrown with dense jangal, the lair of beasts of prey.

About two miles north-west of the fort stood till 1885 the life-size stone figure of a horse, buried in dense jangal; though of rude workmanship, it is nevertheless interesting on account of a fragmentary Gupta inscription of Samudragupta

III.

being incised on the right side of the neck. The attitude is stiff, and the workmanship of the legs is hard, weary, and unnatural, but the back is skilfully caparisoned. Judging from the inscription, it is meant to be a substitute for a real, but costly, sacrificial horse. This stone horse is now standing in the compound of the Lucknow Provincial Museum.

The neighbouring village of Kundilpûr, or Kundanpûr, possessing extensive brick mounds and numerous broken sculptures, claims the honour of being the ancient city of Bhîshmaka, from which place Krishna carried off his daughter Rukhminî. See, however, note on Ahâr in the Balandshahr district.

9. Kherî, large town in tahsîl Lakhîmpûr, lat. 27°-54′ N., long. 80°-51′ E., from which the pargaṇa and district of Kheri derive their names, is of comparatively modern origin, though local tradition claims it to be founded by Kshêmakarṇa, a companion of Janamejaya,¹ the great-grandson of Arjuna, who is said to have performed his great sacrifice for the extirpation of the Nâgas at Dêokâlî, five miles west of Kherî. Others derive the name of Kherî from the abundance of rice and milk (khîr), which was produced in this then pastoral country.

III. The town possesses fourteen Hindû temples, twelve masjids, three imâmbâras, and several dargâhs, of no architectural interest, and a ruined brick fort. Ålamgir's masjid was built in A.H. 1072, Sa'îd Khurd's dargâh in A.H. 970, and that of Chedâ Miyân in A.H. 1157, as stated in their respective Persian inscriptions. The dargâh of Sa'îd Khurd is composed of huge kankar blocks and the large bricks of olden times, here and there intermixed with the common small bricks of the Moghal period.

III. The pargana of Kherî possesses numerous brick mounds, the sites of ancient cities, at the villages of Gûm, Ujâr, Gumchâînî, and Salîmpur, with the remains of large octagonal wells, built of large kankar blocks. Along the banks of the river Ûl are the ruins of an ancient nameless town, consisting in an almost unbroken line of brick-strewn kherâs, extending from the village of Râmpûr-Gôkul to Rangîlnagar.

IIIb. About five miles west of Kherî lies the village of Dêokâlî, which possesses a III. large masonry tank, called Sûrâjkuṇḍ, and extensive brick mounds covered with broken statues of Durgâ, the navagrahas, etc. According to local tradition, Janamejaya performed his great snake sacrifice on the banks of this ancient tank.

 Kukrâ, village in tahsîl Lakhimpûr, 34 miles north-west of Kherî, possesses a small brick fort.

III. At the village of Unchagaon there is an ancient dih, from which Buddhist sculptures have been dug up.

11. LAKHÎMPÜR, tahsîl and head-quarters of the Kherî district, is picturesquely situated on the south bank of the river Ûl, about four miles to the north of Kherî.

About ten miles north-west of Lakhîmpûr, on the banks of the river Ûl and near III. the village of Fath Karrâ, are numerous mounds, covered with broken bricks and blocks of carved stone, imbedded in dense jangal. The principal mound seems to have been crowned by a large temple dedicated to Sûrya, as a large sculpture, representing Sûrya and his seven horses, and broken into four pieces, is still lying

¹ See also article on A h ar in the Balandshahr district.

half-buried in the mound. Large pillars and friezes of the Gupta period, and statues representing Durgâ, Ardhanârî, and Vishņu are lying about in the jangal, which show considerable expression and freedom of execution.

About nine miles to the west of Lakhîmpûr, at the village of Kaimahra, there is a large masonry tank in a ruinous condition. The neighbouring village of Bêl possesses the ruins of a brick fort, ascribed to the Sa'ids of Pihani.

MITHAULÎ, village în pargana Kastâ Abgâon of tahsîl Muhamdî, 22 miles
 south-west of Kherî, contains the ruins of a very strong mud fort.

III.

III.

- 13. Muhampî, tahsîl, lat. 27°-58' N., long. 80°-19' E., 36 miles west of Kherî, possesses the ruins of a large brick fort, having two oblong courtyards. The main part of this fort was built by Sa'îd Maqtadi, the great grandson of Mîrân Sadr Jahân, in the beginning of the reign of Aurangzîb, whilst the outer works were added by Alî Akbar Khân in the time of Sa'âdat Alî Khân, governor of Audh.
 - 14. Nighasan, tahsil, 24 miles north of Kheri, is devoid of objects of antiquarian or architectural interest.
- The village of Pasgawân, ten miles south of Muhamdî, contains a mud-built IIb. fort and sarâi, erected by Haqîm Mehndî Alî, chakladâr of Muhamdî, at the end of last century.
- III. In pargaņa Nighâsan there are the remains of an old brick fort at the village of Munrâ-Munrî.
- The village of Majhgãon, 16 miles north-west of Nighâsan, contains an IIb. extremely plain white marble statue, called Dhanurdhâri Nâth, of apparently Thibetan origin, whose head-dress consists of a high cone rising from a circular cap.

III.—Sîtâpûr District.

- BARÂGÂON, village in pargaṇa Maholî of tahsîl Misrikh, 17 miles north-west
 of Sîtâpûr, is perched on an ancient kherâ, and possesses seven old masonry tanks.
 - 2. Bârî, large village in tahsîl Siddhaulî, 23 miles south of Sîtâpûr, is said to have been founded by Mubâraq Shâh, son of the Emperor Humâyûn, but it was already known to Alberûni¹ as the capital of Eastern Audh, after Kanauj had fallen into neglect and ruin. There are, however, at present no ancient remains of any value visible.
- Biswân, tahsîl, lat. 27°-29′ N., long. 81°-2′ E., 21 miles east of Sitâpûr,
 possesses some kankar-built dargâhs of the early Moghal period, said to have been erected over the bodies of several followers of Sa'îd Sâlâr Masa'ûd; the most note-
- IIb. worthy is called Ek Râtia Rauzâ. The masjid of Mumtâz Khân, built in A.H. 1047, according to its Persian inscription, is remarkable for its solidity and for the large size
- IIb. of the kankar blocks used in its construction. The palace, sarâi, masjid, and dargâh of Shaikh Bâri, erected in A.H. 1173, as stated in several Persian inscriptions, are stately buildings; the mînârs of the masjid presenting curious structural features of clearly Hindû design and workmanship.
- IIb. The village of Bisendî, five miles south-west of tahsîlî, contains the dargâh of Shâh Rukn, erected in A.H. 1041, as stated in a Persian inscription.

^{*} Sachau, Alberûni's India, Vol. I., page 199.

Ia. A copperplate grant of Govindachandra Dêva of Kanauj, dated Samvat 1180,1 was found, in 1885, at the village of Raiwân, eight miles north-west of tahsilî, by a Brâhman, digging for bricks in a small kherâ close to the village. The original plate is now in the Lucknow Museum.

At the villages of Bambhaur and Sândâ in pargana Biswân are several brick-strewn mounds, or dîhs, of considerable height and extent, and some large square wells built of kankar blocks, ascribed to the Bhârs and Kâcheras.

4. Hargam, town in tahsil Sitapûr, lat. 27°-45′ N., long. 80°-47′ E., 12 miles north of head-quarters, is the ancient Haragrama, said to have been founded by king Harischandra of Ayodhya. Local tradition also claims for it the honour of being the capital of King Virata, at whose court the Pandavas lived in concealment during the thirteenth year of their exile. Like Barkhar in the Kheri district, it has a site where Bhîmasena is said to have killed Kîchaka, the chief of the army of King Virata.

Hargâm, though now decayed, was apparently once a very extensive and important city, as evidenced by the height and extent of its ancient *kherâ*, which is covered with broken bricks, terra-cottas, sculptured stones, and an ancient masonry tank, called Sûrâjkuṇḍ. The highest top of the mound is crowned by a dargâh of the early Moghal period, which appears to have been built on the site, and with the materials, of an ancient Hindû temple. The high antiquity of the place is attested by the large hoards of very early Hindû coins that are found amongst its ruins.

5. Khatrâbâd, town in tahsîl Sîtâpûr, lat. 27°-32′ N., long. 80°-48′ E., five miles south-east of head-quarters, is a place of Hindû pilgrimage, whose original name is said to have been Mâsachitra, traces of which are still extant in the appellation of an old masonry tank, called Maswâsi Talâo.

IIb. The town possesses 30 Hindû temples, 40 masjids and dargâhs, a Qadam Rasûl and an imâmbâra of no architectural or antiquarian interest, the oldest buildings dating from the time of Akbar. The Masjid of Shaikh Chotê Makhdûm in mahallâ Miyân Sarâî was commenced in A.H. 993 and finished in A.H. 1056, as stated in two Persian inscriptions, whilst the dargâh of Shaikh Chotê Makhdûm bears the dates A.H. 993 and 994. The Jâmi Masjid was erected in A.H. 1060, during the reign of Shâh Jahân, as stated in its Persian inscription.

I. The pargana of Khairâbâd contains about 21 dîhs, the most prominent of which is at the village of Unâsiâ, four miles south of the chief town of the pargana, being an extensive mound with a wide fosse extending like a horse-shoe round three sides of it.

6. Lâharpûr, town in tahsîl Sitâpûr, lat. 27°-43′ N., long. 80°-57′ E., 17 miles north of head-quarters, was founded, and named Taghlaqpûr, by Fîrûz Shâh Taghlaq, in A.D. 1374, when on his way to the dargâh of Sa'id Sâlâr at Bahrâîch. Thirty years later one Lâharî Pâsî took possession of it and changed the name to Lâharpûr.

IIb. The town possesses 13 masjids, four dargâhs, and six Hindû temples of ordinary construction. According to the tradition of the people, Râjâ Toḍaramalla, the

III.

III.

IIb.

III.

Ш.

Journal, Asiatic Society of Bengal, Vol. LVI., page 107; Indian Antiquary, Vol. XVIII., page 57, where the date is given as Samvat 1187.

famous Hindû minister of Akbar, was a native of this town, whilst Dr. Blochmann¹ states, on apparently good authority, that he was born at Lahôr.

- 7. Mahôlî, large village in tahsîl Misrikh, 15 miles north-west of Sîtâpûr, is said to derive its name from Mahîpâla, who founded it on the ruins of an older town which had fallen into decay. The village possesses the ruins of a brick fort and sarâî, built in the time of Shujâ-ad-daulah, but no other remains.
- 8. Mahârâjnagar, large village in tahsîl Biswân, 16 miles east of Sîtâpûr, III. formerly called Islâmnagar, possesses the ruins of an old masjid.
- 9. Manûâ, large village in tahsîl Siddhaulî, 26 miles south of Sitâpûr, possesses an extensive kherâ, overlooking the river Sarâyân and covering an area of 90 bîghas, said to be the ruins of an old fort, built by King Mândhâtri of Ayodhyâ. According to others, the mound represents the remains of the ancient city of Maṇipûra of the Mahâbhârata, near which Arjuna was slain in battle (raṇa) by his son Babhruvâhana, and in confirmation of this the people point out the village of Raṇûâpâra, at a distance of one mile from Manûâ. But this claim must be negatived, as Maṇipûra was the capital of the Kaliñga country and situated on the sea shore; most probably, however, the ancient name of this once important city was Mânavapura. Last century the place was known as Mânpûr-Mustafâbâd, and from this time date the small dargâh and îdgâh close to the ancient kherâ.

Manûâ is no doubt a place of high antiquity and is worthy of a careful exploration, as its *kherâ* has yielded large bricks of the olden times and innumerable Brâhmaṇical sculptures of exquisite workmanship, some of which are exhibited in the Lucknow Museum.

About six miles north-west of Manûâ lies the village of Nasîrâbâd, perched on a high dîh, and possessing two brick temples, called Kalâpadevî and Âstika, and dating from the tenth century A.D., in a fair state of preservation. Outside the whole surface of the walls is richly decorated with deeply cut arabesque ornaments in perpendicular lines, the effect of which is very pleasing. Each temple had originally four corner temples of smaller size, and decorated with moulded bricks.

At the village of Khairandeshnagar, about 10 miles east of Manûa, are the remains of an old Hindû temple, in plan an octagon standing on a circular plinth.

10. Misrikh, tahsîl, lat. 27°-26′ N., long. 80°-34′ E., 13 mîles south of Sîtâpûr, is undoubtedly a town of great antiquity, being still a noted place of Hindû pilgrimage. The name is locally derived from Sanskrit miśrita, because Rishi Dadh yañch is supposed to have "mixed" the waters of all holy places in India with that of the large sacred tank in the town. This masonry tank, surrounded by pakkû ghâts and a belt of shabby brick temples of modern date, has in its centre a sacred well, called Sarasî. The temple dedicated to Rishi Dadhyañch is said to be very old; but judging from the style of its construction, it cannot be older than about 200 years.

Three miles west of Misrikh, at the village of Pataunjā, are the remains of a very extensive city, and the site of one of its gates is pointed out three miles further to the north-west in the village of Sulţānnagar, where there are the ruins of an old temple marking the spot.

Ш.

III.

Ib.

III.

Hb.

Ш.

III.

¹ Ain-i-Abbari, Vol. I., page 351.

IIb.

The village of Jargawan in pargana Karauna of tahsil Misrikh possesses an ancient masonry tank, called Karjûra.

III. The large village of Machhrehtâ contains the remains of a brick fort and a Ha. large masonry tank, called Haradvaratirtha.

11. NIMKHÂR,¹ or Nimsar, famous place of pilgrimage in tahsîl Misrikh, lat. 27°-26′ N., long. 80°-35′ E., 20 miles south of Sitâpûr, situated on the left bank of the Gûmtì, or Gomatî, is the ancient Naimishâraṇya. The Brâhmaṇas derive the name from nimisha, "a twinkling of the eye;" hence Naimishâraṇya (Nimkhâr), or Naimishasaras (Nimsar) means the forest or pool where in the twinkling of an eye the sage Gauramukha destroyed an army of the Asuras. The Vishnupurâṇa declares that "he who bathes in the Gomatî at Naimisha expiates all his sins;" its popularity is therefore very great. It is noticed in the Âîn-î-Akbarî as a famous large fort, with a great number of Hindû temples and a reservoir.

IIb. This reservoir is called Chakratirtha, and is said to be the place where the chakra, or discus of Vishņu, fell during the contest with the Asuras. The shape of the pool is nearly hexagonal with a diameter of 120 feet. The water springs up from below and flows out by the south side into a swampy rill about 20 feet broad, called the Godâvarî Nâlâ. The pool is surrounded with a number of shabby brick temples and dharmsâlas, and though the water is clear, yet the place looks dirty and uninviting.

III. The fort is situated on a precipitous mound to the south-west of the holy pool, about 1,100 feet long from east to west between 300 and 400 feet broad and 50 feet high. The west end is a high cliff, called the Shâh Burj, which overhangs the Gâmtî. The gate of the fort, which is at the east end, is arched and built of Hindû materials, partly brick and partly kankar blocks, which betray their origin by their carving and by the presence of the svastika symbol. The walls were originally of brick, but they have long ago disappeared, and the only parts of the old fort now standing are the gateway and the Shâh Burj. The foundation of the latter is of Hindû construction, and as there are many carved bricks lying about, it was probably a temple. The fort is provided with a large well, built of kankar blocks, 8½ feet broad and 51½ feet deep to the water level.

The tradition of the place is that the fort was rebuilt in A.D. 1305, by Hâhâjâl, a renegade Hindû who is said to have been the Vazîr of Alâ-ad-dîn Khiljî. The original Hindû fort is believed to have been as old as the Pâṇḍavas; and if the derivation of the name of the place has been truly handed down, it must have been occupied even earlier than the time of the Pâṇḍavas.

On the opposite bank of the Gûmtî there is an old mound called Orâjhâr, Orâdîh, and Bênnagar, which is said to have been the residence of Râjâ Bên, or Vêṇa.

12. Shorâ, village in pargaṇa Kundrî (North) of tahsîl Biswân, 32 miles east of Sîtâpûr, possesses the ruins of an old masjid and a large kherâ, said to be the remains of a fort built by Âlhâ, the famous Banâphar hero at the court of King Parmâl of Mahobâ.

¹ Cunningham, Archaelogical Reports, Vol. I., page 350.

- About six miles north of Sêotâ lies the village of Tambaur, containing the III. dargâh of Shahîd Barhân-ad-dîn and the ruins of an ancient brick fort, called Qilâ Nawâ in the Âîn-î-Akbarî.
 - 13. Sîtăpür, tahsîl and head-quarters of district, lat. 27°-35′ N., long. 80°-43′ E., of comparatively modern origin, is devoid of monumental antiquities of any real mark. The name of the town is locally derived from Sîtâ, Râmachandra's consort, who is said to have tarried in this locality some time during her pilgrimage.
- To the west and east of the present town there are two small mounds, called III. Bairâṭ-kê-dîh, which are covered with broken bricks and fragments of sculpture and pottery.
- About seven miles south-west of Sîtâpûr lies the village of Râmkôţ, perched III. on an ancient dih, the remains of an once important city.
- The village of Pirnagar, 14 miles south of Sitapur, possesses five Hindû temples of no architectural interest, the most frequented being that in honour of Dudhnath, and a masjid erected in the time of Alamgir.
- III. The pargana of Pirnagar contains nine nameless dihs, varying in area from 20 to 50 acres, and raised from the surface of the ground by from 20 to 100 feet. They are covered with fragments of pottery, bricks, and sculptures, and are the sites of ancient fortified cities.
- The village of Shah Qulipûr, 19 miles north-east of head-quarters, possesses IIb. the dargah of Shakh Lam-ad-din, bearing dates A.H. 946 and 976.

X.—FAIZÂBÂD DIVISION.

I.—BAHRÂÎCH DISTRICT.

1. Bahrâîch, tahsîl and head-quarters of district, lat. 27°-35′ N., long. 81°-40′ E., is picturesquely situated on the edge of a high bank under which once flowed the river Ghâghrâ. The name is locally derived from Brahmâ, who is said to have chosen this district, a part of the ancient Gandharvavana, as his own special kingdom, and calling together a company of Rishis, to have established his worship in the midst of these lonely wilds; hence arose the name Brahmâîch,¹ or Bahrâîch, "the assembly of Brahmâ." Another and more probable origin of the name, however, lies in the fact that formerly the whole of the country around was held by the Bhârs.

The present town is celebrated for the dargah of Sa'id Salar Masa'ad, Пb. being of peculiar sanctity, in the neighbouring village of Singha Parasi, two* miles north of head-quarters. According to the Mirâț-î-Masa'ûdî, Sa'îd Sâlâr Masa'ûd, nephew of Sultan Mahmûd of Ghaznî, after an engagement with the Hindûs, rested under the shade of a mahûâ tree, on the bank of the Sûrâjkuṇd, close to the temple of Mahadeva. The place was several marches distant from Bahraîch, as he returned to Bahraich from the Sûrajkuṇḍ by regular stages, and is no doubt to be identified with the present village of Hathili, or Asokpur in the Gonda district. As he had taken a great fancy to the spot, he ordered a platform of masonry to be built under the shade of the mahûû tree to serve him for a seat. Apparently this was the place of his death, as, during the battle, he directed his followers to throw the bodies of the dead believers into the Sûrâjkuṇḍ, while the few troops that remained stood round him in the garden. His chief opponent in this last battle, in A.H. 424, or A.D. 1034, was Suhriddhvaja, Raja of Gonda, who is clearly the Suhal Dêo of the popular legends.

Masa'ûd's dargâh at Bahrâich was not built until two centuries later by Malik Nasîr-ad-dîn Muhammad, elder son of Sulţân Shams-ad-dîn Iltitmish, and it was visited in A.D. 1340 by Sulţân Muhammad Taghlaq, and in A.D. 1374 by Fîrûz Shâh Taghlaq. A Persian inscription over the southern doorway of the inner enclosure of the dargâh states that Amîr Masa'ûd was born in A.H. 405 and departed in the crusade in A.H. 424, at the age of 20 years. A little further to the west of this inscription, there is built into the wall a copperplate, recording in Persian the revenue-free grant of the village, in which the dargâh stands, by Akbar II, of Dehlî. In the malkhâna of the dargâh are two copperplates, the one recording in Persian the release of the dues from the Sa'îd Sâlâr mêlâ by Bandâi Alî in A.H. 1177, and the other the release of the dues from the dargâh by Mirzâ Mehndî Alî Khân in A.H. 1215.

IIb. In and around Bahrâich are situated the dargâhs of several fellow-martyrs of Sâlâr Masa'ûd; the best known of these is that of Rajjab Sâlâr or Miyân IIb. Rajjab, the confidential slave of Sâlâr Sâhû, Masa'ûd's father. The dargâh of

General Cunningham, Archeological Reports, Vol. XI, page 100, gives the ancient name of Bahraich as Vaharānch.

- III. Amîr Shâh, a reputed darwêsh from Baghdâd, is of no interest. The Daulatkhâna, a handsome range of buildings, erected by Asaf-ad-daulah, is now in ruins.
- IIb. At the village of Dekaulî, 12 miles north-east of Bahrâîch, is the dargâh of Amîr Nasîr-ullâ, younger brother of Sulţân Mahmûd of Ghaznî, whom Firdûsî in his Shâhnâmah names Sipâhdâr Tûs.
 - 2. Bahrâmpûr, town in tahsîl Qaisarganj, lat. 27°-7′ N., long. 81°-32′ E., 35 miles south of Bahrâich, lies on the left bank of the Ghâghrâ, and is said to take its name from Bahrâm Khân, one of Sa'îd Sâlâr Masa'ûd's officers, who met his death in the invasion of A.H. 424. The martyr's dargâh has, however, been washed away by the river in A.D. 1876. The town possesses four Hindû temples and three masjids of no interest.
- 3. Bhingâ, village in tahsîl Bahrâich, lat. 27°-42′ N., long. 81°-57′ E., 24 miles north-east of head-quarters, possesses an old brick fort on the left bank of the river Râptî.

IIb.

- At Hâthiyâ Kuṇḍ, 12 miles east of Bhingâ, on the borders of the sâl forest, there is a high kherâ of great extent, said to be the ruins of one of the principal cities of Râjâ Karṇa of the Mahâbhârata. The mound is covered with broken bricks and fragments of sculpture, and the foundations of a large stone temple are still visible.
- 4. Chardâ, or Chahârdah, village in tahsîl Nânpâra, 26 miles north of Bahrâîch, possesses a large brick-strewn kherâ, the ruins of an apparently Buddhist city. These remains are of almost exactly similar character, but of smaller dimensions, as the ruins at Sâheţ-Mâheţ in the Goṇḍā district, which have been identified with the ancient Buddhist city of Śrâvastî. Chardâ is about 40 miles to the north-west of Sâheţ-Mâheţ, and there cannot be a doubt but that it dates from the same age as that larger and better known city. Common tradition assigns it to Suhal Dêo, or Râjā Suhriddhvaja of Goṇḍa, the chief opponent of Sa'id Sâlâr Masa'ûd; but, though it may have been occupied at that time, its construction doubtless dates from the earlier Buddhist period. It probably formed one of that chain of fastnesses which are to be found lying along the foot of the Himâlaya range, and agreeing with this view is the derivation assigned by the natives to its name, it being, they say, the fourteenth (chaudâh) of this system of forts.
- FAKHRPÜR, town in tahsil Qaisarganj, lat. 27°-25' N., long. 81°-31' E., ten miles
 south of Bahrâich, possesses the ruins of a brick fort built in the time of A k b a r.
- 6. Hisâmpûr, village in tahsil Qaisarganj, 20 miles south of Bahrâich, is said to have been founded on the ruins of the old Bhâr town of Purênî by Hisâm-al-Haq, one of the comrades and co-martyrs of Sa'îd Sâlâr. It is, however, not unlikely that the place derives its name from Malik Hisâm-ad-dîn Taghlaq, who was governer of Audh in A.D. 1240.
- III. In pargana Hisampûr there are a number of kankar-built wells, small ruined forts, and old village sites or kherâs, the principal of which are in Purêm, Karnâî, Jarwal, Mohrî, Bhokaurâ-Sakanthâ, Kasehrî Bazarg, Hasnâ-Mulâî, Wairâ-Qâzî, Bhaulî Dîh, all of which, according to local tradition, owe their existence to the Bhârs: at the village of Tawakkulpûr they are said to have built an imposing fortress with 52 towers.

- 7. Ikauṇâ, village in tahsîl Bahrâich, lat. 27°-33′ N., long. 81°-59′ E., 22 miles east of head-quarters, possesses the ruins of an angleless fort which, according to the people, gave to the place the name of Akoṇâ. Most likely, however, these ruins represent the stûpas of Âptanêtravana or Âptâkshivana, a place mentioned by Hiuen Tsiang¹ as being situated 3 or 4 li to the north-west of the Jêtavana monastery at Śrâvastî, which has been identified with the remarkable ruins at Sâheţ-Mâheţ in the Goṇḍâ district, about four miles to the south-east of Ikauṇâ.
- Nânpâra, tahsîl, lat. 27°-51′ N., long. 81°-32′ E., 22 miles to the north of Bahrâich, possesses five Hindû temples, three masjids, and one idgâh of no particular interest.

About four miles west of Nanpara, on the banks of the river Sarjû, are the remains of the very large and most substantially built town of Dûgâon. Abul Fazl in the Âin-î-Akbarî mentions the town as being a copper mint and a flourishing place, the centre of a considerable trade with the hill tribes; and in the Arâish-î-Mahfil it is described in similar terms under the name of Dêokhan.

9. Tanpwå, old village in pargana Ikaunâ of tahsîl Bahrâich, 20 miles east of head-quarters, has been identified by General Cunningham² with the birth-place of Kâsyapa Buddha, called Towai by Fa Hian,³ who places the town at 50 li to the west of Śrâvastî, whilst Hiuen Tsiang⁴ does not give its name, but states that it was about 60 li to the north-west of it. The bearing and distance point to the village of Tandwâ, which is just nine miles to the west of Sâheţ-Mâheţ, the ancient Śrâvastî. There can, therefore, be no doubt as to the identity of the two places, as Tandwâ is a very old site, which is still covered with brick ruins. All the fields around are strewn with broken bricks, and within 1,000 feet of the village to the north-west there is a mound of brick ruins 800 feet long from east to west, and 300 feet broad. Beyond the mound, and to the north of the village, there is a large irregularly-shaped sheet of water, called Sîtâ-dohâr-tâl.

The west end of the mass of ruins is very low, but it is covered with broken walls and fine trees, and was therefore most probably the site of the monastic establishment. The general height of the east end is 16 feet above the fields, but rises to 20 feet at the south-west corner. At this point the mound is formed of solid brick-work, which, after close examination, General Cunningham discovered to be the remains of a large stûpa, with a diameter of 74 feet. The ruined mound of the stûpa is still 14½ feet above the floor of the court in which it stands. Some parts of the massive walls of the courtyard are still standing, and the complete size can be traced by the lines of the brick ruins. It was 365 feet in length from north to south and 160 feet in breadth, with a small outer court at each end, 160 by 100 feet. The lower part of the face of the stûpa was ornamented with a Buddhist railing in brick-work, supported on a line of dentils. These dentils are hollowed out and levelled at the ends; they appear to represent the ends of timber beams and to be copied from an original wooden construction. After having cleared away the rubbish from the outside of the great stûpa nearly all round, General Cunningham found the flights of steps on the

III.

III.

¹ Beal, Le. Vol. II, page 12.

^{*} Archaeological Reports, Vol. I, pages 248-250; Vol. XI, pages 70-78.

Beal, Le., Vol. I, page XLVIII.

^{*} Beal, Le., Vol. II, page 13.

north and west sides nearly perfect, with the outer wall of the stûpa still standing intact. On the south the steps were much broken, and on the east he was unable to dig owing to the presence of a huge banyan tree which stands in the very position which they would have occupied. His survey also revealed the very curious fact that the four gateways did not occupy the four cardinal points, the northern gate being $17\frac{1}{2}$ ° to the east of the magnetic meridian.

There is a small lingam on the mound, which, with the supposed statue of Sîtâ-IIb. mâi in a small modern temple, shares the devotions of the villagers. This figure is 3'4" in height, and presents a dancing girl resting on her left foot on a prostrate human figure, with her right knee bent. Her left hand rests on her hips, while her right hand is raised above her head grasping the branch of the favourite sâl tree. A parrot is perched on her upper left arm under the sâl branches, which on the left side have broken into flower. The stone of which this statue is made is the common red sandstone of the Faṭhpûr Sikrî quarries near Mathurâ; and as the whole of the costume and the attitude and pose of the figure with the crouching man under the feet are similar to those of the Mathurâ figures, there is little doubt that this statue was carved at Mathurâ.

The ruined stûpa is now named after this statue Sîtâ-dohâr, or "Sîtâ's mound," and the large lake close by, which is about a mile in length, is simply known as Sîtâ-dohâr-tâl, or "the lake of Sîtâ's mound."

III. There is an isolated mound 500 feet to the west of this stûpa, which would appear to be the remains of a small monastery. The traces of the walls show a square of 80 feet, with towers at the four corners. A little further to the west-north-west, at a distance of 3,700 feet from the stûpa, there is a long low mound upwards of 800 feet from north to south and 500 or 600 feet from east to west, which may have been the site of the old town. It now belongs to the recently established village of Allabbakshpûr; but as the land still belongs to Taṇḍwâ, the mound most probably represents the site of the old town visited by Fa Hian and Hiuen Tsiang. It is now called Bar-kî-bhârî, or "banyan tree mound."

III. Near the great stûpa on the south side there are the remains of several small isolated buildings containing from two to three rooms each.

At 300 feet to the east-south-east of the great stûpa, there is a small round-shaped mound, which from its appearance seems to be the remains of a second stûpa.

The accounts given by the two Chinese pilgrims of the sacred buildings at Tandwa agree in all main points, but they disagree as to the number of stupas, which Fa Hian makes to be three, while Hiuen Tsiang describes only two. Both of the pilgrims were informed that Tandwa was the birth-place of Kasyapa Buddha, but this is at variance with the Buddhist chronicles, which refer his birth to Banaras.

II.—FAIZÂBÂD DISTRICT.

1. AJUDHYÁ,¹ famous place of pilgrimage, in pargana Havelî Audh of tahsîl Faizâbâd, on the right bank of the river Ghâghrâ, lat. 26°-47′ N., long. 82°-15′ E., two miles east of head-quarters, is the ancient city of Ayodhyâ, described in

III.

Cunningham, Archieological Reports, Vol. I, page 317.

the Râmâyana as situated on the bank of the Sarayû, or Sarjû river. It is said to have been 12 yojanas, or nearly 100 miles in circumference, for which we should probably read 12 kôs, or 24 miles,-an extent which the old city with all its gardens might once possibly have covered. The distance from the Guptar Ghat on the west to the Râm Ghât on the east is just six miles in a direct line; and if we suppose that the city with its suburbs and gardens formerly occupied the whole intervening space to a depth of two miles, its circuit would have agreed exactly with the smaller measurement of 12 kôs. At the present day the people point to Râm Ghât and Guptar Ghât as the eastern and western boundaries of the old city, and the southern boundary they extend to Bharatkund near Bhadarsa, a distance of six kos. But as these limits include all places of pilgrimage, it would seem that the people consider them to have been formerly inside the city, which was certainly not the case. In the Ain-i-Akbari the old city is said to have measured 148 kos in length by 36 kôs in breadth, or in other words, it covered the whole province of Audh to the south of the Ghaghra river. The origin of the larger number is obvious. The 12 yojanas of the Râmâyaṇa, which are equal to 48 kôs, being considered too small for the great city of Ramachandra, the Brahmanas simply added 100 kos to make the size tally with their own extravagant notions. The present city of Ayodhyâ, which is confined to the north-east corner of the old site, is just two miles in length by about three-quarters of a mile in breadth; but not one-half of this extent is occupied by buildings, and the whole place wears a look of decay. There are no high mounds of ruins covered with broken statues and sculptured pillars, such as mark the sites of other ancient cities, but only a low irregular mass of rubbish heaps, from which all the bricks have been excavated for the houses of the neighbouring town of Faizâbâd. This Musalmân city, which is two miles and a half in length by one mile in breadth, is built chiefly of materials extracted from the ruins of Ayodhya. The two cities together occupy an area of nearly six square miles, or just about onehalf of the probable size of the ancient capital of Rama.

According to the Râmâyaṇa, the city of Ayodhyâ was founded by Manu, the progenitor of all mankind. In the time of Daśaratha, the father of Râma, it was fortified with towers and gates, and surrounded by a deep ditch. No traces of these works now remain, nor is it likely, indeed, that any portion of the old city should exist, as the Ayodhyâ of Râma is said to have been destroyed after the death of Bṛihadbala, after which it lay deserted until the time of Vikramâditya of Ujjayini, who, according to tradition, came in search of the holy city, erected a fort called Râmgaṛh, cut down the jangal by which the ruins were covered, and erected 360 temples on the spots sanctified by the extraordinary actions of Râma. The Vikramâditya of this story, General Cunningham¹ takes to be Chandragupta II, of the Imperial Gupta dynasty, A.D. 395—415, whose rule certainly extended to Ujjayinî, as his inscriptions have been found at Sâñchî and Udayagiri Bhilsâ.

There are several very holy Brâhmanical and Jaina temples about Ayodhyâ, but they are all of modern date and without any architectural pretensions whatever; but there can be no doubt that most of them occupy the sites of more ancient temples

Hb.

¹ Archaelogical Reports, Vol. XI, page 97.

IIb. that were destroyed by the Musalmans. Thus Ramkôt, or Hanuman Garhi. on the east side of the city, is a small walled fort surrounding a modern temple on the top of an ancient mound. This fort is said to have formerly covered a large extent of ground, and, according to tradition, it was surrounded by 20 bastions, each of which was commanded by one of Râma's famous generals after whom they took the names by which they are still known. Within the fort were eight royal mansions, where dwelt Dasaratha, his wives, and Râma, his deified son. The name Râmkôt is certainly old, but the temple of Hanuman is not older than the time of Aurangzib. Râm Ghât, at the north-east corner of the city, is said to be the spot where Râma bathed, and Svargadvâram, also called Râm Darbâr, on the north-west, is believed to be the place where his body was burned. Treta-kê-Thâkur is famous as the place where Râma performed a great sacrifice, and which he commemorated by setting up there images of himself and Sitâ. Close by is the Lakshmana Ghât, where his brother Lakshmana bathed, and about one quarter of a mile distant, in the very heart of the city, stands the Janmasthanam, or "birth-place temple," of Rama. Almost due west, and upwards of five miles distant is the Guptar Ghat, with its group of modern white-washed temples. This is the IIb. place where Lakshmana is said to have disappeared, and hence its name of Guptar, from gupta, "hidden or concealed." Some say that it was Râma who disappeared at this place, but this is at variance with the story of his cremation at Svargadvaram.

There are five Digambara temples at Ayodhyâ which were built in Samvat IIb. 1781, in the time of Shuja-ad-daulah, to mark the birth-places of five Tirthamkaras, viz., Adinatha, Ajitanatha, Abhinandanatha, Sumatinatha, and Anantajit, who are said to have been born at Ayodhyâ. The temple of Adinâtha is situated near the Svargadvaram on a mound, known as Shah-Juran-ka-tila, on which III. there are many Musalman tombs and a masjid. According to the local Musalman IIb. tradition, Makhdûm Shâh Jûran Ghorî, who came to Audh with Shahâb-ad-dîn Ghori, destroyed the ancient temple of Adinatha and erected on its ruins the Musalman edifices which gave to the mound the name by which it is still known. Besides these five temples of the Digambaras there is a sixth temple of the Svetambaras. Hb. dedicated to Ajitanatha, which was built in Samvat 1881.

It is locally affirmed that at the Musalman conquest there were three important Hindû temples at Ayodhyâ: these were the Janmâsthanam, the Svargadvâram, and the Treta-kê-Thâkur. On the first of these Mîr Khân built a masjid, in A.H. 930,1 during the reign of Babar, which still bears his name. This old temple must have been a very fine one, for many of its columns have been utilized by the Musalmans in the construction of Babar's Masjid. These are of strong, close-grained, dark-coloured. or black stone, called by the natives kasauti, "touch-stone slate," and carved with different devices; they are from seven to eight feet long, square at the base, centre and capital, and round or octagonal intermediately. On the second and third Aurangzîb built masjids, which are now mere picturesque ruins. A fragmentary III. inscription2 of Jayachchhandra of Kanauj, dated Samvat 1241, and recording the erection of a temple of Vishnu, was rescued from the ruins of Aurangzib's Masjid, known as Tretâ-kê-Thâkur, and is now in the Faizâbâd Museum.

IIb.

¹ Archaelogical Reports (New Series), Vol. I, page 67.

^{*} Archeological Reports (New Series), Vol. I, page 68.

Ib.

The only remains at Ayodhyâ that appear to be of any antiquity are three earthen mounds to the south of the city, and about a quarter of a mile distant. Ш. These are called Maniparbat, Kuberparbat, and Sugribparbat. The first, which is nearest to the city, and whose ancient name is said to have been Chhattarban, is an artificial mound, 65 feet in height, covered with broken bricks and blocks of kankar. The old bricks are eleven inches square and three inches thick. At 46 feet above the ground on the west side there are the remains of a curved wall faced with kankar blocks. The mass at this point is about 40 feet thick, and this was probably somewhat less than the size of the building which once crowned this lofty mound. According to the Brahmanas the Maniparbat is one of the hills which the monkeys made use of when assisting Râma, it was accidentally dropped here by Sugriva, the monkey-king of Kishkindhya. But the common people, who know nothing of this story, say that the mound was formed by the labourers shaking their baskets on this spot every evening on their return home from the building of Râmkôt. It is therefore best known by the name of Jhawwajhâr, or Orajhar, both of which mean "basket-shakings." A similar story is told of the large mounds near Banaras, Nimkhar, Sahet-Mahet, and other places. An inscription of Raja Nandivardhana of Magadha is said to have been discovered buried in this mound during the reign of Nasir-ad-din Haidar of Lakhnâû; but the inscription has never been published and the original plate cannot now be traced.

Five hundred feet due south from this large mound stands the second mound, called Kubêrparbat, which is only 28 feet in height. The surface is an irregular heap of brick rubbish, with numerous large holes made by the people in digging for bricks. It is crowned by two old tamarind trees and is covered with jangal. Close by on the south-west there is a small tank, called Ganêsakund by the Hindûs and Husain Kund or Imâm Talâo by the Musalmâns. Still nearer, on the south-east, is a large oblong mound, called Sugrîbparbat, which is not more than 10 feet above the ground level. It is divided into two distinct positions, that to the north being upwards of 300 feet square at top, and the other to the south upwards of 200 feet. In the centre of the larger enclosure there is a ruined mound containing bricks eight and-a-half inches square, and in the centre of the smaller mound there are the remains of a bâolî, which is said to be the Ganapatikunda of the Purânas.

Between the Maniparbat and Kubêrparbat there is a small Musalmân enclosure, IIb. 64 feet long from east to west and 47 feet broad, containing two brick dargâhs, which are attributed to Sîs Paighambar and Ayûb Paighambar, or the "prophets Seth and Job"; the first is 17 feet long and the other 12 feet. These tombs are mentioned in the Âîn-î-Akbarî and in the Arâish-î-Mahfil. About a mile off, near the police station, there is the dargâh of Nûh, or Noah.

The mounds are surrounded by Musalman tombs, and as it is the Musalman practice to bury the dead along the sides of the high roads close to their cities, General Cunningham infers that the road which now runs close to the westward of the mounds is one of the ancient highways of the district. This is confirmed by the existence of an old masonry bridge of three arches over the Tilahi Nala, to the north-west of the Maniparbat, as well as by the direction of the road itself, which

leads from the south end of the city straight to Bharatkund, and onwards to Sultanpur or Kusapura, and Allahabad, or Prayaga.

There can be no reasonable doubt that Hiuen Tsiang's¹ Pi-so-kia, or Viŝâkhâ, with its enormous number of heretics, or Brâhmaṇas, is the same as the Ayodhyâ² of the Hindûs. He describes the city of Viŝâkhâ as being 16 li or two and ¾ miles in circuit. In his time, therefore, the capital of Râma was not more than half of its present size, although it probably contained a greater population, as not above one-third, or even perhaps less, of the present town is inhabited. The old city then possessed no less than 20 saṅnghârâmas and 3,000 priests, and about 50 Brâhmaṇical temples. From this account we learn that so early as the seventh century more than 300 of the original temples of Vikramâditya had already disappeared, and we may therefore reasonably infer that the city had been gradually declining for some time previously. The Buddhist monuments, however, would appear to have been in good order, and the monks were just as numerous as in the eminently Buddhist city of Banâras.

The first monument described by Hiuen Tsiang is a large saingharama without name. This monastery General Cunningham identifies with the Sugribparbat, being about 500 feet long by 300 feet broad. The great size and rectangular form of this ruin are sufficient to show that it must have been a monastery, but this is placed beyond all doubt by the existence of an interior well and by the remains of cloistered rooms forming the four sides of the enclosure. Its position to the south of the city, and to the east of the road, agrees with the recorded position of the monastery.

Beside the monastery there was a stûpa of Asoka, 200 feet in height, built on the spot where Buddha preached the law during six years. This monument General Cunningham identifies with the Maniparbat, which is still 65 feet high, and which with its masonry facing must once have been at least as high again, and with the usual lofty pinnacle of metal may easily have reached a height of 200 feet. He infers that the earthen or lower part of the mound may belong to the earlier ages of Buddhism, and that the masonry or upper part was added by Asoka.

Hiuen Tsiang next describes the sites of the toothbrush tree and of the monument where the four previous Buddhas used to sit and take exercise, as being close to the great stupa. These places General Cunningham identifies with the court-yard containing the dargahs of Sis and Ayûb, which touches the south side of the Maniparbat. The two tombs he takes to be the remains of the seats of the four previous Buddhas, and the paved courtyard to be the scene of their daily walks, although he was unable to trace their footmarks which were seen by the Chinese pilgrim.

The last monument described by Hiuen Tsiang is a stûpa containing the hair and nails of Buddha. This was surrounded by a number of smaller monuments which followed one another in succession, and by several tanks which reflected the sacred buildings in their limpid waters. The stûpa General Cunningham identifies with the Kubêrparbat, which touches the south side of the enclosure round the dargâhs of Sîs and Ayûb, and is close to the west side of the ruined monastery. One

¹ Benl, Le., Vol. I, page 239.

^{*}Some writers have also identified Ayodhya with the 'O-yu-t' o of Hiuen Tsiang; see e. g., Cunningham, Archaeological Reports, Vol. I. page 294; Dr. Hörnle, The Umisagadasso, Appendix III, page 53. Compare, however, notes on Bihar in the Unio and Jagatpür in the Rai Bareli districts.

IIb.

of the tanks described by the pilgrim may be the Ganesakund; but all the smaller monuments have disappeared long ago, as they afforded cheap and ready materials for the construction of the numerous Musalman tombs, as well as for the neighbouring bridge and masjid.

The people are unanimous in their assertion that the old city to the north of these mounds was called Baretâ; Ayodhyâ, they say, was the capital of Râma, but the latter city was called Baretâ. As this name has no similarity to Viśâkhâ, we can only set it down as another appellation of the old town, for which we have no authority but tradition.

2. Akbarpûr, or Mîrân pûr, tahsîl, 36 miles south-east of Faizâbâd, was formerly a Musalmân town of some importance, and still contains ruins of fine Hib. buildings, a sarâî, imâmbâra and old tombs. On a high cliff of the left bank of the river Tons is the old fort of Akbar erected on the ruins of an old Bhâr

III. castle, said to have been called Sojhâwalgarh. Within the fort is a masjid, built by Akbar in A.H. 976, as is apparent from several Persian inscriptions on the walls, and the dargâh of Sa'id Kamâl, a famous darwêsh. A fine masonry

Ia. bridge of great strength and solidity, built by Akbar in the same year under the supervision of Muhammad Muhsin, spans the river and the low alluvial land which extends for some hundreds of feet eastward on the right bank. In the centre of a large tank, on a ruined brick mound, there is a stone tomb, over which

IIb. are eight roughly-hewn stone pillars, surmounted by a small ruined brick dome. The Persian inscription on one of the interior cornices records the erection of this building by Qâzi Sa'îd Tâj within the lands of Sinjhaulî in A.H. 782, during the reign of Fîrûz Shâh Taghlaq. From this it is evident that the ancient name of the place, prior to the days of Akbar, was Sinjhaulî, apparently a corruption of Sojhâwalgarh.

IIb. At the village of Masa'ûdpûr, or Bhiâon, are the dargâhs of Sahjâ and Kâlka, two famous local necromancers, said to have been the disciples of Sa'îd Masa'ûd, who came from Arabia and died at this place in A.H. 420.

 Amsin, village in tahsîl Faizâbâd, 22 miles south-east of head-quarters, possesses a strong brick fort built by Roshan Ali Khân in Faslî 1170.

III. The pargana contains ruined brick mounds, ascribed to the Bhârs, at the villages of Sirwâ-Pâlî, or Sarâî Dûla, Khîwâr, Alâpûr, Tikrî, Marnû, Mâdhopûr, Jijjwat, Badûghpûr, Bandhanpûr, Basaurâ, and Pakrêlâ.

IIb. At the village of Sirwâ-Pâlî there is a modern brick temple, on the banks of the Ghâghrâ, dedicated to Rishi Sirûgavîra. Sirwâ is said to have been the eastern gate of ancient Ayodhyâ.

IIb. The village of Kasbâ possesses a temple of Kâlikâ Devî of local repute, but of no interest.

4. Bhadarsâ, small town in pargaṇa Haveli Audh of tahsîl Faizâbâd, ten miles south of head-quarters, possesses an ancient tank, called Bhâratakuṇḍ, and the dargâh of Sa'id Zain-al-âbîdîn, or Mîra Zaina.

Bîrhar, village in tahsil Tâṇḍâ, 50 miles south-east of Faizâbâd, is devoid
of antiquities, but the pargaṇa contains ruined brick mounds, or dihs, ascribed to the

Bhârs, at the villages of Korâwân, Chândipûr, Samaur, Rudhâî, Hasanpûr Dhipnî, Sa'îdpûr Lirwadîh, Sonhân, Nâthmalpûr, Bethuriyâ, Pokharbhêta, Sâmdîh, Karâwân, and Ochhawân.

IIb. The village of Rasûlpûr possesses the dargâh of Shâh Makhdûm Sa'id Ashraf Jahângîr, a famous darwêsh of the time of Ibrâhîm Shâh Sharqî of Jaunpûr.

 Πa .

Ib.

III.

III.

III.

IIa.

III.

finest of its kind in Audh.

6. Faizābād, tahsîl and capital of the district, lat. 26°-47′ N., long. 82°-11′ E., on the right bank of the Ghâghrâ, lies west of and adjoins the modern town of Ajudhyâ, which is now within the same municipal limits, both towns being on the site of the ancient city of Ayodhyâ. The present town of Faizābâd owes its existence to Nawâb Mansûr Alî Khân, but most of its interesting buildings date from the time of Shujâ-ad-daulah, viz., the Gulâbbârî, Samanburj, Motî Mahal, Khurd Mahal, Dilkushâ, and the Tripolia, or three-arched gateway in the Chauk. The stuccoed brick tomb of Bahû Begam, the wife of Shujâ-ud-daulah and mother of Asaf-ud-daulah, is the only building of any consequence and the

A copperplate grant of Jayachchhandra of Kanauj, dated Samvat 1243, was found near Faizabad in A.D. 1841; the original plate is now in the Library of the Royal Asiatic Society, London.

- 7. Khandansa, village in tahsil Bîkapûr, 25 miles south-west of Faizâbâd, is devoid of ancient remains; but the pargana contains brick-strewn mounds, or dîhs, ascribed to the Bhârs, at the villages of Sirsend, Bakhaulî, and Jarayyân.
- Majhaurå, large village in tahsil Akbarpûr, 26 miles south-east of Faizàbâd, possesses a ruined brick mound, ascribed to the Bhârs.
- The pargana is rich in ancient mounds, covered with broken bricks and masonry débris, said to be the remains of the former strongholds of the Bhars. The most prominent dihs are at the villages of Asganwan, Rachhpal, Parnanand-pati-urf-Dahwa, Kawariserpal, Sagaicha, Naghiawan, Idhona, Chandapar, Kadipar Gaura, and Tolapati-urf-Jaitpar.
- 9. Mangalsî, town in tahsîl Faizâbâd, nine miles west of head-quarters, on the left bank of the Ghâghrâ, is devoid of antiquities, but the pargaņa contains brick-till. strewn mounds, ascribed to the Bhârs, at the villages of Sirhir, Râîpâr, Sukhâwân, Sarwârî, Ibrâhîmpûr Kandâî, Bîlkhâwân, Dêorâ Kôt, Kalâparpûr, Tharerû, Kôţdîh and Mahôlî.

On the outside of the village of Dhaurahrâ, there is a gateway of handsome proportions, built by Asaf-ad-daulah of Lakhnâû, and an old ruined Hindû temple, sacred to Mahâdeva.

III. temple, sacred to Mahâdeva.
 III. The village of Hâjîpûr possesses an old ruined masjid known as that of Pîr Khwâja Hasan, whose tomb it adjoins.

Near Sonâha are numerous tombs declared by the Musalmâns to be the graves of the soldiers of Sa'id Sâlâr Masa' ûd; the Musalmâns of Audh are, however, apt to associate with Sa'id Sâlâr every object of antiquity to which they can ascribe no certain origin.

III. The village of Ronâhî possesses the ruins of an old masjid, buried in jangal, and the tombs of two martyrs, Aulia Shahid and Makan Shahid.

¹ Journal, Asiatic Society of Bengal, Vol. X., page 98; Indian Antiquary, Vol. XV, page 10.

III.

III.

III. At the village of Pîrnagar are the ruins of an old masjid, and at Kôţ IIb. Sarâwân is an old masjid in good preservation, called Panj-bhayyâ. Inside the enclosure are the tombs of the five brothers, and an upright diagonal monolith of coarse stone; on the western side are the remains of a large platform, flanked by heavy pillars, which is called Ganj-î-Shahîdân.

III. At the village of Mumtaznagar are the ruins of a kankar-built masjid, erected by Mumtaz Khan, in A.H. 1025, as is apparent from a Persian inscription.

III. The village of Tâj pûr contains a brick maqbara of Jamâl Khân and a ruined fort.

III. At Dholi Askarân there are interesting ruins of an enormous fort; bastions of commanding height, crowned by banyan trees of great size and age, overlook a deep moat.

At Bhavannagar are the remains of a small mud fort.

The small town of Mustafâbâd, also called Barâgâon, possesses an old IIb. masjid, standing in lonely bleakness, said to have been built by Sa'id Bâri, the founder of the town.

10. Surhârpûr, small town in pargaṇa Pachhimrâth of tahsîl Bikapûr, 46 miles III. south-east of Faizâbâd, possesses an old masonry fort on a rising ground, ascribed to IIa. the Bhârs, and a curious masonry bridge of Akbar's time over the river Majhoi.

III. Brick-strewn mounds, or dihs, ascribed to the Bhars, are at the villages of Harpur, Khanpur-Pilai, Umran, Bhojgi, Deodi, and Masora.
III. At Yasingarh are the picturesque ruins of a strong mesonry foot by the picture.

At Yasingarh are the picturesque ruins of a strong masonry fort, built by Shaikh Ghulam Yasin.

11. Tâṇpâ, tahsîl, lat. 26°-23′ N., long. 82°-42′ E., 36 miles east-south-east of Faizâbâd, possesses 44 masjids, 34 imâmbâras, and nine Hindû temples of no interest. The dargâh of Shaikh Hârûn is a picturesque ruin about a mile to the east of the town; to the west is an elevated masonry chabûtrâ, called Sâlârgarh.

At the villages of Madarpûr, Thânûpûr, Umêdâ, and Khâspûr are brick-strewn mounds of considerable extent, ascribed to the Bhârs.

III.—Gonpà District.

- Balbampür, town in tahsil Utraula, 28 miles north-east-north of Gonda and about two miles to the south of the Rapti river, is built on the ruins of the ancient IIb.
 Râmgadha Gauda. The modern town possesses 53 Hindû temples and 17 masjids, none of any great pretensions. The modern stone temple of Bilêsvarî Devî is a very handsome structure, profusely carved by the best masons of Banaras and Mirzapür.
 - 2. Dêvî-Pâtan, ancient village in pargaṇa Tulsipûr of tahsîl Utraulâ, 46 miles north-east-north of Goṇdâ, is one of the oldest seats of the Śaiva cultus in Northern India. The earliest legend connects it with Râjâ Karṇa, the renowned hero of the Mahâbhârata, and elder brother by the mother's side of the Pâṇḍavas, being the son of Sûrya by Prithâ or Kuntî before her marriage with Pâṇḍu. Afraid of the censure of her relatives, Kuntî deserted the child and exposed it in the river Ganges, where it was found by Adiratha, a prince of Aṅga, and nurtured by his wife Râdhâ. Brought up at the court of Hastinâpura, he was refused by

Drona the arms of Brahma, which he eventually obtained from Parasurama by faithful service at his retreat on the Mahendra mountain. In after life he attended Duryodhana to the svayamvara, and having taken a prominent part in the great war, was finally granted the city of Malini by Jarasandha, the great King of Magadha and Chedi, and reigned as a tributary of Duryodhana. Malini has been identified by General Cunningham1 with Champanagar, a town on the Ganges in the Bhagalpur district of Bangal; but if Karna remained a tributary to the King of Hastinapura, it is more reasonable to look for his kingdom to the west of Magadha, between Dehlî and Bihâr (i.e., Dand-Bihâr in the Patnâ district of Bangal). In the light of the local legend, the Malini, referred to in the Mahabhârata, was not unlikely the small affluent of the Ghâghrâ which joins the main stream about 50 miles above Ajudhya. Further, as the son of Sûrya and the favorite of the great Saiva hero Jarasandha, Karna himself seems to have been connected with the earliest forms of Saiva worship, and the name Chandrasekhara, by which the god is still known at Dêvi-Pâtan, is certainly derived from times when he was yet worshipped as the beneficent lord of production. It is not, therefore, impossible that the old legend, which ascribes the ancient ruins of an extensive brick-strewn mound, on which the modern temple of Parvati is built, and its adjoining tank, to Râjâ Karna, may have some kind of historical basis, though it is far more probable that the actual existing remains belong to the time of Chandragupta II, of the Imperial Gupta dynasty, who restored the old sacred places at Ayodhya, and who raised at Dêvi-Pâtan a new fane on the legendary spot, now overgrown with jangal. It is to this period that we may ascribe the Puranic legend of Dêvî's dishonour at the hand of Daksha. Siva arrived to find her dead, and taking the self-immolated corpse on his shoulder, carried it eastwards. The dead and live bodies were not to be separated till Vishpu cut the former into fifty pieces with his chakra, and flinging them in as many directions created new places of pilgrimage. Her right arm fell at Dêvi-Pâtan and sank through the earth into the lower world.

A third temple was erected in the beginning of the 15th century A.D. by the great Ratannâth, the third in spiritual descent from Gôrakhnâth, the deified saint whose worship is spread all over the Nepâl valley and many parts of India. That the red sandstone temple, whose fragments are built into the modern edifice, dates from the period of Gôrakhnâtha is proved by a Nâgarî inscription on the doorway. As far as can be judged from the remains, this temple must have been of considerable architectural pretensions, adorned by profuse sculpture, and full of stone images of Śiva, Bhairava, and Kâlî. Its importance was sufficient to attract the attention of the great iconoclast Aurangzîb, whose officer slew its priests, broke the images and defiled its holy places. The Hindûs, however, avenged the desecration by murdering the Musalmân, whose body is said to be buried under the mound known as Sûrbîr.

The modern temple of Pârvatî was shortly afterwards erected on the ruins of the third, under the protection of the neighbouring Râjâs of Tulsîpûr.

3. Gonpá, tahsîl and capital of the district, lat. 27°-15′ N., long. 82° E., is the ancient Gauda, a subdivision of Uttara Kosala, as mentioned in the Purânas. The modern town, however, contains very few objects of interest, and

III.

IIb.

III.

IIb.

Archaelogical Reports, Vol. XV, page 31.

Hb. the Hindû temples are all of recent construction. Near the Chauk are the remnants of the moat which surrounded the old fort round which the present town has grown up; a large sarâi; and the Râdhâkuṇḍ, a large masonry tank with a masonry build-Hb. ing at its edge. In the civil station is the Sagar, a large artificial lake, constructed

by Râjâ Siva Prasâda in Fasli 1120, in the middle of which stands a temple on an island.

III.

IIb.

Hb.

III.

Traditions respecting the famous tooth-brush tree (dantadhâvana) of Buddha still exist at Gonda. Both Fa Hian1 and Hiuen Tsiang2 agree in stating that the dantadhavana of Sha-chi and Visakha was only seven feet high, and that it never grew any higher, which would seem to show that it was only a small tree or shrub; and this, indeed, is actually the case with the datton, or tooth-brush tree of Gondâ, which is a chilbil, or shrub eaten by goats, that never exceeds eight or ten feet. From this tradition, which also exists at Hathili or Asokpûr of the Gonda district, we may infer that it was usual to make cuttings and to take seeds from the famous dantadhàvana of Visâkhâ for distribution to religious establishments, just as cuttings from the bodhi tree at Gay a were made for the same purpose.

Vast ruins of ancient cities are found all along the banks of the Tihrî river, at the villages of Naliyâ and Khargûpûr, which are ascribed to Râjâ Sudâman, a contemporary of Sohil Dêo, or Suhriddhvaja of Gauda. Khargûpûr possesses in a modern temple a large lingam with a handsomely carved argha, which

was dug out of the ruins about 30 years ago.

4. HATHILI, small village in pargaņa Mahâdêva of tahsîl Tarâbganj, 12 miles south-east-south of Gonda, is said to derive its name from Hatila, sister's son of Sa'îd Sâlâr, who was killed in an assault on the large ancient temple of Asokanâtha Mahâdêva, from which the village is also called Asokpûr. His tomb, or rather that of his relative Salar Saif-ad-dîn, who was killed in the same battle, a low-domed building only 20 feet square, is still much frequented as the shrine of a ghazi or martyr for the faith. It is built entirely of large bricks from the ruins of the old temple of Asokanatha. The remains consist of a low mound, 700 feet long by 500 feet broad, with three prominent masses of ruin on the north side. General Cunningham3 made in 1862 an excavation in the north-west ruin near the base of a large mahûû (madhûka) tree, but without any result, as a small Musalmân tomb prevented him from digging in the centre. The kûlis employed on the work voluntarily informed him that the mahûû tree had been the "tooth-brush" of a Râjâ who stuck it in the ground and it grew to be a tree.

The north-east mound is a mere undistinguishable mass of broken bricks, but the central mound is still covered with the ruins of the temple of Asokanatha III. Mahâdêva. Portions of the brick walls which still remain show that the temple was only 12 feet square; but the whole has been lifted up by the roots of a gigantic pipal tree which still hold the bricks together by their interlacings. The lingam was almost completely hidden by the matted roots of the pipal until the tree was cut down in 1862. As the cut stem showed 849 annual rings, the tree must have been planted in A.D. 1013 during the reign of Mahmûd of Ghazni. This, indeed, is about the

Beal, Le., Vol. I, page XLIII.

^{*} Beal, I.c., Vol. I, page 240.

^{*} Archeelogical Reports, Vol. I, page 328.

date of the temple itself, which is said to have been built by Suhriddhvaja, the Râjâ of Asokpûr, and the antagonist of Sa'id Sâlâr. The mound with the mahûâ tree is called Râjâ Sohil Dêo-ka-khalang, or Sohil Dêo's seat. His city of Asokpûr is said to have extended to Domariyâ dîh, two kôs to the north, and to Sareyâ dîh, half a kôs to the south of the temple. At both of these places are old brick-covered mounds, in which large numbers of coins have been found. Most of these belong to the early Musalmân kings of Dehlî, the Ghoris and Khiljîs; but there are also a few early Hindû coins, being Âdivarâha drammas of Râjâ Bhojadêva.

III.

III.

Hb.

III.

IIb.

III.

Hâthilî was no doubt the scene of Sâlâr Masa'ûd's death, in his last battle with Râjâ Suhriddhvaja. According to the Mîrâţ-î-Masa'ûdî, Sa'îd Sâlâr rested under the shade of a mahûâ tree on the bank of the Sûrâjkuṇḍ, close to the temple of Bâlârakh (i. e., Ašokanâtha Mahâdêva) at Ašokpûr, after an engagement with the Hindûs. The place was several marches distant from Bahrâîch, as he had come to the Sûrâjkuṇḍ by regular stages. Having taken a great fancy to the spot, he ordered a platform of masonry to be built under the shade of the mahûâ tree to serve him for a seat. During the battle he directed his followers to throw the bodies of the dead believers into the Sûrâjkuṇḍ, while the few troops that remained stood round him in the garden.

- 5. Machhligaon, small village in pargana Manikapur of tahsil Utraula, 18 miles east of Gonda, possesses an ancient brick-strewn mound, on the top of which is a modern temple, dedicated to Karuanath Mahadeva. The lingam itself, as well as a few stone statues of Siva, were dug out of the khera by the villagers in 1857. Close to the temple there is an old well built of large kankar blocks.
- 6. Mahadéva, village in tahsîl Tarabganj, 14 miles south-east-south of Gonda, possesses an ancient brick-covered dih, near which there is an old temple of Mahadéva, from which the village derives its name.
- At Ludhiyâ Ghât, near Khurâsa, is a deep lake, all around the shore of which are large brick mounds, the remains of ancient mansions, and the palm and date trees of former gardens. Coins of the early Musalmân rulers of Dehli are occasionally disinterred by the rains.
- MATHURA, small village in pargana Balrampûr of tahsîl Utraula, 43 miles
 north of Gonda, possesses a lofty śivala of recent date, and the handsome dargah of Mir Hanifa, erected by Asaf-ad-daulah of Lakhnaû.
- 8. Pachrân,¹ small village in tahsil Gondâ, 18 miles north of head-quarters, stands upon a large mound 150 feet long by 80 feet broad and 25 feet high. Near it is a second mound 20 feet high, apparently formed of solid brick work. Here the Prithvinâth lingam, which is now enshrined in a modern temple on the top of the mound, is said to have been found when the dense jangal which covered the mound was cleared away about 1860. A copperplate grant was also found here in 1868, which was "taken away by Nicholson Sâhib to Gondâ." This inscription has never been published, and the original cannot now be found.

The name of Pachran may perhaps be derived from Pancharanya, or the "five forests," as the place is said to have been a favorite one with the ancient Rishis, Cunningham, Archaeological Reports, Vol. XI, page 100.

whose names are still attached to several spots in the neighbourhood. The solid brick mound on which the temple now stands looks exactly like a ruined stupa; but the presence of the lingam with an ornamented argha, and of a stone figure of Chaturbhuja, or Vishņu, shows that the place must, at least in latter times, have been occupied by Brâhmanas. Most probably the site is an old Buddhist one, which was deserted during the decay of Buddhism under the Gupta rulers.

9. Sâhet-Mâhet, a vast collection of ruins on the south bank of the Râptî in pargaņa Balrāmpūr of tahsīl Utraulā, 42 miles north of Gondā, has been identified by General Cunningham1 as the remains of the famous city of Sravasti, or Savatthi, one of the most celebrated places in the annals of Buddhism. We know from Hiuen Tsiang2 and the Cylonese Buddhist books that Shi-lo-fu-shi-ti, i. e., Śravasti, or Sewet, was to the north of Ayodhya, or in other words, that it was in the district of Gauda or Uttara Kosala, which is confirmed by the statements of no less than four Brahmanical Puranas. As Fa Hian3 also says that She-wei, or Śravasti, was in Kosala, and as General Cunningham discovered in these ruins a colossal statue of Buddha with an inscription of the Indo-Skythian period containing the name of Śrâvastî itself, there can be no doubt whatever that the great ruined city of Sâheț-Mâheț represents the ancient Śrâvasti.

All that now remains of this once famous city is the great fortress on the banks of the Rapti, with a smaller ruin to the south-west, a lofty mound due south on the Balrâmpûr and Bahrâich roads, and numerous small piles of bricks, the remains of ancient stupas scattered here and there within a distance of two miles of the main city.

The fortress is in shape an almost semi-circular crescent with its diameter of one mile and a third in length curved inwards and facing the north-east, along the old bank of the Râptî. The western front, which runs due north and south, for three-quarters of a mile, is the only straight portion of the enclosure. The ramparts vary considerably in height; those to the west being 35 to 40 feet in height, while those on the south and east are not more than 25 or 30 feet. The highest point is the great north-west bastion, which is 50 feet above the fields. The north-east face, or shorter curve of the crescent, was defended by the Rapti which still flows down its old bed during the annual floods. The land ramparts on the longer curve of the crescent must once have been defended by a ditch, the remains of which yet exist as a swamp, nearly half a mile in length, at the south-west corner. Everywhere the ramparts are covered with fragments of brick, of the large size peculiar to very ancient cities; and, though General Cunningham was unable to trace any remains of walls except in one place, yet the very presence of the bricks is quite sufficient to show that the earthen ramparts must once have been crowned by brick parapets and battlements. The portion of the parapet wall, which he discovered still standing in the middle of the river face, was 10 feet thick. The whole circuit of the old earthen ramparts is 17,300 feet, or upwards of three and a quarter miles. This is the exact size of 20 li, which Hiuen Tsiang gives to the "ruins of the walls encompassing the royal precincts," i.e., the portion of the city in which the royal

III.

¹ Archaelegical Reports, Vol. I, pages 330—348; Vol. XI, pages 78—100.

² Beal, Le., Vol. II, pages 1-13.

Beal, Lc., Vol. I, pages XLIV-XLVIII.

palace of Prasenajit stood. It is certain that the suburbs outside the walls must have been very limited, as the place is almost surrounded with the remains of large religious buildings, which would have left but little room for any private dwellings. "Though mostly in ruins, still there are a few inhabitants:" this statement of Hiuen Tsiang is sufficient to show how utterly ruined this once famous city must have been at so distant a period as the seventh century A.D. As Fa Hian describes the population as consisting of "about 200 families" in A.D. 400, while the Cylonese annals speak of Khirâdhâra and his nephews as kings of Sâvatthîpura, between A.D. 275 and 319, the great decline of Śrâvastî must have taken place during the middle of the fourth century, and we may perhaps not be far wrong in connecting it with the reign of Chandragupta II, of the Imperial Gupta dynasty, A.D. 395—415.

Śrâvastî is said to have been built by Râjâ Śrâvasta, the son of Yuvanâśva of the solar race, and the tenth in descent from Sûrya himself. Its foundation therefore reaches to the fabulous ages of Indian history, long anterior to Râma. During this early period it most probably formed part of the kingdom of Ayodhyâ, as the Vâyupurâna assigns it to Lava, the son of Râma. When Śrâvastî next appears in history, in the time of Buddha Śâkyamuni, it was the capital of King Prasênajit. The king became a convert to the new faith, and during the rest of his life he was the firm friend and protector of Buddha. But his son Virûdhaka hated the Śâkyas, and his invasion of their country and subsequent massacre of 500 Śâkya maidens, brought forth the famous prediction of Buddha that within seven days the king would be consumed by fire. As the story has been preserved by the Buddhists, the prediction was of course fulfilled, and upwards of eleven centuries afterwards the tank in which the king had sought to avoid the flames was pointed out to the credulous Hiuen Tsiang.

During the first and second centuries A.D., Śrâvastî would seem to have been under the sway of the Indo-Skythian rulers of Gandhâra, as several inscribed statues of Buddha, dated in the regnal years of Kanishka and Huvishka, have been dug out of the ruined mounds at Sâhet-Mâhet. Later on, Śrâvastî was most likely under the rule of its own kings, as we find Khirâdhâra and his nephews mentioned as Râjâs between A.D. 275 and 319. Shortly afterwards it became a dependency of the powerful Gupta dynasty of Magadha, as Chandragupta II² is undoubtedly the Vikramâditya of Śrâvastî, mentioned by Hiuen Tsiang³ as a persecutor of Buddhists. To this monarch must be ascribed the erection of the 100 Brâhmaṇical temples which were still standing at the time of Hiuen Tsiang's visit. From this time Śrâvastî gradually declined; in A.D. 400 it contained only 200 families, and in A.D. 636 it was deserted, and only a few religious followers haunted the ruins.

But that Buddhism was not completely extinguished at Śrâvasti during the Gupta period and even later, is proved by the discovery of a large collection of baked and unbaked clay and lac seals and of broken statues containing the Buddhist

I Journal, Asiatic Society of Bengal, Vol. VII, page 865.

² Dr. Hörnle in Journal, Asiatic Society of Bengal, Vol. LVIII, Part I, page 101, suggests that Kumaragupta II, Kramaditya, circa A.D. 530, is intended by Vikramaditya.

Beal, Lc., Vol. I, page 106.

IIb.

116.

creed formula inscribed in Gupta characters as well as in Devanagari letters of the seventh and eighth centuries. The most interesting fact, however, is the find of an inscribed slab¹ which shows that Buddhism was still professed at Śrâvastî even so late as the thirteenth century A.D. This inscription was found, in 1885, buried under the ruins of a Buddhist building erected on the old site of Buddha's Vihâra in Jêtavana. It records in Samvat 1276, or A.D. 1219, the erection of a convent for Buddhist ascetics at the town of Ajavrisha by Vidyadhara, the fifth of six sons of Janaka and Jijja, and grandson of Bilvasiva of the Śri Parva-Vastavya family. Janaka, the father of Vidyadhara, is described as the counsellor of Gopala, the ruler of Gadhipura, or Kanauj; and Vidyadhara appears to have held a similar position under the prince Madana, probably a successor of Gopâla. The town of Ajavrisha is said to have been built by Mandhatri of the solar race, and to have its protection entrusted to Karkota (Siva); this proves that the old Buddhist name of the place, viz., Śrāvasti, must have been lost at a very early date. It is also interesting in another respect, because it speaks of the Hindû kingdom of Kanauj as if it were still in existence, though we know that Jayachchhandra of Kanauj was defeated and his capital taken by the Musalmans in A.D. 1193.

Jainism seems to have been very strong at Śrâvastî in the eleventh century A.D., as several statues of Tirthamkaras, dated Samvat 1112, 1124, 1125, 1133, and 1182 have been excavated at Sahet-Mahet, and are now in the Lucknow Museum. At the present day there still exists at Sahet a small Jain temple, dedicated to Sambhunātha, who was born at Savatthi. The eighth Tirthamkara, Chandraprabhanâtha, is said to have been born at Chandrikâpuri, and this place is always identified in local tradition with Sahet-Mahet. Suhriddhvaja, the contemporary of Mahmûd of Ghazni and the opponent of Salar Masa'ûd, is said to have been the last of the Jain rulers of Śrâvasti. With the Ghori conquest of India, the history of Śrâvasti comes absolutely to an end.

At the present day the whole area of the city, excepting only a few clearances near the gateways, is a mass of almost impenetrable jangal, which is broken into a wavy surface by the remains of temples and palaces underneath. All the principal buildings were in the western half, and it is there that the undergrowth is the thickest, only ceasing along two or three broad streets which have been left bare, and indicate the chief features of the old city. The main street was right through III. the centre, and is built so as to command a view of the great mound Orajhar from one end to the other. To the south it debouches by one of the principal gateways, and at the north it ends in a small square, containing among other lofty remains the two principal mounds which may be identified with the two stupas of Sudatta and the Angulimalyas, mentioned by Hiuen Tsiang. The dense brushwood, and the possibility that the city which Hiuen Tsiang saw may have been considerably altered by the Jain rulers of Sravasti, renders the application of that pilgrim's descriptions a difficult and hazardous task, but we may be safe in conjecturing that his palace of Prasenajit was situated among the mounds of the southeastern corner where there is now the small temple of Sambhunatha. The next building mentioned by him is the hall of the law (saddharmamahásala) built by that

¹ Archivological Reports (New Series), Vol. I, pages 70-73; Indian Antiquary, Vol. XVII, pages 61-64.

monarch for Buddha, which would have been situated between the palace and the main street, while the Vihâra of Prajâpatî Bikshuṇi, the maternal aunt of Buddha, would have formed the whole or part of the long and even line of buildings which face the west of the street. The north-west corner of the ruin contains a large open space with a small pond in its centre, and a nearly straight road running from it to another southern gateway and converging with the main street on the Orâjhâr. The eastern half has no very important remains, though the surface is broken everywhere with the dêbris of houses, and it was here probably that the common people had their quarters. The walls are pierced with numerous gateways, the principal being at either end of the main street and the north-eastern bastion, and in the middle and southern corner of the west wall.

At a distance of half a mile from the south-west gate, and separated from the main town by swamps, which probably mark the course of the old moat, is another considerable ruin, generally called Jogini-bhariya, or the "witches' mound," identified by General Cunningham with the great monastery of Jêtavana, which was one of the eight most celebrated Buddhist buildings in India. It was erected during the lifetime of Buddha by Anâthapindada, also called Sudatta, the chief minister of King Prasênajit, and it received its name of Jêtavana, or "Jêta's garden," because the garden in which it was built had been purchased from Prince Jêta.

Hiuen Tsiang places the Jêtavana five or six li, or nearly one mile, to the south of the city; but in his time the city was "deserted and ruined, and there is no record as to its exact limits." We may be safe in concluding that he took his distance of one mile from the remains of the king's palace. Fa Hian makes the distance only 1,200 paces, or about half a mile, which agrees exactly with the actual position of the city gate, which is distinctly marked by a very deep depression in the line of rampart. There is no doubt, however, about the identification of the Jêtavana, as it is the only ruin of any extent, and moreover contains the ruins of the Kosâmbakutî and Gandhakutî temples, which we know were inside its walls. The enclosure is still very clearly marked by a broad mass of ruins, rising from 12 to 15 feet above the ground outside, while the interior has a general elevation of six to nine feet. The mass of ruin consists of two distinct portions which may be called the northern and southern. All the walls and buildings in the former are laid out north to south; but in the latter, only the buildings are so disposed, as the eastern and western surrounding walls of the enclosure have a variation of 20° to the east of north. A deviation from the magnetic meridian of 174° east has been noticed in the old stupa at Tandwa in the Bahraich district, and General Cunningham is inclined to believe that this deviation is a sure token of antiquity. He is, therefore, disposed to look upon the southern portion of the enclosure as the original garden of Jêtavana, to which the northern portion was added by Prince Jêta himself. According to Fa Hian the great garden enclosure of the Jêtavana Vihâra had two gates, one towards the east, the other towards the north; the openings are distinctly marked even at the present day. The only notice that can be found regarding the size of the Jêtavana is the statement of Prince Jêta himself, that his garden was 1,000 cubits long and 1,000 cubits broad, or 4,000 cubits in circuit. General Cun-

Ш.

Ia.

ningham's survey makes it only about 4,500 feet; but it is probable that some portion of the ground outside the present ruins was enclosed as a garden for daily exercise. The whole circuit, therefore, may easily have been increased to 6,000 feet, or 4,000 cubits.

III. General Cunningham, in 1876, made excavations in 20 distinct mounds of ruin in the Jêtavana, of which ten turned out to be temples and five stûpas, while the remaining five were either dwelling-houses or mounds of rubbish previously dug up for bricks.

When Hiuen Tsiang visited Śrâvastî in A.D. 636, he found the Jêtavana Vihâra so completely ruined, that nothing more than "the foundations remain, with the exception of one solitary brick building, which stands alone in the midst of the ruins, and contains an image of Buddha." This very statue of colossal size, being seven feet four inches in height and bearing an imperfect inscription of the Indo-Skythian period, was found in 1863 by General Cunningham inside a small ruined brick temple.

The only other ancient remains in the Jêtavana that are worthy to be noticed III. are five wells, one of which is octagonal in shape. It differs from all others in having the top of each side curved with a projection of nine inches towards the middle of the well.

To the north-east of the monastery of Jêtavana, there was a stipa built on the spot where Buddha had washed the hands and feet of a sick bhikshu and had cured his sickness. The remains of this stûpa still exist in a mass of solid brickwork, at a distance of 550 feet from the garden of Anâthapindada. This ruined mass, which is 24½ feet in height, is built entirely of large bricks, 24 by 10 by 3½ inches, which is a sufficient proof of its antiquity.

To the east of the sâmghârama, at a distance of 100 paces or 250 feet, there was

a large deep trench, which was said to be the spot where the earth had opened and engulfed Dêvadatta, the cousin and implacable enemy of Buddha. This place has been identified by General Cunningham with a large deep tank, 600 feet long and 250 feet broad, called Bhulanan, within 200 feet of the south-east corner of the III. ruined monastery. Close by, on the south side, there was another great ditch, in which Kukâlî, the bhikshuni, had been swallowed up alive for slandering Buddha. This is represented by the Lambaha Tal, a long narrow tank, only 200 feet to III. the south of the Dêvadatta gulf. The third great fissure or hollow is described by Hiuen Tsiang as being at 800 paces, or 2,000 feet, to the south of the second. According to the legend, this was the spot in which a Brahmani girl, named Chańschâ, had been engulfed alive for falsely accusing Buddha of incontinence. This Chanscha gulf is represented by a nameless deep tank, 600 feet long by 400 feet broad, which lies 2,200 feet to the south of the Kukâlî gulf. The exact correspondence of position of these three tanks with the three great fissures or gulfs of the Buddhist legends offers a very strong confirmation of the correctness of identification of the Jogini-bhariya mound with the great Jêtavana Vihâra,

The Chinese pilgrims next describe a pair of temples of equal size, of which one was situated to the east and the other to the west of the road, which should therefore be the main road that led from the city towards the south. Hiuen Tsiang says that

the first temple was only 70 paces, or 175 feet, to the east of the monastery, while Fa Hian places it at the same distance from the eastern gate, but towards the north. The position of these temples is doubtful, as there are no remains in the immediate vicinity of the Vihara that correspond with the description. General Cunningham Ш. discovered, however, in another position the remains of two temples which answer the description so accurately as to leave but little doubt that they must be the buildings in question. The first, or west temple, is described by both pilgrims as containing a seated figure of Buddha; while the second, or east temple, belonged to the Brâhmanas. Both were 60 feet in height, and the Brâhmanical temple was called the "shadow-covered," because, as the credulous Buddhists asserted, "when the sun is rising, the Deva temple does not east its shade on the Vihara, but when it is setting. the Vihâra obscures the Dêva temple." The ruins of these temples are situated to the east and west of the road leading from the city, and due east and west from each other. They correspond, therefore, exactly as to the relative position with each other; but instead of being only 70 paces, or 175 feet, from the monastery, the nearest is nearly 700 feet from the great mound of ruins.

To the north-west of the garden of Anathapindada, Hiuen Tsiang places a well and a small stupa, which marked the spot where Mudgalaputra vainly exerted his spiritual power in order to lift the girdle of Sariputra. As the distance is not mentioned, it may be inferred that the stupa was close by, and therefore General IIb. Cunningham would identify the site with that of the dargah of Pîr Barana in the small village of Husain Jot, which is within 700 feet of the north-west corner of the monastery. Near the same place there was also a stupa of Asoka and a stone pillar, which the king had raised to note the spot where Buddha had taken exercise and explained the law. General Cunningham could find no trace of any of these monuments, and concludes that the stupas, as usual, must have furnished materials for the erection of Pir Barana's dargah.

A few hundred feet outside the city on the road to the Jêtavana lies the village of Chakra Bhânḍâr, occupying a large mound, 450 long by 350 feet broad, on the top of which there is still a very fine mango tree which General Cunningham believes to be a descendant of the famous tree at Sewet, which grew up in a moment from a stone planted by Ananda at Buddha's desire, as related in both the Burmese and Cylonese chronicles.

III.

IIb.

Nearly a mile to the south-east of the Jêtavana Vihâra is the high congeries of bricks known by the name of Orâjhâr, or "basket shakings." The great mound is a solid mass of earth 70 feet in height, which was formerly crowned by a brick temple. This ruin is identified by General Cunningham with the Pûrvârâ ma Vihâra built in honour of Buddha by the lady Visâkhâ of Śrâvasti, the most celebrated of all females in Buddhist history. The top of the mound is protected by two Musalmân tombs, but General Cunningham cleared the north face completely, and the other three faces partially, till he reached the paved brick floor which surrounded the original Buddhist temple, at a height of 55 feet above the ground. The wall of the temple on the north face is only 20 feet long, and though General Cunningham failed to reach the other two corners of the building, there can be no doubt that it must have been a square. Its height, at 3½ times its size, would not

therefore have been more than 70 feet, but as its floor is 55 feet above the ground, the total height of the temple would have been 125 feet. The wall of the north face is divided into four panels by pilasters, six inches thick, of an exceedingly ancient style of architecture. From the fact that two of the chief thoroughfares of the city so converge as to command a view of this mound, we may be safe to conjecture that it was more ancient than the plan of the present remains, and consequently one of the oldest monuments left in the neighbourhood.

III. The stùpa mentioned by Hiuen Tsiang as belonging to the Pûrvârâma monastery may perhaps be represented by a small mound close to the north-east corner of the Orâjhâr. The mound is only eight feet high, but an excavation which was made to the depth of 11 feet, showed it to be made of solid bricks of large size, twelve by nine by three inches. It is 40 feet in diameter, and when complete with its pinnacle it must have been about 60 feet in height. From its vicinity to the Pûrvârâma there is little doubt that this is the stûpa which Visâkhâ built on the spot where Buddha had overcome the Brâhmanas in argument.

The last place mentioned by the pilgrims is the spot where King Virûdhaka halted with his army to converse with Buddha, and out of respect for the teacher gave up his expedition against the Sâkyas, and returned to his capital. Hiuen Tsiang states that this famous spot was close to the stûpa of Visâkhâ on the south side, whilst Fa Hian says it was four li to the south-east of the city. The former is the more probable position, as it is on the highway to Kapilavastu, the capital of the Sâkyas. Close by there was a stûpa to mark the spot where 500 Śâkya maidens were afterwards massacred by Virûdhaka for refusing to enter his harîm. Near the stûpa there was a dry tank, or gulf, in which Virûdhaka had been swallowed up. The only large water, however, that can be found is a nameless tank close to the south side of Visâkhâ's monastery, and therefore in the very position indicated by Hiuen Tsiang, but there are no existing remains near it that could be identified with the stûpa of the 500 Śâkya maidens.

The monuments of Śravasti, or Dharmapattana, hitherto described by the Chinese pilgrims, are directly connected with the personal history of Buddha. The places where he passed 25 years of his life, sat and walked, where he taught his law, and where he worsted the Brahmanas in argument, were all specially holy in the eyes of devout Buddhists. But these sacred monuments formed only a small portion of the Buddhist buildings of the great city of Sravasti, where, according to Hiuen Tsiang, the monuments were counted by hundreds. Fa Hian, however, quotes a tradition which limited their number to ninety, at a period not remote from his own time, and as he visited the place nearly two centuries and a half earlier than Hiuen Tsiang, when most of the monasteries were in ruins, we may be satisfied that their number never reached one hundred even at the most flourishing period of Buddhism. General Cunningham traced the ruins of nine monasteries in the immediate neighbourhood of the old city, and there are probably as many more within a range of two miles. He found also the foundations of at least ten temples of various sizes, but they were all in too ruinous a state to be of any interest. But when we remember that the Jêtavana itself, as well as nearly the whole of the 90 monasteries of Śrâvasti, were in complete ruins upwards of twelve centuries ago, it is more

III.

wonderful that so much should still be left for the use of the archæologist than that so little should remain of all the magnificent buildings of this once famous city.

Notwithstanding the excavations made by General Cunningham in 1862 and 1876, and by Dr. Hoey, C.S., in 1885, as yet very little is known of the ruins covered with dense jangal inside the old city, which must contain relics which would do much to elucidate some of the most interesting periods of Indian history. There can be no doubt whatever that a thorough and properly conducted excavation would be of great success and yield many Buddhist and Jain relics; but it ought to be gone about in a scientific method.

10. Utraulâ, tahsîl, lat. 27°-20′ N., long. 82°-28′ E., 32 miles north-east of Gondâ, possesses the ruins of a large ancient brick fortress surrounded by a deep moat, the remains of which are still traceable, and covered by a circle of outlying forts, at a distance of from one to one and a half miles. Other remains of some line interest are the tomb of Alî Khân, who took the fortress from the Hindûs in A.D. 1552, and a large oblong stone tank to the west of the town built by the same

Pathân conqueror.

XI.—RÂÎ BARELÎ DIVISION.

I.—Pratapgarh District.

1. Atehå, village in tahsil Pratapgarh, 26 miles north-west of head-quarters, possesses the ruins of an old fort popularly ascribed to the Bhars. III.

311

III.

Ia.

The village of Rângî, near Prasâd pûr, is the only place of antiquarian note in the pargana, being undoubtedly of great antiquity, as large hoards of Indo-Baktrian coins have been dug out of its ruins. To judge from the extent of these remains, Rangi must at one time have been a very large and populous city. At the north-west end of the village are to be seen the ruins of an extensive brick fortress surrounded by a wide and deep fosse, and at a distance of half a mile to the south-west lies a smaller oblong ruin, measuring about 250 yards by 150, and surrounded by a moat some 30 yards wide. These ruins offer, no doubt, a very promising field to the Archæological Department.

At Mustafâbâd, on the banks of the Sâi, are the remains of a large brick fort.

III. 2. Bihār, 1 or Tusārān - Bihār, old town in tahsil Kandā, 30 miles south-west of Pratapgarh, is situated on the northern bank of an old bed of the Ganges, down which the flood waters of the river still find their way in the rains. The modern town stands on a mound rising to 20 feet in its highest parts. There is a little fort III. at the south-west angle, near which is a small modern brick temple containing a IIb. curious group of figures, apparently of the Indo-Skythian period, locally called Ashtabhujî (Durgâ). To the south-east of the town, and on the northern bank of the old river bed, there is a very extensive mound of brick ruins about half a mile in III. length, with a detached mound at the east end, called Tusaran. Nothing is known as to the origin of the name; but General Cunningham ventures to guess that it may have been Tusharama, or "the Tushara monastery," that is, the monastery built by the king of Tusharas. At the western end, this mound rises high and almost hemispherical in shape. Here General Cunningham made an excavation, in which bricks were found 151 by 101 by 3 inches; but as the site was covered with Musalman tombs, he was obliged to stop the work, after finding some large bricks IIb. with rounded faces like the bars of a Buddhist railing. The middle portion of the great mound is generally higher than the western half; but an excavation made at one of the highest points on the southern side disclosed nothing of interest.

But, in spite of General Cunningham's failure to discover any remains of ancient buildings, there can be no doubt whatever that the Tusaran mound is the site of an old Buddhist establishment. The very name of Bihar is peculiarly and exclusively Buddhist; it is also known by the name of Sûâ Bihâr, or "the red monastery," an appellation which was common to Buddhist monasteries. There is nothing Buddhist about the old group of figures inside the modern temple; but outside the temple there were formerly two small stupas in stone, which were known to the people as Buddha and Buddhi. These names, no doubt, were given to the stones when their Buddhist origin was still known; they were both removed to the public garden at Belâ-Pratâpgarh.

¹ Cunningham, Archivological Reports, Vol. XI, page 63.

The other remains at Bihâr are few and unimportant. In the dargâh of Shahîd IIb. Mardan, the door-sill is formed of the architrave of a Hindû temple; it is very richly carved, but of small dimensions, being only three feet four inches in length. Under the early Musalmân rulers, Bihâr was the head-quarters of a large district, and even now it is known by the name of Subâh-Bihâr.

During the rains large hoards of coins, especially of the old Hindû and Indo-Skythian types, are frequently found in the ruins. From these discoveries, and more especially from the presence of the curious group of sculpture in the modern temple of Bihâr, it is evident that the rule of the Indo-Skythians had been extended as far to the east as the junction of the Ganges and Jamnâ.

There is some probability that Tusârân-Bihâr may be the 'O-ye-mu-khi, Hayamukha, or Ayomukha, of Hiuen Tsiang, The kingdom was about 2,500 li, or 400 miles, in circuit, and the chief town itself had a circumference of about 20 li, or upwards of three miles. There were five samphârâmas, with about 1,000 monks who belonged to the Sammatiya school, and ten temples of the Brâhmanical gods.

Not far to the south-east of the city, close to the bank of the Ganges, there was a stùpa of Asoka, 200 feet in height, built on the spot where Buddha had repeated the law for three months. Beside it were traces where the past four Buddhas walked and sat. There was also another stone stûpa containing relics of Buddha's hair and nails. Close by there was a saṅghārāma with about 200 disciples in it, and a richly adorned statue of Buddha; the towers and balconies were wonderfully carved and constructed, and rose up imposingly above the building.

In this account it will be noticed that all the Buddhist buildings are placed to the south-east of the town, which is the very position which the great mound of ruins bears with reference to the town of Bihâr.

Two miles and a half to the east of Tusaran-Bihar there is a small village named Gaura, with the ruins of a small but richly carved temple of Sûrya. The walls of the temple were built entirely of brick, but the entrance doorway was of stone. In plan it was a square of 21 feet eight inches, with a chamber 11 feet square. It was raised on a platform nearly 48 feet square, paved with bricks-on-edge and plastered, the outer walls being faced with blocks of kankar. The walls were properly decorated with deep carvings in brick. Many of these were of the ordinary flower and leaf patterns, but there was also a very curious continuous moulding formed of bricks 8½ inches in height, representing a double line of small niches one above the other, with two lines of small dentils only half an inch square. There must also have been a line of figures, as a broken statue of a naked man on horse-back and fragments of two other figures were exhumed from the ruins. Nothing whatever is known about the temple, and the mound of ruins is simply called Narâjat Bîr.

General Cunningham,² in 1876, made a complete excavation of the temple, both inside and outside, which brought to light the sill, jambs, and the architrave of the doorway. The door-sill bore the usual lions and elephants, but in the middle of the

III.

¹ Beal, Lo., Vol. I, page 229.

² Archaelogical Reports, Vol. XI, page 70.

III.

III.

IIb.

III.

III.

 Πb .

Hb.

Hb.

architrave there was a figure of Sûrya seated in a chariot drawn by seven horses. There were also several broken figures, amongst which he recognised Vishņu with his club and discus, and two groups of Gaurî-Śańkara, of which the larger one was two and-a-half feet in height. General Cunningham found nothing, however, to show the date of the temple; but he does not think it can be older than the eighth or ninth century. The kalasa, or pinnacle, was a star of eight points, each formed of a separate brick with bevelled edges.

The neighbouring village of Sakardâha has the ruins of an ancient stone temple, the basement of which consisted of several layers of huge blocks of hewn kankar, built up upon a solid square mound of bricks of great size.

Râmpûr possesses a high kherâ, the ruin of an ancient brick temple. Fragments of stone statues and carved pillars are lying about at the foot of the mound.

The village of Barâî contains the dargâh of Pîr Bahrâm.

The village of Behtî possesses, on an island in the middle of a large lake, the ruins of an ancient temple. It is locally believed that this large lake was dug by some Râjâ of Ayodhyâ as a votive offering (yâga), and burnt grain is occasionally found in great quantities beneath its surface.

The village of Bhadrî contains the ruins of a strong fort, covered with picturesque clumps of bamboos, and two conical brick temples of small size, called kûkar dêora or "dogs' dwellings." At Âlhâpâr, a few miles off, is another dêora.

At the villages of Dilêrganj and Newâdâ are a small square fort, Rang Mahal and Dîwânkhâna with masjid, built by Tâj Khân during the reign of Jahân-gîr, in A.H. 1021 and 1024, as stated in several Persian inscriptions.

The village of Shâh pûr possesses the dargâh, Qadam Rasûl and a masjid, built by Akbar in A.H. 972, as stated in two Persian inscriptions. At the village of Aimah Râjî Muhammad Hayât, near Kâth-kâ-pul, is the tomb of Sa'îd Kamâl-ad-dîn, dated A.H. 995.

III. The village of Deviganj is a very picturesque old place and contains the ruins of many fine buildings.

- 3. Dhârûpûr, village in pargaṇa Râmpûr of tahsîl Kandâ, 24 miles west of III. Pratâpgarh, possesses the ruins of a large Hindû fort which was taken and destroyed by Mansûr Alî Khân.
- 4. Mânikpûr, small town in tahsîl Kandâ, lat. 25°-46′ N., long. 81°-26′ E., 36 miles south-west of Pratâpgarh, is a picturesque ruin of an ancient city, perched on the high banks of the Ganges, where plam trees cluster round numerous masjids, maqbaras, and dargâhs in all stages of decay.

According to popular tradition, Mâṇikpûr is said to have been founded by Mâna-dêva, a younger son of Râjâ Bâladêva of Kanauj, who named it after himself, Mâ-napura; and his descendant, Mâṇikyachandra, step-brother of Jayach-chhandra Râṭhor, when inheriting the throne, is said to have changed the name to Mâṇikyapura, or Mâṇikpûr. To attribute, however, the foundation of the town to Mâṇikyachandra Gaharwâr is quite a mistake, as underneath the foundations of the present fort of Mâṇikpûr the remnants of ruined masonry temples and palaces are still visible, which attest to the town having been founded at a much anterior date than that of Mâṇikyachandra. This is proved by the fact that in Samvat 1092.

or A.D. 1035, the whole country round Māṇikpûr belonged to the kingdom of Kauśāmbî, as recorded in an inscription of Yaśaḥpāla found in the east gate of the fort of Karrā, six miles to the south of Māṇikpûr. Indeed, it is not the least likely that the town continued under the dominion of Kanauj for any length of time. When the Buddhist pilgrim Hiuen Tsiang visited Audh in the seventh century, Māṇikpûr must have been in the kingdom of 'O-ye-mu-khi, or Ayomukha¹; at any rate it was not under Kanauj.

In the Mirâţ-i-Masa'ûdî it is recorded that during the reign of Sulţân Mahmûd Ghaznavî, Mâṇikpûr was attacked by a detachment of the army sent by Mahmûd under his brother-in-law, Sâlâr Sâhû, and his nephew, Sâlâr Masa'ûd, to invade Audh in A.D. 1040. An engagement took place on the land now known as mauzâ Chau-kâpâr pûr, formerly a part of Mâṇikpûr, in which Malik Quţb Haidar, one of Sâlâr Masa'ûd's sardârs, lost his life, whose tomb is still pointed out.

The Tārikh-î-Firishta states that Quṭb-ad-din Îbâq fought a battle with Rājâ Jayachchhandra and conquered Kanauj in A.D. 1193; the latter sought refuge in the fort of Karrâ, and his brother, Mâṇikychandra, in that of Mâṇikpûr. The Musalmâns pursuing them divided their forces into two detachments and sent one under Qiyâm-ad-dîn, the son of Quṭb-ad-dîn, to subdue Mâṇikpûr, while Quṭb-ad-din himself remained at Karrâ. Two months' war swept away thousands both of the besiegers and of the besieged, but at last the Râjâs of both places took their families with them, left their forts and retreated to Kaṇṭîṭ in the Mirzâpûr district. Since this time, Mâṇikpûr ceased to belong to the Hindûs, and it may be stated to be one of the earliest Musalmân settlements in Audh.

There are, however, very few ancient remains attesting to the glory of so celebrated a place as Mâṇikpûr, which was formerly the most important town of the district of Pratâpgarh, if not of the whole province of Audh. There are twenty-two masjids, mostly erected during the reign of Akbar, Shâhjahân, and Aurangzîb; tombs of Râji Sa'îd Nûr, inscribed A.H. 965, of Mîr Tûfân, A.H. 995, of Shâh Hisâm-ad-dîn, A.H. 1008, of Bibî Sâleha, daughter of Shêr Shâh, and of Shâh Qâsim in the Ahâta-î-khângâh; the remains of the Rangîn Mahal, Sang Mahal, and Chihal Satûn; and the ruined brick fort overhanging the Ganges.

III. To the east of the town there are the ruins of the ancient brick fort, pentagonal in shape, with the remains of a masjid built in the time of Shâhjahân on a bluff point, about 120 feet high, overhanging the Ganges. This fort dates, no doubt, from the early Hindû period, as large ornamental bricks and sculptured kankar blocks are occasionally found, and the foundations of large Hindû stone temples are still traceable.

IIb. The Jâmi Masjid, Sang Mahal, Rangîn Mahal, and Chihal Satûn were erected in mauzâ Shahâb-ad-dînâbâd by Râjî Sa'îd Abdul Qâdir Khân, alias Mîr Âdil, a mansabdâr of 2,000 in the time of Shâhjahân. The stone of which these splendid edifices were constructed was brought from Faṭhpûr Sîkrî, where Abdul Qâdir purchased the quarry, and the enormous size of some of the slabs is truly astonishing, considering the distance from which they came. The buildings themselves are now in a more or less ruinous state, but nevertheless bear distinct

Hb.

¹ See note on Bihar in the Pratapgarh district.

III.

III.

III.

III.

III.

III.

Ib. Satûn, or "hall of forty pillars," still retains many beautiful portions, and the stone carvings are remarkably deep and well defined. The edifice overhangs the bank of the Ganges, and has balconies boldly projecting over the river, with finely carved columns and delicate tracing. Part of it has fallen down, and one apartment has been entirely carried away with the encroachment of the current.

IIb. On the bank of the Ganges there are six modern Hindû temples dedicated to

On the bank of the Ganges there are six modern Hindû temples dedicated to Mahâdêva and one to Jvâlâmukhî. The fragments of ancient sculptures collected near these temples belong, however, all to the worship of Vishau.

At the village of Samâdâbâd, now included within the limits of mauzâ III. Chaukâpârpûr, are the ruins of several palatial residences built by Nawâb Abdûs Samâd Khân Gardezî, during the reign of Akbar. Some of the edifices which he erected were of such beauty, and the stones employed in the buildings of such magnificent carving, that Asaf-ad-daulah, nearly two centuries after, removed considerable portions of them to Lakhnâû, where they now grace the great Imâmbâra.

The village of Kâlakankar Mahmûdâbâd, about four miles north-west of Mâṇikpûr, possesses the ruins of a large brick fort on the left bank of the Ganges. The village of Kûrmaganj is built on an old brick-strewn dih. Two miles further off, at the village of Murassapûr, or Nawâbganj, is a mud fort, built by Asaf-ad-daulah of Lakhnâû.

Three miles to the east of Manikpur lies the hamlet of Kiawan, perched on an ancient brick mound, with ruins of a small stupa, and of a mediæval stone temple on the banks of a dried up tank, called Sûrâjkund.

About eight miles south-west of Mânikpûr, on the north bank of the Ganges, is the old village of Karâîtî, possessing the remains of an extensive city in the shape of a high kherâ. To the east of the village is a ruined citadel, having vaulted rooms and bastioned walls.

III. At mauzâ Âsthân there is an extensive brick-strewn dih, from which a slab has been dug up, bearing a fragmentary inscription written in characters of the sixth century. The stone is now in the possession of Nawâb Ibn Husain.

5. PATTî, tahsîl, 13 miles east of Pratâpgarh, possesses a ruined brick mound.

On the left bank of the river Saî stands the high kôt of Bilkhar, within the lands of Yahyapûr, which undoubtedly represents a ruined Buddhist stûpa, and is therefore worthy of a careful exploration. A celebrated lingam, known as Bilkharnath, is standing on the highest point of the mound, and marks the spot of an old brick temple erected on the ruins of the Buddhist stûpa at the time when Brahmanism won its final victory over Buddhism. The ruined kôt is situated on an elevated plateau surrounded on three sides by ravines and broken ground covered with scrub jangal, and on the fourth side by the river Saî. The fosse is clearly distinguishable all round.

At the village of Parasurâmpûr, a pilgrimage place of local repute, 12 IIb. miles south-east of Pattî, is a noted fane of Pârvatî, who is worshipped under the name of Chauhârjâ. According to the tradition of the people, a portion (pittam, the bile) of Pârvatî's dead body fell here when she burnt herself at her father's

sacrifice. The temple is said to be of remote antiquity, and in proof of it the attending priests assert that the famous Banaphar hero, Alha, worshipped Dêvî here, and made a well at this place which is still visible. But, judging from its style of construction, it cannot be older than about two hundred years. Close by there is a high khera, covered with fragments of some interesting stone statues and broken bricks, which undoubtedly represent the ruins of a more ancient temple of Pârvatî.

III. The village of Dâûdpûr contains the ruins of a strong brick fort, said to have been built by Dâûd Khân in the reign of Alâ-ad-dîn Khiljî.

6. Pratâpgarh, tahsîl, lat. 25°-53′ N., long. 81°-59′ E., was founded in A.D. III. 1618 by Râjâ Pratâp Singh on the ruins of the ancient town of Alârikhpûr, or III. Arôr. He built a new fort of considerable size, which is a fair specimen of Hindû architecture. Its outer walls and flanking works were pulled down after 1857; but an inner keep and little walled garden still remain.

Four miles north of Pratâpgarh lies Belâ, the head-quarters of the district, with a modern temple dedicated to Belâ Bhavânî.

The public garden contains a fair collection of miscellaneous antiquities from different parts of the district, illustrating the style of decoration that prevailed in the neighbourhood during the period immediately prior to the Musalman invasion.

IIb. At Katra Mêdnîganj there is an inscribed stone mill, dated Samvat 1636.

Hb.

At the junction of the Sakarnî and Sâî, about five miles east of Pratâpgarh, IIb. stands the old temple of Durgâ, called Pañchasiddha, within the lands of mauzâ III. Banbìrkâchhî. Close by there is a high kherâ, from which heavy rains wash down numerous coins of the early Hindû period.

IIb. Another celebrated shrine of Durgâ, known as Chandikâ Dêvî, is at the old village of Sandwâ Chandikâ, 11 miles north of Pratâpgarh.

III. The village of Gondâ, four miles south of Pratapgarh, possesses an extensive IIb. kherâ, crowned with a small modern temple, near which several interesting fragments of ancient sculpture have been collected by the villagers.

About 15 miles west of Pratapgarh lies the village of Hindaur, said to have been founded by a rakshasa, named Handavi. The village must once have been a place of some importance, as is shown by the extent of its remains. The ruins of the ancient fort, said to have been built by Handavi, are still traceable.

II.—Râî BARELÎ DISTRICT.

1. Bachhráwán, old village in tahsil Digbijayganj, 20 miles north-west of Rái III. Bareli, possesses an extensive brick-strewn mound, the site of an old town, locally ascribed to the Bhárs.

IIb. At the village of Thûlendî, there are the plain tombs of Malik Tâj-ad-dîn IIb. and several other shahîds, the companions of Sâlâr Masa'ûd, as well as two tanks constructed by the same Malik Tâj-ad-dîn under the name of barâ hauz and chhotâ hauz, on the northern and southern limits of the village. The ruins of a strong mud fort and of two stone masjids built by Sultân Ibrâhîm Sharqî, in

A.H. 820, are still to be seen, and form a picturesque object in this flat country.

- About four miles east of Thûlendi lies the old village of Hardôi, possessing Hb. the tomb of Agha Shahîd of Salar Masa'ûd's army and a ruined mud-built fort of the III. time of Ibrahîm Shah Sharqi of Jaunpûr.
 - 2. Dâlmât,1 tahsîl, lat. 26°-5′ N., long. 81°-9′ E., 16 miles south-west of Râî Barelî, is said to have been founded by the Râțhor Dâla Dêva, brother of Râja Bâla Dêva of Kanauj, a contemporary of king Bahrâm Ghôr of Persia. Though there are remains of more ancient buildings, tradition asserts that the Bhars of the great tribe of Ahîrs took possession of Dâlmâû after the death of Râjâ Pratâpa Chandra of Kanauj in A.D. 530. In A.H. 423 Sâlâr Sâhû invaded the place and granted
- it to Malik Abdulla. The existence of the tombs of Maliks Ghâlib, Mubâraq, Alî, Hb. and Wali, and of other shahids, are proofs that the Musalmans had possessions here in the time of Sa'id Salar Masa'ad. The town prospered during the reign of Sultan
- Iltitmish of Dehlî, by whom the tomb of Makhdûm Badr-ad-dîn Badr Alam in IIb. mahallâh Makkhanpûr was erected, which was repaired in A.H. 1023, as stated in a Persian inscription. An inscribed slab,2 dated A.H. 716, records the appointment of a mu'azzin to a Jâmi Masjid by Mubâraq Shâh I., and another slab, dated A.H. 759, mentions the erection of a masjid by Fîrûz Shâh Taghlaq. On the ruined
- site of this masjid stands now an idgah of modern date. During the reign of Sultan IIb.
- Ibrahîm Shah Sharqî, Dâlmâû was included in the kingdom of Jaunpûr; a IIb. masonry well³ and garden on the banks of the Ganges at Makkhanpûr, one mile southeast of Dâlmâû, erected by Ibrâhîm Sharqî, still exist, and in the same garden is raised on a terrace the tomb (maqbara) of Muhammad Shah Sharqi, who was killed in battle by his brother, Husain Shah, near this place in A.H. 863.
- Ibrâhîm Shâh Sharqî repaired also the old Hindû fort of Dâlmâû, now an imposing III. ruin on the summit of a lofty artificial mound, overlooking the Ganges. After the restoration of this fort, Dâlmâû became a place of importance, and is frequently mentioned in Firishta. During the rule of Nawab Shuja-ad-daulah, the grandeur of the place and the respectability of its residents commenced to decline, and continued declining so much that at present it does not exhibit any trace of its former eminence. III.
 - The old Hindû fort of Dâlmâû is situated on a bluff point, about 100 feet high, overhanging the Ganges. It is an irregular quadrangle with its base on the river forming one of the long sides; it might, however, be more correctly described as shaped like a javelin head, with its point to the south-east, one edge along the river, another to the east facing the ruins of the old town, and two short sides forming an advancing angle at the back. The two north-eastern sides are respectively 163 and 315 yards long, the other two are of nearly equal dimensions, and the entire circumference may be estimated at 900 yards, or above half a mile. The corners, however, are advanced considerably, and the space is therefore circumscribed within by retreating ramparts. The land sides particularly are almost crescent-shaped, and a good flanking fire could be kept up from the advancing angles on every part of the rampart. The defences consist of vast earthen mounds from 40 to 60 feet high and some hundreds of feet

Cunningham, Archaelogical Reports, Vol. XI, page 60.

This slab was found in the rained fort of Dalman and is now in the Lucknow Museum. It is interesting in another respect, as it bears on the reverse a second Persian inscription, recording the erection of a masjid by Sarandûz Khan, in A.H. 1065, in the reign of Shahjahan.

This well was repaired in A.H. 990 during the reign of Akbar, as stated in a Persian Inscription.

thick; for in point of fact, except at one break of the middle, where a deep hollow extends right through from the river face, the fort consists of an immense artificial mound, covering about eight acres, which was originally crowned with a wall, and appears to have been partially fenced with masonry all round. At the south-east corner of the river face the masonry is still standing, the earth is cased with brickwork about four feet thick, and sloping at an angle of about 30 degrees to the ground; from this at a perpendicular height of about 40 feet the battlements rise wall within wall, each outer one acting as a buttress for that on the inside, and the whole is crowned by a ruined masjid and a bâradarî, an open pavilion, about 100 feet above the river, to which at this point the descent is a sheer perpendicular. The masjid and bâradarî were built in A.H. 1049 by Nawâb Sarandâz Khân, faujdâr of Dâlmâû, in the reign of Shâhjahân, as stated in a Persian inscription inside the masjid. From the bâradarî a bucket can be lowered down to the Ganges. The entire river face is scarped by the action of the water; to the land sides the slopes are more gradual, but still would be very difficult to escalade.

III.

It does not appear as if this work was originally designed for military purposes: there is no fosse on the land side and never has been. It further appears on examination that the steep scarp in many places was replaced originally by terraced steps, some of which with their brick easings are still to be seen. The remains of wells, too, are found outside the defences, only one small and modern well is within the III. enclosure; the mass of earthwork also is quite beyond what would be required even to resist modern artillery, and for defence against the engines of mediæval India exhibits an unaccountable prodigality of labour. It is apparent on inspection that the work is one of different ages; in several places the torrents of rain from the high plateau within have forced their way out, forming yawning rifts or ravines, on entering which it appears that considerably within the present outer line of circumvallation there exists a brick wall of excellent material and fine work laid without mortar, resembling in all respects the early Buddhist work to be seen at Sarnath. This wall appears to have been formerly all round the place; in some spots it has been removed; on others the upper wall, which was formerly much higher than it appears at present, has tumbled down in vast masses, forming a glacis of mixed materials and concealing the ancient wall; the wall in fact has doubled over, and the inner casing of earth alone is visible.

III. The interior is studded here and there with ruined stone pavilions, masjids, and tombs of very inferior workmanship, dating mostly from the time of Akbar and Shâhjahân. A fine gateway to the east is also of comparatively late date, apparently having been erected by Ibrâhîm Shâh Sharqî, and largely composed of carved slabs, pieces of pillars and architraves, which formed part of some ancient temple. The carvings are partly buried in the brick-work, and the architraves have been worked in upside down; some of them, from their bee-hive shaped bosses, are probably as old as the time of the Guptas. There are also fragments of pillars and sculptures in the ruined masjid of Shâhjahân's time, and in many places under trees.

It would appear that this fort consists really of the ruins of two Buddhist stupas. These were generally circular and had a perpendicular casing of masonry which rose

in terraces, while the top was shaped into a round solid tower; they were accessible by stairs, supplied with balustrades. Apparently two of these stupas adjoined, as was often the case; the original height was probably not less than 150 feet. After the peaceful period, witnessed by Fa Hian and Hiuen Tsiang, had expired, some powerful Brâhmanical leader, Râjâ Dâla Dêva or his ancestor, destroyed the stûpas, and, seeing the advantage of the position, connected the ruined mounds, forming the whole into a vast plateau with a hollow in the centre, which was not filled up to the original level.

This of course is mere conjecture; what seems certain is that the entire structure is an artificial one. The floods have laid low the very foundation, and at a depth of 60 feet from the surface, bricks and pottery pared away by the river attest that the entire mass has been placed there by the hand of man. If so, this huge mound would have served no known purpose but that for which the Buddhist raised his stupa; while the terraces, the brick plinth and wall, the ancient carving, and numerous stone pillars, lintels and balustrades, of types well-known in Buddhist architecture, attest the same fact.

This ruined mound, with its tottering pavilions and crumbling battlements, is the most picturesque object on the banks of the Ganges in Audh. The deep stream flows under the overhanging battlements from which yearly it cuts a portion away. In the face of the cliff so formed are seen walls, floors, arches and vaults; beautifully carved blocks of stone protrude themselves; here and there appear large earthen jars, probably used for some funeral purpose-all seem thrown together in one chaotic compost. These fragments of ancient buildings, seen in vertical section, are embedded in the clay, and present a strange medley of relics of the past. Each year some structure is unearthed by the river, is seen for a few months by the boatmen whose vessels pass underneath, and with the floods of the next monsûn is again swept away

On an isolated mound named Jaychand, a short distance to the north-west of the town, there are the remains of a dargah, built entirely of Hindû materials. Ib. There are eight round pillars, each in two or three pieces, with most of the ornaments cut off. The place is said to have belonged to the two famous, and rather ubiquitous, heroes Âlhâ and Ûdal, and is popularly known as Âlhâ Ûdal-kî-baithak. Hb.

A little further to the north is the dargah of Makhdum Jahaniya, built entirely of the ruins of an old Hindû temple, in A.H. 1005, as stated in a Persian inscription. IIb.

Other objects of interest in the town are the masjid of Makhdûm Badr-ad-dîn, repaired by Mîrzâ Sakr-ullah, during Akbar's reign, and the sarâî and masjid of Mîr Sakhâwat Alî near Purânî Bâzâr, built by Hâjî Zâhid in A.H. 1006, as stated in their respective Persian inscriptions. The temple of Banvari Dêvî, said to be a IIb.

very old one, is a commonplace structure of recent date.

At Pakhrâûlî, three miles to the south-east of Dâlmâû, on the banks of a large jhil, is a modern temple, dedicated to the mythical heroes Dâl and Bâl, near IIb. which there are some broken pieces of sculpture and an inscribed column.

About five miles north-west of Dâlmâû lies the village of Bahâî with two large brick-strewn mounds, surrounded by deep ditches. On the top of the highest khera III. there are the ruins of a small kankar-built masjid.

A little further on, near the village of Sathanpûr, there is another large III. mound, covered with broken pottery, bricks and terra-cottas.

At the village of Khajûrgâon and Chilaula are ruins of large earthen III. forts.

The village of Khiron possesses the remains of a large mud fort.

III.

III.

III.

III.

IIb.

III. Jalalpûr-Dehî, eight miles east of Dâlmaû, contains the ruins of an IIb. ancient Hindû town and the tombs of Saidan Shâh and Bhilaul, shahîds of Sâlâr Masa'ûd's army.

- 3. Inhauna, village in tahsîl Digbijayganj, lat. 26°-32′ N., long. 81°-32′ E., 28 miles north-east of Râî Barelî, is devoid of antiquities; but the neighbouring village of Majhita contains the ruins of an ancient brick fort, ascribed to the Bhars.
- 4. Jagatpûr, small village in tahsîl Dâlmâû, on the road from Mânikpûr to Dâlmâû, 18 miles south of Râî Barelî, possesses, at a little distance to the northeast of the road, a high brick mound, extending over a mile in length and breadth. III. The kherd is surrounded by a deep ditch, which widens into a large sheet of water on the north side, on the banks of which stands the hamlet of Sankarpar. In the IIb. middle of the great mound are the remains of a ruined brick stûpa of very old date, being a conical mound upwards of 30 feet high. The bricks are from 14 to 15 inches
- long by 9 inches broad and 21 inches thick. The basement of the stûpa is 25 feet six inches square, above which rises the hemisphere upwards of 20 feet in diameter. The crown of the dome was, therefore, more than 33 feet high above the ground, to which may be added a pinnacle of umbrellas, placed one over the other, up to 17 feet, which would make the total height of the stupa just 50 feet. A short distance to the north of this ruined stûpa are the foundations of a small building, measuring 14 feet III.
- square outside, which no doubt represent the ruins of a small vihâra. About half a III. mile to the east of this stupa are the ruins of a large building, apparently a samghàràma. Numerous traces of solid brick-work and large quantities of broken terra-cottas, burnt and unburnt clay seals, and Buddhist coins prove the great antiquity of the place. On topographical grounds and from a calculation of distances, the

place may safely be identified with the O'-yu-t'o of Hiuen Tsiang.1

About six miles to the north-west of Jagatpûr lies the old village of Kankûr, on the north bank of the Ganges, with a high brick-strewn dih and the foundations of a large building. This place corresponds exactly with the site of the stupa and monastery of Vasubhandhu Bodhisattva, which the pilgrim places at 40 li to the northwest of the ruins of the preaching hall of Asanga Bodhisattva near 'O-yu-t'o.

 Jais, old town in tahsil Salôn, lat. 26°-18' N., long. 81°-36' E., 20 miles east of Rai Bareli, is said to be the ancient Ujalikanagara, the seat of a Bhar kingdom. The rising ground on which the present town is built covers the remains of this ancient fortified capital, and the irregular appearance of the town is locally attributed to the caprice of its monarch, who in constantly recurring fits of drunkenness had a methodical madness for raising fortifications. The old Hindú town was taken by Sa'îd Imâm-ad-dîn Khiljî, in the time of Mahmûd of Ghaznî, who,

however, was slain in battle, and whose tomb is still pointed out below the town.

¹ Beal, I.c., Vol. I, pages 224-229.

Some curious sepulchres are found in the town, being eight or nine yards in length; they are attributed to the followers of Sa'id Imâm-ad-dîn Khiljî.

IIb. The only remains of interest are the Jami Masjid, crowning the hill, which was erected by I brahim Shah Sharqi on the ruins, and from the materials, of an old Hindû temple. Close by is the masjid of Shaikh Abdul Karim, built in A.H. IIb. 1085, during the reign of Alamair, as stated in a Parsian incarintian. The derests

1b. 1085, during the reign of Âlamgîr, as stated in a Persian inscription. The dargâh of Sa'id Makhdûm Ashraf Jahângîr, who shut himself up in a cell for 40 days at this place, is a commonplace structure.

At the village of Ashrafpûr, three miles south of Jâis, in the house of Mir Muhammad, are two inscribed red sandstone slabs, dated A.H. 977, which have apparently been removed from the ruins of a masjid built by Akbar.

Four miles south-east of Jais lies the village of Nasîrâbâd, partly built on a rising ground which covers the ruins of an ancient brick fort, said to have been erected by Sultan Ibrâhîm Shâh Sharqî in the name of his son, Nasîr-addîn. Another tradition makes Nasîr-ad-dîn Humâyûn of Dehlî the founder of the town and fort.

6. Mustafâbâd, village in tahsîl Sâlôn, 22 miles south of Râî Barelî, possesses the remains of many fine buildings, as tombs, imâmbâras, and palaces, built by Abdul Khâliq in the time of Shâhjahân.

III. At the old village of Kandarâîn are the same and

 At the old village of Kandarâîn are the ruins of a large brick temple, apparently dedicated to Siva, as many interesting fragments of Saiva statues are lying about at the foot of the temple mound.

About four miles east, on the Ganges, is Pâṇḍukôţ, which contains some III. broken statues of good workmanship. Close by is Chaṇḍâû, which also has some III. interesting fragments of ancient sculpture.

7. Râî Barelî, tahsîl and head-quarters of district, lat. 26°-14′ N., long 81°-17′ E., is pleasantly situated on the river Sâî, here spanned by a fine masonry bridge of IIb. five arches, 28 feet broad. The picturesque temples and masjids of the old town are now rather in decay; but the huge crenelated battlements and gateways still rise grandly above the fields. The old town is said to have been founded by Bhârs, and after them called Bhâraulî, altered afterwards to Barelî. Some say that it is called Râî Barelî from Râhî, a village three miles to the north-east of Barelî, the original head-quarters of the pargana. The town was handed over to Shaikhs and Sa'ids in A.H. 820 by Sultân Ibrâhîm Sharqî, who repaired and strengthened III. the old Hindû fort. Husain Shâh Sharqî changed the name to Husainâ-

III. The fort is a vast quadrangular structure consisting of a high earthen mound which has been faced with huge bricks, being two feet long, one foot thick, and one and a half wide. The western gate leading to it is still standing, and is composed well about 35 feet in diameter, lined with huge bricks, supporting balconies and containing chambers on a level with the water. In the interior are various buildings of no interest, mostly erected during the reign of Shujâ-ad-daulah. There are no distinct traces of Buddhist origin about the fort except the huge bricks which undoubtedly belonged to some local temple of very old date. Unlike the Dâlmâû

fort there is no elevated plateau inside. There is a fosse outside, and the original design of the work was obviously for military purposes; but it is possible that some earlier structure may have been embraced in the circumvallation.

IIb. Near the gateway of the fort is the tomb of Makhdûm Sa'id Jâfrî of Jaunpûr, erected by Ibrâhîm Shâh Sharqî.

IIb. The fine Jâmi Masjid was built by Sultân Ibrâhîm Shâh of Jaunpûr, and repaired in A.H. 1098 by Âlamgîr, as stated in an Arabic inscription. Another IIb. great masjid was built in A.H. 1040 by Nawâb Jahân Khân, during the reign of Shâh jahân.

IIb. A magnificent palace, called Rang Mahal, and the maqbara of Nawâb Jahân Khân adorn the suburb of Jahanâbâd in the village of Ikhtiyârpûr, which has always been considered a mahallâh of Râi Barelî.

The village of Alîganj, on the Dâlmâû road, possesses an extensive and high brick mound, from which several beautifully carved statues of Vishņu have been dug out a few years ago.

About six miles north of Râi Barelî stands the large village of Bhâwan with an extensive brick-strewn kherâ, said to be the ruins of a strong masonry fort built by Sultân Ibrâhîm Shâh Sharqî on the ruins of a Bhâr castle.

8. Sâlôn, tahsîl, lat. 26°-4′ N., long. 81°-36′ E., 20 miles south-east of Râî Barelî, is said to derive its name from Śâlivahana, who relieved the country from the presence of the asura Sahasrabâhu, and founded the town. A high brick-strewn kherâ is pointed out as the remains of Sahasrabâhu's fort.

At the village of Naîn, two miles north of Salôn, are the ruins of a strong brick fort in the middle of ravines, covered with brushwood, which extend to the bank of the Sai, here a narrow deep channel, with lofty banks, picturesquely clothed with jangal.

9. Thunh, small village in pargana Bachhrawan of tahsil Digbijayganj, 22 miles north-west of Raî Bareli, possesses an old brick-strewn dih, in which a hoard of 25 Gupta gold coins was discovered in A.D. 1885. Two of these belong to the reign of Chandragupta I., and the remaining 23 to that of Samudragupta; 16 specimens from this hoard are now in the Lucknow Museum Coin Cabinet.

III.—Sulţânpûr District.

Aldemâů, village in tahsîl Kâdipûr, lat. 26°-15′ N., long. 82°-26′ E., 20 miles south-east of Sulţânpûr, contains a high and extensive kherâ, the ruins of a fort and city ascribed to the Bhârs. This ancient town is said to have been destroyed by the Sharqî kings of Jaunpûr, and in confirmation of this local tradition are pointed out the remains of many Musalmân tombs, which are still to be IIa. found amongst the ruins. The tombs of Juriya Shahîd and of Shaikh Makhdûm Mârûf are the most noteworthy.

III. The pargana of Aldemâû possesses no less than 49 kherâs, the deserted sites of fortified towns, locally ascribed to the Bhârs, which, however, are no doubt the ruins of Buddhist cities, destroyed by fire, when Brâhmanism won its final victories over Buddhism.

III.

III.

¹ Proceedings, Aziatic Society of Bengal, for 1886, page 86.

- At Mêopûr Khâs was formerly a strong mud fort, the site of which is now III. marked by a much-reverenced mound of earth.
- In the south-east corner of the pargana, on the left bank of the Gumti and III. overhanging the river, are the extensive remains of the old fort of Dvaraka, still difficult of approach from ragged and steep ravines. The natural position must have been very strong, and the artificial works immense. Ia.
 - The village of Patna possesses an extensive khera on the banks of the Gumti, from which two elaborately carved statues of the Jaina Tirthamkara Adinatha have been dug out in A D. 1850. These statues are now in the Faizâbâd Local Museum.
- IIb. At the village of Bilwai there is a noted lingam, which was discovered in the raised bank of an ancient tank at the end of last century.
- IIb. There is a celebrated modern shrine of Hanuman at the village of Begeth û â. which is deemed to be of great antiquity. Close by are two ancient ponds, named Makarîkund and Hatyaharana, with which important mythological legends are associated.
- 2. Amerif, or Garh Amethî, tahsil, lat. 26°-16' N., long. 81°-54' E., possesses III. the ruins of an old brick fort on a commanding position overlooking a lake, mentioned in the Ain-i-Akbari.
- At the villages of Râîpûr, Tikrî, Shâhgarh and Bithâ are extensive brick-strewn mounds, undoubtedly the ruins of Buddhist cities, but locally ascribed to III.
 - 3. Dпора̂р, famous place of Hindû pilgrimage in pargaņa Châṇḍâ of tahsil Kâdipûr, 18 miles south-east of Sulţânpûr, is situated on the right bank of the Gûmtî. The legend of the place is as follows:-After Râmachandra had killed the giant Râvaṇa, he wandered about trying to obtain purification for his guilt in having thus extinguished a portion of the spirit of Brahmâ; but all his efforts were ineffectual, until he met with a white crow, when he was informed by the muni Vasishtha that the crow had become white from having bathed in the river Gomati (Gûmtî) at a particular spot. Rama proceeded to bathe at the spot, and was immediately "cleansed" from his sin. The place was accordingly named Dhûtapâpa, or "cleanser of sins," and the town which soon sprang up beside it was called Dhûtapâpapura. In the Vishnupurana Dhûtapapa is given as the name of a river distinct from the Gomati; but as the name immediately follows that of the Gomati, it is probable that the term may have been intended only as an epithet of the Gomati, in allusion to the legend of Râma's purification. An annual mêlâ is held here on the 10th day of the waning moon of Jyaishtha, at which time it is said that about fifty thousand people assemble to bathe in the far renowned pool of Dhopap.
- The site of Dhopap is evidently one of very considerable antiquity, as the whole country for more than half a mile around it is covered with extensive mounds strewn III. with broken bricks and pottery. The place is said to have belonged to the Bhar Rajas of Kusabhavanapura, or Sulţanpûr. The village of Dhopap is now a very small one, containing less than 200 houses, but they are all of burnt brick, and numerous foundations are visible on all sides near the Gumti. Several carved stones have been collected by the people from the ruined wall of the fine old masonry fort

¹ Ounningham, Archeological Reports, Vol. I, page 315.

overlooking the Dhopâpghât. All of these stones point unmistakably to the existence at some former period of a large temple at Dhopâp, which was probably situated immediately above the bathing ghât. It seems almost certain, however, that there must once have been a considerable number of temples at this place, for the whole of the eastern wall or river front of the fort has been built or faced with square stones, which, by their carvings and cramp holes, show that they belong to Hindâ

temples.

The fort, called Garhâ or Shêrgarh, is situated to the north of the village on a lofty natural mound overhanging the Gûmtî on the east. To the north and south the place is defended by two deep ravines supplied with running water, and to the west by a deep dry ravine. The position is, therefore, a strong one; for, although the neighbouring mounds to the north and west rise to nearly the same height, yet they once formed part of the city, which can only be approached over much low and broken ground. The strength of the position would seem to have early attracted the notice of the Musalmân Emperors of Dehlî, as the fort is stated to have been repaired by Salîm Shâh, the second son of Shêr Shâh. The fort itself is a small place, its northern, eastern and western faces being only 550 feet each, whilst its south face is but 250 feet. The greater part of the stone work of the south-east tower has fallen into the river, where many of the stones are now lying, and much of the eastern wall has also disappeared. The entrance gate was on the south side, near the river bastion.

On the west mound, just behind the fort, there is an old dilapidated masjid of the Sharqi period, built of mere rubble bricks, originally of five domes, three of which only remain standing. The only inscription in the masjid is the Kalimah or Musalman creed, engraved in very large letters on a black stone. The Arabic letters of this inscription are arranged in the same manner as on the gold coins of the Sharqi kings.

The neighbouring village of Bikhar is perched on an ancient mound, and believed to have been founded by Vikramaditya of Ujjayini.

Five miles further up the Gumti is Paparghat, possessing the ruins of the large city of Shahabad, that Mansur Ali Khan, Safdar Jang, attempted to build nearly two centuries ago; but, ere the walls had reached many feet in height, a plague broke out, and the work was suspended, never to be resumed. Here an annual fair is held on the eighth and ninth of Chaitra in honour of Mari Bhavani, or the goddess of death. Paparghat is obviously a corruption from Mari Pari, "the angel of death," who is supposed to have destroyed the army of the Moslim invader.

Four miles north of Dhopâpghât, on the left bank of the Gûmtî, stands the old village of Dêrâ, perched on a high dîh. Subsequent to his purification at Dhopâpghât, Râmachandra is said to have crossed the Gûmtî at Dêrâ the same evening, and here he is supposed to have performed the dîpadanam ceremony, and thenceforth the place was known as Dîpanagaram. Why the name was changed to Dêrâ no one can explain.

I. The adjoining village of Harsen, built on an extensive kherâ, is also reverenced for its associations; for it is said that after performing the lamp ceremony, Râmachandra slept in this village.

Three miles above Dêrâ stands the old village of Nânâmâû, where there is a noted lingam, called Narmadêsvara.

III.

Ш.

III.

III.

III.

III.

- III. The village of Arjunpûr contains the remains of a large fort built by Salîm Shâh, and said to have been called Makarkala. The walls are about three feet thick with bastions here and there, and enclose a large area now under cultivation.
- III. The village of Arju contains a large well built with bricks nearly two feet in length, and ascribed to the Bhars.
 - 4. Musafirkhana, tahsil, lat. 26°-24′ N., long 81°-52′ E., is devoid of antiquities; but the neighbouring village of Bhagapir, also called Ganaur, possesses an interesting group of ruined brick temples of the tenth century, locally called Teligarhi after the builder, a rich oilman of the Bhar period. These temples were arranged in two lines all of which have fell and the lines all of which have fell and the lines all of which have fell and the lines are selected.
- Ib. arranged in two lines, all of which have fallen down with the exception of two. The best preserved of these two is in plan a square of 40 feet externally, with a chamber of 22 feet long and 18 feet broad, covered with a pointed dome. The lower part of the temple consists of plain bold mouldings, above which there is a series of panels, filled with Saiva groups in terra-cotta, and divided from each other by pilasters.
- Ib. The second temple is in plan an octagon standing on a circular plinth, with a square chamber of 12 feet diameter, and no portico. This chamber was originally covered with a pointed dome, built with bricks end to end after the Hindû fashion. Outside the whole surface of the walls is richly decorated with deeply cut arabesque ornament, being repeated from top to bottom.
- Ib. Close by, at the village of Pali, is a very fine statue of Sarya and some good pieces of ancient sculpture standing on the débris of a large brick temple.
- The village of Karthuni, on the road to Sultanpûr, possesses also some interesting fragments of early sculpture, on the summit of a large kherâ.
- At the village of Isauli, five miles north-east of Musafirkhana, are the ruins of a high brick fort, ascribed to the Bhars, on the left bank of the Gamti.
- About 12 miles north-west of Musafirkhana lies the village of Nihalgarh, variously called Chak Jangla or Jagdispûr, possessing the ruins of a mud fort, erected by Nihal Khan in A.D. 1715.
- About six miles north of Nihâlgarh lies the old village of Sâthan, perched on III. an extensive Bhâr kherâ on the right bank of the Gâmtî. A little further up the river, the village of Kishņî occupies a high brick-strewn plateau, surrounded by IIb. ravines. The only building still standing and worthy of notice is a masjid built by Qâzî Abd-us-Sattâr in the reign of Âlamgîr.
- 5. Sultanpur, tahsil and head-quarters of district, lat. 26°-15′ N., long. 82°-7′ III. E., lies on the right bank of the Gamti, and is built near and partly upon the ruins of the ancient city of Kusapura, or Kusabhâvanapura, named after Râma's son, Kusa. The original Hindû town was situated on the left bank of the Gamti on a little peninsula formed by a bend in the river's course. Shortly after the Musalmân invasion it belonged to a Bhâr Râjâ, who was expelled by Sultân Alâ-ad-dîn Khiljî. The old defences of the town were strengthened by the conqueror, who lib. built a masjid within the town and to the north-west of the fort, and above ald.
- built a masjid within the town and to the north-west of the fort, and changed the name of the place to Sultanpur. The site of Kusapura was, no doubt, selected by its founder as a good military position on account of its being surrounded on three sides by the Gumti. The place is now entirely desolate; the whole population having been removed to the new civil station, variously called Chhaoni Sadr, or Kampû,

on the opposite or right bank of the river. The only remains of the ancient city now extant are the fort and two large brick wells at the south verge of the present town, about a mile from the river. The ruined fort of Sultanpur now forms a large III. dih, called Majhargaon, in the middle of the town, 750 feet square, with brick towers at the four corners. On all sides it is surrounded by the broken bricks of the ruined city, the whole together covering a space of about half a mile square, or about two miles in circuit.

The ancient Kusapura has been identified by General Cunningham¹ with the Kia-shi-po-lo, or Kasapura, of Hiuen Tsiang.² The size of ancient Sultanpur agrees very closely with that of Kasapura given by Hiuen Tsiang, who describes the place as being 10 li, or 1¾ miles in circuit. According to the Chinese pilgrim, there was by the side of the city the old saṅnghārāma of Dharmapâla Bodhi-sattva, of which the foundation walls alone existed. "By the side of this place is a stūpa built by Asoka Rājā; the walls are broken down, but it is yet 200 feet or so in height. There Buddha in old days declared the law for six months; by the side of it are traces where he walked. There is also a hair and nail stūpa." The remains of these Buddhist edifices may safely be identified with the ruins at the village of Mahmūdpūr, five miles north-west of Sultānpūr, which is perched on an ancient mound of somewhat larger size than that of Sultānpūr.

On the right bank of the Gûmtî, immediately below the civil station, a place is still pointed out under the name of Sîtâkuṇḍ, where Sîtâ is said to have bathed while accompanying Râma into his exile.

In the village of Hasanpûr-Bandhûâ, four miles north-west of Sulţânpûr, is a fine large masonry tank, called Sâgar, on the border of which stands an imposing pile of buildings.

The village of Lohrâmâû possesses a noted temple of Dêvî, which is built on the ruins of an older brick temple.

In the village of Kotwâ, nearly at the summit of a lofty brick-strewn mound overlooking the Gûmtî, stands a celebrated shrine, called Set Barâh. In point of size this temple is very insignificant, but this is more than compensated by its great sanctity. It is dedicated to the Śveta Varâha, or "white boar" incarnation of Vishņu. In the immediate neighbourhood are several brick-strewn mounds of various dimensions; the largest of them is said to have been a Bhâr fortress. It is very probable that a town of considerable importance once existed here, and that there once stood on this spot a famous temple, dedicated to Vishņu in his Varâha Avatâra, which was long ago destroyed.

III. On the borders of the village of Jurapattî are the ruins of an old fort, called Koțhot, which is simply a corruption of Kôţ-ut, or the "fort on the other side." The popular account of Koţhot is that after the capture of Kuśabhâ-vanapura by Sulţân Alâ-ad-dîn Khiljî the Musalmâns erected two fortresses. The principal one was Sulţânpûr on the north bank of the Gûmtî on the ruined site of Kuśapura; the other a kind of outpost, called Kôţ-ut, was built a few miles from it on the south side of the river.

III.

IIb.

IIb.

IIb.

III.

Hb.

III.

¹ Archwelogical Reports, Vol. I, page 313.

^{*} Beal, Lc., Vol. I, page 237.

About ten miles west of Sultanpur lies an interesting group of old villages called Bhanti, Narhay, Dhamaur, Sambhar, and Sanichra, all of which are perched on high mounds, apparently the sites of ancient brick temples. The fragments of door-jambs, lintels, pillars, cornices, and the broken Brahmanical and Jain statues, lying about on these mounds, and especially on the banks of the Jhadhkund at Kurh, clearly show that the cella of these temples was of stone, decorated in the same style as the Mahoba and Khajuraho temples, whilst the tower was of moulded bricks. This part of the country is worthy of a careful exploration.

XII.-ADDENDA ET CORRIGENDA.

Page 4, No. 4, Balandshahr.—Add to foot-note 3:—"Indian Antiquary, Vol. XVIII, page 289."

Page 6, note 2 .- Add :- "Corpus Inscriptionum Indicarum, Vol. III, page 68."

Page 8, No. 3, Марна.—For "Îsvarâ was the daughter," etc., read: "Îsvarâ was the daughter of Bhâskara [varman] of Singhapura by Jayâvalî, the daughter of Kapilavardhana. It gives," etc., and after "Sênavarman," insert "Aryavarman," and add after "page 245, note:"—"It has been published in extenso in Epigraphia Indica, Vol. I, pages 10-16, with a fac-simile by Dr. Burgess."

Page 11, line 14.—After "page 794 sqq." insert "and by Dr. Bühler in Indian Antiquary, Vol. XIX, pages 122—126."

Page 17, note 3.—After "Vol. XIII" add "pages 306-310."

Page 20, No. 2, Badaon, line 3.—This inscription has been edited in *Epigraphia Indica*, Vol. I, pages 61—66.

Page 31, line 2 .- For "nailed" read "railed."

Page 39, line 3.—Delete here and elsewhere the word "Kuṭila." Dr. Bühler in Epigraphia Indica, Vol. I, page 76, has proposed, on good grounds, to remove Prinsep's term "Kuṭila alphabet" from Indian palæography, and to describe the characters of the Dêwal inscription as Nagari of the North Indian type, of the tenth century.

Page 39, line 12 .- For "Chhindu" read "Chhinda."

_____, 10 lines from bottom.—For "Vîravarman" read "Vairavarman."

———, Add to foot-note 1:—" Epigraphia Indica, Vol. I, pages 75—85."

Page 41, line 22.—For "Viravarman of the Chhindu race" read "Vairavarman of the Chhinda race."

Page 69, No. 4, Barrsar,—Add to foot-note:—" and Vol. VII, pages 5—11."

Epigraphia Indica, Vol. I, page 207, mentions a Chandella inscription of Para-mârdi Dêva, dated (Samvat) 1252, now in the Lucknow Museum, which, by some mistake, is said to have been found in an ancient mound at Baţêŝar, whilst the slab was obtained in 1884 through the tahsildâr of Mahobâ from the banks of a lake at Bagrârî in the Hamîrpûr district. This inscription is referred to by General Cunningham in his Archwological Reports, Vol. XXI, page 82, No. 52.

Page 78, No. 9, Kanauj.—After "Kanyakubja" add "or Mahodaya."

Page 86, No. 9, Bilsar.—Add to text:—"One of these inscriptions has been published in Corpus Inscriptionum Indicarum, Vol. III, pages 42—45."

Page 87, No. 21, Patiali.—After "Mahabharata" insert "under the name of Patali."

Page 90, note 1.—Add:—" and Vol. XVIII, page 19."

Page 92, note 1.—Add:—" Epigraphia Indica, Vol I, pages 179—184."

"Professor Kielhorn conjectures that the place where the inscription originally was put up was called Gavidhumat. This name has hitherto been met with only in Patanjali's Mahabhashya, in a passage which says that Samkasya (the modern Sankasa in the Farrukhabad district) is four yojanas distant from Gavidhumat."

Page 92, No. 15, Râhan.—For "a copperplate grant of Govindachandra Dêva," etc., read: "a copperplate grant of Madanapâla and Govindachandra Dêva," and add to note 2:—"Indian Antiquary, Vol. XVIII, page 14."

Page 98, 16 lines from bottom.-For "northex" read "narthex."

Page 105, 8 lines from bottom.—Delete the word "Buddhist"; and in line 3 from bottom, delete "Bauddha and". Dr. Burgess considers the naked female figures on pillars as Jaina and not Bauddha.

Add to text under Kankâlî Tîlâ: "A liberal grant by the Government of the North-Western Provinces enabled Dr. Führer, in January, 1890, to resume the excavation of the great Jaina temples, buried under that mound. He discovered to the east of the large Svêtâmbara temple, unearthed in 1889, a brick stûpa of 47' diameter, and to the west another large Jaina temple which belonged to the Digambara sect. The excavations on these sites yielded 80 images, 120 railing pillars, bars and copings, as well as a considerable number of toranas and other architectural pieces, all of which are adorned with exquisite sculptures. He also obtained a large number of inscriptions, which undoubtedly belong to the Indo-Skythian period, and furnish most important information regarding the history of the Jainas. Their dates range between the year 5 of the Dêvaputra Kanishka and the year 86 of the Indo-Skythian era, or assuming the latter to be identical with the Saka era, between A.D. 83 and 164. These new inscriptions prove the correctness of the Jaina tradition with respect to the early existence of six divisions of monks, not traced before, and they corroborate the statements of the Kalpasûtra regarding the early subdivisions of the Jaina monks in ganas, kulas, and śakhas. In addition, they settle another important question. According to the Śvêtâmbara scriptures, women are allowed to become ascetics; but we have hitherto had no proof that this doctrine was really ancient. The new finds leave no doubt that it was; the suggestion of some orientalists, according to which the Svêtâmbaras copied the Bauddhas in this practice must, therefore, be rejected as erroneous.

"These remarkable inscriptions have been edited for the Epigraphia Indica, and all the archæological treasures unearthed have been deposited in the Lucknow Museum,"

Page 106.—Add to text under Chaubâra mound:—" Professor Bühler is of opinion that this mound undoubtedly hides the ruins of an ancient Vaishnava temple, and that a thorough exploration of the same will yield documents elucidating the history of the hitherto much underrated Bhâgavatas, a sect which is older than the Bauddhas, and even than the Jainas."

Page 107, line 5.—After "Mahâditya" insert: "and a beautifully written slab, dated Samvat 1207, but partly damaged in the middle. These inscriptions have been edited by Dr. Bühler for the Epigraphia Indica.

"An undated Gupta inscription of Chandragupta II, and another on the pedestal of a standing statue of Buddha, dated Samvat 230, were found in the Katrâ mound in A.D. 1853 and 1871 respectively, whilst an inscription of Skandagupta, dated Samvat 135, was found in 1871 in the Jamâlpûr mound. These inscriptions have been published in Corpus Inscriptionum Indicarum, Vol. III, pages 25, 262, 273."

Page 108, line 15 .- For "Sawar" read "Sawai."

______, 2 lines from bottom.—For "wall" read "well."

Page 110, line 7.—The characters on the Parkham statue, though ancient, are of a form that was still in use in the first century A.D., and Dr. Burgess is disposed to assign it no earlier a date than the first century B.C.

Page 118, No. 7, Jhansi.—Add to text:—"In 1887, the then Officiating Commissioner forwarded to the Lucknow Museum three inscribed stone slabs of the Chandella period, which had been recovered from the ruined fort walls. One contains a fragmentary inscription of Sallakshanasimha, and the other a complete record of Vîravarman Dêva, dated Samvat 1318. The first inscription mentions the Chandella king Kîrttivarman, the contemporary of the Chedi king Karna-dêva and of the Paramâra Udayâditya, the ruler of Mâlava, see Epigraphia Indica, Vol. I, pages 214—216. These inscribed slabs originally belonged to the ruined temples of Dûdâhî in the Lalitpûr district, which is no doubt the ancient Dugdhakupyagrâma, mentioned in the fragmentary inscription of Sallakshanasimha."

Page 119, line 9.—Add to text:—"Apparently at the foot of this hill Lieutenant W. Price, in 1813, discovered the Chandella inscription of Madanavarmadêva, which is now in the Indian Museum at Calcutta; see Asiatic Researches, Vol. XII, pages 357—374; Epigraphia Indica, Vol. I, pages 195—207."

Page 119, No. 1, BANPÛR.—After "inside the temple," insert "of which one bears date Samvat 1001."

Page 120, line 17.—For "Samvat 933" read "Samvat 919."

- ———, line 21.—After "Samvat 1051" insert "Samvat 1001, 1022, 1030, 1052, 1105, 1133, 1207, 1208, 1300, 1354, 1493."
- ————, 10 lines from bottom.—This inscription has been published in the Indian Antiquary, Vol. XI, page 311, and Vol. XVIII, page 237.
- ______, 7 lines from bottom.—Add to text:—"Near the Naharghati, there is a valuable record of Svamibhata, dated Samvat 609, written in characters of the later Gupta period."

Page 124, line 13.—After "small temple" insert "and a sati pillar, dated Samvat 1343. The village of Garhâ possesses over the lintel of a ruined lingam temple a long record of Samvat 1014, and close by a sati monument, dated Samvat 1352."

Page 124, 11 lines from bottom.—For "stood" read "set." This inscription has been published in the Epigraphia Indica, Vol. I, pages 162—179.

Page 128, note 1.—Add:—"Indian Antiquary, Vol XIII, pages 306—310; Vol. XIX, pages 122—126."

Page 129, note 1.—Add:—"Corpus Inscriptionum Indicarum, Vol. III, pages 1—17."
Page 132, line 3.—An inscription of the fifth century A.D. on one of these statues has been published in Corpus Inscriptionum Indicarum, Vol. III, page 271.

Page 133, 2 lines from bottom.—For "Samvat 126" read "Samvat 129." See Corpus Inscriptionum Indicarum, Vol. III, page 45.

Page 136, 8 lines from bottom.—For "Sainvat 86, 98, and 140" read "Sainvat 88, 98, and 148." See Corpus Inscriptionum Indicarum, Vol. III, pages 36—40, 264, and 267.

Page 142, 11 lines from bottom.—For "Samvat 136" read "Samvat 139." See Corpus Inscriptionum Indicarum, Vol. III, page 266.

Page 144, 5 lines from bottom.—For "tomb" read "town."

Page 157, note 1 .- Add: "Indian Antiquary, Vol. XIV, pages 260 and 261."

Page 175, line 12.—Add to text:—An inscription of Paramardi Dêva, dated Samvat 1252, was found at Bagrari, close to Mahoba, and it has been published in Epigraphia Indica, Vol. I, pages 207—214; Journal, German Oriental Society, Vol. XL., pages 51—54. See, also, above Addendum to page 69, No. 4.

Page 185, 5 lines from bottom.—"The statement is contrary to that in the Report (pages 64—66). I visited and examined the masjid, and am persuaded there is not a pillar in situ in it, of any temple, and if they are from a temple (which is allowed) there is nothing to show it was Bauddha rather than Jaina or Hindû."—J. Burgess.

Page 211, note 2.—Add:—"Indian Antiquary, Vol. XVIII, pages 58 and 59. See also l.c. pages 129—143, where five grants of Jayachchhandra, dated Samvat 1232, 1233, and 1236, have been published."

Page 215, note 2.—Add:—"Indian Antiquary, Vol. XIV, page 139. The inscription records that in Samvat 1083, a Buddhist stupa and a dharmachakra were repaired, and a new gandhakuṭi was built, by the two brothers Sthirapâla and Vasantapâla, who were probably the sons of Mahipâla, king of Gauḍa."

Page 216, line 5.—Two of these inscriptions have been published in Corpus Inscriptionum Indicarum, Vol. III, pages 281, and 284—286, the latter being a record of king Prakatâditya.

Page 230, line 5.—After "Kumâragupta" insert "II." This important inscription has been published in Journal, Asiatic Society of Bengal, Vol. LVIII., pages 85—105, and gives the following vamédvali of nine generations of the early Gupta dynasty:—(1) Gupta, (2) Ghatotkacha, (3) Chandragupta I, (4) Samudragupta, (5) Chandragupta II, (6) Kumâragupta I, (7) Puragupta (younger brother of Skandagupta), (8) Narasimhagupta, (9) Kumâragupta II.

Page 257, line 8.—Add to text:—"Within three miles of the celebrated fortress of Bijaygarh are several rock shelters in which there are rudely drawn figures of men and animals, as rhinoceros, sambhar stag and hinds, sketched in outline in red paint. See Journal, Asiatic Society of Bengal, Vol. LII, Part II, pages 56—64."

XIII.—APPENDIX.

(1) LIST OF MONUMENTS AND BUILDINGS CLASSIFIED UNDER Ia.

NORTH-WESTERN PROVINCES.

		ayo.	1 uyo.
	I.—Mîrath Division.		III.—Kumâon Division—(concluded).
1.	Allgarh District—		2. Kumûon District—
	Kôl, or Kôîl: dargâh of Shâh Tlâh Bakhsh,	2	Nil.
	Do., tomb of Muhammad Gêsû		3. Tarûl District—
	Khân	2	Nil.
2.	Bulandshahr District—		
	Bulandshahr : dargah of Khwaja Lal Ali,	5	IV.—Âgrâ Division.
	Do., maqbara of Miyan Bahlol,		1. Âgrâ District—
	Khân Bahâdur	5	The second secon
3.	Dêrah Dûn District—		Agra : Baland Bagh, Ram Bagh, Zahra
	Kalsi: stone containing the 14 edicts of		Bagh, and Dehra Bagh 53
	Ašoka	7	Do., Chinî-kâ-Rauza and tomb of Îti- mâd-ad-daula 54
1981	Mirath District—		måd-ad-daula 54 Do., Fort of Akbar 55
-		10	Do., Motî Masjid and Dîwân-î-Âm56, 57
	Mîrath : Asoka pillar, now at Dehlî	.40	Do., Machchî Bhawân, Nagîna Masjid,
5.	Muzaffarnagar District -		and throne of Jahangir 58.
	Bhukarherî: old tomb of Bala Garîb	10	Do., Dîwân-î-Khâs, Saman Bûrj, and
	Nath	12	Khās Mahal 59
	Jhanjhana: masjid and tomb of Shah Abdul Razak	13	Do., Shish Mahal, Angari Bagh, and
0	Sahâranpûr District—	10	Jahangiri Mahal 60
.0.	Ambahta : tomb of Shah Abal Maali	14	Do., Jahangir's bath and Somnath
	Khizrabad: golden lat of Firaz Shah,		gates 61
	now at Dehli	16	Do., Tripolià, or market place 62
	T D D		Do., Bágh Khân Alam and Tâj Mahal, 63
	II.—ROHILKHAND DIVISION.		Do., Bågh Mahâbat Khân 64
1.	Badâon District—		Do., Baoli near Bagh Ladli Begam 68
	Nil.	- 1	Fathâbâd: Mubârak Manzîl 70
2.	Barell District—		Fathpur Sikri : Baland Darwaza, dargah
	Fatehganj West, or Bhitaura : large	00	and masjid of Salîm Chhishti 70
	obelisk of red sandstone	26	
	Râmnagar, or Ahichhattra: ruined Bud-	28	Do., tomb of Islâm Khân 71 Do., Panch Mahal 73
	dhist stûpa	20.	Sikandra: tomb of Akbar 76
3.	Bijnör District— Nil.		
A	Murâdâbâd District—		2. Farrukhâbûd District—
4.	Nil.		Nil.
ō.	Pilibhît District—		3. Îlâh District—
- 20	Nil.		Nil.
6.	Shahjahanpur District—	- 54	4. Iţâwah District—
	Nil.	85	Nil.
	III.—Kumhon Division.		
1.	Garhwâl District—		5. Mâînpurî District—
	Nil.	1	Nil.

	Page.			Page,
	IV.—Âgrâ Division—(concluded).		VI.—Allahabad Division—(concluded).	
6	Mathurâ District—	6.	Jaunpûr District—	
0.	Brindâban : temple of Gobind Dêva 98	100,000	Jaunpûr : Atala Masjid	180
	Sa'dâbâd : tahsîlî 110		Do., Jhanjhri Masjid	181
	V.—Jhansi Division.	1		182
			THE RESERVE AND ADDRESS OF THE PARTY OF THE	184
1.	Jalûun District—		Sikrārā: stone bridge over Sāī	185
20	Nil.	0	VII.—BANARAS DIVISION.	
2.	Jhânsî District— Îrichh : Jâmi Masjid 117		The state of the s	
		1.	Azamgarh District—	Takat (a)
0		111	Dabhaon : inscribed lât	188
0,	Lalitpûr District— Nil.		Ghosf: inscribed slab of A.H. 760	188
		2.	Bâliyâ District—	
	VI.—Allahâbâd Division.	1	Nil.	
1.	Allahâbâd District—	3.	Banâras District—	2000
	Allahâbâd: fort of Akbar and stone		Banâras: Buddhist Vihâra at Râjghât	Para I
	pillar of Asoka 127, 128		Sårnåth : stone stůpa (Dhamek)	
	Do., tomb of Shah Begam and	100	Do., ruined brick stupa (Chaukandi),	215
	house of Tambôli Begam 130	4.	Basti District—	
	Pabhôså: Buddhist cave in face of hill 143	1/2	Nil.	
2.	Bândâ District—	9.	Ghāzīpûr District—	one
	Kålanjar: ancient hill fort 149		Lâtiyâ : stone pillar	232
3,	Futhpur District—	0	Pahlâdpûr: inscribed monolith	234
5	Nil.	9.	Gôrakhpûr District—	200
4.	Kāṇhpûr District— Mūsānagar: Dēojāni tank 170	7	Bhågalpûr : inscribed låt	239
		400	Mirzápûr District—	252
			Ahraura: inscribed pillar near Belkhara Chunar: hill-fort	oro
ð.	Hamirpûr District— Nil.		TT 10 A / 10 T 1 T 1	261
			Hallya: inscribed slab	:201:
	AU	DH.		
	VIII.—LAKHNÂÛ DIVISION.		X,-Faizâbâd Division,	
1.	Bâra Bankî District—	1	Bahrâich District—	
	Nil.	200		
2.	Lakhnûû District—	2.	Nil. Faizābūd District—	
	Lakhnau: tomb of Sa'adat Alf Khan,	Α,		000
	Murshid Zadi, Muhammad		Akbarpûr: Akbar's stone bridge	300
	Alf Shâh, and Ghâzî-ad-din	3.	Gondâ District—	
	Haidar 266		Såhet-Måhet: colossal statue of Buddha,	
	Do., Residency 267		inscribed	310
3.	Unão District—		XI.—Râî Barelî Division.	
	Nil. IX.—Sitapûr Division.	1.	Pratâpgarh District—	
1	Hardôî District-	5	Bihâr: two small Buddhist stûpas in stone,	214
1	Nil.	2.		914
5	Kherî District—	1	Nil,	
200	Khairigarh: inscribed stone horse 285	3.	Sultânpûr District-	
3.	Sitûpûr District—		Aldemâû: two statues of Âdinâtha at	
200	Nil.		Patna	326
				0.00

APPENDIX.

(2) LIST OF MONUMENTS AND BUILDINGS CLASSIFIED UNDER 16.

NORTH-WESTERN PROVINCES.

	Page.			Page.
	I Mirath Division.		III.—Kumâon Division.	
1	Aligarh District—	1.	Garhicâl District—	
-	Kôl: well of Hâfiz Muhammad Afzal in		Mandhal: carved slabs, capitals, pillars,	
	compound of Jâmi Masjid 2		friezes, &c., of ancient temple,	46
2.	Bulandshahr District—		Śrînagar : palace of King Ajayapâla	46
~	Bulandshahr: well adjoining the tomb of	2.		
	Khwaja Lal Barani 5		Champavat : inscribed pillar in compound	
	Shikarpar: Barakhambha 7		of temple of Balésvar	48
Q	Dêrah Dûn District—	-	Do., inscribed pillar in compound	
٥.	Nil.		of temple of Mahârudra at	
A.	Mirath District—		Râigâon	49
4.	Bêgamâbâd : :nasjid of Nawâb Zafar Alî 9	3.	Tarâî District—	
	Garhmuktêsar: ancient fort, repaired by		Nil.	
	Marâthas 9		IV.—Âgra Division.	
	Hapar: baoli of Ashar Khan, near Jasrap-	1	A CONTRACTOR OF THE CONTRACTOR	
	nagar Asharpur 10		Agrā District—	63
	Muzaffarnagar District—	2	Âgrā : Sahēliān-kā-gumbaz	
а,	Nil.		Do., Takht Pahlwan and tomb of Firaz	0.4
0	Sahâranpur District—		Khân	no.
6.	Nil.		Do., Chhattri Râjâ Jaswant Singh	00
			Do., tomb of Sådik Khân	
	II.—ROHILKHAND DIVISION.		Do., supposed tomb of Salabat Khan	68
1.			Do., stone horse on Sikandra road	68
	Badaon : Shams-f-Idgah 20	811	Do., supposed tomb of İtibar Khan	-2273
-	Do., tomb of Chimni Khân 22	3	Do., Guru-kû-Tîl	
	Do., another tomb, called Chaukon 22		Fathabad: sarai and tank built by	
	Do., tomb of Sultan Ala-ad-din Alam		Aurangzîb	77.1
	Shâh and of his wife 22		Faṭhpûr Sikrî : Jahângîrî Mahal Do., Bîrbal's house	70
	Do., tomb of Dåolat Khân 22		7.00	700
	Do., tomb of Shâhzâdâ Fath Khân 23		Do., Mariâm's koṭhî Do., Khâs Mahal	MO
2.	Bareli District—			
	Bareli: tomb of Hâfiz-al-Mulk Rahmat			
	Khân 25		1.71	- MO
	Fatehganj West, or Bhitaura: tombs of			NO.
	Najib and Baland		7/77	70
	Ķhān, Rohillas 26			Pro
	Râmnagar : stone figures of Buddha 27			70
	Do., inscribed stone of the Gupta			23
	period at Dilwari 29	'	Do., Kâshmîr Sarâi Fîrûzâbâd: tomb of Shâh Sûfî near Sûfîpûr,	
	Do., inscribed bas-relief of two		Îtimâdpûr: building in the Bûrhiâ-kâ-	The Colonia
	lions 29		talâo	PV 4
3.	Bijnör District—			III PE
	Nil.		Jajão : grand royal saráî Kherâ : sepulchral cairns	-
4.			Sikandrâ : bâradarî of Sikandar Lodî	
	Nil.	0	Farrukhâbâd District—	
5.		25.		78
	Nil.	0	Fathgarh: fort	
6.	Tarabas Andrews (Andrews and Andrews and A	3,	Nil.	
	Nil.		21115	

		Page.			Page.
	IV AGRA Division - (concluded).		1000	VI.—Allahâbâd Division.	
4.	Itâwah District—		1	Allahâbâd District—	1616
	Chakarnagar : magnificent well	90			130
5.	Måinpuri District—	L.U	-	Bîthă: octagonal cupola in middle of	79.00
	Râprî : Îdgâh of Malik Kâfûr	95		Jamnâ	Contract I
6.	Mathurâ District—			Do., statue of Chandika Maya	
	Brindâban : temple of Madan Mohan	98			135
	Do., temple of Gopinath	99	1	Garhwa: pillars and architraves of Gupta	-
	Do., temple of Jagal Kishôr	99		period	136
	Do., temple of Rådhå Ballabh	99		Do., colossal statues of Brahma,	2000
	Chhâtâ : large fort-like sarâî	100		Vishnu, and Siva	
	Gaņêsvara : umbrella of a stûpa	100		Do., small temple containing colossal	
	Gobardhan: temple of Haridêva	101		figure of Sûrya	
	Mahâban : Assî Khambhâ	103	9	Do., mediæval temple inside fort	
	Mathurâ : Śiva Tâl	107	3	Ginja Hill: drawings of men and animals	
	Do., Jamnå Bågh	108		on hill	-
	Môrâ : old well with a large inscribed slab,	108		Katka : sculptured obelisk	
	Noh Jhil: dargah of Makhdum Sahib	179327		Kohnrår: old båoli	
	Shâh Hasan Ghorî	109		Kosâm Inâm : inscribed monolith	141
	Sahpāû: satî monument	110		Båndå District—	340
	Tumaulå: life-size statue of Buddha	111		Ansûyâjî : inscribed basalt rock	
	V.—Juansi Division.			Barhå Kotrå : mediæval temple	
			1	Dadhwâmânpûr-Garrampûr : Chandella	
1.	Jalâun District—			temple	
	Kålpî: tombs of Madår Såhib, Ghafûr			Gonda: two Chandella temples	
	Zanjanî, Chôr Bîbî, Bahâdur			Gulrampar: Bilhariya Math	
		113	3	Kâlanjar: Sîtâkund, Sîtâsêj, Pâtâl Gangâ	
2.	Jhansî District—	10/2/20		and Påndukund	
	Barûâ Sâgar : old Bundela castle	114		Do., great lingam temple of Nîla-	
	Do., small Chandella temple	115		kantha	
	Do., temple-tower of the ninth			Lauri: large stone elephant, inscribed	
	century near Phaterâ			Mâû: two-storeyed priests' house at Pûra,	
	Bhander : caves and rock-cut tanks			Råmnagar: Chandella temple and priests	
	Do., Chandella temple at Bharauli	115		house	156
	Gehrahő; old Chandella temple	116	1 - 1	Rasin: sati pillars and temple of Chandi	
	Gûrsarâî: bâradarî near Râî Tâl	117	0	Mahêsvarî	156
	Kishnî Khûrd : Chandella temple	117	0,	Fathpur District—	202
	Måå: temple of Kedåranåtha	119		Bahûâ: brick temple of Kakôra Bâbâ	158
3.	Lalitpûr District—			Bindki: brick temple of tenth century at	
	Bânpûr Khûs ; naudvâri	119		Tinduli	. 159
	Dêogarh : Jain temples inside the fort	120		Hathgâon : Jaychandî Masjid	
	Do., Gupta temple on the plain below	7500		Do., stone pavilion of Jahangir's	
	the fort	120		time	. 161
	Důdůhî: great Jain temple	122	4.	Künhpür District—	
	Do., temple of Brahma	122		Bhîtargâon : great brick temple, called	
	Jhaloni: inscribed slab	123		Devâl	
	Madanpûr : five Jain temples and one tem-	100		Do., pretty little brick temple a	
	ple of Mahâdêva	123		Parâulî	
	Sîrônî Khurd : torana near Jain temple	125		Do., two small brick temples at	
	Tal Bahat: Maratha fort	125	8.0	Râr	. 167

		Page.	1		Page.
	VIALLAHABAD DIVISION-(concluded)).		VII.—Banaras Division—(concluded)	
4	. Känhpür District—(concluded).		3.	Banâras District—	
	Bhîtargâon : large brick temple at Bedâ-			Banâras: observatory of Râjâ Mânasimha,	198
	Bedaunå	167		Do., remains of a Buddhist chaitya	200
	Do., brick temple at Kanchlîpûr,	168		near Bakarîyâ Kund	201
	Do., two brick temples at Sarhâr-		1	Do., Buddhist temple, near Bakari-	
	Amauli	168		ya Kund	202
	Bilhaur: inscribed well at Subhanpar	168		Do., remains of a Buddhist chaitya	
	Mûsânagar : the Mukhadêvî temple	170	Name of the last	near Râjghât	204
5.	Hamîrpûr District —			Do., two small structures near Mîrâ	
	Dinâî : large lingam temple	170		Såhib's dargåh	205
	Do., Jain temple	171		Do., Sonâ-kâ-talâo	209
	Jalalpur: two images, inscribed, at Punian,	172		Do., Nâga Kûpa	211
	Kulpahar: two granite temples at Mo-			Naubatpûr: masonry well	212
	hâri	173		Pindrah : inscribed slab at Asla	213
	Do., diminutive plain Chandella			Sårnåth: excavated chamber near tower	
	temples at Karerâ	173		Dhamek	215
	Makarbai: Jain temple and tank of Chan-		4.	Bastî District—	
	della period	174		Nil.	
	Do., flat-roofed Jain temple at		5.	Ghâzîpûr District—	
		174		Bhîtarî : bridge over Gangî	229
	Mahobà: Kakra Math	175		Do., inscribed lât	229
	Do., palace of Parmâl	176		Nārāyanpūr: ancient sculptures	233
	Do., low-roofed square temple at	300		Sa'îdpûr: old statues representing Varâha	
	Sijhāri	177		Avatāra and Krishņa with	
	Do., flat-roofed temple at Urwara	177	7.0	Gåpîs	235
	Do., large Chandella temple at Râhi-	ā	6.	Gôrakhpûr District—	
	THE CONTRACTOR OF THE CONTRACT	177	10	Kahâon : inscribed monolith	243
	Råth: two bårakhambhås	177		Kasîû: colossal Nirvâņa statue of Bud-	1016
5.	Jaunpûr District—	700			245
	Jalalpur : old bridge over Sat				246
	Jaunpar: masjid of Ibrahim Naib Barbak,			Khakhundû: ancient Brâhmanical and	040
	Do., masjid Khâlis Mukhlis	181	12	Jain statues	248
	Do., Lâl Darwâza Masjid Zufarâbâd : masjid of Shaikh Barhan	185		Motirâm-kâ-Addâ : large bâolî	249 250
		186	~	Rudrapûr: statue of Vishņu Mîrzâpûr District—	200
	2000 NO 10 100	100	4.	Ahraurå: stone obelisks at Hetunpår	253
	VII,—BANERAS DIVISION.			791 4414 1 17 7	255
	Azamgarh District—			Do., stone obelisks	256
	Nil.	-		Chunar : Brahmanical sculptures in south-	200
	Bâliyâ District—			west corner of fort	258
	Nil.			Do., inscribed rock near Durga Kund,	260
		14.00		Dog mounded to a near Darga Analy,	~00
		AU	DH.		
	VIII.—LAKHNÂÛ DIVISION.			VIII.—Lakhnåû Division—(concluded).	
1)	Bâra Bankî District—		1000	Unãô District—	
	Nil.			Bångarmåå: tombs of Sa'id Muzaffar-ad-	
	Lakhnûû District—			Alexandron State of the Control of t	269
	Lakhnaû: Asaf-ad-daulah's bridge over	20000		Harha: large dwelling-house at Badarqa	22.65
	Gûmtî	266		Harbans	272

	Page.	1		Page.
	IX.—Sitapur Division,		X.—FAIZÂBÂD DIVISION—(concluded).	
1.	Hardôî District—	2.	Faizabad District—(concluded).	
T	Nil.		Faizābād: stuccoed brick tomb of Bahū	
2.	100 x 100 x		Rogam	301
	Nil.	3.	Gonda District-	901
3.	Sîtûpûr District—	100	Nil.	
	Manûa: two brick temples of tenth cen-		XI.—Rât BARELT DIVISION.	
	tury at Nasîrâbâd 289	1.	Pratûpgarh District—	
	200		Mâṇikpûr: Chihal Satûn	318
22	X.—Faizābād Division,	2.	Rat Barelt District—	910
1.	Bahrâlch District—		Dâlmâû: dargâh on Jaychand mound	322
6	Nil.	3.	Sultanpar District—	044
2.			Musåfirkhåna: ancient brick temples at	
	Ajudhya: old masonry bridge over Tilahî		Bhāgūpūr	328
	Nala 298	1.	Do., statue of Sûrya at Pûlî	328
	The second second second second second			0.20
	(3) LIST OF MONUMENTS AND BU	IIL	DINGS CLASSIFIED UNDER IIa	
	NORTH-WESTE			9
			EOVINCES.	
	I.—Mirath Division.	1 3	TT D	Page.
1.	Aligarh District—	1	II.—ROHILKHAND DIVISION—(concluded)).
	Kôl: fort 2	1840	Baddon District—(concluded).	
2.	Bulandshahr District—		Badaon; dargah of Imad-al-mulk and	
	Dankaur: ancient temple and masonry	0	takiâ of Minâ Shâh Barelî District—	23
	tank 6	4.		
3.	Dêrah Dûn District—	1	Aonla: Begam's masjid	24
	Dêrah: three reservoirs attached to Sikh	2	Bareli: tomb of Shahdana	26
	temple 7	0.	Bijnor District—	
1.	Mirath District—		Chândpûr : fort-like tahsîlî	30
	Parichhatgarh: ancient brick fort 12		Môrdhaj: Shigrî mound	32
5.	Muzaffarnagar District—		Nagînă: old Pathân fort, now used as	
	Jalalabad: ancient well in fort of Ghaus-	4	tahsili	33
	garh 13		Amrohâ : great bâolî	
	Majhêrâ : four tombs and an octagonal	5.	Pilibhit District—	34
	well 13	-	Nil.	
	Sambalhêrâ: tomb of Hazrat Ibn Salâr, 14	6.	Shahjahanpar District—	
	Thâna Bhawân: two masjids and one		Nil.	
	maqbara 14		III.—Kumâon Division.	
•	Saharanpur District—	1.	Garhical District—	
	Rurkî: well called Haqîmwallâ at Jwâla-	-	Nil.	
	pûr 18	2.	Kumâon District	
	Sahāranpūr: old Robilla fort 18		Nil.	
	II.—ROHILKHAND DIVISION.	3.	Tarât District—	
	Badâon District—	E(8)	Nil.	
	Badáon : square tomb near tomb of Shâh-		IV.—ÂGRÎ DIVISION.	
	zêdâ Fath Khân 23	1.	Agra District—	
	Do., tomb of Makhdûmah Jahân 23		Nil.	
	Do., tomb of one of the sons of Ala-	2.	Farrukhabad District	
	ad-dîn 23		Nil.	

	70	60.09	
	IV.—Âgra Division—(concluded).	6.	Page.
3	. İtah District—		VI.—ALLAHABAD DIVISION—(concluded).
	Sorôn: temples of Sîtâ Râmjî and Varâhajî, 8	9	6. Jaunpûr District—
4	. Itawah District—		Nil.
	Nil.	-	VII.—Banaras Division.
5.	Mainpuri District—		1. Azamgarh District—
	Nil.		Nil.
6.	Mathurâ District—	- 13	2. Bâliyâ District—
	Nil.		Nil.
	V.—Juansi Division.	100	3. Banâras District—
1.	Jalaun District—		Banâras : Bakarîyâ Kuṇḍ 199
	Nil.		Do., Buddhist ruins at Tiliya Nala 205
2.	Jhânsî District—	14	4. Basti District —
	Nil.		Khirnîpûr : ancient tank 224
3.	Lalitpûr District—		Râmpûr: ancient tanks and ruined brick
	Nil.		stûpa 225
	VI.—ALLAHÂBÂD DIVISION.	1	5. Gházîpûr District—
1.	Allahâbâd District—		Bhîtarî : old sculptures in small brick en-
	Nil.		closure 228
2.	Bândâ District—		Dhânapûr: small flat-roofed structure at
	Nil.		Hingotâr 230
3.	Fathpûr District—		Ghâzîpûr: large garden, tank and tomb of
	Nil.		Nawâb Shaikh Abdullâ 231
4.	Kânhpûr District—	6	. Gôrakhpûr District—
	Bhîtargâon : brick temple at Khurdâ 167		Nil.
5.	Hamîrpûr District—		. Mirzâpûr District—
	Akonå: four Chandella temples and small		Bhadohî : old Śaiva temple at Samradh 255
	masonry tank 170)	Bijaygarh : hill fort 256
	A	UDH.	
	VIII,-LAKHNÂÛ DIVISION.	-	
1.	Bâra Bankî District—		X.—FAIZĀBĀD DIVISION—(concluded),
	Nil.	2.	. Faizābād District—
2.	Lakhnûû District-		Faizābād: interesting buildings of Shujā-
	Nil.		ad-daulah's time 301
3.	Unão District—	1	Mangalsi: handsome gateway at Dhau-
	Nil.		rahrâ 301
	IX.—Sîtâpûr Division.		Surharpûr: masenry bridge over Majhôî, 302
1.	Hardôî District—	3,	Gondâ District—
	Mallawan: fine well 280		Nil.
	Såndî: bas-relief representing a chaitya-		
	like structure 282		XI.—Răi Bareli Division.
8	Shahabad: maqbara of Nawab Dilêr Khan, 283	1.	
	Kheri District—		Nd.
	Nil.	2.	
1.	Sttåpür District—		Rai Bareli : crenelated battlements and
	Misrikh: large masonry tank at Machh-		gateways 324
	rehtā 290		Do., ancient baoli inside fort 324
	X.—Faizābād Division.	8,	Sultanpur District
	Bahraich District—	1	Aldeman . Musulman tombe 905
	Nil.		Dhopâp : noted lingam at Nânâmâû 327
	EMAN	1	T. T

(4) LIST OF MONUMENTS AND BUILDINGS CLASSIFIED UNDER 116.

NORTH-WESTERN PROVINCES.

		Page.			Page.
	I.—Mîrațh Division.			I Mirath Division-(concluded)	
1.	Aligarh District—		4.	Mirath District—(concluded).	
	Jalalî : masjids	1		Mîrath: Hindû temples on banks of Sîti	-
	Kôl: Jâmi Masjid of Nawâb Sâbit Khân,	1			11
	Do., Moti Masjid	2		The TANKS OF MAIN AND AND	11
	Do., masjid of Ibrâhîm Sikandar Shâh,	2		70	12
	Do., dargah of Shah Jamal and idgah,	2		Sardhanâ: Hindû temples	. 12
	Pilkhâna: small masjid	3	5.	Muzaffarnagar District—	
2.	Bulandshahr District—		100	The shand a gament of T. A. CAL I	. 13
	Ahar : Jami Masjid	4		Kâirâna: masjids and dargâhs	
	Bulandshahr: îdgâh and Jâmi Masjid	5		Khātauli : Jain temples and sarāi	-
	Do., masjid of the Moghals,			Mornah : masjid of Bibi Jhabba	
	masjid above the Kôt,			Sambalhêrâ : masjid of Sa'îd Mâkhan	211
	and Gumbaz-1-Qâziân,			Thâna Bhawân: old temple of Bhavânî	
	dargûh of Makhdûm			devî	10
	Shâh	5	6.	22-24 C24 (25-11) (A. 11)	
	Dankaur: masjid inside fort Karanbâs: temple of Sîtalâdevî	6		A-1-140	
	THE RESERVE OF THE PARTY OF THE	6		Ambahtå: masjids and tomb	
	Kasna: tomb of 1kram Khan Kharja: Jain temple and tomb of Makh-	ů,		Bhagwanpar: mausoleum at Sakrauda	. 14
	dûm Sâhib	6		Dêoband : Hindû temples, satû pillars, and	
	Shikarpur: masjid of Imam Sa'dat			masjids Gångôh : maqbaras and masjids	
	Khān	7		Hardwar: old Hinda temples and Brah	
3.	Dêrah Dûn District—			The state of the s	
	Dêrah: Sikh temple, or Gurudvåra	7	-	Jhabarhêrâ: masjid and well	.15, 16
	Madha : old Hinda temples	8		Kankhal: old temple of Dakshesvara and	10
	Do., old temple of Mahadêva at Ban-			group of small temples	
	kaulî	8		Manglaur : masjid of Shah Wilayat	
	Do., old temple of Mahasu at Hanôl,	8		Nakûr : Jain temple	-
4.	Mirath District—			Râjûpûr : masjid	
	Ajrâra : Hindû temple	8		Râmpûr: Jain temple and dargâh of	
	Bagpat: Jain and Vaishnava temples,			Shaikh Ibrâhîm Pîr	1896
	masjids	9		Rûrki : mausoleum at Pîrân Kalhar	**
	Balênî : Hindû temple	9		Do., Jāmi Masjid at Jaurāsi	18
	Barnâwâ: dargâhs of Badr-ad-dîn Shâh			Sahāranpūr: four masjids	18
	and Shah Ala-ad-din, maq-			Sarsawa: tomb of Pir Mardana Shahid	18
	bara of Pîr Sarwâr	9		Sahansrå: temple of Sahansarå Thåkur	19
	Bêgamâbâd : Hindû temple	9		II.—ROHILKHAND DIVISION.	
	Garhmuktêsvar: Hindû temples, tomb of		1.	Badâon District—	
	Ganj Baksh, and Jâmi				
	Masjid	9		Alâpûr: Hindû temples and masjid	20
	Ghâzîâbâd : masjids and Hindû temple Hâpûr : Jâmi Masjid	10		Badaon: Jami Masjid and minor masjids, shrines and tombs	
	Hâpûr : Jâmi Masjid Khekârâ : Jain temple	10	×	Do., small tombs and Qabaristân	21, 22
	Lonî: dargâh and masjid at Behtâ			Shahd	
	Hājipār	10		Biggulf - market - 2 to 4 4 4	
	Mawâna : old Hindû temple	10		Kakrala . Hinda tamala t	
	Do., dargâhs at Bâîsumâ	10		Sahaswân: Hindû temples and masjids	23
	THE RESERVE THE PROPERTY OF THE PARTY OF THE			The man manifes	41

	Pag	war i	n.	200
	II.—Rohilkhand Division—(continued).	10.	II.—ROHILKHAND DIVISION—(concluded).	ige,
1.	Badaon District-(concluded).		5. Pilibhit District—	
	Ujhani: masjids, îmambara, Qadam-î-	-1	70	
		24	The state of the s	no
2.	Bareli District—		ples	38
170	Aonlà: masjids and mausoleums24,	25	Dêorîyâ : plain brick temples	39
		25	Pilibhît : masjids	40
	+++ (7 / 420 H 200 T 7 7)	26	6. Shâhjahânpûr District—	98
	Ramnagar: Buddhist statues worshipped	20	Khudaganj: masjid and Hinda temples	42
		27	Mati: statue of Kali in modern temple	42
		61	Shâhjahânpûr: masjids and tombs	43
		27	Tilhår: brick fort and residence	43
	The state of the s	61	III.—Kumãon Division.	
	Do., modern temple of Parsva-	20	The section of the se	
		29	1. Garhwâl District—	
		29	Badrînâth: temple of Badarinâtha and	
		29	Taptakuṇḍ	44
		59	Dêwalgarh : old temple	44
	Shahi: Hindu temple S	29	Gôpêsvar : old temple	44
3.	Bljnor District—		Joshîmath : Jyotirlingam and temples	45
	Bîjnôr : masjids and Hindû temples	30	Karnprayag : old temple	45
	Do., large bâolî at Ţuṇḍapura 8	30	Do., old temple at Simli	45
	Chândpûr: masjids, dargâh, and Hindû		Kedârnâth : Hindû temple	45
		30	Mandhal : old Hindû temple	45
	Jahanabad : tomb of Nawab Sa'id Muham-		Nandákinî: temple of Nandadêvî at	
		30	Satôl	46
	1100	31		46
	Mandawar: Jami Masjid and dargah of			46
	Hidâyat Shâh31, 3	12		10
		33	Srînagar: temple of Kamalêsvar and	10
	Najibâbâd; entrance gateway of old	"		46
		33	The state of the s	46
		33	2. Kumûon District—	-
		34		46
		230		47
	TO CONTRACT OF THE PARTY OF THE	34		47
4.	Murâdâbâd District—			47
	Amrohâ: masjids, dargâhs, karbalâs,			47
	Hindû temples and dharm-		Barmdêo: shrine of Pârvatî at Pûrna-	
	salas 34, 3	5	giri	47
	CONTROL OF THE PARTY OF THE PAR	5	Bhâinskhêt: old temple of Sûrya	47
	The state of the s	5	Bhikîyâ : temple of Naulêsvar	47
	Bilarî: Hindû temples, masjids, and dar-		Bhîm Tâl : Hindû temple	47
	gâh 3	5	Champûvat : Hindû temples	48
	Håsanpûr: masjids and Hindû temples 3	6		49
	Muradabad: Jami Masjid, tombs and			49
		7	Walter Control of the	49
		7		49
	Sambhal: Jami Masjid, tirthas and sacred			50
	wells37, 3	8	The A. T. P. COLA . COLAR	50
	Do., old Hindû temple at Chandâyan, 3		705 - 4:1 0 + 1	50
	Ujhāri: masjids, dargāh, and Hindû temple, 3	E10		
	Clause, muslims, and gam, and granter temple, o	9	Sûî Bisûng : temple of Balêsvar	50

Saiva temples	
3. Tarât District— Kâsipār: temple of Jvâlâdêvî and other Saiva temples 51 IV.—Âorâ Division. 1. Âgrâ District— Âgrâ: Battîs Khambhâ 53 Do., Jâmi Masjid 62 Do., dargâh of Jalâl-ad-dîn Bukhâri 63 Do., Faṭhpārî Masjid 63 Do., masjid in Tâj compound 64 Do., dargâh of Ahmad Bukhâri 64 Do., Makhnî-kâ-gumbaz 65 Do., îdgâh 65 Sakît: masjids and dargâh of Misrî Shahîd 8	
Saiva temples 51 IV.—Âgrâ Division. 1. Âgrâ District— Âgrâ: Battîs Khambhâ 53 Do., Jâmi Masjid 62 Do., dargâh of Jalâl-ad-dîn Bukhâri 63 Do., Faṭhpūrī Masjid 63 Do., masjid in Tâj compound 64 Do., dargâh of Ahmad Bukhâri 64 Do., Makhnî-kâ-gumbaz 65 Do., îdgâh 65 Sakît: masjids and dargâh of Misrî Do., îdgâh 65 Shahîd 8	
Saiva temples	84
IV.—ÂGRĂ DIVISION. 1. Âgrâ District— Âgrâ: Battîs Khambhâ	
1. Âgrâ District— Âgrâ : Battîs Khambhâ 53 Do., Jâmi Masjid 62 Do., dargâh of Jalâl-ad-dîn Bukhâri 63 Do., Faṭhpūrî Masjid 63 Do., masjid in Tâj compound 64 Do., dargâh of Ahmad Bukhâri 64 Do., Makhnî-kâ-gumbaz 65 Do., îdgâh 65 Shahîd 8	85
Âgrâ: Battîs Khambhâ 53 Hazrat Pîr Zarî 8 Do., Jâmi Masjid 62 Kâsganj: masjid 8 Do., dargâh of Jalâl-ad-dîn Bukhâri 63 Mârhara: tomb of Sa'îd Shâh Barkat- 1	00
Do., Jâmi Masjid 62 Do., dargâh of Jalâl-ad-dîn Bukhâri 63 Do., Faṭhpūrī Masjid 63 Do., masjid in Tâj compound 64 Do., dargâh of Ahmad Bukhâri 64 Do., Makhnî-kâ-gumbaz 65 Do., îdgâh 65 Shahîd 8	86
Do., dargâh of Jalâl-ad-dîn Bukhâri 63 Do., Faṭhpūrī Masjid 63 Do., masjid in Tâj compound 64 Do., dargâh of Ahmad Bukhâri 64 Do., Makhnî-kâ-gumbaz 65 Do., îdgâh 65 Sakît: masjids and dargâh of Misrî Shahîd 8	87
Do., Faṭhpūrī Masjid 63 Do., masjid in Tāj compound 64 Do., dargāh of Ahmad Bukhāri 64 Do., Makhnī-kā-gumbaz 65 Do., fdgāh 65 Sakīt: masjids and dargāh of Misrī Shahīd 8	0.4
Do., masjid in Tâj compound 64 Do., dargâh of Ahmad Bukhâri 64 Do., Makhnî-kâ-gumbaz 65 Do., îdgâh 65 Sakît: masjids and dargâh of Misrî Shahîd 8	OH
Do., dargâh of Ahmad Bukhâri 64 Sahâwar : dargâh of Faqîr Tâj-ad-dîn 8 Do., Makhnî-kâ-gumbaz 65 Sakît : masjids and dargâh of Misrî Do., îdgâh 65 Shahîd 8	87
Do., Makhnî-kâ-gumbaz 65 Sakît: masjids and dargâh of Misrî Do., îdgâh 65 Shahîd 8	87
Do., îdgâh 65 Shahîd 8	88
The state of the s	lon.
	88
Do., dargâh of Shâh Wilâyat 65 Sarâî Aghat : sarâî and masjid 8	88
Do., Akbarî Masjid 66 Sôron : temple of Sîtâ Râmjî and tomb	
	88
Do., masjid of Mata'mid Khân 66 4. Ilâwah District—	
Do., masjid Makhan Nishân 67 Aurâîyâ: masjids, Hindû temples and	
	90
Batêsar: temples of Mahâdêva and Pârvatî 69 Do., masjid at Ammâ Shaganpûr 9	90
	90
Bîrthala: temple of Mahâdêva Lîla Vilâsa, 69 Do., Hindû temples and bâradarî 9	91
Fathpur Sikri: small masjid in garden 73 Harchandpur: stone representing the	
Kinninghad + magnet dangaha and Hinda	91
formalism Wal TRANSA II I I I I I I I I I I I I I I I I I	92
Do., tembs of Fîrûz Khwâja and Phaphûnd: Hindû temples, masjids and	~
Amore Box Khilin Wil	92
Titue 1 And a market and a mark	92
Thomas a chains of Paka Gualla 24 Sunt Tuli 22 2	92
Jajão : masjid 75 5. Mainpurt District-	9,0
Kanarani tomb of Shailsh Amkan 75 Hatha Cantle A. 11 III 15	93
771.4.10	93
Pindhat Hinda temples 70 Whench to 1 6 25 244	
Samel : Hinda tample and tank 70 W. A. 10	94
9 Farrickhâhâd Diviriet Malannal - Li III 34	94
Formybhihad Hinda temples and medide 77	0.4
Kâmpil: temple of Râmêsvara Mahâdêva Naushahr: tombs of Hâjî Abû Sa'îd and	94
and Jain temples 78 Nell-W. VIA	
Kanani Ajavnal's tample 70 Pondhet H' 14 .	94
Do Jami Masiid and tombe of Bala Dane.	95
The state of the s	96
Habita Habita	96
Muhammad Kanauji 80 Shikôhâbâd : masjids and Hindû temples, 9 Do., tomb of Sa'îd Shaikh Makhdûm 6. Mathurâ District—	97
The state of the s	
the same and the s	97
minor tombs, 81 Barsana: Hindû temples and tanks 9	97
Makranduagar: temple of Siva 81 Bathan: tank with stone ghât	98
Raushanîbâd : masjid 83 Do., Hindû temple	98
Bisawar: Hindû temples and Musalman	
Lakutgant masud	98

	Page.	1		Page
	IV ÂGRÎ DIVISION-(concluded).		V JHANST DIVISION-(concluded).	- 190
6.	Mathura District—(concluded).	2.		
559	Brindîban : Hindû temples 100		Bhander : masjid of Aurangzib's time	115
	Chaumuhā: temple of Bihārijî and sacred		Gürsarâl: fort	
	ponds 100		Îrichh: Musalman tombs and masjids	116
	Chhâtâ : old Hindû temple in sarâî 100		Do., mud fort at Pûnch	
	Do., temple of Yasodha-Nandana at		Jhansi: Hindu temples on the Lakshmi	
	Nandgåon 100			118
	Gobardhan: tank and cenotaphs 100, 101		Mâû: Hindû temples and Jain temple	
	Gôkul : Hindû temples 101		Raṇipūr : Jain temple	
	Hathana: temple of Lakshmi-Narayana, 101	3.	Lalitpûr District—	7.00
	Jâwara : sacred grove of Chandraban and	1200	Bânpûr Khâs: Jain temples	119
	dargâh 101		Lalitpûr: masjid of the time of Fîrûz	
	Khâîrâ: Hindû temples and tanks 102			123
	Kôsî: Hindû temples, tanks, masjids and		Do., Hindû and Jain temples	
	tombs 102		Madanpûr: small Hindû temple at Mar-	1.00
	Do., well at Kôtwân 102			124
	Kôta : large kund with masonry cause-		Saurai: Jain and Hindû temples of the	
	way 102		Chandella period	
	Kursandå: Hindû temples 102		Sîrônî Khurd : Jain temples 124	
	Lohaban: temple of Gôpînâtha 103			125
	Mahaban: Hinda temples and tomb of		Tal Bahat: sati monuments and tomb of	
	Sa'îd Yahya 103, 104		Pîr Tâj Bâj	126
	Måt: Hindû temples and masjids 104		VI.—ALLAHABAD DIVISION,	-
	Mathura: Hindû temples and masjids 104-108	1.	Allahâbâd District—	
	Nandgaon: temple of Nand Raiji and	82	Allahabad: Hinda temple inside fort	127
	sacred lake 109		Do., Hinda temples and satt	
	Rådhåkund : Hindû temples and dharm-		pillars	130
	sûlas 110		Do., colossal figure of Hanuman	
	Rål: cenotaphs (chhattris) 110		Do., Musalman tombs in the	
	Sa'dâbâd: Hindû temples, masjids and		burial-ground at Kydganj,	131
	tomb 110		Araîl: Hindû temples	
	Sahar: old buildings with carved stone		Do., temple of Somësvara Mahadêva at	
	gateways 110		Dêorakh	131
	Sahpaa: Jain temple of Neminatha 110		Bâra: temple of Bhairava	131
	Shahpar: Hinda temple and masjids 110		Bitha: inscribed figure of Buddha, dated	
	Shergarh: Hindû temples, Jain temple		Gupta Samvat 126	133
	and masjids 111		Châtl: sandstone masjids	134
	Surîr: Hindû temples 111		Jhûsî: Hindû temples and masjid	138
			Do., inscribed Musalman tomb at Fir-	
	V.—Juansi Division.		ûzpûr	138
	Jalaun District—		Karra: masjids, tombs, and Hinda tem-	
-	Georgia Describe			, 139
	Kâlpî: Musalmân tombs and masjids 113		Do., masjid and tombs at Daranagar,	139
	Do., Hindû temple at Akbarpûr 114		Do., rauza of Qutb Alam at Kach	
	Kûnch: bârakhambhâs said to be Musal-		Darya Bard	139
	mån tombs 114		Do., rauza of Faqîr Hâshim at Ismâîl-	
	Do., tomb of Mahmûd Shâh Ghâzî in		pår	139
	citadel 114		Do., masjid of Allah Dad Khan at	
	Orâî: tomb of Pîr Sarwânî 114		Shâhzûdpûr	139

	Page.		Page.	
	VIALLAHABAD DIVISION -(continued).		VI ALLAHABAD DIVISION-(continued).	
1.	Allahábád District—(concluded).	3.	Fathpur District—(concluded).	
	Kosâm Inâm: temple of Pârasvanâtha 141		Garhî Jâr: mausoleum at Dalêl Kherâ 160	
	Kotwa: old Hinda temple at Kankra 143		Jûfarganj : masjid of Nawâb Bâkir Alî	
	Lachhagir: masjid and tomb at Damgarh, 143		Khan 162	
	Månda : old stone fort 143		Khajuhû: Hindû temples, masjids, bûra-	
	Pabhôsa: temple of Padmaprabhanatha	-	darîs, sarûî, tank and garden, 162	
	and Hindû shrine 144		Korå: båradarî, masjids and båolî 163	
	Sikandrå: dargåh of Sa'îd Sâlâr Mas'ûd		Malwa: masjid, imambara, and karbala 164	
	Ghâzî at Mâlîpûr 144 Singraur : masjid and tomb of Muham-		Naubasta : Hindû temples 164	
	The state of the s		Râmpûr Thariâon : Hindû temple 164 Ren : large stone lingam 165	
	Links when the same and the sam	987		
2.		*	Kanhpur District— Akbarpur Birbal; ancient temple of	
0	Atrahat : Hindû temples 145		Daniel and a second	
	Augūsī: Jūmi Masjid 145		Rādhā-Krishna 165 Bāzîdpār : masjid and tomb of Fîrûz	
	Bândă: Hindâ and Jain temples, and		Sháh's time 165	
	masjids 146		Bilhaur: masjid of Aurangzîb's time 168	
	Bilgåon: Hindå temples 147 Bisaurå Buzurg: Hindå temples and		Do., masjid Gemti at Pihânî 168	
v	masjid 147		Bithûr: Hindû temples and ghâts 168	
	Chitrakût : Hindû temples 147		Kanhpar: Hinda temples and masjids 168	
	Do., Hinda temples and bathing		Charali: old temple of Jvålamukhi Dêvî 168	
	ghâts at Sîtâpûra 148		Derâpûr: masjids and masonry tank 168	
	Karwî: Hindû temples and masjids 154		Do., tomb of Sandal Shah at Bich-	
	Do., Hindû temples and masjids at		hiāpūr 168	
	Tarûhwan 154		Ghåtampår: old temple of Kudhå Dêvî 168 Jåjmåû: temples of Siddhêsvara and Sid-	
	Khandeh: Hindû temples 154		DLA TAA'A	
	Khaptihå: Hindû temples and masjid 154		Do., tomb of Makhdûm Shâh at	
	Majhgawân : Hindû temples 154		Bûnîdaûn	
	Narâyanî: Hindû temples 155		Khwaja Phûl : mausoleum of Itimâd Khân, 169	
	Pachnehî: Hindû temples and masjid 155 Pailânî Khûs: masjid of Himmat Bahû-		Makanpûr: shrine of Shâh Madâr and	
	dur Kâsim 155		masjids 169 170	
	Râsîn: temple of Ratannâtha and old		Mawar: tomb of Hazrat Mutahar and	
	Śivâla 156		masjid 170	
	Do., masjid of Aurangzib's time at	5.	Hamirpûr District—	
	· · Donâ 157) I i	Gaurahri : Hindû temple 171	
	Sihondâ: temple of Angulesvarî Dêvî 157		Jaitpûr: modern Hindû temples 171	
	Simaunî : masjid of Shâh Qulî Sultân 157		Jalálpûr: masjids and Hindû temples 172	
	Sindhan Kalan: Hindu temples and		Jhalokhar: temple of Devîjî Bhanyâ Rânî, 172 Kabrâîa: small temples of Bhavânî Dêvî, 173	
	masjids 157		Kharaila - ald III. JA	
3,	Fathpur District—	38	Kulpahar: Hindu temples, masjids and	
	Asnî: shrine of the Asvinî Kumâras 158		idosha	
	Do., group of modern Hindû temples 158		Do., old temple of Vishnu and Jain	
	Dêomâî: Hindû temples 159	1	temple at Sahêt Mahêt 173	
	Dhâtâ: temple of Pârvatî 159		Do., small Chandella temples at	
	Fathpûr: masjids and maqarbas 159, 160		Tell Pahari and Towah	
	Garhî Jâr : rauza of Bahâdur Khân 160		Makarbai : Chandella temple at Sakara 174	

	Pag	e.	Page.
	VI.—ALLAHABAD DIVISION—(concluded).		VII.—Banaras Division—(continued).
5.	Hamîrpûr District—(concluded).		3. Banâras District—(concluded).
	Mahoba: Hinda temples and masjids, 174-17	7	
	Maskarå: temple of Mahêsa 17	522	Banâras : Lât Bhairava, rauza, and battîs
	Panwari : dargahs of Bhai Khan and Pir		khambhā 206
	Haqîm 17	7	Do., Hindû temples and mas-
	Rath : Hindû temples, masjids and well 17	200	jids 207, 208, 210
6	Jaunpûr District—		Do., wells and kunds 211
380	Jaunpûr: minor masjids and tombs, 184, 18	5	Do., dargâhs and tomb of Lâl Khân, 212
	Machhlishahr: masjids and idgah 18	7.00	Basnî: Hindû temples and masjids 212
	Mariaha : masjid and idgah 18		Chandrautî : Jain temples 212
	Zafarâbâd: dargâhs of Fîrâz Shâh's time, 18	65.	Dândupûr : masjids 212
	VII.—Banâras Division.	100	Dumrî : masjid, satî temple, and dharm-
			sålå 212
A.	Azamgarh District—	-	Jålhûpûr: Hindû temples 212
	Azamgarh: stone sugarcane press 18	120	Kaithî: Hindû temples 212
	Chiraîyakôt: mausoleum of Hâtim Khân, 18		Naubatpûr: Hindû temple and masonry
	Dohrîghât: masjid of Jahân Khân 18	122	sarâî 212
	Kopā : masjid of Mîrzâ Âtâ Bêg 18		Pindrah: tomb of Mir Muhammad at
	Maharajganj: old temple of Bhairava 18	9	Aslâ 213
	Måhal: masjid of Humåyûn's time at		Råmnagar: brick fort and temple of
	Qasbah Nigûn 18		Vyāsa 213
	Maa Nathhanjan: tomb of Malik Tahir, 18	9	Sakaldîhâ: Hindû temples and masjids 213
	Muhammadâbâd Gohnā: tomb of Pîr		Do., temple of Kolésvara Nâtha at
	Kůshûnî 19	0	Chaturbhujpûr 213
	Do., masjid of Alamgir's		Sårnåth: tanks and temple of Pårsva-
	time at Ganjahra 19	0	nâtha 214
	Nizâmâbâd: tomb of Kalandar Shâh at	00	Sa'îdrâjâ : dargâh of Sa'îd Râjâ Ahmad 216
	Kalandarpûr 19	0	Tarî : Hindû temples, masjids and imâm-
	Sarai Mîr : dargah of Lal Khan and tomb		
	of Shah Alf 19	0	
2.	Bâliyâ District—		4. Bastî District—
	Bâliyâ : Hindû temples 19	1	Bakhirâ Dîh : great lake 217
	Chît Fîrûzpûr: Musalmân convent and		Bânsî : Hindû temple and masjid 217
	tombs 19	2	Barah Chhetra: kund and temple of
	Kharid: dargah of Rukn-ad-din Rukn		Varâha Avatâra 218
	Alam 19	8	Bastî: old castle 218
	Rasrå : large and small masjids 19	200	Bharf : old tank 223
	Sikandarpûr : Hindû temple 19	200	Katahla: small modern Hindû temples at
3.	Banâras District—		Sarayat 223
٥.	Bairant : small Hindû temples 195, 196		Maghar: rauza of Kabîr Dâs and tomb of
	Banâras : Hindû temples below and above	1	Qâzî Khalîl-ur-Rahmân 224
		2	Do., temple of Śiva at Kôpa 225
	The second secon	42	Tama : temple of Tamésvara Nåtha 226
			The state of the s
	Do., dargah of Fakhr-ad-dîn Alawî	- 12	5. Gházipúr District—
	and small masjid 200	S	Bahâdurganj : masjid and îdgâh 227
	Do., rauza and other small buildings, 201		Bhîtarî: imîmbâra and masjid 228
	Do., Musalmân cemetery 202		Ghâzîpûr : masjid, imâmbâra and tombs, 231
	Do., dargah of Mira Sahib 205	1	Sådiåbåd: tombs of Målik Mardån and
	Do., square enclosure called Makh-	1	Sådî 234
	dûm Sâhib 205		Sa'ldpûr: dargûhs 234, 235

	Page.			Page.
	VII.—Banaras Division—(continued).		VII.—Banaras Division—(concluded).	
6.	Gôrakhpûr District—	7.		
	Bânsgâon: Hindû temples and masjids 237		Agôrî Khâs : Saiva temples at Gothânî	252
	Barhaj: Śaiva temples, masjid and tomb, 237	3	Ahraura: tomb of Sa'id Ashraf Ali at	
	Barhalganj: Saiva and Vaishnava temples, 237	8	Rasûlpûr	252
	Barhi: tank, sivala, and ancient statues		Akorhî : Hindû temples	254
	of Narayana and Lakshmi at		Ashtabhuja: sacred tank and temples	254
	Mithabel 238		Baraini: stone temple and sati monu-	
	Bhågalpûr: temple of Chaturbhûjî Nârâ-		ment	254
			TH 1 1 A 111	255
	The state of the s		Bhadohi: maspids Bhaili: cave dargah of Makhdam Sahib	200
	Göpälpår: brick eastle 242	al		OFF
	Gôrakhpûr: sarûî, imâmbâra and masjids, 242	3	Chîrâgh-î-Hind	255
	Do., temple of Gôrakhanâtha 242	-	Bijaygarh: tomb of Sa'id Zain-al-	
	Do., ancient tank at Jattal 249	2.	Abdîn	256
	Itâya : dargâh of Abdûl Qâdir Hazrat 24		Bindhåchal: temple of Vindhyêsvarî	257
	Kahaon : old wells and tanks 248		Do., old masjid at Kantit	257
	Khakhundû: Jain temple 248		Chakia: mausoleum of Latif Shah	258
	Lâr: Hindû temple, masjids and imâm-		Chunar: temple of Bhartrinatha	258
	bâra 248		Do., dargâh of Shâh Kâsim Sulai-	
	Majhauli: Saiva temples and castle 248		mânî	259
	Do., masjids at Salîmpûr 248		Do., masjid, fountain and Rang	
	Padarâunâ: tomb of Barhan Shahîd 249		Mahal	259
	Rudrapûr: temple of Dûdhnâth (Śiva) 250		Do., temple of Kâmâkshî Dêvî	260
	Sõhanâg : temple of Parašurāma 250	2	Mîrzâpûr : Hindû temples and masjids	262
				202
	The same of the same of the same of	UDH		
	VIII.—LAKHNÂÛ DIVISION.	1	VIII.—LAKHNÂÛ DIVISION— (continued).	0
1.	Bâra Bankî District—	2.	.—Lakhnāû District—(concluded).	
	Baddû Sarâî: dargâh of Malâmat Shâh 26	3	Lakhnåû: masjids, karbalås and dargāhs	
	Do., temple of Jagannatha Dasa and		of Asaf-ad-daulah's time	266
	tank 26	3	Do., great Imâmbâra and Rûmî	1070000
	Bara Banki: Hindû temples and masjids, 26		Darwâza	266
	Do., masjid of Akbar's time at	100	Do., tomb of Shaikh Mina	267
	D AA ART AYAR DO	,	Do., masjids of Akbar's and Shah	201
		`	Takanta Ataua	OOM
	Fathpûr: masjid of Abul Fazl and imâm- bûra 26			267
	The second secon		Mohânlâlganj: dargâhs, tomb, and Ganj	
	Kursî: tomb of Sa'îd Nûr Alî Shâh at	. 0	Shahîdân at Nagrâm	268
	Mansar 26-	3.		- Conservation
	Rudauli: dargah of Shah Ahmad and		Ajgâôn : masjid at Asîwân	268
	tomb of Zohra Bîbî 26	1	Baksar Ghât : temple of Vakêsvara	268
	Satrikh: dargah of Salar Saha 26		Do., modern Hindû temples at	
	Siddhaur: temple of Siddhêsvara Ma-		Samgrampar	268
	hâdêva, tomb of Qûzî Qutb		Bångarmåå: old shrines and dargåhs	269
	and masjid 264		Bihâr: dargâh and îdgâh	271
2.	The second secon		Do., tomb of Mahâbat Shâh at Pâtan	272
1	Amethi: masjids and tombs of Akbar's	1	Pariar: temple of Somesvara Mahadeva	212
	time 269			070
	Bîjnôr: Ganj Shahîdân and tomb of		Pûrwî: temple of Bilêsvara Mahâdêva	273
	and the same of th	21	a manadeva	
	Malik Ambar 96		and March Assessed	CO. Marie
	Malik Ambar 26		and Musalmân tombs	273
	Kåkorî : tombs and dargûhs 26	5	Do., Hindû temple and masjids at	
五五		5		273 273

	Page	e.		Page.
	VIII.—LAKHNAT DIVISION—(concluded).		IX.—Sitapur Division—(concluded).	L age.
3.			2. Kheri District—(concluded).	
			Goļā-Gôkarņnāth: temple of Gôkarņnātha,	284
	Pürwä: noted lingam and dargah 27:	3	Do., masjids and Musalman	201
	Safipûr: masjids, tombs, dargûhs and		To a delivery and the second s	004
	Hindû temples 27	4	Do., lesser shrines and tombs	284
	Do., temple of Râmasvâmî Mahâdêva			
	at Vakarma 27	4	of the Mahants	
	Do., temple of Parvatî at Baliraj		Khairigarh: dargâh of Pîr Sa'âdat Alî	285
	Atâha 27	4	Kheri: masjids, imāmbāras, dargāhs, and	
	Do., masjid at Qâzîpûr 27	4	Hindû temples	
	Såtan: temple of Sîtalâ Devî and old		Do., masonry tank at Dêokâlî	286
	square well 27	5	Nighāsan: fort and sarāī at Pasgawān	
	Unão: masjids and Hindû temples 27	6	Do., marble statue at Majhgaon	287
	IX,-Sîtâpûr Division.		3. Sitâpûr District—	
1.	Hardôl District—		Biswan: dargahs of the early Moghal	
	Bâwân: ancient tank and dargâh 27	~	period	287
	AND THE RESERVE OF THE PARTY OF		Do., palace, sarâî and masjids	287
			Do., dargâh of Shâh Rukn at Bisendî,	287
	Do., dargāhs and masjids 27	8	Hargâm : dargâh and ancient masonry	
	Do., dargah of Sa'id Sughra, tomb		tank	288
	and well at Bojhar 27		Khairabad: masjids, dargahs, Qadam	
	Do., masonry well at Naumalikpûr, 27	8	Rasûl, imûmbûra and	
67	Do., dargah of Qazi Buddha at		Hindû temples	200
	Mahmûdnagar 27	8	Lâharpûr : masjids, dargâhs, and Hindû	200
	Do., masjid and masonry well at		temples	000
	Nazratnagar 27	8		
	Gôpamâû: bâradarî and dargâh of Lâl	- 1	Manûâ : dargâh and îdgâh	
-	Pîr 279	9	Misrikh: masonry tank and Hindû temples,	289
	Do., masjid and well of Humâyûn's		Do., ancient masonry tank at Jar-	200
	time 279	9	gawân	290
٠.	Do., Jûmi Masjid, îdgâh and square	22	Nimkhar: sacred pool, temples, and	-
	well 279	9	dharmsålas	290
	Do., temple of Göpînâtha 279	9	Sîtâpûr: Hindû temples and masjid at	
	Kalyanmal: noted lingam in modern		Pirnagar	291
	temple 280	0	Do., dargâh of Lâm-ad-dîn at Shâh	12707624
	Mallawan: masjids, imambaras, dargahs,		Qulîpûr	291
à'	and Hindû temples 280	0	X.—Faizabad Division.	
	Påli: masjids and Hindû temple 28.	CA .	1. Bahráich District —	
	Pihani : tomb of Abdul Ghafur 281	10	Bahrûîch: dargâh of Sa'îd Sâlâr Masa'ûd,	292
	Do., masjid and tomb of Mîrân Sadr		Do., dargah of Rajjab Salar	292
	Jahan 281		Do., dargâh of Amîr Nasîr-ullâ at	
	Såndi: masjids, dargåhs, and Hindû		Dekaulî	293
	temples 282	2	Bahrampur: Hindu temples and masjids,	293
	T) 1 1 1 1 1 1 0000	9	Bhinga: old brick fort	293
	Sandîlâ: masjids, tomb, and bârakhambhâ, 282		Nanpara: Hinda temples, masjids and	
	Shâhâbâd : Jâmi Masjid of Nawâb Dilêr	3	îdgâh	294
	the contract of the contract o		Tandwa: statue of Sîtâmâî in modern	
		10	temple	295
2.	Kherî District—	1	2. Faizâbâd District—	
	Balmiar-Barkhar: small Hinda temple 283		Ajudhya: Brahmanical and Jaina tem-	
	Dhaurahra: Hinda temples and masjids, 284	1		297
				ATTION.

	Page.	Page.
X FAIZ SBAD DIVISION-(concluded)		XI.—Rât BARELT DIVISION—(concluded).
2. Faizābād District—(concluded).		1. Pratâpgarh District—(concluded).
Ajudhyā: Bābar's masjid	. 297	Bihâr: tomb of Sa'îd Kamâl-ad-dîn at
Do., dargahs of Sis, Ayab and Nal		Aimah Rājî Muhammad Hayāt, 316
Paighambar		Manikpar: masjids, tombs, Rangin and
Akbarpûr: sâraî, imâmbâra, and old		
	000	Sang Mahals 317
tombs		Do., Saiva temples 318
Do., stone tomb in centre of large		Pattî: temple of Pârvatî at Parasurâm-
tank		pûr 318
Do., dargâhs at Masa'ûdpûr		Pratapgarh: temple of Bela Bhavani at
Amsin: brick fort		Belâ 319
Do., brick temple of Rishi Siragavîra	0	Do., inscribed stone mill at Katra
at Sirwâ-Pâlî	300	Mêdnîganj 319
Do., temple of Kâlikâ Devî at Kasbâ,		Do., temple of Durga at Banbir-
Bhadarsi : ancient tank		kåchhî 319
Bîrhar : dargâh of Shâh Makhdûm Sa'îd		Do., temple of Durgâ at Sandwâ
Ashraf Jahangir at Rasûlpûr	The second second second	
		Chandiká 319
Mangalsî: old masjid at Kôt Sarâwân		Do., modern temple at Gondâ 319
Do., old masjid at Mustafâbâd	7000000	2. Rât Barelt District—
Tâṇḍâ: masjids, imâmbûras and Hindû		Bachhrawan: tombs and tanks at Thu-
temples	302	lendî 319
3. Gondâ District—		Do., tomb of Agha Shahîd at
Balrampur: Hindu temples and masjids,	302	Hardôî 320
Dêvî-Pâtan : temple of Pârvatî	303	Důlmåů: masjids, tombs, well and garden, 320
Gonda: sarat, masonry tank, and Hindu	JAN 1000	Do., dargah of Makhdam Jahaniya, 322
temples	1888-1889-1881	Do., masjids and temple of Banvari
Machhligaon : modern temple of Maha-		The state of the s
dêva		Devi 322 Do., temple of Dâl and Bâl at
Mahâdêva: old temple of Mahâdêva	10.000000000000000000000000000000000000	75 7 3 4 4 4 4
Mathura: Šivala and dargah of Mir		D
TT 10		Do., tombs at Jalálpûr-Dehî 323
Hanifa	AND DESCRIPTION	Jais: masjids, tombs and dargah 323, 324
Pachran: noted lingam in modern temple,		Rat Bareli: temples, masjids, and baoli
Såhet-Måhet : temple of Sambhunåtha		in fort 324
Do., dargâh of Pîr Barâna at	-	Do., Jāmi Masjid 325
Husain Jot	311	Do., maqbara and Rang Mahal at
Do., Musalman tombs on top of		Jahanâbâd 325
Orâjhâr mound	311	3. Sulţânpûr District—
Utraula: tomb of All Khan and stone		Aldered A. matel 11:
tank	313	Do., modern shrine of Hanuman and
XI.—Rât Barelî Division.	0.0007/A	
1. Pratâpgarh District—		Ancient ponds at Begethus, 326
Bihår: group of figures in modern brick		Musäfirkhäna: masjid of Alamgir's time
Armed a	0.0000000000000000000000000000000000000	at Kishnî 328
	314	Sultanpur : masjid of Ala-ad-din Khilji's
Do., Musalman tombs	314	time 328
Do., dargâh of Shahîd Mardan	315	Do., Sîtâkund below civil station, 329
Do., dargâh of Pîr Bahrâm at Barâî	316	Do., large masonry tank at Hasan-
Do., fort, Rang Mahal, Dîwânkhâna with		pûr-Bandhûû 329
masjid at Dilêrganj and Newâdâ,	316	Do townt AT 1 A 44
Do., dargâh, Qadam Rasûl and masjid	40	Do., temple of the Sveta Varaha at
at Shahpar	316	V s
	1000	Догwа 329

(5) LIST OF MONUMENTS AND BUILDINGS CLASSIFIED UNDER III.

NORTH-WESTERN PROVINCES.

	and the same of th	Page.	1		Page.
	I.—Mirath Division.	- my us		I Mirath Division - (concluded).	Lage.
1.	Aligarh District-		6.	Sahâranpûr District—(concluded).	
	Akrâbâd: mound at Kherâ Bajherâ	1	10	Bhagwanpar: ruined masjid at Sakrauda,	714
	Do., deserted site at Såhêgarh Kherâ,	i		Hardwar: old square fort and lofty	
	Do., ancient site at Nagaria Khera,	1		and the second s	40
	Hathras Khas: ruined fort and Hinda			Toudhaum - 132-r	- 42
	temple	1		Mr. St	
	Jalali : ancient Hindû sites	î		Ti - 41 41 1 1 2 To 1 1 1 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	
	Lakhana : ancient mounds	3		Charles A	100
	Sånkåra : ruined fort and mound	3	1		
	Såsni: mud fort and mound	3		71 1 1 1 1	18, 19
	Tappal: ruined fort	3		Sahansri : ruined fort	19
	Tuksûn: ancient kherû and mud fort	3		II.—ROHILKHAND DIVISION.	
0			1.	Badâon District—	
2.	THOMPSON SOMEON		-	Badâon : ancient ruined fort	20
	Ahar: ruined temple of Ambika and large			Bisauli : ruined Shisha Mahal	23
	tumuli	4		Kôt Śâlbâhan : brick-strewn fort mound,	
	Anapshahr: ruined brick fort and temple,	4		Sahaswan: fort mound, tank, and old	AT.
	Aurangabad Chandôk : ruined fort, town			ruined tombs	24
	and temple	4		Salîmpûr : mud fort	
	Bulandshahr: ruined mound and fort	4, 5		Shaikûpûr: old village site and ruined	21
	Dankaur: large fort of Akbar's time	6		tomb	24
	Dibhai: ruined fort	6		Ujhani : ruined tomb and Qadam Rasal,	24
	Indôr: ancient fort and mounds	6	0	Bareli District—	21
	Shikarpur: khera and old ruined fort	7	A.	The state of the s	200
3.	Dêrah Dûn District—			Aonla: small ruined castle and tombs	24
	Nil.			Attarchendî : ruined fortress	25
4.	Mirath District—			Bareli: tomb of Muhammad Yar and	1188
	ALCO ALCO ALCO ALCO ALCO ALCO ALCO ALCO			earthen fort	25
	Ajrûra: razed fort	9		Do., minor Moslîm shrines	26
	Barnawa: brick-strewn mound	9		Gwala Prasiddh : ruined ancient city	26
	Do., ruined fort at Sirsâr	9		Kâbar; fort mounds and ruined temple,	26
	Mirath: high brick fortress 10	986		Pachômî: ancient mounds	26
	Muzaffarnagar Saîni: ancient mound	12		Råmnagar: great fortress and ruined tem- ples 2'	1 1800
	Råjå Karan-kå-Kherå: ruined village site,	12			7, 28
	Sarāwā: old kherās	12		Do., old tanks and ancient mounds, 2: Shishgarh: ancient fort	The state of the s
5.	Muzaffarnagar District—		(2)		29
	Bhainswâl: old mound containing grave		3.	Bijnor District—	
	of Pîr Ghâib	12		Afzalgarh: ruined brick fort	30
	Hasanpûr : ruined masjid	13		Barhapura : ruined city and fort	30
	Jalalabad: ruined fort of Ghausgarh and	10		Bijnor: ruins of ancient town and castle	
	masjid	13		mound	30
	Kâîrâna; ruined bâradari, tank and	10		Chandî: ruined buildings	30
	garden	13		Chândpûr : old well	30
	Kotêsra : old ruined fort	13		Kîratpûr: ruined fort, wells and masonry	
3.	Sahâranpûr District—	-		tank	31
		5405	1	Laldhang : ancient village site in the	
	Ambahta: ruined fort	14	To.	ravines of the Rawasan	31
	Bahât : old deserted town	14		Mandawar : ruined fort mounds	31

Page.	1
II.—ROHILKHAND DIVISION—(concluded).	III Krastov Dane Page.
3. Bijnôr District—(concluded).	III.—Kumâon Division—(concluded). 2. Kumâon District—(concluded).
MA-II-2	Champavat - old mined1
Najîbâbâd : tombs and dismantled castle	Dhilling day of the state of th
A The state of the	Gonadio Hat. 11
Sabalgarh: ruined castle and deserted	Kôtalourh : mined foot
village sites33, 34	Hauralhar mind to 1 0 2 at
Tîp: ancient kherâ 34	Kota: old ruined fort
4. Murûdâbûd District—	3. Tarâi District— 50
Amrohâ : minor tombs and gates of old	Chaturbhûj: old ruined fort 50
fort34,35	Kāsipūr; deserted ancient city51, 52
Do., old temple mound at Bhêrâ	IV.—ÂGRÂ DIVISION.
Bharatpûr 35	1. Âgrâ District—
Bilârî : old mounds or dîhs 35, 36	Achners small stone fout - 2 72 1 4 4
Hasanpur: old mounds, the deserted sites	Agra: lifts for drawing water and remains
of forts and temples 36	ref or minimum 17.3
Muradabad: sati pillars, old fort and	Do., traces of old gardens and mauso-
mounds36, 37	omme
Sambhal: old fort, îdgâh, bâolî and	Do., remains of Moti Bagh, ruined mas-
mounds37, 38	jids and gardens 55
Thåkurdwåra: ruined mounds 38	Do., the Mîna Bâzâr inside Fort 57
5. Pilibhit District—	Do., ruins of old palaces and gardens
Barkherâ: ruined ancient fortified city 38	below Fort eo
Bîsâlpûr : deserted site at Maraurî 38	Do., ruins of large palaces and walled
Dêorîyâ : ruined fort mounds 39	gardens
Jahânâbâd: ruined temple mounds39, 40 Pilibhît: old brick fort and ruined village	Do., ruins of Jodh Bai Mahal
100	Do., ancient hammam, or bath 66
Pûranpûr : large ruined cities buried in	Do., ruined gardens
dense jangal40, 41	Do., ruined palace, gardens and sarif, 69
6. Shâhjahânpûr District—	arge mud fort of the Hinda noviced an
GAIA DAGA 1 . 1 . 1	Bâh : palace and garden 69
19181818181 - 11 2 t	Batesar: ruined fort and mounds 69
Kant : mined magiid and LL	Fathpûr Sîkrî : Jahûngîr's school 72
Kherâ Bajhêrâ : deserted site of ancient	Do., Ankh Michauli and astrologer's
# house	
Mati: deserted site of large fortified city 42	Do., waterworks and Hiran Minâr 73 Fîrûzâbûd : large ruined tank 74
Do., ruined brick temples at Thânêkâ, 42	Do., ruins of old situated to 74
Miranpür Katra: old mound	Do., ruins of old city of Chandwar 74 Hathkant: ruined old fort 74
Shahjahanpar: ruined fort 43	Jågnår : ruined fort, tank and cave 75
Tilhâr : old ruined fort 43	Kassaundi: series of 52 forts and ancient
III.—Kumaon Division,	tank
	Kågåraul: old fort mound 75
Contract Con	Anniragarh : mud fort and mounds
Adbadri : ruined temples 44 Chandpur: large ruined fort 44	dillauli : Barndari and
Karnpravac's small ruined tort 44	wall
Karnprayâg; small ruined temples 45 2. Kumâon District—	Pinâhât: tank, wall around town, and
Barésyar - Machal tember	IOTI
Baijnath old Ranchula f	Parna : old fort
- January and Management of the second of th	Sikandra : Hans Mahal 19
	76

	Pe	age.	1		Page.
	IV ÂGRÃ DIVISION-(continued).			IV AGRA DIVISION-(continued).	
2	. Farrukhûbûd District—		3.	Îtâh District—(concluded).	
	Amritpûr : old ruined fort	77		Sarâî Aghat : lofty and extensive kherâ,	88
	Bhôjpûr : traces of fortifications	77		Sôron : ancient mound	00
	Bishangarh : castle	77		Thâna Daryâoganj : ruined brick fort	- com
	Chhibraman : ruined castle and old sarai,	77	4.		1
	Farrukhâbâd : city wall and mud fort	77		Abarianna caldaillana da	89
	Indargarh : ruined fort at Pûrab Rêi	78		A 5 A . 1 . Pa	00
	Kanauj: ruined fort and brick-strewn	1000		3 - 46 VI 4 11 1 - 2 - 2 1	-00
	mounds	79		DATA ALL DA	-
	Khairnagar : brick fort and old khera	81		Didla A	-00
	Khudaganj: ruined saraî	81		Chahaman	.00
	Muhammadâbâd : old castle	82		Tahasah sadda anta di Para	0.7
	Pakhna Bihar: ruined Buddhist vihara and			V. 35-3-5	92
	Bråhmanical temples	82		Mant. Lhand	-
	Pilkhana : ancient mound	82		TAIR 1 T T T T T	92
	Raushanābād ; old masonry well	83		11 1	60
	Sakrāwa : ruined brick castle	83			92
	Sankisa: ancient mounds	83		Phaphûnd: old town site and ruined fort	00
	Saurikh : ruined eastle	84	5.		92
	Shamsabad: ruins of the old town of		U.	Māinpuri District—	
		84		Akbarpûr Aunchhâ: ruined brick and	
	Tålgråm : traces of old brick castle	84		mud fort	92
		84		All Khera: old deserted site	92
3.	Santage Control of th	28		Anjana: ruined mud fort and Buddhist	
,,	William Town Color			chaitya	92
	Aliganj: mud fort and tombs84,			Do., ruined Buddhist shrines at	
		85		Jasrão	93
	The state of the s	85		Asauli: old mound	93
	1 2 11 11	85		Azamābād Ārāon: old kherā	93
		85		Bhanwat : large ruined buildings	93
		85		Bharaul : ruined tank and masjid	93
		85		Bhongaon: large ruined fort	93
		85		Ekå : mud fort	93
		86		Karhal: remains of brick fort and temple,	93
		86	-	Karîmganj: kherâ and ruined mud fort,	93
		86		Do., ruined Hindû temple at	
		36		Thâkurâ	94
		36		Khergarh : old fort of the Chauhans	94
		86		Kishnî : large kherâ	94
		87		Kuraôlî : ancient kherâ at Rasemâ	94
	Malawan: remains of old kankar-built			Mahôlî Shamshêrganj: kherâ	94
	The state of the s	37		Maînpuri : old Chauhan fort	94
		37		Mustafabad : mud fort and old well	94
		37		Naushahr : old town site	94
	Do., ruins of Buddhist temple at	100		Nonaira : extensive ancient mound	94
		37	1	Padham : lofty mound and ruined old	
	Do., remains of Buddhist temple	No.		fort	95
	AND THE PARTY OF T	7		Sauj : ancient kherā	97
	Patiali: ruins of large fort 8	37	-	l'akrâra Daulat : large old kherî	97

	Page.		Pag
	IV ÂGRÂ DIVISION-(concluded).	V Jhansi Division-(concluded).	*
6	. Mathura District-	2. Jhansi District—(concluded).	
	Aring: ruined fort and tank 97	Mâû : old briek fort	118
	Aurangabad : ruined masjid of red sand-	Do., remains of Chandella temple at	110
	stone 97	Marhâ	119
	Chaumuhâ: remains of large sarâî 100	3. Lalitpûr District—	***
	Jâit : ruined statue of hooded serpent 101	Bar : Hindû brick maqarbâs	119
	Köth: long mound 102	Chândpûr : old deserted town with groups	TOTAL CO.
	Mahaban : old fort mound 103	of ruined temples	119
	Måt: old mud fort 104	To 1 11 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	, 120
	Mahwân : long high mound 104	Do., group of small ruined Jain tem-	· ·
	Mathura: lofty mounds, ruined tank and	100 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	120
	old city walls 105, 106	TATALA TO	123
	Do., large mound, sati burj and	Madanpur: small ruined temples at	
	ruined old fort 107, 108	TO PRODUCE A CONTRACT OF A CON	124
	Magôrâ : rudely sculptured stone 108	VI.—Allahâbâd Division.	
	Noh Jhil: extensive brick fort 109	1. Allahâbâd District—	
	Pâli Kherâ: old kherâ 109	Allahatas Tt. A TA A	100
	Parkham: low mound 109	Dish a	130
	Ral: ruined fort and tank 110	Garband and I To	
	Râyâ : fort mound 110	Jhost : mined foot 1	135
	Sahpau: old fort mound and ruins of Jain	Karrâ: ruined fort and small Hindû	138
	temple 110	town la	190
	Shahpar: ruined fort at Chauka 111	Karari : ancient fort 138,	
	Shêrgarh: large ruined fort 111	Khairagarh : old ruined fort	140
	Sônkh: ruined old fort 111	Kôh Inâm: ruined masjid of Fîrûz Shâh's	110
	V.—JHANST DIVISION.	time	140
1.	Jaláun District—	Kohnrar: ruined fort and baok	740
	T-18	Kosam Inam: ancient fort and mounds, 140.	142
		Lachnagir: large ruined fort	
	Kûlpî: ruined fort, tombs and masjids 112 Kûnch: ruined citadel and small pool 114	Mah: old ruined fort near Jalalpar	
		Malakah : extensive mound at Shinnan	143
	Walls and a state of the state	Markhaman : brick-strewn mounds	143
	0.44	Panâsâ : old tîlâ	144
	Do., earth-forts at Hardôl Mafi and	Singraur: deserted town site	144
	Bajhera Kherâ 114	Do., large mound	145
2.	Tidant District	Sorion : extensive old mound	145
		2. Bândâ District—	
	Barûâ Sâgar : ruined Chandella temples 115	Augast : ruined fort	145
	Do., large ruined Chandella	Båndå: ruined fort Bhûragarh at Bhur-	CEO.
	temple at Bangama 115	endi	146
	Gûrsarâî: ruined temples and tanks at	Dargarh: ruined fort	146
	Sirwabaran 116, 117	Barha-Kotra: caves and small ruined	20
	Kishnî Khûrd: ruined Chandella temple at Sakrûr 117	temples	147
	richh: remains of walls and gateways in	Girwan : rock-cut figure	148
	18:14	Gonda : large caves at Rank	49
	Do., large ruined Chandella temple at	Guirampur: ruined stone templas	49
	The state of the s	Jaspura : old ruined fort	49
	Patha-Sigauli 118	Maintar: ruined masside	53


			Page.			Page.
	VI.—ALLAHABAD DIVISION—(con	tinued).		VI.—ALLAH SET DIVISION—(concluded	
2.	Bândâ District—(concluded).			4.	Känhpür District—	
	Karwî : ruined brick fort at Tarâhw	1000	154		The state of the s	165
	Do., old ruined temple at Khoh		154 154		Akbarpûr Bîrbal : old temple of Râdhâ-	
	Lauri : small stone fort		620		Krishņa	
	Marpha: hill fort and ruined Jair		194	1	Bhitarguon: ruined brick temple	
	ples		154	18	Do., brick temple at Simbhuâ	
	Marwal: small ruined fort		155			168
	Mâû: ruined temples at Rithorâ					168
	Do., large ruined lingam temp		100			169
	Hatovâr		155	1		169
	Oran : small ruined fort				Mûsânagar : old ruined fort at Umargarh,	
	Råmnagar : lake and ruined temple		156			170
	Do., large cave high up in			-		170
	hill		156	0.	Hamirpûr District—	181
	Râsîn : ruined Chandella temple at					171
	pûr		157		Hamîrpûr : ruined fort and tombs	171
	Sihonda: large ruined fort		157		Do., deserted village site at Badan-	171
	Simauni : ruined fort		157		pûr Do., brick-strewn kherûs at Itûrû	
					and Pachkhaurâ	
3.	Fathprir District—					171
	Amaulî: ruined masjids and tombs	***	157		Jaitpûr: ruined fort 171	
	Aphûî: brick-strewn mound				Kabrâîa : tank and ruined Chandella tem-	, 110
	Asnî: ruined fort mound		158		ples 172	173
	Asothâr : extensive brick-strewn mo	10000	158		Kulpahâr : ruined palace and tomb	
	Aurai : ancient village site at	Tik-	21		Do., ruined granite temples at	
	sariyâ	***	158		Chârnâ	
	Bindkî: carved stone slabs		159			173
	Fathpur: ruined fort				Makarbai : large ruined granite temple,	174
	Garhî Jâr : ruined masjid	775	160		Do., ruined tank and temple at	
	Ghâzîpûr : ruined fort	1.0	160		Barsî Talâo	
	Do., extensive ruins of ancien		-		Mahobâ: ruined temple in Madan Sâgar,	175
	tified town at Painâ	***	160		Do., ruined fort, stone pillar, and	
	Gunîr : mounds and temple ruins		160		mounds 176	, 177
	Haswa: old ruined fort		161	17.	Maudha: ruined stone fort	177
	Do., stone elephant				Râth : brick-strewn mounds at Kachhwâ,	178
	Jafarganj: ruined fort		162		Do., ruined temple at Rorâ	178
	Khairai: ancient temple mounds		102		Sayar: mud fort	178
	Khakhrêrû: ruined masjid on old te mound		169		Srinagar: ruined fort, tank, and temple,	178
					Sumërpûr : brick-strewn mounds	
	Kora : large ruined fort Kot : remains of ancient fort					178
	Kutilâ : ruined forts			The same	Sapa: ruined fort	178
	Kutiya: ruined fort and fragment		200	6.	Jaunpûr District—	
	figure sculpture		164		Jaunpur: dismantled fort and shrine of	
-	Naubasta: brick-strewn mounds		200		Karar Bir 179-	-184
	stone elephant		164		Do., rained palace inside fort	184
1	Ren : brick-strewn mounds				Macchlishahr: ruined fort and masjid	
	Sâh : old fort		2322		Zafarâbâd : ruined stone fort	

	1	Page.			Page.
	VII.—Banaras Division.	ALL WATER		VII.—Banaras Division—(continued)	
1	. Azamgarh District—		2.	The state of the s	
	Amla Bazar: ruined mud fort	187	-	Sikandarpûr: ruined fort and mounds	194
	Atraulia : mud fort	187		Turtîpâr: deserted ancient site and lake,	194
	Azamgarh: dilapidated fort	187		Wated a salared from	195
	Do., ruined mud forts at Har-		1	75-51-55-1-55-1-51-1	
	bânspûr	187	3		195
	Azmatgarh: ruined fort	187	-	Baburî : brick fort and ruined temple	105
	Chiraîyakôt: ruined mound	187		The same of the sa	
	Do., deserted ancient site near			Dalas Casso, and the Total State of the	, 196
	Bhatri	187		Banâras : mounds and small round struc-	196
	Dabhâon : old tank and mound	188		funor	000
	Déogâon: ruined stone temples at Râm-			Do swined Padalita 1 712	
	garh	188		Do., remains of large ruined fort	
	Ghosî: ruined mud fort	188		Do., brick-strewn mounds	209
	Kauria: large ruined mud forts at Ariaon			Bardodon : winad builds foot	210
	Jahanianpar and Awank	188		Buent - mined fort	212
	Kopå: mud fort	189		Chandauli : ruined brick fort	
	Måhal : old tanks and mounds at Dêhduâr,	189		Jalhonon ald mined Date as c	
	Måå Nåtbhanjan : ruined market-place	190		Moohal Sarat - mined batch ford	212
	Muhammadâbûd Gohnâ: large tank	190		Nanhatrale . brick atnown	212
	Do., ruined stone			Pindada Lafet P	212
	temples at Ind-			Do., ruined palace at Aslâ	212
	pûr Bhîra and			Sakaldîhâ : ruined brick fort and kherâ	
	Dêolâs	190		Normaliah . Lata .	213
	Nizâmâbâd : tomb of Nizâm-ad-dîn	190	119	Sa'idraja: deserted village site and ruined	-216
	Powůí: ruined mud fort	190	п	Forto	No.
2.	Bâliyâ District—	2,19091		Tari - rained fort	216
	Båghaunch : large mound	190	4.	Basti District—	216
	Bâliyâ: ruined mounds at Beduwall,		.00	Amorba 1 777	rason
	Vazîrapûr, Dharmâolî and			Rolchied Dille and and a	
	Muhammadpûr	191		Bangle mined baids &	217
	Bansdih: ruined mounds	191		Barah Chhetra: ancient town site and	217
	Barmayan: ruined Buddhist monastery,	192			200
	Bhâlsand : ancient village site	192		Basti: brick-strewn mounds or kherâs	218
	Chhâtâ : ruined stûpa	192			
	Chît Fîrûzpûr : ruined mounds at Pakkâ			Bhari ald tonk and the	
	Kôţ	192		Katable - brink at-	223
	Garwar : ruined castle	192		Khirminur amined hat a	223
	Haldî: ruined fort	192		AND THE PARTY OF T	161
	Husainabad: ruined tank and masjid	192		Machar · described will	224
	Karnaî: large ruined mound	193		le brand a	aure -
	Kathaurâ : ruined fort	193		Maholi ruined Puddling to	
	Kharid: deserted town site	193		Nagar Khas + Jacob 1 4	
	Lakhnêsar Dîh : brick-strewn mounds	193		Dampor Daorina	
	Maniar : high mounds	193		Isma: brick-strong 7	
	Nåråyanpår : old ruined temple	193		Waril: deserted william at	
	Do., ruined mounds at Lakshmi-		5.	Ghdzîpûr District—	227
	pûr	194		Aonribar : deserted to-	300
	Rasrā: tank and earthen tombs	194		Dura: deserted mounds	227
		-		deserted mounds	227

Page.	Page,
VII.—Banâras Division—(continued).	VII.—Banaras Division—(concluded),
5. Gházîpûr District—(concluded).	6. Görakhpür District—(concluded).
Barhanpar : old ruined fort and kheras 227	Gôpûlpûr : extensive mounds 242
Bharault Gangatir: ruined buildings 227	Gôrakhpûr : ancient mounds, 242, 243
Bhîtarî : ancient deserted site 228	Kahâon : extensive brick mound 243
Bîrpûr : ancient sculptures 230	Kasîâ : lofty ruined mounds, 244-247
Dhânapûr: ancient fort and large brick	Khakhundû: ruined tanks and mounds, 248
mound 230	Majhauli: ruined brick fort at Kundilpar, 248
Do., ruined fort at Hingotar 230	Nichlaval: large ruined brick fort 249
Dildårnagar : ancient town site 230	Padarâunâ : brick-strewn mounds 249
Ghâuspûr : brick-strewn mounds 231	Rånîghât : large ruined brick fort 249
Ghâzîpûr: ruined mud fort and kherês, 231, 232	Rudrapûr: ruined great fort and
Jalalabad : ruined brick fort 232	mounds 249, 250
Kåsimåbåd: ruined fort on ancient	Târakulwâ: ruined Buddhist stûpas 251
mound 232	7. Mîrzâpûr District—
Masson Dih: ruined mounds 233	A 31.46
Nârâyanpûr : ancient town site, 233, 234	A - 5 - 5 T/1 5 1 - 1 - 2 - 5 1 - 2 - 5
Sa'idpûr: old ruined fort and mounds 235	A1 A 1 7 4 6 6
Shaikhânpûr : ancient sculptures 236	Ahugî: ruined Saiva temples on low
Udharanpûr: extensive brick mounds 236	A 2 4
Zamânîyû: deserted mound and carved	Ashtabhuja: cave and half ruined temple, 254
stones 237	Bhadohî: ruined fort of the Mônas at
6. Gôrakhpûr District—	Suriânwân 255
Anââlâ : ancient kherâ 237	Bhuili: ruined fort 255
Bairâûnû Khûs : ruined fort 237	Bindhachal: ruined forts and temples 257
Bánsgáon: old díh 237	Chunâr : row of dâlâns or cloisters 260
Barhaj: ruined fort on banks of Rapti 237	Dibhôr : rude stone cell 260
Barhi: extensive ruins of a very large	Halîyâ : old mud fort 261
ancient city 237, 238	Karsotå: large irrigation tank 261
Bhanapar: ruined castle and mounds 239	Kêrâ Mangraur : ruined hill forts 261
Chetiyûon: ancient town site and mounds	Korådih : large lake 262
of ruins 239—241	Mîrzâpûr: ruined temple of Vindhya-
Dêorîyâ : extensive mounds 241	vāsinī 262
Dhuriapar : enormous ruined fort and	Patîta : large mud fort 262
mounds 241	Pår: large masonry tank 262
Gagaha: ancient deserted site and mounds, 241	Saktisgarh: stone fort and ruined temple, 262
477	
AUI	on.
VIII.—LAKHNAO DIVISION.	VIII.—LAKHNÄÜ DIVISION—(continued).
ne ne ne ne ne ne ne ne ne ne ne ne ne n	
	2. Lakhnáû District—
Aliabid: ruined buildings 263	Amethi: Bhar dihs and mud fort, 264, 265
Bûra Baûkî : bare kherâ, well and ruined	Bîjnôr: ruined brick fort and tombs 265
masjid 263	Kåkorî : old ruined brick fort 265
Daryabad : ancient village site 263	Kasmandî Kalân: ruined dargâhs and
Dêwâ : ruined fort mound and sarâi 263	brick mounds 265
Haidargarh: brick-strewn mounds 264	Lakhnaa: artificial mound within Machha
Kursi: ruined mounds or dihs 264	Bhawan Fort 265
Subehå : old kherå and brick fort 264	Do., Qaisar Bagh buildings 267

S. Lakhnáū District—(concluded). 2. Lakhnáū District—(concluded). 2. Lakhnáū District—(concluded). 2. Lakhnáū dargāh and old cantoments at Marjāon 267 Mahonā: ruined brick fort and kherās 267 Mahiyābād: old ruined brick fort 267 Mohānlālganj: deserted mounds 267 Nigohān: ruined Bhār dlh 268 3. Undo District— Ajāōn: extensive dlh and tombs 268 Baksar Ghlṭ: dilapidated fort 268 Baksar Ghlṭ: dilapidated fort 268 Bahgarmāū: extensive ruined mounds, 269—271 Bihār: large ruined brick fort 272 Harhā: large ruined brick fort 272 Harhā: large ruined brick fort 272 Mawāt: Bhār dlh 273 Rasalābād: ruined brick fort 273 Parark: ruined brick fort 273 Parark: ruined brick fort 273 Parark: ruined brick fort 273 Parark: ruined brick fort 273 Parark: ruined brick fort 273 Parark: ruined brick fort 273 Parark: ruined brick fort 273 Parark: ruined brick fort 273 Safīpūr: ruined forts and kherās 274 Unāo: ruined fort and masjid 273 Safīpūr: ruined brick fort 277 Bāwān: deserted village sites 277 Bāwān: deserted town site 279 Baradād: ruined brick fort 279 Baradād: ruined brick fort 277 Bāwān: deserted town site 279 Baradād: ruined brick fort 279 Baradād: ruined brick fort 287 Baragādan: ancient village lites 279 Baradād: ruined fort and dalhs-274 Vunāo: ruined brick fort 287 Baragādan: ruined brick fort 287 Baragādan: ruined brick fort 287 Baragādan: ancient kherā 288 Mahāli: ruined masonry tank and dlh 288 Mahāli: ruined brick fort and sarāt at Pasagawān 288 Mahāli: ruined brick fort and sarāt at Pasagawān 287 Baragādan: ancient kherā and ruined 188 Baragāda: ancient kherā and ruined 188 Baragāda: ruined brick fort and sarāt at Pasagawān 288 Mahāli: ruined brick fort 287 Bigrām: lofty tilās 279, 280 Kalyānmā: ruined brick fort 287 Baragādan: ancient kherā and ruined 188 Baragāda: ruined brick fort, 289, 290 Nimkhār: ruined forts and dalhs 280 Nimkhār: ruined forts and dalh 288 Mahāli: ruined brick fort and sarāt at Pasagawān 288 Mahāli: ruined brick fort and sarāt at Pasagawān		Page.	Page.
Lakhnâû District—(concluded). Lakhnâû chargân and old cantomments at Marjalon 267 Malyñabât : cid ruined brick fort and kherâs 267 Malyñabât : cid ruined brick fort 267 Malyñabât : cid ruined Brick fort 268 Malyñabât : cid ruined Brick fort 268 Asohât : ruined Brick fort 268 Asohât : ancient village site 268 Bângarmââ : extensive dih and tombs 268 Bângarmââ : extensive ruined mounds, 269—271 Bihâr: large ruined brick fort 272 Harhât : large ruined brick fort 273 Kursat : ruined brick fort 272 Mawât: Bhâr dih 272 Pariâr : ruined brick fort 273 Parsandan : ruined brick fort 273 Pariâr : ruined brick fort 273 Parasandan : ruined brick fort 273 Rasâlâbâd : ruined fort and masjid 273 Rasâlâbâd : ruined fort and stone figure of Sarwan Bâbâ 273 Rasâlâbâd : ruined fort and kherâs 274 Sañchânkôt : great mounds 273 Rasâlâbâd : ruined fort and kherâs 274 Sañchânkôt : great mounds 275 Biwân : deserted town site 277 Biwân : deserted village sites 277 Biwân : deserted illage sites 279 Bawân : large ruined brick fort 277 Bawân : large ruined brick fort 277 Bawân : large ruined brick fort 277 Bawân : deserted town site 277 Bawân : large ruined brick fort 277 Bawân : large ruined brick fort 277 Bawân : deserted vown site 277 Bawân : deserted vown site 279 Bawân : deserted vown site 279 Bawân : deserted vown site 279 Bawân : large ruined brick fort 279 Bawân : large ruined brick fort 279 Bawân : deserted vown site 279 Bawân : large ruined brick fort 287 Bawân : deserted vown site 279 Bawân : deserted vown site 279 Bawân : deserted vown site 279 Bawân : large ruined brick fort 287 Bawân : deserted vown site 279 Bawân : deserted vown site 279 Bawân : deserted vown site 281 Bawân : brick-strewn mounds 288 Bahaabân : ruined brick fort and artined fort 287 Bawân : deserted vown site 281 Bawân : mud fort and amajid 289 Mahâli : ruined b		VIII.—LAKHNÂÛ DIVISION—(concluded).	IX.—Sitapur Division—(concluded).
Mahonā: ruined brick fort and kherās 267 Maliyābād: old ruined brick fort 267 Mohān Alganj: deserted mounds 268 Nigohān: ruined Bhār dlh 268 3. Undo District— Ajgāōn: extensive dlh and tombs 268 Baksar Ghāt: dilapidated fort 268 Bangarmāū: extensive ruined mounds, 269—271 Bihār: large ruined brick fort and dlhs, 271, 272 Harāh: large ruined brick fort and dlhs, 271, 272 Harāh: large ruined brick fort 272 Mavāi: Bhār dlh 272 Mavāi: Bhār dlh 272 Pariār: ruined brick fort 273 Parsandan: ruined brick fort 273 Parsandan: ruined brick fort 373 Pārwā: ruined brick fort 373 Pārwā: ruined brick fort and stone figure of Sarwan Bābā 273 Rasālābād: ruined fort and masjid 273 Safīpūr: ruined fort and kherās 274 Sanehānkōt: great mounds 274 Unāo: ruined fort and kherās 274 Barwān: deserted twillage sites 277 Bāwān: deserted twillage sites 277 Bāyān: deserted town site 277 Barwān: large ruined brick fort 277 Barwān: large ruined brick fort 277 Barwān: large ruined brick fort 277 Barwān: large ruined brick fort 277 Barwān: deserted town site 277 Barwān: large ruined brick fort 277 Barwān: large ruined brick fort 277 Barwān: deserted town site 277 Barwān: deserted town site 277 Barwān: deserted town site 277 Barwān: large ruined brick fort 277 Barwān: deserted town site 277 Barwān: deserted town site 277 Barwān: large ruined brick fort 277 Barwān: deserted town site 277 Barwān: deserted t	2		
Mahonā: ruined brick fort and kherās 267 Maliyābād: old ruined brick fort 267 Mohān Alganj: deserted mounds 268 Nigohān: ruined Bhār dlh 268 3. Undo District— Ajgāōn: extensive dlh and tombs 268 Baksar Ghāt: dilapidated fort 268 Bangarmāū: extensive ruined mounds, 269—271 Bihār: large ruined brick fort and dlhs, 271, 272 Harāh: large ruined brick fort and dlhs, 271, 272 Harāh: large ruined brick fort 272 Mavāi: Bhār dlh 272 Mavāi: Bhār dlh 272 Pariār: ruined brick fort 273 Parsandan: ruined brick fort 273 Parsandan: ruined brick fort 373 Pārwā: ruined brick fort 373 Pārwā: ruined brick fort and stone figure of Sarwan Bābā 273 Rasālābād: ruined fort and masjid 273 Safīpūr: ruined fort and kherās 274 Sanehānkōt: great mounds 274 Unāo: ruined fort and kherās 274 Barwān: deserted twillage sites 277 Bāwān: deserted twillage sites 277 Bāyān: deserted town site 277 Barwān: large ruined brick fort 277 Barwān: large ruined brick fort 277 Barwān: large ruined brick fort 277 Barwān: large ruined brick fort 277 Barwān: deserted town site 277 Barwān: large ruined brick fort 277 Barwān: large ruined brick fort 277 Barwān: deserted town site 277 Barwān: deserted town site 277 Barwān: deserted town site 277 Barwān: large ruined brick fort 277 Barwān: deserted town site 277 Barwān: deserted town site 277 Barwān: large ruined brick fort 277 Barwān: deserted town site 277 Barwān: deserted t		Lakhnaû: dargah and old cantonments	Aurangabad : ruined brick fort and release 200
Maliyabhd: old ruined brick fort 267 Mohánlalganj: deserted mounds 267 Nigohān: ruined Bhir dih 268 3. Unao Diatriet— Ajgāōn: extensive dih and tombs 268 Bahsar Ghāt: dilapidated fort 268 Bahsar Ghāt: dilapidated fort 268 Bangarmāū: extensive ruined mounds, 269—271 Bihār: large ruined brick fort 272 Mawāt: Bhār dih 272 Mawāt: Bhār dih 272 Mawāt: Bhār dih 272 Mawāt: Bhār dih 272 Pariār: ruined brick fort 273 Parasandan: ruined masjids 273 Parasandan: ruined brick fort 273 Parasandan: ruined brick fort 273 Parasandan: ruined brick fort 273 Parasandan: ruined brick fort 273 Parasandan: ruined brick fort 273 Parasandan: ruined fort and stone figure of Sarwan Bābā 274 Vuñāo: ruined fort and kherās 274 Vuñāo: ruined fort and kherās 274 Bahannagar: deserted town site 277 Bawān: large ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: ruined brick fort 277 Bawān: large ruined brick fort 277 Bawān: deserted village sites 277, 278 Gopamāā: ruined brick fort and deserted village sites 279, 280 Kalyāṇanal: ruined brick fort and deserted village sites 280 Mallāwān: large dih at Bānsā 280 Pāli: large deserted town site 281 Sānjd: deserted village sites 280 Mallāwān: large dih at Bānsā 280 Pāli: large deserted town site 281 Sānjd: deserted village sites 280 Mallā ruined brick fort 281 Sānjd: deserted village sites 280 Mallāwān: large dis at Bānsā 280 Sānjd: deserted town site 281 Sānjd: deserted town site 481 Sānjd: deserted town site 481 Sānjd: desert		at Mariâon 967	Balmiår-Barkhår: large ruined mound
Maliyābād : old ruined brick fort Mohānlālganj : deserted mounds Nigohān : ruined Bhār dih 268 3. Unāo District— Ajgāōn : extensive dih and tombs Asohā : ancient village site Askar Ghāṭ : dilapidated fort 268 Baksar Ghāṭ : dilapidated fort 269 Baksar Ghāṭ : dilapidated fort 260 Baksar Ghāṭ : dilapidated fort 272 Kursat : ruined brick fort 272 Barāā : ruined brick fort 273 Parāār : ruined brick fort 273 Parāār : ruined brick fort 273 Parāār : ruined brick fort 274 Bashāhābd : ruined fort and dhanāba 274 Bashāhābd: ruined fort and masjid 273 Bashāhābd: ruined fort and masjid 274 Bahannagar : deserted town site 275 Baraān : large ruined brick fort 276 Baraān : large ruined brick fort 277 Baksān : large ruined brick fort 278 Biswān : bick-strewn mounds, 284 Bhūt: large deserted town site 279 Baraān i lofty dilās 277 Baraān i lofty dilās 277 Baraān i lofty dilās 277 Baraān i lofty dilās 277 Baraān i lofty dilās 277 Baraān i lofty dilās 277 Baraān i lofty dilās 277 Baraān i lofty dilās 277 Baraān i lofty dilās 278 Biswān : bick-strewn mounds 288 Bhūt i vined brick fort and deserted Bhūt i ruined brick fort and masjid 289 Ba		Mahona: ruined brick fort and kheras 267	Daniel Control of the
Mohahallganji : deserted mounds 267 Nigohān : ruined Bhūr dih 268 3. Uhōō District— Ajgāōn : extensive dih and tombs 268 Asohā : ancient village site 268 Bahgarmāū: extensive ruined mounds, 269—271 Bihīr : large ruined brick fort and dihs, 271, 272 Harhā : large ruined brick fort and dihs, 271, 272 Harhā : large ruined brick fort 272 Mawāi : Bhār dīh 272 Mohān : dihs and ruined masjids 273 Parsandan : ruined brick fort 273 Parsandan : ruined brick fort and stone figure of Sarwan Bābā 273 Rasālābād : ruined brick fort and stone figure of Sarwan Bābā 273 Safīpār : ruined fort and masjid 273 Safīpār : ruined fort and kherās 274 Vuñāo : ruined fort and kherās 274 Sanehānkōt : great mounds 274 Unāo : ruined fort and kherās 276 Barwān : large ruined brick fort 277 Bawān : large ruined brick fort 273 Britāpār : ruined brick fort and masjid 278 Britāpār : ruined brick fort and masonry fort and brick roined fort and masonry tanks 288 Baksar fort 279 Britan : large ruined brick fort and masonry tanks 287 Britāpār : ruined brick fort and dih. 288 Baksar ind fort and sarāi 289 Mahārijagar : old ruined masjīd 289 Mahārijagar : old ruined masjīd 289 Mahārijagar : old ruined masjīd 289 Mahārijagar : old ruined masjīd 289 Mahārijagar : old ruined fort and mound 290 Sēotā : ruined fort		Maliyabad : old ruined brick fort 967	
Nigohân : ruined Bhâr dih 3. Unão District— Ajgãôn : extensive dih and tombs Ajgâôn : extensive dih and tombs Ajgâôn : extensive dih and tombs Asobâ : ancient village site Baksar Ghất : dilapidated fort Bâhâr : large ruined brick fort Bâhâr : large ruined brick fort and dihs, 271, 272 Harhâ : large ruined brick fort Bâhâr : ruined brick fort Mawâî : Bhâr dih Band ruined masjids Pariâr : ruined brick fort Pârwâ : ruined brick fort Pârwâ : ruined brick fort Safipâr : ruined brick fort Safipâr : ruined brick fort and stone figure of Sarwan Bâbâ Safipâr : ruined fort and masjid Safipâr : ruined fort and masjid Safipâr : ruined fort and skerâs Line of trand kherâs Safipâr : ruined fort and masjid Safipâr : ruined fort and kherâs Safipâr : large ruined brick fort Sarwân : large ruined brick fort Sarwân : large ruined brick fort Sarwân : large ruined brick fort Sarwân : large ruined brick fort Sarwân : large ruined brick fort Sarwân : large ruined brick fort Sarwân : large ruined brick fort Sarwân : large ruined brick fort Sarwân : large ruined brick fort Alamnagar : deserted town site Alamnagar : deserted town site Saryân : lofty tilâs Saryân : sort and sarwân : 287 Barwân : large ruined brick fort Sarwân : large ruined brick fort Sarwân : large ruined brick fort Sarwân : large ruined brick fort Sarwân : large ruined brick fort Nighâsan : mul fort and sarâl at Pasgawân Do., ruined brick fort at Munrâ- Munrî Saryân : shervên mounds Saryân : shervên mounds Saryân : wined brick fort and sarâl : 288 Kaniribadi : old masonry tanks and ruined masonry tanks Saryân : viined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruined brick fort Sarwân : ruin		Mohanlalganj: deserted mounds 267	and sometime
A jgálón : extensive díh and tombs 268 A sobá : aneient village site 268 Baksar Ghát : dilapidated fort 268 Baksar Ghát : dilapidated fort 268 Baksar Ghát : dilapidated fort 268 Bahsar Ghát : dilapidated fort 272 Bihát : large ruined brick fort and díhs, 271, 272 Harhá : large ruined brick fort 272 Mawát : Bhár díh 272 Mohân : diha and ruined masjids 273 Pariâr : ruined brick fort 273 Pariâr : ruined brick fort 273 Pariâr : ruined brick fort 273 Parsandan : ruined brick fort 273 Rasálábád : ruined brick fort and stone figure of Sarwan Bábá 273 Sasíphár : ruined brick fort and stone figure of Sarwan Bábá 273 Sasíphár : ruined fort and masjid 273 Sasíphár : ruined fort and kherás 274 Sañchánkôt : great mounds 274 Unâo : ruined fort and kherás 274 Barwán : large ruined brick fort 277 Barwán : large ruined brick fort 277 Bawán : deserted town site 277 Barwán : large ruined brick fort 277 Bigrám : lofty tílás 277, 278 Gópamát : ruined masonry fort and brick mounds 279 Gandwá : ruined brick fort and deserted village sites 279, 280 Kalyāņmal : ruined brick fort and deserted forts 281 Pihánî : huge masonry well and ruined fort 281 Pihánî : huge masonry well and ruined fort 281 Sândî : deserted village sites and ruined fort 281 Sândî : deserted village sites 281 Pihánî : huge masonry well and ruined fort 281 Sândî : deserted village sites 281 Sândî : deserted village sites and ruined fort 282 Sandilâ : ruined masjid and brick fort 282 Sandilâ : ruined masjid and brick fort 282 Sandilâ : ruined masjid and brick fort 282 Sandilâ : ruined masjid and brick fort 282 Sandilâ : ruined masjid seerted site estredis con dithe textensive deserted site seerted s		Nigohân : ruined Bhâr dih	
Agodni: ancient village site 268 Baksar Ghất: dilapidated fort 268 Baksar Ghất: dilapidated fort 268 Baksar Ghất: dilapidated fort 268 Bangarmiå: extensive ruined mounds, 269—271 Bihất: large ruined brick fort 272 Kursat: ruined brick fort 272 Mawất: Bhất đih 272 Pariâr: ruined brick fort 273 Parsandan: ruined brick fort 273 Parsandan: ruined brick fort 273 Parsandan: ruined brick fort 273 Parsandan: ruined brick fort 273 Parsandan: ruined brick fort 273 Parsandan: ruined brick fort 273 Safipār: ruined forts and kherās 274 Sanchāhkēt: great mounds 273 Safipār: ruined fort and masjid 273 Safipār: ruined fort and kherās 274 Sanchāhkēt: great mounds 274 Unāo: ruined fort and kherās 274 Bawān: large ruined brick fort 277 Bāwān: large ruined brick fort 277 Bāwān: large ruined brick fort 277 Bāwān: large ruined brick fort 277 Bāwān: large ruined brick fort 277 Bāwān: large ruined brick fort 277 Bāwān: large ruined brick fort 277 Bāwān: large ruined brick fort 277 Bāwān: large ruined brick fort 277 Bāwān: large ruined brick fort 277 Bāwān: ruined masjid 273 Gandwā: ruined masjid 279 Gandwā: ruined masjid 279 Gandwā: ruined masonry fort and brick mounds 279 Katratārā 279 Barwān: large ruined brick fort 277 Barwān 107 Barwān: large ruined brick fort 277 Bāwān: brick-strewn mounds, ruined masonry tanks 288 Khairābād: ruined brick fort at Munrā-287 Biswān: brick-strewn mounds 288 Mahāli: ruined brick fort and masjid 289 Mahāli: ruined brick fort and masjid 289 Mahāli: ruined brick fort and masjid 289 Mahāli: ruined brick fort, 289, 290 Mallāwān: large dih at Bānsā 280 Kalyāmal: ruined brick fort and deserted forts 281 Pihānî: huge masonry well and ruined fort and mounds 290 Sötōt: ruined forts and druined forts 281 Bahrāte truined musika 281 Khairipādi: ruined brick fort and diha, 285 Khairipādi: ruined brick fort and diha, 286 Khairipādi: ruined brick fort and sarāl 289 Mahāti: ruined brick fort, 289, 290 Mallāwān: large daserted town site 281 Sāndīd: deserted village sites 281 Sāndīd: deserted town site 281 Bahrāted bri	3.	Unão District—	Park and the second sec
Asohā : ancient village site		Ajgâôn : extensive dih and tombs 268	
Bängarmål: extensive ruined mounds, 269—271 Bihår: large ruined briek fort and dihs, 271, 272 Harhå: large ruined briek fort 272 Kursat: ruined briek fort 272 Mohån: dihs and ruined masjids 272 Pariår: ruined briek fort 273 Parsandan: ruined briek fort 273 Parsandan: ruined briek fort 273 Parsandan: ruined briek fort and stone figure of Sarwan Bābā 273 Sañpūr: ruined forts and kherås 274 Sañpūr: ruined fort and masjid 273 Sañpūr: ruined fort and kherås 274 Unāo: ruined fort and kherås 274 Barwān: large ruined briek fort 277 Barwān: large ruined briek fort 277 Barwān: large ruined briek fort 277 Barwān: large ruined briek fort 277 Barwān: large ruined briek fort 277 Barwān: large ruined briek fort 277 Barwān: large ruined briek fort 277 Barwān: large ruined briek fort 277 Barwān: large ruined briek fort 277 Barwān: large ruined briek fort 277 Barwān: large ruined briek fort 277 Barwān: large ruined briek fort 277 Barwān: large ruined briek fort 277 Barwān: large ruined briek fort 277 Barwān: large ruined stone fort and mounds 288 Khairipād: large ruined briek fort and dih 286 Kkhairigarh: large ruined stone fort and mounds 286 Kkurā: ruined briek fort and dih 286 Kurā: ruined briek fort and dih 286 Kurā: ruined briek fort and dih 286 Kurā: ruined briek fort and dih 286 Kurā: ruined briek fort and dih 286 Kurā: ruined briek fort and dih 286 Kurā: ruined briek fort and dih 287 Muhamd: large ruined briek fort and mounds 287 Sātāpūr District— Barāgāon: ancient kherā and ruined masonry tanks 288 Khairibād: old masonry tanks 288 Khairibād: old masonry tanks 288 Khairibād: old masonry tanks 288 Mahūd: ruined briek fort and dargāh, 289 Mahūd: extensive kherās and ruined forts and dargāh, 290, 291 Sitāpūr: deserted town site 287 Barādāl: ruined briek fort and dargāh, 290, 291 Sitāpūr: deserted town site 289 Mahūd: curined briek fort and dargāh, 290, 291 Sitāpūr: deserted town site 289 Mahūd: curined briek fort and dargāh, 290, 291 Sitāpūr: deserted town site 289 Mahūd: deserted town site 289 Mahūd: curined briek fort a		Asohā : ancient village site 268	The same of the sa
Bibâr: large ruined brick fort and dibs, 271, 272 Harhâ: large ruined brick fort 273 Kursat: ruined brick fort 273 Mawâi: Bhār dih 272 Mohân: dihs and ruined masjids 272 Pariār: ruined brick fort 273 Parsandan: ruined brick fort 273 Parsandan: ruined brick fort 273 Parsandan: ruined brick fort 273 Parsandan: ruined brick fort and stone figure of Sarwan Bābā 273 Safīpār: ruined forts and kherās 274 Sanchānkôt: great mounds 287 Barkân: deserted town site 277 Bawân: deserted town site 277 Bawân: large ruined brick fort 277 Bawân: large ruined brick fort 277 Bawân: large ruined brick fort 277 Bawân: deserted town site 277 Bawân: large ruined brick fort 277 Bawân: large ruined brick fort 287 Gopamân: rude stone images, ruined fort 279 Hardôi: deserted town sites 279 Hardôi: deserted town sites 279 Balgrām: lofty tilās 277, 278 Gopamân: ruined brick fort and deserted village sites 289 Mallāwān: large deserted town site 281 Pihāni: huge masonry well and ruined forts 281 Sāndīi deserted village sites and ruined forts 281 Sandīlā: ruined masjid and brick fort 281 Sanchānkôt: great mounds 286 Kherî: ruined brick fort and dih 286 Khurā brick fort and dih 287 Mithaulf: ruined brick fort 287 Muhamāi: large ruined brick fort 287 Muhamāi: large ruined brick fort 287 Muhamāi: large ruined brick fort and masjid 287 Satīdpār District— Barāgāon: ancient kherā and ruined masonry tanks 288 Khiriābād: old masonry tanks 288 Khiriābād: old masonry tank and dih 288 Khiriābād: old masonry tanks 288 Khiriābād: old masonry tanks 288 Mahālā ruined brick fort and sarāi 289 Mahārājnagar: old ruined masjid 289 Mahārājnagar: old ruined masjid 289 Mahārājnagar: old ruined fort and deserted village sites 281 Pihānī: huge masonry well and ruined forts 281 Sandīlā: ruined brick fort 281 Sandīlā: ruined brick fort and dihard 283 Sandīlā: ruined brick fort and diha		Baksar Ghât : dilapidated fort 268	Haidarābād : ruined jangal-clad forts 205
Harhâ : large ruined brick fort		Bangarmaû: extensive ruined mounds, 269-271	Khairigarh : large ruined stone fort and
Kursai: ruined brick fort		Bihar: large ruined brick fort and dihs, 271, 272	manus Is
Mawfâl: Bhâr dith		Harna: large ruined brick fort 272	
Mohân: dihs and ruined masjids 272 Pariâr: ruined brick fort 273 Parsandan: ruined brick fort 273 Parsandan: ruined brick fort 273 Pârwâ: ruined brick fort and stone figure of Sarwan Bâbâ 273 Rasâlâbâd: ruined fort and masjid 273 Sañpâr: ruined fort and masjid 273 Sañpâr: ruined fort and kherâs 274 Unâo: ruined fort and kherâs 274 Unâo: ruined fort and kherâs 276 IX.—Sîrâpûr Division. 1. Hardôt District— Âlamnagar: deserted town site 277 Bawân: large ruined brick fort 277 Bâwân: deserted village sites 277 Bâwân: lofty tilâs 277, 278 Gôpamâû: ruined masonry fort and brick mounds 279 Gandwâ: ruined masonry fort and deserted town site 279 Hardôî: deserted town site 279 Kalyâṇmal: ruined brick fort and deserted town site 280 Pâli: large deserted town site 281 Pihânî: huge masonry well and ruined fort 281, 282 Sandîlâ: ruined masjid and brick fort 281, 282 Sandîlâ: ruined masjid and brick fort 281, 282 Sandîlâ: ruined masjid and brick fort 281, 282 Sandîlâ: ruined masjid and brick fort 281, 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282		Mursat: ruined brick fort 272	Kulpak aminod holds & a see
Pariâr: ruined brick fort 273 Parsandan: ruined brick fort 273 Parsandan: ruined brick fort 273 Pârwâ: ruined brick fort and stone figure of Sarwan Bâbâ 273 Rasâlâbâd: ruined fort and masjid 273 Sañpâr: ruined forts and kherâs 274 Sañchânkôt: great mounds 274 Unâo: ruined fort and kherâs 274 Unâo: ruined fort and kherâs 276 Bi LX.—Sirâpîr Division. 1. Hardôt District— Âlammagar: deserted town site 277 Barwân: large ruined brick fort 277 Bâwân: deserted village sites 277, 278 Gôpamâû: ruined masges, ruined fort and brick fort and masjid 279 Gandwâ: ruined masges, ruined fort and brick mounds 279 Hardôî: deserted town sites 279, 280 Mallâwân: large dîh at Bânsâ 280 Pâli: large deserted town site 281 Pihânî: huge masonry well and ruined fort 281 Sândîlâ: ruined masjid and brick fort 281 Sândîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 281 Fakhrpûr: ruined brick fort 282 Fakhrpûr: ruined briek fort 282 Mithaulî: ruined mud fort 287 Mithaulî: large dind fort 287 Mithaulî: large dind fort 287 Nighâsan: mud fort and sarâl at Pasgawîn 287 Nighâsan: mud fort and sarâl 287 Nighâsan: mud fort and sarâl er Pasgawîn 287 Barâgâon: ancient kherâ and ruined masonry tanks 287 Barâgâon: ancient kherâ and ruined mud nasonry tanks 287 Barâgâon: ancient kherâ and ruined mud nasonry tanks 287 Barâgâon: ancient kherâ and ruined mud nasonry tanks 287 Barâgâon: ancient kherâ and ruined mud nasonry tanks 287 Barâgâon: ancient kherâ and ruined mud nasonry tanks 287 Barâgâon: ancient kherâ and ruined mud nasonry tanks 288 Mahâlî: ruined brick fort and dasonry tank and dîh 288 Mahâlî: ruined brick fort and masonry tank and dîh 289 Mahârâjnagar: old ruined masjid 289 Mahârâjnagar: old ruined masjid 289 Mahârâjnagar: old ruined masjid 289 Misrikh: deserted town site and ruined temple and brick fort, 289, 290 Nimkhâr: ruined fort and dargâh, 290, 291 Sitâpûr: deserted town site at Hâthiyâ Kuṇḍ 293 Ch			Lakhîmpûr: brick-strewn mounds ruined
Parsandan: ruined brick fort		Bookan: diffs and ruined masjids 272	tombers 1 to 1
Pûrwâ: ruined brick fort and stone figure of Sarwan Bâbâ 273 Rasâlâbâd: ruined fort and masjid 274 Sañchânkôt: great mounds 274 Unâo: ruined fort and kherâs 276 IX.—Sirâpûr Division. 1. Hardôî District— Alamagur: deserted town site 277 Bâwân: deserted village sites 277, 278 Gôpamâû: ruined sorte mounds 279 Gandwâ: ruined masonry fort and brick mounds 279 Hardôî: deserted town sites 279 Hardôî: deserted town sites 279 Hardôî: deserted town sites 279 Hardôî: deserted town sites 279 Hardôî: deserted town sites 279 Hardôî: deserted town sites 279 Hardôî: deserted town sites 279 Hardôî: deserted town sites 280 Pâli: large deserted town site 281 Pihânî: huge masonry well and rained forts 281 Sândî : deserted village sites and ruined fort 281, 282 Sandîlâ: ruined masjid and brick fort 281 Sândîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282		Pariar: ruined brick fort 273	Mithault : mined 1 f.
figure of Sarwan Bâbâ 273 Rasâlâbâd: ruined fort and masjid 273 Safîpûr: ruined forts and kherâs 274 Unâo: ruined fort and kherâs 276 IX.—Sîrâpûr Division. 1. Hardôî District— Âlamnagar: deserted town site 277 Barwân: large ruined brick fort 277 Bâlgrâm: lofty tîlâs 277, 278 Gôpamâû: ruined masonry fort and brick mounds 279 Gandwâ: ruined masonry fort and brick mounds 279 Hardôî: deserted town sites 279 Kalyânmal: ruined brick fort and deserted village sites 280 Mallâwân: large dân at Bânâ 280 Mallâwân: large dân at Bânâ 280 Mallâwân: large dân at Bânâ 280 Mallâwân: large dân at Bânâ 280 Pâli: large dên at Bânâ 280 Pâli: large deserted town site 281 Pihânî: huge masonry well and ruined forts 281 Sândî: deserted village sites and ruined forts 281 Sândî: deserted village sites and ruined forts 281 Pihânî: huge masonry well and ruined forts 281 Sândî: deserted village sites and ruined forts 281 Sândî: ruined masjid and brick fort 281 Sândî: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined brick fort at Munrâ Munrî 287 Barûnî brick strewn meunds 287 Barâgân: mient kherâ and ruined masonry tanks 288 Khairâbâd: old masonry tank and dîh 288 Mahârâṇagar: old ruined masjid 289 Mahârâṇagar: old ruined masjid 289 Mahârâṇagar: old ruined masjid 289 Mahârâṇagar: old ruined masjid 289 Mahârâṇagar: old ruined masjid 289 Mahârêṇagar: ol		Parsandan: ruined brick fort 273	Muhamdi - langa min - 1 1 1 1
Rasûlâbâd : ruined fort and masjid 273 Safîpûr : ruined fort and kherâs 274 Sanchânkôţ : great mounds 274 Unâo : ruined fort and kherâs 274 Unâo : ruined fort and kherâs 276 IX.—Sirâpûr Division. 1. Hardôî District—		rurwa: ruined brick fort and stone	Nighāsan : mud fort and sarāi at Pasca-
Safipfir: ruined forts and kherâs		ngure of Sarwan Bâbâ 273	nurfine.
Sanchânkôt: great mounds 274 Unâo: ruined fort and kherâs 276 IX.—Sirâpûr Division. 1. Hardôt District— Barwân: large ruined brick fort 277 Bâwân: deserted town site 277 Bâwân: deserted village sites 277, 278 Gôpamâû: ruined masonry fort and brick mounds 279 Hardôt: deserted town site 279 Hardôt: deserted town site 279 Kalyânmal: ruined brick fort and deserted village sites 280 Mallâwân: large dîh at Bânsâ 280 Pâli: large deserted town site 281 Sândît: deserted village sites and ruined fort 281, 282 Sandîtâ: ruined masjid and brick fort 282 Sandîtâ: ruined masjid and brick fort 282 Sandîtâ: ruined masjid and brick fort 282 Sandîtâ: ruined masjid and brick fort 282 Sandîtâ: ruined masjid and brick fort 282 Munrî 287 Barûgâon: ancient kherâ and ruined masonry tanks 288 Biswân: brick-strewn mounds 288 Hargâm: kherâ and masonry tank and dîh 288 Mahârîjnagar: old ruined masjid 289 Mahârâjnagar: old ruined masjid 289 Mahârâjnagar: old ruined masjid 289 Manûâ: extensive kherûs and ruined temple and brick fort, 289, 290 Nimkhâr: ruined forts and dargâh, 290, 291 Sîtâpûr: deserted village sites 281 Sândîtâ: ruined masjid and brick fort 281 Sândîtâ: ruined Daulatkhâna 293 Bhingâ: deserted town site at Hâthiyâ Kuṇḍ 293 Fakhrpûr: ruined brick fort 293 Fakhrpûr: ruined brick fort 293		Saffinance 7 fort and masjid 273	Do., ruined brick fort at Munra-
Unâo: ruined fort and kherâs IX.—Sitâpûr Division. 1. Hardôî District— Âlamnagar: deserted town site Alamnagar: deserted town site Bâwân: large ruined brick fort Bâwân: deserted village sites Bilgrâm: lofty tîlâs 277, 278 Gôpamâû: rude stone images, ruined fort and masjid 279 Gandwâ: ruined masonry fort and brick mounds 279 Hardôî: deserted town sites 279, 280 Kalyânmal: ruined brick fort and deserted village sites 280 Mallâwân: large dîh at Bânsâ 280 Pâli: large deserted town site 381 Sândî: deserted village sites and ruined fort 281 Sândî: deserted village sites and ruined fort 281 Sândî: deserted village sites and ruined fort 281 Sândî: deserted village sites and ruined fort 281 Sândî: deserted village sites and ruined fort 281 Sândî: deserted village sites and ruined fort 281 Sândî: deserted village sites and ruined fort 281 Sândî: deserted village sites and ruined fort 281 Sândî: deserted village sites and ruined fort 281 Sândî: deserted village sites and ruined fort 281 Sândî: deserted village sites and ruined fort 282 Sandîlâ: ruined masjid and brick fort 283 Bahrâich: ruined brick kherâ and ruined masonry tanks 288 Khairâbâd: old masonry tanks and dîh 288 Mahâlî: ruined brick fort and sarâî 289 Mahârâjnagar: old ruined masjid 289 Manûâ: extensive kherâs and ruined temple and brick fort, 289, 290 Nimkhâr: ruined fort and mound 290 Sêotâ: ruined forts and dargâh, 290, 291 Sîtâpûr: deserted village sites X.—Faizâpân Division. 1. Bahrâich: ruined Daulatkbâna 293 Bhingâ: deserted town site at Hâthiyâ Kuṇd Chardâ: brick-strewn kherâ 293 Fakhrpûr: ruined brick fort		Sangharia 274	Munuf
IX.—Sitâpûr Division. 1. Hardôt District—		Unio: rained fort 111	
1. Hardôt District— Alamnagar : deserted town site 277 Barwân : large ruined brick fort 277 Bâwân : deserted village sites 277 Bilgrâm : lofty tîlâs 277, 278 Gôpamâû : rude stone images, ruined fort and masjid 279 Gandwâ : ruined masonry fort and brick mounds 279 Hardôî : deserted town sites 279 Kalyâṇmal : ruined brick fort and deserted village sites 280 Mallâwân : large dîh at Bânsâ 280 Pâli : large deserted town site 281 Pihânî : huge masonry well and ruined forts 281 Sândî : deserted village sites and ruined forts 281 Sândî : deserted village sites and ruined fort 281 Sândî : ruined masjid and brick fort 282 Sandîlâ : ruined masjid and brick fort 282 Fakhrpûr : ruined brick fort 283 Fakhrpûr : ruined brick fort 283 Fakhrpûr : ruined brick fort 283 Fakhrpûr : ruined brick fort 283 Fakhrpûr : ruined brick fort 283 Fakhrpûr : ruined brick fort 283			
Alamnagar: deserted town site 277 Barwân: large ruined brick fort 277 Bâwân: deserted village sites 277 Bilgrâm: lofty tîlâs 277, 278 Gôpamâû: rude stone images, ruined fort and masjid 279 Gandwâ: ruined masonry fort and brick mounds 279 Hardôî: deserted town sites 279, 280 Kalyânmal: ruined brick fort and deserted village sites 280 Mallâwân: large dîn at Bânsâ 280 Pâli: large deserted town site 281 Pihânî: huge masonry well and ruined forts 281 Sândî: deserted village sites and ruined fort 281 Sândî: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Fakhrpûr: ruined brick-strewn mounds 288 Khairâbâd: old masonry tank and dîh 289 Mahârî; ruined brick fort and sarâî 289 Mahârî; ruined brick fort and sarâî 289 Mahârî; ruined masjid 289 Mahârî; ruined brick fort and sarâî 289 Mahârî; ruined masjid 289 Mahârî; ruined brick fort and sarâî 289 Mahârî; ruined brick fort			masonry tanks 007
Hargâm: kherâ and masonry tanks 288 Barwân: large ruined brick fort 277 Bâwân: deserted village sites 277 Bilgrâm: lofty tîlâs 277, 278 Gôpamâû: rude stone images, ruined fort and masjid 279 Gandwâ: ruined masonry fort and brick mounds 279 Hardôî: deserted town sites 279, 280 Kalyânmal: ruined brick fort and deserted village sites 280 Mallâwân: large dîh at Bânsâ 280 Pâli: large deserted town site 281 Pihânî: huge masonry well and ruined forts 281 Sândî: deserted village sites and ruined fort 281, 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masonry tanks 288 Khairâbâd: old masonry tank and dîh 288 Mahâlî: ruined brick fort and sarâî 289 Mahârâjnagar: old ruined masjid 289 Mahârâjnagar: old ruined masjid 289 Manûâ: extensive kherâs and ruined temple and brick fort, 289, 290 Nimkhâr: ruined fort and mound 290 Sêotâ: ruined forts and dargâh, 290, 291 Sîtâpûr: deserted village sites 291 X.—Faizâbâd Division. 1. Bahrâich District— Bahrâich: ruined Daulatkbâna 293 Bhingâ: deserted town site at Hâthiyâ Kuṇḍ 293 Chardâ: brick-strewn kherâ 293 Fakhrpûr: ruined brick fort 289 Fakhrpûr: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Mahârâjnagar: old ruined masjid 289 Manûâ: extensive kherâs and ruined temple deserted town site and ruined temple and brick fort, 289, 290 Nimkhâr: ruined forts and dargâh, 290, 291 Sîtâpûr: deserted village sites 291 X.—Faizâbâd Division. 1. Bahrâich: ruined Daulatkbâna 293 Chardâ: brick-strewn kherâ 289 Fakhrpûr: ruined brick fort 289	1.		Biswân: brick-strewn mounds
Bâwân: deserted village sites 277 Bilgrâm: lofty tilâs 277, 278 Gôpamâû: rude stone images, ruined fort and masjid 279 Gandwâ: ruined masonry fort and brick mounds 279 Hardôî: deserted town sites 279, 280 Kalyânmal: ruined brick fort and deserted village sites 280 Mallâwân: large dîh at Bânsâ 280 Pâli: large deserted town site 281 Pihânî: huge masonry well and ruined forts 281 Sândî: deserted village sites and ruined fort 281 Sândî: deserted village sites and ruined fort 281, 282 Sandîlâ: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Mahâlî: ruined brick fort and sarâî 289 Manâî: extensive kherâs and ruined temple 289, 290 Nimkhâr: ruined fort and mound 290 Sêctâ: ruined forts and dargâh, 290, 291 Sîtâpâr: deserted village sites 291 X.—Faizâbâd di dimasonry tank and dîh 289 Mahâlî: ruined brick fort and sarâî 289 Manâî: extensive kherâs and ruined temple 289, 290 Nimkhâr: ruined fort and mound 290 Sêctâ: ruined forts and dargâh, 290, 291 Sîtâpâr: deserted village sites 291 X.—Faizâbân Division. 1. Bahrâich District— Bahrâich: ruined brick fort 293 Bhingâ: deserted town site at Hâthiyâ Kuṇḍ 293 Fakhrpâr: ruined brick fort and sarâî		Alamnagar: deserted town site 277	Hargam : khera and masonry tanks
Bilgrâm: lofty tîlâs 277, 278 Gôpamâû: rude stone images, ruined fort and masjid 279 Gandwâ: ruined masonry fort and brick mounds 279 Hardôî: deserted town sites 279, 280 Kalyânmal: ruined brick fort and deserted village sites 280 Mallâwân: large dîh at Bânsâ 280 Pâli: large deserted town site 281 Pihânî: huge masonry well and ruined forts 281 Sândî: deserted village sites and ruined fort 281 Sândî: ruined brick fort and sarâî 289 Mahâî: ruined brick fort and sarâî 289 Mahâî: ruined brick fort and sarâî 289 Mahâî: ruined brick fort and sarâî 289 Mahâî: ruined brick fort and sarâî 289 Mahâî: ruined brick fort and sarâî 289 Mahâî: extensive kherâs and ruined temple 289 Misrikh: deserted town site and ruined temple and brick fort, 289, 290 Nimkhâr: ruined fort and mound 290 Sêotâ: ruined fort and dargâh, 290, 291 Sîtâpûr: deserted village sites 291 X.—Faizâbân Division. 1. Bahrûich District— Bahrûich: ruined brick fort 293 Bhingâ: deserted town site at Hâthiyâ Kuṇḍ 293 Chardâ: brick-strewn kherâ 293 Fakhrpûr: ruined brick fort		Barwan : large rained brick fort 977	Khairabad : old masonry tank and dib
Gópamâû: rude stone images, ruined fort and masjid		Bâwân : deserted village sites 277	Maholi : ruined brick fort and sarai oco
Gandwâ: ruined masonry fort and brick mounds 279 Hardôî: deserted town sites 279, 280 Kalyânmal: ruined brick fort and deserted village sites 280 Mallâwân: large dih at Bânsâ 280 Pâli: large deserted town site 281 Pihânî: huge masonry well and ruined forts 281 Sândî: deserted village sites and ruined fort 281 Sândî: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Fakhrpûr: ruined brick fort 293 Fakhrpûr: ruined brick fort 293 Fakhrpûr: ruined brick fort 293 Fakhrpûr: ruined brick fort 293 Fakhrpûr: ruined brick fort 293		Bilgram : lofty tîlâs 277, 278	Maharajnagar : old ruined masiid
Gandwâ: ruined masonry fort and brick mounds		Gopaman: rude stone images, ruined fort	Manûâ: extensive kherâs and ruined
Hardôî: deserted town sites 279, 280 Kalyânmal: ruined brick fort and deserted village sites 280 Mallâwân: large dîh at Bânsâ 280 Pâli: large deserted town site 281 Pihânî: huge masonry well and ruined forts 281 Sândî: deserted village sites and ruined fort 281 Sândî: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Misrikh: deserted town site and ruined temple and brick fort, 289, 290 Nimkhâr: ruined fort and mound 290 Sêotâ: ruined forts and dargâh, 290, 291 Sîtâpûr: deserted village sites 291 X.—Faizâbân Division. 1. Bahrâich District— Bahrâich: ruined Daulatkhâna 293 Bhingâ: deserted town site at Hâthiyâ Kuṇḍ 293 Chardâ: brick-strewn kherâ 293 Fakhrpûr: ruined brick fort		and masjid 279	Hindû temple
Hardôî: deserted town sites 279, 280 Kalyânmal: ruined brick fort and deserted village sites 280 Mallâwân: large dîh at Bânsâ 280 Pâli: large deserted town site 281 Pihânî: huge masonry well and ruined forts 281 Sândî: deserted village sites and ruined fort 281 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Fakhrpûr: ruined brick fort 289, 290 Nimkhâr: ruined fort and mound 290, 291 Sêotâ: ruined forts and dargâh, 290, 291 X.—Faizâbân Division. 1. Bahrâîch District— Bahrâîch: ruined Daulatkhâna 293 Bhingâ: deserted town site at Hâthiyâ Kuṇḍ 293 Chardâ: brick-strewn kherâ 293 Fakhrpûr: ruined brick fort		Gandwa: ruined masonry fort and brick	Misrikh: deserted town site and ruined
Kalyanmal: ruined brick fort and deserted village sites 280 Mallawan: large dih at Bansa 280 Pali: large deserted town site 281 Pihana: huge masonry well and ruined forts 281 Sandila: ruined masjid and brick fort 282 Sandila: ruined masjid and brick fort 282 Nimkhar: ruined fort and mound 290 Seota: ruined forts and dargah, 290, 291 X.—Faizaban Division. 1. Bahraich District— Bahraich: ruined Daulatkhana 293 Kund 293 Charda: brick-strewn khera 293 Fakhrpar: ruined fort and mound 290 Charda: ruined forts and dargah, 290, 291 X.—Faizaban Division. Charda: brick-strewn khera 293 Fakhrpar: ruined fort and mound 290 Charda: ruined forts and dargah, 290, 291 X.—Faizaban Division. Charda: brick-strewn khera 293 Fakhrpar: ruined fort and mound 290 Charda: ruined forts and dargah, 290, 291 X.—Faizaban Division. Charda: brick-strewn khera 293 Fakhrpar: ruined fort and mound 290 Charda: brick-strewn khera 290 Fakhrpar: ruined forts and mound 290 X.—Faizaban Division. Phihana: ruined forts and mound 290 X.—Faizaban Division. Phihana: ruined forts and dargah, 290, 291 X.—Faizaban Division. Charda: brick-strewn khera 293 Fakhrpar: ruined forts and dargah, 290, 291 X.—Faizaban Division.		mounds 279	temple and brick fort 280 200
Ralyanmal: ruined brick fort and deserted village sites 280 Mallâwân: large dîh at Bânsâ 280 Pâli: large deserted town site 281 Pihânî: huge masonry well and ruined forts 281 Sândî: deserted village sites and ruined fort 281 Sândî: deserted village sites and ruined fort 281 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined brick fort 282 Sêndî: ruined forts and dargâh, 290, 291 X.—Faizâbâd Division. 1. Bahrâich District— Bahrâich: ruined Daulatkhâna 293 Kuṇḍ 293 Chardâ: brick-strewn kherâ 293 Fakhrpûr: ruined brick fort 293		Hardor: deserted town sites 279, 280	Nimkhar: ruined fort and mound 200
Mallâwân: large dîh at Bânsâ 280 Pâli: large deserted town site 281 Pihânî: huge masonry well and ruined forts 281 Sâṇdî: deserted village sites and ruined fort 281, 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined masjid and brick fort 282 Sandîlâ: ruined brick fort 282 Sandîlâ: ruined brick fort 282		Kalyanmal: ruined brick fort and desert-	Seota : ruined forts and dargah. 200 201
Pâli : large deserted town site 281 Pihânî : huge masonry well and ruined forts 281 Sândî : deserted village sites and ruined fort 281, 282 Sandîlâ : ruined masjid and brick fort 282 Sandîlâ : ruined masjid and brick fort 282 Sandîlâ : ruined masjid and brick fort 282 Sandîlâ : ruined masjid and brick fort 282 Sandîlâ : ruined masjid and brick fort 282		Mallant ded village sites 280	Sitapur: deserted village sites 291
Pihânî : huge masonry well and ruined forts 281 Sândî : deserted village sites and ruined fort 281, 282 Sandîlâ : ruined masjid and brick fort 282 Sandîlâ : ruined masjid and brick fort 282 Fakhrpûr : ruined brick fort 293 Fakhrpûr : ruined brick fort 293		Dati: lenge dih at Bânsâ 280	X.—Faizâbâd Division.
Såndî: deserted village sites and ruined fort 281, 282 Sandîlâ: ruined masjid and brick fort 282 Shingî: deserted town site at Hâthiyâ Kund 293 Chardî: brick-strewn kherâ 293 Fakhrpûr: ruined brick fort 293		Pilate and the street town site 281	1. Bahraich District—
Sandî : deserted village sites and ruined fort 281, 282 Sandîlâ : ruined masjid and brick fort 282 Fakhrpûr : ruined brick fort 293 Fakhrpûr : ruined brick fort 293		r mann; nuge masonry well and ruined	Bahraich: ruined Daulatkhane
fort 281, 282 Chardâ : brick-strewn kherâ 293 Sandîlâ : ruined masjid and brick fort 282 Fakhrpûr : ruined brick fort		Sandt desart 200 281	Bhingû : deserted town site at Hathing
Sandîlâ : ruined masjid and brick fort 282 Chardâ : brick-strewn kherâ 293 Fakhrpûr : ruined brick fort	- 1	fact deserted village sites and ruined	Kund
Pakhrpûr : ruined brick fort 282 Fakhrpûr : ruined brick fort	. 8	Sandila - minal - "1 11 12 281, 282	Charda: brick-strewn khera
		Sard : brick strong 181	Fakhrpûr : ruined brick fort
Shahahad : dib rained baid 283 Hisampar : old ruined wells, forts, and		Sárá : brick-strewn dihs 283	Hisampur: old ruined wells, forts, and
mounds		PANAL .	mounds
Torts 283 Tkaunā : ruined angleless fort 294		283	Ikauna : ruined angleless fort

X.—Faizābād Division—(concluded). 1. Bahrāich District—(concluded). Nānpāra: ruined town site 294 Taṇḍwā: ruined mounds 294, 295 2. Faizābād District— XI.—Rāt Barrit Division—(concluded). Bihār: ruined temple of Sārya at 6 Do., ruined temples, forts and k	Gaura, 315 heras, 316 316
1. Bahrâich District—(concluded). Nânpâra: ruined town site Taṇdwâ: ruined mounds 294 Do., ruined temples, forts and k	Gaura, 315 heras, 316 316
Nanpara: ruined town site 294 Bihâr: ruined temple of Sarya at C Tandwa: ruined mounds 294, 295 Do., ruined temples, forts and k	herâs, 316 316
Apudhya: ruined mounds, tombs and masjids 297, 298 Akbarpûr: old ruined fort 300 Amsin: ruined brick mounds 300 Bîrhar: ruined dîhs 301 Khandânsa: brick-strewn mounds 301	316—318 t, 318, 319
Majhaurâ: ruined brick mounds 301 Mangalsî: ruined dîhs, temple, masjid and tombs 301, 302 Surhârpûr: ruined masonry fort 302 Tânḍâ: brick-strewn mounds 302 3. Goṇḍâ District— Balrâmpûr: ancient town site 302 Bachhrâwân: deserted village site, r forts, tanks and masjid Dâlmâû: ruined fort and mounds, Inhaunâ: ruined brick fort at Majhî Jagatpûr: ruined brick mounds Jâîs: ruined forts Mustafâbâd: ruined tombs, imâmb Dêvî-Pâtan: brick-strewn mounds 303 Goṇḍâ: vast ruins of ancient cities 304 Hâthilî: ruined brick-covered mounds, 304, 305 Sâlôn: kherâ and ruined fort	ls, 319, 320 320—323 itâ 323 323 323, 324 sâras, les 324
Machhligaon : ancient khera 305 Mahâdêva : ruined brick mounds 305 Pachrân : ruined dîhs 305 Sâheţ-Mâheţ : great ruined fortified	325, 326 ands, 326 and 326—328 and 328
Bihår: ruined brick mounds 314 forts and mounds,	328-330



XIV.-INDICES.

(1) LIST OF PROPER NAMES OF PERSONS, WITH DATES AND PLACES WITH WHICH THEY ARE ASSOCIATED.

Pages.	Pages.
	Abûl Fazl, Akbar's historian, his house at
Α.	Fathpûr Sîkrî 71
Abbâs Alî, repaired shrine of Makhdûm	, his assassin driven into the fort
Jabaniya at Kanauj in A.H.	of Îrichh as a last refuge 118
1209 81	Abûl Hasan, Qâzî, built masjid at Qâzîpûr in
Abdul Jalil Bilgrami, Sa'id, his tomb at Mar-	А.Н. 1072 274
hára, dated A.H. 1017, 87	Abûl Ma'alî, Shah, his tomb at Ambahta 14
Abdul Kaddûs, Shaikh, his mausoleum at	Achalavarman, king of Singhapura, men-
Gângôh built in A.H. 944, 15	tioned in stone inscrip-
Abdul Karîm, Shaikh, built masjid at Jâîs	tion at Madha 8
in A.H. 1085 324	Achehail Singh, built brick fort at Sakal-
Abdul Khâliq, built tombs, imâmbâras, and	777707
palaces at Mustafabad 324	, built temple of Kôlêsvara Nâtha at Chaturbhujpûr, 213
Abdul Majîd, Sa'îd, built Chhangâ darwâza at Amrohâ in A.H. 1051 35	
	Adbhût Singh, servant of Bâlwant Singh, built brick fort at Moghal
Abdul Maqtadi, Sa'id, founded Pihani in A.D. 1540 281	Sarâî 212
	Adil Khân, Rohilla, repaired Saddo masjid
Abdul Qûdir Hazrat, his dargâh at Gôrakh- pûr 243	at Amroha 35
pûr 243 Abdul Qûdir Khûn, Sa'îd, built Jûmi Masjid,	Âdinātha, first Jina, born at Ayodhyâ 297
Sang Mahal, Rangin Mahal,	Âdirâjâ, Ahîr, traditional builder of the Âdi
and Chihal Satûn at Mânik-	Sågar at Råmnagar 28
pûr 317	Adiratha, prince of Auga and foster-father
Abdullâh Khân, Nawâb, his masjid and	of king Karna 302
tomb at Ujhânî 24	Âdityavardhana, king of Sthânvîsvara 189
Abdullah Shah, Sa'id, his dargah at Behta	Afzal Khân, Nawâb, built brick fort at
Håjîpûr and Baisumâ 10	Afzalgarh 30
Abdun Nabî Khân, built Jâmi Masjid at	, poet, his mausoleum known as
Mathurá in A.H. 1071 108	Chînî-kâ-rauzâ at Âgrâ 54
Abdur Razāk, Shāh, his tomb and masjid at	Ahîr, caste, subdued Kôl 1
Jhanjhana, built in A.H.	Ahmad, Sa'îd, Râjâ of Karrâ, founded Sa'îd-
1033 13	rājā 216
Abdus Samād Ķhān, Nawāb, built fort at	Ahmad Bokhârî, his dargâh at Âgrâ 64
Fathpûr in A.H. 1111 159	Ahmad Husain Khân, Nawâb, built garhî at
, his tomb at Fathpur built in	Fathpûr 159
A.H. 1121 159	Ahmad Shah, Sa'id, his tomb at Badaon 23
Abdus Samad Khan, built palatial residences	Ajātašatru, Buddhist king of Banāras 197
at Samādābād 318	Ajayapâla, king of the Chandra dynasty,
Abdus Sattar, Qazi, built masjid at Kishni, 328	built palace at Srinagar in
Abhinandanatha, fourth Jina, born at	A.D. 1358 46
Ayodhyâ 297	, Tômara Râjâ, built temple at
Abû Muhammad Kambôh, his maqbara at	Kanauj 79
Mîrath, built A.D. 1658, 12	, king of Mathura, his inscription of
Abû Yar Muhammad Khân, his maqbara at	Samvat 1207 at Mahaban, 103, 332
Mtrath, built A.H. 1039, 12	Ajipâl, yogî, built temple at Ajrâra 8

Pages.	Pages.
Ajitamalla, Kâyath, built sarâl at Ajitmal	Akbar Shah, his inscription of A.H. 1014
in A.H. 1049 89	near Delhî gate of the Fort
Ajitanatha, the second Jina, or Tirthamkara,	at Âgrā 56
born at Ayodhya 297	, his inscription of Samvat 1621
Akbar Shâh, Sultân, built Jâmi Masjid at	at Kausambi 142
Gângôh in A.H. 963 15	, his inscription of Samvat 1640
, his inscription of A.H. 970 at	in Fort Kâlañjar 152
Sakit 88	, his tomb at Sikandri, com-
, built masjid at Shahpar in	pleted by Jahangir in A.D.
А.Н. 972 316	1612 77
, built great stone bridge at	Ala-ad-din Alam Shah, Sa'id, Sultan, his
Jaunpůr from A.H. 972-75, 184	tomb at Badâon, dated A.H.
, built bridge and masjid at	877 and 882 22, 179
Akbarpûr in A.H. 976 300	
, his inscription of A.H. 977 at	dûm Shâh, his mausoleum at
Sali 85	Pîrân Kalhar, built in A.H.
, built masjid at Ashrafpar in	1036 18
A.H. 977 324	——— Muhammad Shâh, Khiljî, Sulţân,
, his inscription of A.H. 979 in	expelled Bhars from Kusa-
masjid adjoining dargah of	pura 328
Sålim Chhishti at Fathpür	, murdered Jalâl-
Silcri 70	ad-dîn Fîrûz Shîh at Karrî
, repaired dargah of Wilayat	in A.H. 695 138
Shah at Badaon in A.H.	, his inscription
981 21	of A.H. 703 at Khakhrêrû 162
, altered and added to Sikandar	, his inscription of A.H. 711 at
Lodi's fort at Agrâ in A.D.	Rāprī 95
1567 56	
, built palaces and city walls at	dargâh at Barnâwâ, built in
Fathpûr Sîkrî from A. D.	A.H. 1082 9
1571—86 70	Alamgir, Sultan, see Aurangzib.
, took the fort of Chunar in	Alam Singh, built temple at Râmpûr Tha-
A.D. 1575 259	riñon 164
, built fort at Allahâbâd in A.H.	Alap Khân, Sultân of Mândů, mentioned in
982 127, 128	inscription of Samvat 1481
, his inscription of A.H. 983 on	found at Déogarh 120
Baland Darwâzâ at Faṭhpûr Sîkrî 71	Alexander the Great, his coins found at
Sîkrî 71 ———, built bridge at Sarûî Akbar-	Balandshahr 4
âbâd in A.H. 987 263	Alha, Banaphar chief, dwelling-house at
his inscription of A.H. 988 on	Chhillà ascribed to— 135
dargah of Salim Chhishti at	—, built fort at Scota, Sîtâpûr district 290
Fathpûr Sîkrî 71	, worshipped Parvati at Parasuram-
, his inscription of A.H. 1008	pûr 319
in the Fort of Agril 56	Ali Bahadur, Nawab, built masjid at
, took fort of Îrichh in A.H.	Båndå 146
1009 118	- Khân, his tomb at Utraulâ 313
, his inscription of A.H. 1010	— Mardân, built Bâdshâhî Mahal at Faiz-
on Baland Darwâzû at Fath-	Muhammad Pakitta 1: 6: 17
Au COL 21	- Muhammad, Rohilla chieftain, his mau-
pur sikir 11	soleum at Aonlâ 24

INDICES. 363

Pages.	Pages.
Alî Vardî Khân, built tank at Jâgnêr in	Åryavarman, king of Singhapura, mentioned
Akbar's time 74	
Allâh Dâd Khân, built masjid at Shâhzâdpûr	Madhā 331
in A.H. 1138 139	Asad Khan, minister of Aurangzib, built
	tomb of Kalandar Shah at
A.H. 1030 65	Kalandarpûr in A.H. 1118, 190
Altamsh, Sultan, see Shams-ad-din Iltitmish.	Asaldĉo, Râjbhâr chief, built old tanks at
Amarasimha, deified hero of the Sengur tribe,	Dêhdûâr 189
his temple at Nagpura 193	Ashâdhasêna, king of Kausâmbî, his cave
Ambar, Shaikh, his tomb at Kagaraul 75	inscription at Pabhosa 144
Ambika, Rishi, ruined fort near Ambirik	Ashar Khân, built bâolî at Jasrûpnagar-
ascribed to— 234	Asharpûr 10
Âmîn-ad-daulah, Nawâb, built small masonry	Ashraf All, Sa'id, his tomb at Rasûlpûr 252
fort at Sambhal 38	Jahangir, Sa'id, famous darwesh, his
, built brick castle at Sak-	dargāh at Rasūlpūr 301
rûwû 83	, his dargâh at Jâis 324
Amîr Nasîr-ullâh, younger brother of Sultân	Ashraf Khân, built fort at Chaukî 111
Mahmud of Ghazni, his	Asoka, Emperor, his edict inscription at
dargâh at Dekaulî 293	Khālsi 7
Amritapāla, Rāshtrakūta, prince of Vodā-	, his edict pillar at Dehli,
mayûtâ 20	brought from Mîrath10, 11
Ananda, Buddhist teacher, stupas at Ma-	, his Śiyâlik ediet pillar,
thurs ascribed to 10	brought from Topra16, 17
Ananga, Dôr Râjâ, his copperplate grant of	, his edict pillar at Allah-
Samvat 1133 found at Manpar	ábád 127—130
Anantajit, the 14th Jina, born at Ayodhya, 297	** ** ** ** ** ** ** ** ** ** ** ** **
Anathapindada, chief minister of King Pra-	, built stûpas at Ahichhattra, 28
senajit, built great monas-	Asvatthaman, son of Drona, founded Aso-
tery of Jêtavana at Śrâ-	thâr 186
vastî 30	, founded Asohâ 268
Anekamalla, Råjå, erected royal edifices at	Aurangzîb, Sulţân, built masjid at Alâpûr in
Gôpêsvar in Śake 1113 4	4 A.H. 1071 20
Anga Dêva, Raja, built Kora 163	, built Îdgâh at Akbarpûr in A.H.
Ani Râî, Badgûjar Râjā, built brick fort	1072 147
and temple at Anûpshahr	built masjid at Kherî in A.H.
Aniruddha, first cousin and disciple of Bud-	1072 286
dha 24	, built masjid of Maruf Pir at
Anûp Rûî, Badgûjar Rûjû, built Anûp-	Kairana in A.H. 1077 13
shahr	4, built Jāmi Masjid at Banāras in
Apsarodêvî, queen of Râjyavardhana I, king	A.H. 1077 207
of Sthanvisvara 18	built masjid at Deeband in A.H.
Araru Singh, built fort at Ghazipûr about	1078 15
A.D. 1691 16	0, built Bâdâm Masjid at Badâon in
, built fort at Asothâr 15	
, rebuilt old citadel, called Fath-	, built Jâmi Masjid at Hâpûr in
garh, at Painů 16	
Arjmand Bânu Begam, queen of Shâbjahân,	
her tomb at Agri, dated	A.H. 1086 18
	4, built Khurmā Masjid at Badāon
Ariun, Râiâ, constructed large tank at Pûr, 26	2 in A.H. 1092 22

	Pages.		Pages.
Aurangzîb, Sultân, his inscription of A.H.		Bacchus, his statue found at Pâlî Kherî near	
1097 at Sarâî Aghat	88	Mathena	
, built masjid at Donâ in A.H.	- 77	Bâchhal Râṇî, mother of Gûgâ Chauhâna,	109
1103	157	born at Sarsâwâ	10
-, his inscription of A.H. 1104 at	10-77/5/5	Badan Singh, Rājā of Bhadāwar, built tem-	18
Kådirganj	87	ple of Vatêsvaranâtha at	
- , built bâolî at Sâhanpûr in A.H.		Batêsar in Samvat 1703	
1109	34	Body-od-din Shih bis dancil + D A A	69
, built masjid of Pir Muhammad at		Badr-ad-dîn Shâh, his dargâh at Barnâwâ,	
Thâna Bhawân in A.H. 1114,	14	built in A.H. 948	
, defeated his brother Dârâ Shikôh	the contract of	Pol- 1 Lie Wie his dargâh at Salî	
at Samoghar in A.D. 1638	70	Badr-al-Islâm Khân, his tomb at Barelî	26
, destroyed the temple of Kesa-		Bahâdur Khân, founded Shâhjahânpûr in	
vadêva at Mathurâ in A.D.		A.D. 1647	42
1001	106	-, fought against Akbar Shah	
, built dargah and masjid of Abd-	700	at Singraur	145
ullâh Shâh at Behtâ Hâjî-		, his fort and rauza at Garhi	
pûr	10	Jar	160
, made deep most round the Fort	10	- Shah, Sultan, built Khudai Masjid	
	***	at Gorakhpûr	242
of Agra	56	Shahîd, his tomb at Kâlpî	113
, restored the dargah of Makhdûm		Bahlôl Lodî, Sultân, said to have founded	
Akhai Jamshid Sâhib at Kan-		Kîratpûr	31
auj	81	Bahrâm Khân, officer of Sa'id Sâlâr, founded	0.1
, destroyed temple of Sîtâ-Râma	95	Bahrampûr	293
at Sorôn	89	Bahû Begam, wife of Shujâ-ad-daulah, her	200
, destroyed temple of Parvati at		mausoleum at Faizābād,	301
Devî-Pâtan	303	Baijnath Singh, courtier of Raja Balwant	201
, built Mubarak Manzil at Fatha-		Singh, built fort at Baij-	
bâd	70	nathroni	010
, built Bådshåhî Bågh at Khajuhå,	162	Bâkir Alî Khân, Nawâb, built masjid at	216
Ayodhyâ Râi, Râjbhâr chief, built mud		Fathpûr in A.H. 1075,	
fort at Ariâon Jahâniyân-		, built fort and masjid at	159
pûr	188	Johnson	
Azam Khân, built fort at Azamgarh about		Bakht Singh, Rájá of Bhadáwar, built tem-	162
A.D. 1760	187	ple of Walance and tem-	
Azam Shahîd, his tomb at Badaon, dated		ple of Madan Gopâl at Bâh	
1744 5-44	22	in A.D. 1752	69
A course Prince of the land of the land	187	Bála Bái, Ráni of Gwáliar, built temple at	
	-	Baladaya king of V	9
В.		Båladeva, king of Kanauj, contemporary	
Baba Bik, built masjid of Shah Kabir at		with Bahram Ghor, 316,	320
Towns A. C. A TT CO.	185	Bala Gharib Nath (Shah), his tomb at Bhu-	
Bâbar, Sulțân, built Jâmi Masjid at Ayodhyâ	200	Båland Dåta. 1 21 karheri	12
A TE ODA	297	Båland Råjås, built Agôrî Khâs	252
	201	, occupied fort of Bijament	256
at Sambhal	37	, built large tank at Kar-	
, built garden palaces in Zâhra and	07	80 Eit	261
Dahma Paul at A A	59	, constructed large tanks at	PANIFIE .
, built mausoleum of Chândan Shahîd	53	Noradih and PA=	262
ot Ismailnos Nos ad 3t-	QT	Baland Khan, cunuch of Jahangir, made	
ne rammibut Mut-un-mit	81	Baland Bagh at Agra	52

INDICES. 365

Pa	iges.					P	ages.
Baland Khân, Rohilla, fell in battle at Fath-		Bhag	vân Dâs, l	Râiâ of J	aypûr, erecte	d satî	
ganj	26		O STATE OF THE OWNER, WAS		Mathura in		
Bâla Pîr, or Shaikh Kabîr, tutor of Nawâbs				1000			107
Dilêr and Bahâdur Khân, his		Bhag	van Dâs.		r, mentione		
tomb at Kanauj, dated A.H.	5		Maries Inchina	The second second	inscription a		
1076 80 &	259				jî		145
Balarâma, destroyed asura Kola at Kôl	1	Bhars	dvåia. Ri		to have resid		
Balban, Sultân, see Ghîâs-ad-dîn Balban.					***		192
Baldêva Singh, Râjâ of Bhâratpûr, his		Bhara			f Kumaon, hi		
cenotaph at Gobar-	-	2000000		The state of the s	late grants of		
	101				at Asargâo		
Bali, asura, said to have founded Baliyâ or					rsaa		49
Balpûr	40	Bhar	tribe, tr		builder of fo		
, said to have built Parasûa Kôt	11.00	(Contraction)	A STATE OF THE OWNER, WHEN PARTY AND PARTY.		***		252
for his Ahîr servant	40				Bhadohî		254
Bâlwant Singh, Râjâ of Banâras, built brick	-				ts along the		
fort at Råmnagar in A.D.					ohi		255
	213				tor of large to		
, re-built portion of stone fort	-10				***		261
	252				Haidargarh,		
, repaired stone bridge near		70	201111012	sand. S	Subeha and A	methî,	264
Bijaygarh in Samvat			ditto	ditto			
	256	,	CITO 10		Kâkorî		265
	197		ditto	ditto	Arjunpûr,		
Bânêsura, son of Mahâbali, said to have built	-0.747 M	,	341.832	OHIERO .	hAra, Siris		
Kotalgarh	50				Nagram		267
Bappa Agnimitra, king of Ahichhattra,	-		ditto	ditto	Nigohan		268
mentioned in cave inscription at		,	ditto	ditto	Mawai		272
	144		ditto		Panhan		273
Barhan Shahîd, officer of Sa'îd Sâlâr, his	200	,	ditto		Bambhaur		
dargâh near Padaraunâ,	949	,			Såndå	***	288
Bariar Singh, father of Rani Gulab Kun-	~10		ditto	ditto	country a		
war, built brick fort at		,	1000000		Bahraîch		292
100 N 100	213		ditto	ditto	pargana of	His-	
Bâsdêo, mythical founder of Bareli, built	210		ditto		ampûr	***	293
mud fort at Bareli	25		ditto	ditto	Akbarpûr an	d par-	
Bûz Bahâdur Chandra, Râjû of Kumâon, his	20	,			gana of Am	Contract to the second	300
copperplate grant of Sake		1	ditto	ditto	pargapa of		
1654 at Pinnâth	50	,	31110	- AV. (100)	dânsâ, Maj		
, his copperplate grant	. 00				and Manga		301
of Sake 1566 at Siloti	48		ditto	ditto	Surharpûr,		
, his copperplate grant	40			SETTING A	na of Pac		
of Sake 1586 at Champâvat,	48				rath and		
, erected temple at	10				Tândâ	***	302
Bhim Tal	48		ditto	ditto	Ateha in P	ratâp-	
Bellan, Thakkura, treasurer of Gôsala Devî,	20	,		Towns Co. S. O. I.	garh distric	CONTRACTOR OF THE PARTY OF THE	314
queen of Govindachandra Dêva			ditto	ditto	Bachhrawan	100	319
	187		ditto	ditto	Dâlmâû abou	t A.D.	
	101	,			530	***	320
Bên, Râjâ Chakravartti, see Vêṇa. Bhâgmal, Râjâ, built fort at Phaphund	92		ditto	ditto	Inhauna and	Jais,	323
Bhagmal, Raja, built fort at Phaphund	9	3		resorting.			
	U	-					

Pages.	Pages.
Bhar tribe, formerly occupied Rat Bareli 324	Bhûdêva Dêva, Râjâ of Katyûrî dynasty, his
-, ditto ditto Bhawan and par-	inscription at Bagesvar 47
gaņa of Aldemāū, 325	Bhûiyâs (Bhûmiyas), aboriginal tribe, occupy
-, ditto ditto Dhopap 326	the Mîrzâpûr district, 255
-, traditional builder of large well at	Bhuvanapâla, Râshtrakûța prince of Vodâ-
Arju 327	mayûtâ 20
-, formerly occupied Musafirkhana and	Bhyars, aboriginal tribe, expelled from
Sultanpar 327	Farrukhâbâd district by Chan-
-, ditto ditto Kôtwâ 329	della Râjpûts 82
Bhargava, Rishi, said to have founded	Bîbî Râjî, queen of Mahmûd Shâh Sharqî,
Bhârgâon 86	built Lal Darwaza Masjid at
Bhartrinatha, younger brother of Vikrama-	Jaunpūr 183
ditya of Ujjayinî, resided	Bîbî Sâlehâ, daughter of Sulțân Shêr Shâh,
at Chunar 258	her tomb at Manikpur 317
Bhâskara (varman), king of Singhapura,	Bihâr Mal, Râjâ of Jaypûr, his widow com-
mentioned in stone inscription	mitted sati at Mathura 107
at Madha 8, 321	Bijlî Khân, erected cenotaph of Kabîr Dâs at
Bhil (Bhilla) tribe, formerly occupied Bil-	Maghar in A.D. 1450 224
grâm 277	, re-built Korâ in Akbar's time 162
Bhîmapâla, Râshtrakûța prince of Vodâma-	Bijlî Râjâ, traditional founder of great fort
yūtā 20	of Nathâwân 265
Bhîmasêna, king, his painted inscription of	Bîrbal, Râjâ, Akbar's general and companion,
Samvat 52 on Ginjâ Hill 137	born at Kâlpî 119
Bhîmasêna, son of Pâṇḍu, killed Kîchaka at	, his palace at Faṭhpûr Sîkrî 72
Hagrâm 288	, his record of Samvat 1632 on
Bhîmavarman, king of Kansâmbî, his stone	Asoka's lât at Allahâbâd 130
inscription of Guptasamvat	Bîr Singh Dêo, Râja of Orchhâ, his inserin.
139 at Kosām 142	tion of Samvat 1676 at Sir-
Bhishmaka, Raja of Vidarbha, his capital	Wabaran 117
identified with Ahar, Baland-	, built stone fort at Jhansi 118
shahr district 3, 4	Bisrâm Singh, tahsîldâr of Bâlwant Singh,
- with Kundilpar, Kheri dis-	built temple and sarâî at
triet 286	Naubatpûr 212
Bhoja Deva, king of Northern India, his	Brahmå, temple dedicated to—at Dûdâhî, 122
inscription of Samvat 964	
and Sake 784 at Dêogarh 120	scribed 136
, mentioned in huge inscription	Brihadbala, king of Ayodhya 296
of Samvat 964 at Sîronî	Buddha, born under sål tree in Lumbini
Khurd 124	garden at Kapilavastu, the mo-
, traditional builder of fort at	dern Bhûîlâ Dîh 218, 221
Bhôjpur, Farrukhâbâd dis-	expounded his doctrine at Ayodhyâ, 299
trict 77	, ditto ditto Banaras, 198, 213
, traditional site of palace at	- ditto dista
Agra ascribed to 68	, ditto ditto Sâketam 275
, his coins (Adivaraha drammas)	, ditto ditto Śrâvastî 307
found at Asokpûr 305	, attained nirvâṇa at Kusinagaram, 244
Bhri Shaka, Indo-Seythian king, his coins	, his charcoal ashes enshrined in
found at Tip 34	attem at Maria
Bhabala Dêva, Râjâ of Haldî, built fort at	, early statues of —found at Anyor,
Waina 195	mone Gabandhan
	near Gooardnan 101

Pages.	Pages.
Buddha, early statues of found at K6l 1	Chandragupta, II., mentioned in seal inscrip-
, ditto ditto Mathura 105	tion found at Bhitari 334
-, ditto ditto Pakhna Bihar, 82	, his undated inscription
, ditto ditto Sahet-Mahet, 306, 310	found at Mathura 332
, ditto ditto Sarnath, dated	- built temple of Pârvatî at
Samvat 1083 215	Devî-Pâtan 303
C.	city of Śrâvastî 307
Chait Singh, successor of Balwant Singh,	, said to have re-built Ayo-
embellished Râmnagar 213	dhyâ 296
Chakra, Râjâ, made Kausâmbî capital after	, his coins found at Manhan
the destruction of Hastina-	near Bastî 218
pura 140	, his coins found at Kotwa,
Champat Rai, commander of Prithviraja's	Gorakhpûr district 241
army, dug Chora Tal and	Chandrapâla, Râjâ, built fort at Asâî
built two barakhambhas at	
Transfer	
Chamscha, Brahmani girl, engulfed alive at	Chandraprabhânâtha, 8th Jina, born at Chandrikâpuri, a
	later name of Śrā-
Sravasti for falsely accusing Buddha of incontinence 310	vastl 308
	The second secon
Chand, famous Raja, traditional site of capi-	Chandrasêna, Dôr Râjâ of Baran, killed
tal of —at Aurangabad Chandok, 4	Khwaja Lal Ali in A.D.
——, poet, gives wrongly Samvat 1241	1193 5
as date of Chandella war 124	Chandravarman, traditional founder of
, mentions Orâî as battle-field between	Chandella dynasty, said
Prithîrâjâ and Parmâl 113	to have built fort Kâlañ-
, mentions Chandravarman as founder	jar 150
of Mahobâ 175	, traditional founder of
— Khân, built masjid at Barelî in A.H.	Mahoba 174, 175
1149 25	Cherû tribe, traditional founder of Chîrâiya
Chândan Shahîd, his tomb at Ismâîlpûr Nûr-	Kôt 187
nd-dfn 81	, formerly occupied Bansdih 191
Chandella, clan, formerly occupied Bijay-	, built forts at Zîrâbastî and
garh 257	Waina 195
Chandra, Råshtrakûta prince of Vodámayûta, 20	Chhîpi Khân, famous Bâchhil chief in Shâh-
Chandragupta, prince of Jalandhara, men-	jahân's time, built brick
tioned in stone inscription	fort at Kâmp 284
at Madhâ 8	Chimni Khan, his tomb at Badaon built in
, I., king of Imperial Gupta	Sikandar Lodi's time 22
dynasty, mentioned in	Chiragh All Shah, his tomb at Senthal 29
seal inscription found at	Chôr Bibi, her tomb at Kâlpi 113
Bhitari 334	D.
, his coins found at Tanda,	
Rat Barelt district 325	Dadhyaneh, Rishi, traditional founder of
II., king of Imperial Gupta	Misrikh 289
dynasty, his mutilated	Daksha, dishonoured Devî, or Pûrvatî, 16, 303
inscription of Samvat	, sacrifice ofinterrupted by Siva
88 at Garhwa 136	at Kankhal 16
, mentioned in cave inscrip-	Dâladêva, Râthor prince, traditional founder
tion near Chunâr 260	of Dâlmâû 320

(1) Hist of Professional States	
Pages.	Pages.
Dâolat Khân, built masjid at Makanpûr in	Dharani Varaha, king, his undated inscrip-
А.Н. 1022 170	tion found at Ghosi 188
, tomb of—at Badâon 22	Dhîradeva, Râjâ of Haldî, built fort at Haldî,
Dûra, or Mahi, architect, built fort at	about A.D. 1643 192
Mirath 10	Dildår Khån, Pathån, traditional founder of
	Dildårnagar 230
Dârâ Shikôh, defeated by his brother Aur-	Dilêr Khân, Nawâb, built Bala Pîr's
angzīb at Samonghar in A.D.	
1638 70	dargah at Kanauj in A.H.
Darya Khan, subahdar of Muhammad Ibra-	1076 80
hîm Sharqî, founded Darya-	, founded Shâhjahânpûr in
båd 263	A.D. 1647 43
Dasaratha, king of Ayodhya, fortified	, founded Shahabad in
the town with towers and	A.D. 1677 283
gates 296	Divåkaravarman, king of Singhapura, men-
Dattavarman, king of Singhapura, mention-	tioned in stone inscrip-
ed in stone inscription at	tion at Madha 8
Madha 8	Divodâsa, Buddhist king of Banâras 197
Dåûd Khân, built fort at Dâûdpûr in	Domana Deva, Raja, built brick fort at
the time of Ala-ad-din	Chandauli 212
Khiljî 319	Dom-kattar tribe, traditional builder of
Daurân Khân, Vazir Âzam, Nawâb, palace	The state of the s
of—at Âgrà 64	
Daya Râma, built fort at Hâthras Khâs 1	Dôr Râjpût clan, took possession of Baran
	about A.D. 1000 5
Devadatta, Buddhist king of Banaras 197	Drona, tutor of the Pandavas, traditional
, cousin and enemy of Buddha,	founder of Dankaur 6
swallowed up alive at Sra-	The state of the s
vastî 310	of Gurgâon 30
Devaki, mother of Krishna, resided at Ma-	-, foretold Adiraja his elevation to
thurâ 107	sovereignty 28
Devalabdhi, grandson of Chandella Yasovar-	, refused the arms of Brahma to king
man, built temple of Brahma	Karna 303
at Dûdâhî 123	Drupada, king, held court at Kâmpil, the
Devapâla, Râshtrakûța prince of Vodâma-	American & TEA
yûtû 20	traditional builder of stronghold
Devavarman Deva, Chandella king, his cop-	as also and The state of
perplate grant of Sam-	Drupedi develter of Devel
vat 1107 found at Nan-	Drupadi, daughter of Drupada, married the
yaurâ 177	five Påndavas at Kåmpil 78
Devî Singh, Thâkur, built fort at Nôh Jhîl	Dûndi Khân, Rohilla, built masjid, imâm-
in A.D. 1740 109	bûra, and fort at Bisaulî
Dhâkra Râjpût, clan, expelled from Dund-	about A.D. 1750 23
	, built palaces at Muradabad 37
	Duryodhana, Kuru prince, traditional site of
Dhanadêva, king of the Sûriyan (? Sabara)	lac palaces of—at Lachhå-
tribe, traditional founder of	gîr 143
Dhanapûr 230	ditto at Barnawa, 9
, copper coins offound at Ma-	() () () () () () () () () ()
sâon Dîh 233	F.
Dhungadeva, Chandella Râjā, his copper-	Faizî Fayazî, brother of Abal Fazl, built
plate grant of Samvat 1055	school of Manney
found at Nanyaurů 177	tomb of at A A
	s como of—at Agra 68

INDICES. 369

P	ages.	Page	08.
Fakhr-ad-dîn Alawî, dargâh of-at Banâ-	- 111	Fîrûz Shâh, III., Taghlaq, Sulțân, visited	
ras	200	Jaunpûr in A.H. 772 17	79
Faqîr Alî Bêg, governor, built bâoli near		, his inscrip-	
Tilbegampûr in A.H.		tion of A.H. 777 at	
945	7	Banâras 20)1
Fath Alî Khân, rebelled at Ajrara in Faslî		, built tomb	
1202	9	of Hazrat Ibn Sålår at	
Fath Khan, Shahzada, tomb of-at Badaon,		Sambalhêra in A.H.	
dated A.H. 860	23		14
, Rohilla, built twelve-domed mas-		, his inscrip-	
jid at Âonlâ	24	tion of A.H. 778 at	200
Fathmand Khan, founded Fathpur-Haswa		Jaunpûr 18	50
in A.H. 917	159	, his inscrip-	
Fath Muhammad Khân, Dehlî prince, found-		tion of A.H. 781 at Zafar-	400
ed Fathpûr, Bâra Bankî		åbåd 18	56
district	264	, his inscrip-	
Fayaz Ali, Qazî of Balandshahr, finished		tion of A.H. 782 at	000
Jâmi Masjid in A.D.		Akbarpûr 30)()
1830	5	, built dargâh	
Fazl Alî Khân, destroyed Zamâniyâ in A.D.	22222	at Bângarmâû în A.H.	20
1760	237	784 26	39.
Fazi-ullâh, Sa'îd, tomb of—at Dârânagar,	200	, his inscrip-	
dated A.H. 1008	139	tion of A.H. 786 at Kôh	10
, son-in-law of Sultan Farrukh		Inâm 14	£U.
Siyar, tomb of—at Shikar-	~	tion of Samvat 1415 at	
pûr, dated A.H. 1131	7	Lalitpûr 12	22
Fidaî Khân, Nawab, restored rauza of Kabîr			
Shâh at Maghar in A.D.	224	Ašoka's ediet pillar from	
Fîrûz Khân (Khwâja), eunuch of Jahângîr,	201		11
mausoleum of—at Âgrâ	65	- removed	~
, tomb of—at Fîrûz-	00	Asoka's edict pillar from	
Abâd	74	11 Marian Control of the Control of	16
Fîrûz Shâh, II., Khiljî, Sultân, founded Jalâ-	200	, removed	
lâbâd, Shâhjahânpur dis-		Aśoka's ediet pillar from	
trict	41	Kausambî to Prayaga 12	28
, murdered by his nephew at	22	, traditional	
Karrå in A H. 695	138	founder of Fîrûzâbûd,	
Fîrûz Shâh, III., Taghlaq, Sultân, his in-		Kheri district, in A.D.	
scription of A.H. 759 at		1350 28	34
Dâlmâû	320	, visited fort	
, his inscrip-		of Khairigarh in A.D.	
tion of A.H. 760 at Cha-		1355 28	35
kêsar	188	, visited dar-	
, his inscrip-		gâh of Sa'id Sâlâr at Bah-	
tions of A.H. 761 and		râich in A.D. 1374 29	92
762 at Bâzîdpûr, 165	, 169	, converted	
, built mas-		Ataladevî temple into a	
jid at Saṇḍilâ in A. H.		masjid at Jaunpûr in	
769	282	A.D. 1376 18	31
	-	121	

			70	
		ages.		ages.
	G.		Gosala Devî, queen of Govindachandra Dêva,	
	Gâdhi, Râjā of Gâdhipura, the modern Ghâ-	000	mentioned in inscription	
	zîpûr	236	of Samvat 1201 at Dab-	100
	Gaṇḍa Dêva, Chandella king, lost Kâlañjar	150	haon	188
	in A.D. 1023	262	Govindachandra Dêva, Râthor king of Kan-	
	Gangâ Bîbî, built masjid at Mîrzâpûr Ganj Baksh, tomb of—at Garhmuktêsar,	202	auj, his copperplate	
*	dated A.H. 682	9	grant of Samvat	
	Garga, Rishi, reputed hermitage of—op-		1161 found at Bisúhí	-00
	posite Asnî	158		90
	Gauramukha, believed to have destroyed the	100		
	asuras at Nimkhâr	290	auj, his copper- plate grant of Sam-	
	Ghafûr Zanjâni, Shaikh, tomb and well of	~0.0	vat 1166 found at	
	-at Kâlpî, built in		77.47	00
	Aurangzib's time	113	Râhan Râthor king of Kan-	92
	Ghatotkacha, king of Imperial Gupta	220	auj, his copperplate	
	dynasty, mentioned in		grant of Samvat	
	seal inscription found at		1174 found at Bisâhî,	90
	Bhîtarî	334		50
	Ghîâs-ad-dîn Balban, vazîr of Sultân Nâsir-)E2700	auj, his copperplate	
	ad-dîn Mahmûd, erected the		grant of Samvat	
	great minâr at Kôl, in A.H.		1180 found at Rai-	
	652	2	wân	200
	, Sultan, built Dargah Sharif at	1000		200
	Garhmuktêsar in A.H. 682	9	auj, his copperplate	
	- built masjid of Shah Wilayat at		grants of Samvat	
	Manglaur in A.H. 683	17	1181 and 1185 found	
	built masjid at Sakît in A.H. 684,	88	at Banâras	211
	———— built eastle at Bhôjpûr	77	, Rathor king of Kan-	17.44
2	built fort at Kâmpil	78	auj, his copperplate	
	- during his reign the city of		grant of Samvat	
	Jaunpûr was known	179	1188 found at Rên.	165
	— Taghlaq Shâh, Sulțân, changed		, his pillar inscription	
	name of Harapura to Haya-		of Samvat 1201 at	
	pura	10	Dabhâon	188
	, inscription of—dated A.H.		, his copperplate in-	
	722, at Mahobâ	176	scription of Samvat	
	Ghulam Ahmad, Shaikh, built idgah at		1208 found at Ban-	
	Amrohâ	35	glwan	263
	Ghulâm Haidar, tomb of —at Dârânagar,		, his copperplate in-	
	dated A.H. 1128	139	scription of Samvat	
	Gopa, Râjâ, traditional founder of Gôpa-	2500	1209 found at Mach-	
	māū	279	hlishahr	185
	Gopāla, Rājā of Gādhipura, or Kanauj	308	Gûgâ Chauhâna, born at Sarsâwâ	18
	, Rājā of Ahichhattra, mentioned in	200	Gulab Kunwar, Rani, wife of Balwant	100
	cave inscription at Pabhosa	144	Singh	213
	— Dêva, Rûshtrakûta prince of Vodâ-	-	Guman Singh, Raja of Jaitpur, built fort of	-3030
	mayûtâ Gorakhnûtha, inscription of his time at Devî-	20	Bhûragarh, A.D. 1746	146
	Pâton	000	Gunaprabha, monastery of-at Manda-	1000
	raian	303	war	32

... 293

(1) List of proper names of persons, with date	s and	places with which they are associated—(continu	ed).
Pa	iges.	P	ages.
Gupta, first king of Imperial Gupta dynasty,		Haradatta, traditional founder of Hapar,	
mentioned in seal inscription found		about A.D. 983	10
	334	conquered Mîrath and built fort,	11
Gupta dynasty, list of kings and queens of		Haranatha built fort at Asnî in Akbar's	
given in Bhîtarî seal inscrip-		time	158
	334	Harbans, Kâyath, Râjâ, built dwelling-house	
	4	at Badarqâ Harbans în	
, coins and inscription offound at		A.H. 1052	272
Râmnagar	29	Haribala, undated inscription of-on	
-, inscriptions of-found at Garh-	-100	colossal nirvâna statue of Buddha	
	136	at Kasiâ	245
	230	Harischandra, king of Ayodhya, traditional	
	140	founder of Hargâm	288
		, Râjâ of Kumâon, his copper-	
H.	-	plate grant of Sake 1383 at	
Håfiz Muhammad Afzal, built well at Köl in		Dadågåon	48
А.Н. 930	2	Harshavardhana, king of Sthanvisvara, his	
Hâfiz Mujâhid-ad-dîn, Haqîm, built nabî-	-77	copperplate grant of	
khûna at Badûon	-	Samvat 25 found at Ma-	
in A.H. 420	22	dhuban	189
Hafizah Begam, tomb of-at Allahabad,		Hasan Mahdî, Vazîr of Mahmûd Ghaznavî,	
dated A.H. 880	131	built Jâmi Masjid at Mîrath	
Hâhâjâl, Vazîr of Alâ-ad-dîn Khiljî, said to		in A.H. 410	11
have rebuilt old fort of Nim-		Håshim Faqir, rauza of-at Ismailpur,	
	290	dated A.H. 1038	139
Hâjî Abû, Sa'îd, founded Naushahr in the	eco.	Hâtila, sister's son of Sa'id Sâlâr, killed in	400
reign of Shâhjahân	94	battle at Asokpûr	304
Hâjî Harnâyam, shrine of—at Kanauj	79	Hâtim Khân, mausoleum of-at Chirâiyâ-	001
Hâjî Zâhid, built sarâî and masjid at		kôt	187
Dâlmâû in A.H. 1006	322	Hazâm-ad-dîn Hasan, Qâzî, built masjid at	-
Hammîra Dêva, Râjâ, built fort at Hamîr-	044	Kôh Inâm in A.H. 786	140
	171	Hazrat Tbn Sålår, tomb of-at Sambalhêrâ,	-
Hammîras, Musalmâns mentioned under	111	built in A.H. 777	14
this name in an inscription		Hazrat Pîr Zarî, shrine of-at Jâlesar,	180
of XIIth century found at		built in A.H. 1012	86
Badâon	20	Hidâyat Shâh, dargâh of—at Mandâwar,	32
Hamsadhvaja, Rājā, traditional founder of	20	Himmat Bahadur Kasim, built masjid at	0.2
Haswa	161	Pailânt in A.D.	
Hamsagupta, prince of Gupta dynasty, built	TOT	1702	155
fort at Jhûsî	138	Hindûpat, Râjâ of Pannâ, built fort at Bar-	100
Hamza Shahîd, tomb of-at Alîganj, built	100	garh	146
by Yâkût Khân	84	Hiranyakasipu, daitya king, said to have	130
Handavi, rakshasa, traditional founder of	01	been slain by Vishnu at	
	319	Sôron	88
Haqim Khan, Nawab, built masjid and well	013	, traditional site of palace	00
at Jhabarhêrû in A.H. 1198,	16	of—at Deokali	118
Haqîm Sultân Muhammad, built masjid at	10	Hîra Singh, Râjâ, built mud fort at Ekâ	92
Jaunpûr in A.H. 978	185	Hisâm-ad-dîn Taghlaq, governor of Audh,	-0.2
Haradatta, Dôr Râjpût chief, took possession	100	said to have founded Hisâm-	
4 Th	Ĕ	-Ar in A D 1940	202
of Baran and ballt fort	5	pur m A.D. 1240	293

Pages	. P	ages.
Holf, Jaina priest, his inscription of Samvat	Ibrâhîm Shâh Sharqî built mud fort and two	1.5
1481 at Dêogarh 120		319
Humâyûn Muhammad, Sultân, his inscrip-		320
tion of A.H. 936 in fort Kålañ-	repaired old Hindû fort	520
jar 15	The state of the s	320
— built masjid at Kachpûrwâ, Âgrâ,	built Jâmi Masjid at Jâîs,	324
in A.H. 937 5		UNI
- built mausoleum of Shaikh Abdul	old Hindû fort at Râî	
Kuddûs at Gângôh in A.H.	Th: 14	324
944 16		021
, his inscription of A.H. 960 at	tomb of Makhdûm Sa'îd	
Qasbâh Nigûn 189		205
, his undated inscription at Sårnåth, 21	THE PARTY OF THE P	325
		325
- besieged and took fort of Chunâr	Sikandar Shâh Lodî, Sulţân, built	
in A.D. 1536 25		-
visited Lakhnâû in A.D. 1530 26		2
Husain Shâh Sharqî, Sultân of Jaunpûr,	built fort at Kôl in	
built shrine of Makhdum	A.H. 931	3
Jahâniya at Kanauj in A.H.	Ikdil Khân, eunuch, built sarâi and mas-	
881 8		
finished Jâmi Masjid at Jaun-	1042	92
pûr in A.H. 883 18	AND DESCRIPTION OF THE PROPERTY OF THE PROPERT	23
built Jāmi Masjid at Machhli-	Tkram Khan, officer of Shahjahan, tomb of	
shahr 18		6
, traditional builder of masjid	Imad-al-mulk, tomb of—at Badaon, dated	
at Husainābād 19		23
Hûshang Ghorî, Sultân of Mândû, mentioned	Imâm Sa'âdat Khân built masjid at Shikâr-	
in inscription of Samvat	pûr in A.H. 1057	7
1481 at Dêogarh 12		
Huvishha, Indo-Skythian king, inscriptions	built in A.H. 901	13
of-found at Mathurà 10		177
I.	at Balandshahr	4
1	, coins of-found	1.0
Thâd-ullâh, Sa'id, traditional conqueror of	at Pachômî	26
Bhadohi 25		20
Ibrâhîm Nâîb Bârbak, brother of Fîrûz Shâh	A TOACCA	914
Taghlaq, built fort	Indo-Sassânian dynasty, coins of—found	314
and masjid at Jaun-	or Dan	65
pûr in A.H. 778 18	Indo-Skythian dynasty, coins of—found	95
- Pîr, Shaikh, dargâh of at Râm-	o+ Sahamal	
pûr 18	at Sâhēgarh	1
- Shâh Sharqî, Suljan of Jaunpür,	, cortis 01 10und	
built Jâmi Masjid at Kan-	at Tip	34
auj in A.H. 809 80	, coins of found	
built tomb of Shah Madar at	RE MRII	42
Makanpûr 168	, coins of—found	
- finished Ataladêvî Masjid at	ac I aunam	95
Jaunpûr 180, 181	, coins of—found	
built Jhanjhri Masjid at Jaun-	av tusaran-binar,	315
LAN.	, inscriptions of	
pur 181	found at Rûmnagar,	28

Indo-Skythian dynasty, inscriptions of—found at Mathura 105, 332	Pages	Pages.
found at Mathura 105, 332 inscriptions of—found at Pakhna Bihār 82 inscriptions of—found at Bhītā 182 inscriptions of—found at Bhītā 183 inscriptions of—found at Bhītā 183 inscriptions of—found at Bhītā 183 inscriptions of—found at Bhītā 183 inscriptions of—found at Srāvastī, Indradēva, Rājā of Katyūrī dynasty, copper—plate grant of—at Baijināth 183 Irādat Khān, Rājā of Āramgarh, founded Kopā in A.D. 1745 189 Isānašiva, head of monastery at Vodāmayūtā, built Šaiva temple 20 Islām Kān Rāmi, Vazīr, palace of—at Āgrā 62 — Shāh, grandson of Salim Chhishti, dated A.H. 988 71 — Sūr, Sulṭān, built tomb called chaukon at Badāon in A.H. 957 22 —, built majid inside fort Kālānjār 152 Isvarā, wife of prince Chandragupta of Jalandhara, built temple at Madhā 8 —, king of Maukhari dynasty, undated inscription of—at Madhā 8 —, king of Maukhari dynasty, undated inscription of—at Jaundpri 179 Itibār Khān, Khwāja, tomb of—at Āgrā 68 —, built large stone-walled sarāi at Kōsā 102 Itimād-ad-daulah, minister of Jahāngir, tomb of—at Āgrā 68 Itimād-ad-daulah, minister of Jahāngir, tomb of—at Āgrā 68 Itimād-ad-daulah, minister of Jahāngir, tomb of—at Āgrā 68 Itimād-ad-daulah, minister of Jahāngir, tomb of—at Āgrā 68 Itimād-ad-daulah, minister of Jahāngir, tomb of—at Āgrā 169 Itimād-ad-daulah, minister of Jahāngir, tomb of—at Firdzābād, dated 169 Itimād-ad-daulah, minister of Jahāngir, tomb of—at Firdzābād, dated 169 Itimād-ad-daulah, minister of Jahāngir, tomb of—at Firdzābād, dated 169 Itimād-ad-daulah, minister of Jahāngir, tomb of—at Firdzābād, dated 169 Itimād-ad-daulah, minister of Jahāngir, tomb of—at Firdzābād, dated 169 Itimād-ad-daulah, minister of Jahāngir, tomb of—at Firdzābād, dated 169 Itimād-ad-daulah, minister of Jahāngir, tomb of—at Firdzābād, dated 169 Itimād Khān, built strong fort at Khwāja 169 Itimād-ad-daulah, minister of Jahāngir, tomb of—at Firdzābād, dated 169 Itimād-ad-	Indo-Skythian dynasty, inscriptions of-	J.
Jagachehhandra, Råjä of Kumåon, undated copperplate grant of— found at Bhítů 132 found at Sarivat teap 48 found at Bhítů 132 found at Sarivat teap 48 found at Bhítů 132 found at Sarivat teap 48 found at Bhítů 132 found at Sarivat teap 48 found at Bhítů 132 found at Sarivat teap 48 found at Bhítů 132 found at Sarivat teap 48 found at Bhítů 132 found at Sarivat teap 48 found at Bhítů 132 found at Sarivat teap 48 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat teap 74 found at Sarivat	found at Ma-	Control of the Contro
found at Pakhna Bihar 82 1632	thurâ 105, 332	
Bihàr 82 , inscriptions of—found at Bhítů 132 , inscriptions of—found at Bhítů 132 , inscriptions of—found at Srávastů, 307 Indradéva, Růjů of Katyûrî dynasty, copperplate grant of—at Baij-nath 47 Irådat Khûn, Růjú of Âxamgarh, founded Kopů in A.D. 1745 189 Isânašiva, head of monastery at Vodůmayůtů, built Saiva temple 20 Islům Khûn Růmi, Vazůr, palace of—at Fathpûr Sikri, dated A.H. 988 71 —Sûr, Sultân, built tomb called chaukůn at Baddon in A.H. 957 22 — Shûh, grandson of Salim Chhishti, tomb of—at Fathpûr Sikri, dated A.H. 988 71 —Sûr, Sultân, built tomb called chaukůn at Baddon in A.H. 957 22 — built masjid at Kairânâ in A.H. 958 13 —, built masjid inside fort Khlañjar 152 Išvarů, wife of prince Chandragupta of Jilandhara, built temple at Madhâ 8 —, king of Maukhari dynasty, undated inscription of—at Madhâ 8 —, king of Maukhari dynasty, undated inscription of—at Jaunpûr 179 Itibûr Khâu, Khwāja, tomb of—at Āgrå 68 —, built large stone-walled saråi at Kôsi 102 Itimâd-ad-daulah, minister of Jahângîr, tomb of—at Agrå 68 —, built strong fort at Khwāja Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Fritūzâbād, dated 1034 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Fritūzâbād, dated 1034 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Fritūzâbād, dated 1034 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Fritūzâbād, dated 1034 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Fritūzâbād, dated 1034 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Fritūzâbād, dated 1034 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Fritūzâbād, dated 1034 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Fritūzâbād, dated 1034 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Fritūzâbād, dated 1034 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Fritūzâbād, dated 1034 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Fritūzâbād, dated 1034 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at	, inscriptions of	The Control of the Co
, inscriptions of found at Bhith 132	found at Pakhna	
found at Bhitât 132		
1632	, inscriptions of	
Jagat Singh, diwân of Râjâ Chhait Singh, built Jagatganj from the ruins of a stôpa at Sârnâth, 215 nâth		The state of the s
Indradêva, Râjâ of Katyûrî dynasty, copperplate grant of—at Baijnāth Trâdat Khân, Râjâ of Âxamgarh, founded Kopâ in A.D. 1745 Isânaŝiva, head of monastery at Vodâmayûtâ, built Saiva temple Islâm Khân Râmi, Vazîr, palace of—at Âgrâ		Tours Single Minter of Data Charle Story
ruins of a stûpa at Sûrnâth, 215 râdat Khân, Râjâ of Âzamgarh, founded Kopâ in A.D. 1745 189 Isânaŝiva, head of monastery at Vodâmayûtâ, built Śaiva temple 20 Islâm Khân Râmi, Vazîr, palace of—at Âgrâ		
Trâdat Khân, Râjâ of Âzamgarh, founded Kopâ in A.D. 1745 189		
Samvat 1628 74		Tarmal Die Panmin built fast at Thomas in
Jahânârâ Begam, daughter of Shâhjahân, private apartments of shansiva, head of monastery at Vodâmayûtâ, built Saiva temple 20 Islâm Khân Râmi, Vazîr, palace of—at Âgrâ 62 Shâh, grandson of Salīm Chhishti, tomb of—at Faṭhpūr Sikri, dated A.H. 988 71 Sūr, Sulṭân, built tomb called chaukôn at Badâon in A.H. 957 22 built masjid at Kairânâ in A.H. 958 13 built masjid at Kairânâ in A.H. 958 13 built masjid in A.H. 1010 130 Jalandhara, built temple at Madhâ 8, 331 Isvaravarman, king of Sighapura, mentioned in stone inscription at Maḍhâ 8 king of Maukhari dynasty, undated inscription of—at Agrâ 68 built large stone-walled sarâi at Kôsî 102 Itimâd-ad-daulah, minister of Jahângîr, tomb of—at Āgrā, 54, 55 Itimâd Khân, built strong fort at Khwāja holl 169 tumb of—at Firûzâbâd, dated tumb fort of Lat Latical Rain and the fort of Agrâ at Gâdgôn in A.H. 1019 in the fort of Agrâ at Gâdgôn in A.H. 1019 in the fort of Agrâ at Gâdgôn in A.H		
Sanašiva, head of monastery at Vodāmayūtā, built Śaiva temple		Johanara Rogam daughter of Shahiahan
Saint Name Saiva temple 20 Islâm Khân Rûmi, Vazîr, palace of—at Âgrâ 62 Shâh, grandson of Salîm Chhishti, tomb of—at Faṭhpūr Sikri, dated A.H. 988 71 Sūr, Sulṭân, built tomb called chaukôn at Badâon in A.H. 957 22 Jahângîr, Nûr-ad-din, Sulṭân, built Khusrû Bāgh at Allahābād, built in A.H. 1173 33 Jahângîr, Nûr-ad-din, Sulṭân, built Khusrû Bāgh at Allahābād in A.H. 1010 130 Sulṭân, built masjid in-side fort Kālañjar 152 Sivarâ, wife of prinee Chandragupta of Jahandhara, built temple at Maḍhā 8 Jahângîr Khân, tomb of—at Maḍhā 8 Jahāngār 58 Jaṭ at Allahābād, 129, 130 Jahāngār 58 Jaṭ at Allahābād, 129, 130 Jahāngār 56 Jahāngār 56 Jahāngār 56 Jahāngār 56 Jahānābād .		
Salam Khân Râmi, Vazîr, palace of—at Âgrâ 62		-in the fort of Acres 60
Shah Kalin, Valar Palace of Agra 62		
—— Shâh, grandson of Salîm Chhishti, tomb of—at Faṭhpūr Sikrî, dated A.H. 988 —— 71 —— Sūr, Sulṭān, built tomb called chaukôn at Badāon in A.H. 957 —— 22 —— built masjid at Kairānā in A.H. 958 13 —— built masjid inside fort Kālaūjar 152 fīšvarā, wife of prince Chandragupta of Jālandhara, built temple at Maḍhā —— 8 —— tioned in stone inscription at Maḍhā —— 8 —— king of Maukhari dynasty, undated inscription of— at Jaunpūr 179 fītibār Khān, Khwāja, tomb of—at Āgrā 68 —— built large stone-walled sarāi at Kōsi —— 102 fītimād-ad-daulah, minister of Jahāngīr, and 169 fītimād Khān, built strong fort at Khwāja Phāl —— 169 Twaz Beg, Khān Bahādur, Hizabr-i-Jang, tomb of—at Faṭpābād, dated —— shail masjid at Khān, built kārapā —— 169 fītimād Khān built strong fort at Khwāja phāl —— 169 Twaz Beg, Khān Bahādur, Hizabr-i-Jang, tomb of—at Faṭpābād, dated —— in the fort of dated A.H. 1019, in the fort of Agrā 61 —— 169 Twaz Beg, Khān Bahādur, Hizabr-i-Jang, tomb of—at Faṭpābād, dated —— 162 —— 162 —— 162 —— 163 —— 163 —— 164 —— 165 —— 166 —— 1		from A. H. 1053 to 1058 69
Nathhanjan 189		
Jahângîr Khân, tomb of—at Najîbâbâd, built in A.H. 1173 33 Jahângîr, Nûr-ad-dîn, Sulţân, built Khusrâ Bâgh at Allahâbâd in A.H. 957 22		-7 10
Sûr, Sultân, built tomb called chaukôn at Badâon in A.H. 957 22		Jahangir Khan tomb of at Naithabad
Sur, Sultān, built tomb called chaukôn at Badâon in A.H. 957 22 Dahângîr, Nûr-ad-din, Sultān, built Khusrû Bâgh at Allahâbâd in A.H. 1010 130 Sultān, black marble throne of, dated A.H. 1011, in the fort of Âgrâ, 58 A.H. 1011, in the fort of Âgrâ, 58 A.H. 1014 on Aŝoka's lât at Allahâbâd, 129, 130 A.H. 1015 in the fort of Âgrâ 56 A.H. 1015 in the fort of Âgrâ 56 A.H. 1015 in the fort of Âgrâ 56 A.H. 1015 in the fort of Âgrâ 56 A.H. 1015 in the fort of Âgrâ 56 A.H. 1018 23 A.H. 1018 23 A.H. 1018 23 A.H. 1019, in the fort of Âgrâ 68 A.H. 1019, in the fort of Âgrâ 61 A.H. 1019, in the fort of Âgrâ 61 A.H. 1029, 35 A.H. 1034 15		
Bâgh at Allahâbâd in A.H. 957 130 13		ACCORD TO BE CARRED TO SELECT THE SECOND SECURITIES AND SECOND SE
A.H. 957		Bach at Allahahad
Sultān, black marble throne of —, dated A.H. 1011, in the fort of Âgrâ, 58		The state of the s
Throne of dated A.H. 1011, in the fort of Âgrâ, 58		Sultan black marble
A.H. 1011, in the fort of Âgrâ, 58		
Îsvarâ, wife of prince Chandragupta of Jâlandhara, built temple at Madhâ 58 ple at Madhâ 8, 331 Îsvaravarman, king of Siûghapura, mentioned in stone inscription at Madhâ 8 , king of Maukhari dynasty, undated inscription of at Jaunpâr 8 , king of Maukhari dynasty, undated inscription of at Jaunpâr 179 Îtibâr Khân, Khwâja, tomb of—at Âgrâ 179 Îtibâr Khân, Khwâja, tomb of—at Âgrâ 68 —, built large stone-walled sarâî at Kôsî 102 Îtimâd-ad-daulah, minister of Jahângîr, tomb of—at Âgrâ, 54, 55 54, 55 Îtimâd Khân, built strong fort at Khwâja 169 Twaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbâd, dated 169 Twaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbâd, dated 169		A.H. 1011, in the
Jâlandhara, built temple at Madhâ		fort of Âgrû, 58
ple at Madhâ 8, 331 Îsvaravarman, king of Siâghapura, mentioned în stone inscription at Madhâ	AND THE RESIDENCE OF THE PARTY	, his inscription of
Îsvaravarman, king of Siaghapura, mentioned în stone inscription at Madhâ 8 , his inscription of A.H. 1015 in the fort of Ågrå 56 , king of Maukhari dynasty, undated inscription of at Jaunpâr 179 179 Îtibâr Khân, Khwâja, tomb of—at Âgrâ 68 Jalâl at Badâon in A.H. 1018 23 , stone bath of—, dated A.H. 1019, in the fort of Âgrâ 61 dated A.H. 1019, in the fort of Âgrâ 61 , built Masjid-î-Chillaat Amrohâ in A.H. 1029, 35 Amrohâ in A.H. 1029, 35 Îtimâd Khân, built strong fort at Khwâja Phâl 169 Twaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbâd, dated 169 Twaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbâd, dated —in the fort of		
tioned in stone inscription at Maḍhâ 8		lất at Allahâbâd, 129, 130
at Madhâ 8		, his inscription of
		A.H. 1015 in the fort
undated inscription of—at at Jaunpûr	The state of the s	of Ågrå 56
ât Jaunpûr 179 Îtibâr Khân, Khwâja, tomb of—at 68 Âgrâ 68 —, built large stone-walled sarâi the fort of Âgrâ at Kôsî 102 Îtimâd-ad-daulah, minister of Jahângîr, Amrohâ in A.H. 1029, 35 tomb of—at Âgrâ, 54, 55 , built Masjid Rêrî Îtimâd Khân, built strong fort at Khwâja at Gâûgôh in A.H. Phâl 169 Twaz Beg, Khân Bahâdur, Hizabr-i-Jang, , so-called palace of tomb of—at Firûzâbâd, dated —in the fort of		, built Ziârat-î-Shaikh
Îtibâr Khân, Khwâja, tomb of—at A.H. 1016 23 Âgrâ 68 dated A.H. 1019, in the fort of Âgrâ 61 102 , built Masjid-î-Chillaat Amrohâ in A.H. 1029, 35 35 Îtimâd Khân, built strong fort at Khwâja at Gâûgôh in A.H. 1034 15 Twaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbâd, dated , so-called palace of , so-called palace of -in the fort of		Jalal at Badaon in
Âgrâ 68 dated A.H. 1019, in the fort of Âgrâ 61 at Kôsî 102 , built Masjid-î-Chilla at Amrohâ in A.H. 1029, 35 Îtimâd ad-daulah, minister of Jahângîr, tomb of—at Âgrâ, 54, 55 Amrohâ in A.H. 1029, 35 , built Masjid Rêrî Îtimâd Khân, built strong fort at Khwâja at Gâûgôh in A.H. 1034 Phâl 169 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbâd, dated , so-called palace of in the fort of		A.H. 1018 23
		, stone bath of,
at Kôsî 102 Îtimâd-ad-daulah, minister of Jahângîr, tomb of—at Âgrâ, 54, 55 Îtimâd Khân, built strong fort at Khwâja Phûl 169 Twaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbûd, dated Twaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbûd, dated Twaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbûd, dated Twaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbûd, dated		dated A.H. 1019, in
Îtimâd-ad-daulah, minister of Jahângîr, Amrohâ in A.H. 1029, 35 tomb of—at Âgrâ, 54, 55 built Masjid Rêrî Îtimâd Khân, built strong fort at Khwâja at Gâûgôh în A.H. Phâl 169 1034 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, , so-called palace of tomb of—at Firûzâbâd, dated —in the fort of		the fort of Âgra 61
tomb of—at Âgrâ, 54, 55 Îtimâd Khân, built strong fort at Khwâja Phûl 169 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbûd, dated Twaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbûd, dated in the fort of		, built Masjid-î-Chilla at
Îtimâd Khân, built strong fort at Khwâja Phûl 169 Iwaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbûd, dated Twaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbûd, dated in the fort of		Amroha in A.H. 1029, 35
Phûl 169 Twaz Beg, Khân Bahâdur, Hizabr-i-Jang, tomb of—at Firûzâbûd, datedin the fort of		, built Masjid Rêrî
Twaz Beg, Khân Bahâdur, Hizabr-i-Jang,, so-called palace of tomb of—at Firûzâbâd, datedin the fort of		
tomb of —at Firûzâbûd, dated —in the fort of		1034 15
4 TT 1100		, so-called palace of
A.H. 1189 74 Âgrû 60	44.00	
05		A CONTRACTOR OF THE CONTRACTOR

		Continue	u.j.
was a second state of the second	Pages		ages.
Jahûngîr, Nûr-ad-dîn, so-called palace of-		Jât tribe, constructed fort at Sâsnî and	
at Faṭhpûr Sîkrî	. 7	Tuhsân, Alîgarh district	3
Jahân Khân, Nawâb, built masjid and Ran	g	, traditional founder of Mîrath	10
Mahal at Râi Barelî în A.H		Jatilabdhi, king, inscription of-in fort	
1040		7741 61	152
, Râjâ of Âzamgarh, built masji	1	Jawahir Mal, merchant, built Sîtâkund at	100
at Dohrîghât		Mîrath in A.D. 1714	99
	î	Jawâhir Singh, Jâṭ Râjâ of Dîg and Bhârat-	11
in A.H. 1168	200	pûr, desecrated Akbar's	
Jajhar Khan, dargah of-at Badaon, dated		tent to Cit 2.4	(1200)
A.H. 950	800	, erected cenotaph of his father,	77
Jalal-ad-din, traditional builder of fort at		, exected conocaph of his lather,	
Sirsår		Sûraj Mal, at Gobardhan	101
		John Mainer King	
dated A.H. 1057		of Kanauj, copperplate	
		grants of—, dated	
II.	12	Samvat 1232, 1233 and	
Jalal Khan, governor of Jaunpar, built		1236	334
bridge over the Såi at Jalål-		, stone inscription of	
pår in A.D. 1510		—, dated Samvat	
Jala (varman), king of Singhapura, men-	1/8	1241, found at Ayo-	
tioned in stone in the		dhyâ	297
tioned in stone inscription		, copperplate grant of	OWNER.
at Madhà	8	, dated Samvat	
Jamadagni, Rishi, said to have resided at	-	1243, found near	
Khairā Dih		TT - 41 42	301
, traditional founder of Zama-		, buried his treasures	101
niyâ	236	at Asnî before his	
Jamal Shah, Shams-ad-din Ariffn, dargah		last fight with Mu-	
of—at Kôl, dated A. H.		ham - 1 (1) A	**
949	2	, traditional builder of	58
Janamejaya, celebrated king, performed		Bullion Transfer	
great snake sacrifice at Ahâr,		, built fort at Hath-	38
Balandshahr district	3	nA.	
, at Dêokâlî,		gâon 1	61
Kherî district	286	, built fort at Kuṭilâ, 1	63
Jarasandha, king of Magadha and Chedi,		, built temple of Ata-	
granted the city of Malini to		ladêvî and another	
king Karna	303	close to Muktaghât	
Jarasimha, Rājā, said to have built palace at		at Jaunpûr 18	80
Jargaon	36	, built stone fort at	
Jas, Bhêr Râjâ, traditional founder of	2.5	Zafanālāā	35
Jasnaul, or Bara Banki	263	odyapata, Tomara Raja, killed by the Chan-	
Jaswant Singh, Båghel Råjå, built eastle and	200	dena Raja of Kalaniar in A D	
tank at Tirwâ	84	1022	70
, Râjâ of Jôdhpûr, ehhattrî	GI	dayavan, wife of Bhaskaravarman of Sincha	200
(mausoleum) of—at Râj-		Dura	1
months A and	in.	seta, prince of Sravasti, added the next	
Jat tribe, took fort of Köl and changed the	67	Portion to the difference	0
name to Ramgarh about A.D.		Jhabbû Bîbî, wife of Nawâb Hasan Khân,	ð.
1757	100	built masjid at Mornah in	
1191	3	A.H. 1138	3
		1	1

Page	Pages
Jhâmajî, see Makhdûm Jahâniya Jahângasht.	Kalyânachandra III, Râjâ of Kumâon, cop-
Jñanachandra, Raja of Kumaon, his copper-	perplate grant of—,
plate grant of Sake 1320 at	dated Sake 1629 and
Dadâgûon 4	8 1654, at Bangātalā 48
, his copper-	, copperplate grant of
plate grant of Sake 1334	dated Sake 1655, at
and Samvat 1469 at	Champavat 48
Tapnipâl 4	
, his copper-	Bâh, Agrâ district 69
plate grant of Sake 1341	Kamâl-ad-dîn, Sa'îd, tomb of-near Kâth-
at Govinda-Pachauli 4	8 ka-pul, dated A.H. 995 316
, his copper-	Kamal Khan, tomb of-at Karra, dated
plate grant of Sake	A.H. 989 139
1356 at Râigâon 4	
Jodh Bai, queen of Jahangir, mausoleum	traditional site of capital of
ofat Ågrå 6	5 —at Kansmandi Kalân, 265
, palace at Fathpur Sikri, wrongly	Kanakamuni Buddha, born at Kanakpûr 221
ascribed to 7	1 Kanishka, Indo-Skythian king, inscriptions
Jûnân, cousin of Fîrûz Shâh, III, said to	of-found at Mathurs, 106, 332
have given name to Jaunpür 17	9 Kapila, Rishi, performed religious austeri-
K.	ties at Hardvår 15
	, said to have resided at Kâpilî
Kabîr Bâla, Shâh, son of Kâsim Sulaimânî	Dih 222
Shâh, mausoleum of-at	Kapilavardhana, Råjpåt chief, father of
Kanauj 80, 25	lsvarå, princess of Jal-
Kabîr Dâs, or Shâh, Hindû reformer, ceno-	andhara 331
taph of—at Ma-	Karamat Alf, Maulavi, built imambara at
ghar, built in A.D.	Fathpûr 264
1450 224	Karam Bêg, grave of-, dated 1118, at
, masjid built at Jaun-	Fathpûr 159
pår in honor ofin	Karna, Rājā, traditional founder of Karan-
A.H. 991 185	
Kachera, tribe, traditional founder of Bam-	, traditional founder of Raja
bhaur and Sândâ 288	
Kaiqubâd, Sultân, built masjid at Amrohâ	, traditional founder of fort at
in A.H. 686 35	Karawar 35
Kalandar Shâh, tomb of—at Kalandarpûr,	, traditional founder of Karn-
dated A.H. 1118 190	prayAg 45
Kalil-ur-Rahman, governor of Maghar, tomb	, traditional founder of Râo
of—at Maghar 224	Karna 276
, Qâzî, built Khudâî Masjid	, traditional founder of Hathiya
at Gorakhpûr 242	Kund 293
Kalyanachandra I, Raja of Kumaon, copper-	, traditional site of capital of
plate grants of——, dated Sake 1362 and	
	Karnadeva, king of Chedi, mentioned in
1383 at Dådågåon 48	stone inscription found at
H, Râjâ of Kumâon, copper-	Jhânsî 333
plate grant of—, dated Sake 1481, at	Kåša, king of Banåras 197
Dalladan 10	Kåsim Khån, superintended building of Fort
Dådågåen 48	at Agrā 56

Pages.	ages.
Kâsim Sulaimâni, Shâh, mausoleum of-, Khwâja Lâl Alî, dargâh of-at Baland-	self.ca+
dated A.H. 1016, at shahr, dated A.H.	
Chunâr 259 1030	5
Kâsinâth Adhikâri, servant of Bâz Bahâdur — Baranî, tomb of—at Baran	5
Chandra, founded Ka- Kichaka, chief of the army of king Virâța,	
sipûr 50 killed at Hagrâm	288
Kåsyapa Buddha, born at Tandwå 294 Kilkili Såhib, tomb of-in the ruined fort	
Katîra, Râna of Mewâr, built fort at Jalêsar at Sarsûwâ	18
in A.D. 1403 86 Kîrttichandra, Râjâ of Kumâon, copperplate	
Khairandesh Khan, Nawab, built masjid at grant of-, dated Sake	
Mîrath 12 1422, at Pââ	48
Khân Bahâdur Khân, âmil of Azamnagar, Kîrttivarman, king of Chandella dynasty,	
built brick fort at Thana inscription of —, dated Sam-	
Daryâoganj 89 vat 1154, at Deôgarh	120
	120
ganj 93 Gerâhô	116
Khângar, Râjâ, father of Râjâ Rôl, the, mutilated inscription of	****
founder of Kågåraul 75 found at Mahobå	175
Khân-î-Azam Khân, mukhtâr of Kharîd, ———, constructed Kîrat Sâgar at	710
built masjid at Kharîd in Mahobâ	174
A.H. 933 193 — , mentioned in large stone in-	11.2
Khirâdhâra, king of Śrâvastî, about A.D. scription found at Jhânsî,	333
275 307 Kôl tribe, traditional builder of fort near	000
Khizr Khân, built sarâî Abdûrrasûl at Sarâî Ahraurâ	252
Aghat in A.H. 1097 88 ——, traditional builder of fort Bijay-	404
Khūbū Kôka, Shaikh, foster brother of garh	256
Jahângîr, repaired Jâmi Krakuchchhandra Buddha, born at Nagara,	221
Masjid at Badâon in A.H. Kripânâth Singh, built brick fort at Barâ-	241
1013 21 gâon in A.D. 1737	212
Khushâl Singh, âmil of the Nawâb of Far-, built brick fort at Pind-	212
rukhâbâd, built fort at râh	213
Nidhauli 87 Krishna, founder of Kalachuri dynasty, con-	210
Khusrû Shâh, son of Jahângîr, tomb of—, quered Kâlañjar in A.D. 250	150
dated A.H. 1931, at Allah- ond horn at Mathura	150
abad 130 cradled at Mahahan	106
Khwâja Alî, tomb of—at Kachpûrwâ, ——, decoyed away Rukminî from	103
Âgrû, dated A.H. 968 55 the temple of Ambikû at	
Basant Khân, built fort at Airira	
376 43 37 4 3	4
Thethirm Redshalt built	
Sakit in A.H. 970. 88 Wannell A.	2430
Îsa, the Jâmi Masjid at Jaunpûr Kshêma, Râjâ of Mekhala, resided at Khem-	286
built in honor of 182 rainar resided at Knem-	g/Luc
T T A COLUMN TO THE COLUMN THE CO	221
of the Factors D	
, constructed canal Kharé	a constitution
at Baddon in A.H. 798. 23 Knår Dhir Sahi tanditi	286
- Karrak, tomb of at Karra, built	
A.H. 709 and repaired Kukâlî Ruddhiet nun and I	237
A II cost	
Sråvastî for slandering Buddha	310

(1)	List of	proper	names of	persons,	with	dates and	places	with	which	the	y are	associated-	(continued).	
-----	---------	--------	----------	----------	------	-----------	--------	------	-------	-----	-------	-------------	--------------	--

Kumåragupta I, king of Imperial Gupta dynasty, inscription of ——————————————————————————————————	Pages,	Pages.
dynasty, inscription of —, dated Sanivat 98, found at Bilarar	Kumaragupta I, king of Imperial Gupta	Lâlâ Davâl Dâs, merchant, built the Talâh
-, dated Sainvat 96, found at Billaar 86 -, inscription of, dated Sainvat 98, found at Garhwâ 136 -, inscription of, dated Sainvat 129, found at Mankuâr 133 -, undated inscription of at Garhwâ 134 -, undated inscription of at Garhwâ 135 -, undated inscription of 136 -, mentioned in seal inscription of 136 -, mentioned in seal inscription of 134 -, mentioned in undated inscription of Sainvat temples at Devâl in Sainvat 1049 219 -, inscribed bricks of 136 -, gold coins of Skanda-gupta at Bhitari 230 -, gold coins of found at Jahasi 138 -, gold coins of found at Jahasi 138 -, gold coins of found at Koṭwâ 241 -, ting of Imperial Gupta dynasty, inscribed copper-silver seal of found at Bhitari , 230, 334 -, found at Bhitari 241 -, ting of Imperial Gupta dynasty, inscribed copper-silver seal of found at Bhitari 241 -, ting of Imperial Gupta dynasty, inscribed copper-silver seal of found at Bhitari 241 -, ting of Imperial Gupta dynasty, inscribed copper-silver seal of found at Bhitari 241 -, ting of Imperial Gupta dynasty, inscribed copper-silver seal of found at Bhitari 241 -, ting of Imperial Gupta dynasty, inscribed copper-silver seal of found at Bhitari 241 -, ting of Imperial Gupta dynasty, inscribed copper-silver seal of found at Bhitari 241 -, ting of Imperial Gupta dynasty, inscribed copper-silver seal of found at Bhitari 241 -, ting of Imperial Gupta dynasty, inscribed copper-silver seal of found at Bhitari 241 -, ting of Imperial Gupta dynasty, inscribed copper-silver seal of found at Bhitari 241 -, ting of Imperial Gupta dynasty, inscribed copper-silver seal of found at Bhitari 241 -, ting of Imperial Gupta dynasty, inscribed copper-silver seal of found at Bhitari 241 -, ting of Imperial Gupta dynasty, inscribed copper-silver seal of found at Bhitari 241 -, ting of Imperial Gupta dynasty 241	dynasty, inscription of	
Sainvat 98, found at Garhwâ 136	—, dated Samvat 96,	0.0 425 333 Acc. 70 P.S.
Sanivat 98, found at Gaphwâ	found at Bilsar 86	
Sanivat 98, found at Garhwâ	, inscription of, dated	
Garhwâ	Samvat 98, found at	
	Garhwâ 136	
Sainvat 129, found at Mankuâr	, inscription of, dated	
Mankuâr at Sârlpfar at Sârlpfar at Sârlpfar at Sârlpfar at Sârlpfar at Sârlpfar at Sârlpfar at Garhwâ at G	Samvat 129, found at	
Saiva temples at Devâl in Sainvat at Sârphar , undated inscription of—		Lalla, Rûjâ of the Chhinda race built two
Lal Pîr, dargâh of—at Gopāmāû, built in A.D. 1332		1010
at Garhwâ 136 —, mentioned in seal inscription found at Bhitari 334 —, mentioned in undated inscription of Skandagupta at Bhitari 220 —, inscribed bricks of— found at Bhitari 230 —, gold coins of—found at Jhâs 241 —, gold coins of—found at Kôṭwâ 241 —, liking of Imperial Gupta dynasty, inscribed copper-silver seal of—found at Bhitari, 230, 334 Kuŝamba, Rājā, traditional founder of Kanauj 78 Lidli Begam, sister of Faizl and Abūl Fazl, tomb of—at Āgrā, dated A.H. 1004 68 Lakhaṇadeva, king of Kanauj, pillar inscription of—at Āgrā, dated A.H. 1004 68 Lakhaṇapala, Rāshṭrakūṭa prince of Vodāmayūṭā, undated inscription of—found at Badāon 202 Lakshmichandra, king of Katyūri dynasty, erected temple at Bagösvari na A.D. 1450 Lakshmichandra, kaif monument of—at Sāhanpūr, dated A.H		224
Lakshmichandra, king of Kanauj, pillar inseription of—at Âgrâ, dated A.H. 1004 Lakshmichandra, king of Katyûri dynasty, erected temple at Bagês-var in A.D. 1450 Lakshmi Rânî, satt menument of—at Kâthanadeva, king of Katyûri dynasty, erected temple at Bagês-var in A.D. 1450 Lakshmi Rânî, satt menument of—at Kâthanadeva, king of Katyûri dynasty, erected temple at Bagês-var in A.D. 1450 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Lakshmi Rânî, satt menument of—at Sâhanpdr, dated A.H. 1016 Latlí Shâhb, mauscleum of Rau, sat Chakiâ 225 Lakshmi Rânât, traditional founder of Sânapdr, dated Samat late of Sânapdr, dated Samat late of Sânapdr, dated Samat late of Sânapdr, dated Samat late of Sânapdr, dated Samat late of Sânapdr, dated Samat late of Sânapdr, dated Samat late of Sânapdr, dated Samat late of Sânapdr, dated Sânapdr, dated Sânapdr, dated Sânapdr, dated Sânapdr, dated Sânapdr, dated Sânapdr, dated Sânapdr, dated Sânapdr, dated Sânapdr, dated Sânapdr, dated Sânapdr, d	The Contract	A TO A SAME
tion found at Bhitari 334 mentioned in undated in- scription of Skanda- gupta at Bhitari 220 miscribed bricks of— found at Bhitari 230 gold coins of—found at Jhūsi 138 gold coins of—found at Kōṭwā 241 Lohajangha, assura, traditional founder of Lohajangha, assura, traditional founder of Lohajangha, assura, traditional founder of Lohajangha, assura, traditional founder of Lohajangha, assura, traditional founder of Lohajangha, assura, traditional founder of Lohajangha, assura, traditional founder of Lohajangha, assura, traditional founder of Lohajangha, assura, traditional founder of Lohajangha, assura, traditional founder of Vihatkathā of Sômadeva 103 Lorî, washerman, mentioned in connection with a ruined stūpa at Sārnāth 215 M. Madana, Rājā, copperplate grant of—, said to have been found at Zamā- niyā 236 miyā 236 matitional founder of Kanauj 230 miyā 236 Lakhaṇadeva, king of Kanauj, pillar inscription of—, dated Samivat 1253, at Belkhārā 252 Lakhaṇapāla, Rāshṭrakūṭa prince of Vodāma- yūtā, undated inscription of —found at Badāon 20 Lakshmichandra, king of Katyūri dynasty, erected temple at Bagēš- var in A.D. 1450 47 Lakshmī Rānī, satī menument of—at Sāhanpdr, dated A.H. 1116 34 Barāh Chhetra 225 Lava, son of Rāmachandra, traditional ruler of Śrāvastī 367 Lodi Shāh, Bādshāh, tomb of—at Kālpfi 113 Lohajangha, assura, traditional founder of Lohabau 103 Madana, Rājā, copperplate grant of—, said to have been found at Zamā- niyā 236 myat 140 matritional founder of Kanau, prition of Samīvat 1276 found at Sāhet-Māhet 308 Madanapāla, Rāshṭrakūta prince of Vodāma- yūtā, undated inscription of —found at Badāon 20 Lakshmīchandra, king of Kanauj, copper- plate grant of—, dated Samīvat 1106, found at Rāhan 332 Madanavarman Dēva, king of Chandella dy- nasty, copperplate grant of—, dated Samīvat 1190, found * at Augūsī 145		
Latif Shâh, mausoleum of—at Chakiâ 257		The second secon
scription of Skandagupta at Bhitari 220 inscribed bricks of — found at Bhitari 230 gold coins of — found at Jhúsi 138 gold coins of — found at Kôṭwā 241 Lohaban 104	, mentioned in undated in-	The state of the s
General Bhîtari		
Lodd Shâh, Bâdshâh, tomb of—at Kâlpl 113		A A A A A A A A A A A A A A A A A A A
found at Bhîtarî 230 Lohajangha, asura, traditional founder of Lohaban 103 104 Lohajangha, asura, traditional founder of Lohaban .		
Jhûsî 138 —, gold coins of—found at Kôṭwâ		
The state of the s	The second secon	100 TO 10
Lakhaṇadeva, king of Kanauj, pillar inscription of —found at Baltari 253, at Belkhārā 252 Lakshmīchandra, king of Katyūri dynasty, erected temple at Bagēsvar in A.D. 1450 241 Lakshmī Râṇi, satī monument of —at Sāhaupūr, dated A.H. 1116 34		
Madana, Râjâ, copperplate grant of——, said to have been found at Zamâniyâ		
dynasty, inscribed copper-silver seal of—found at Bhîtarî, 230, 334 Kušâmba, Râjâ, traditional founder of Kau-śâmbî 140 Kušanābha, Râjâ, traditional founder of Kanauj 78 L. Lâdli Begam, sister of Faizi and Abūl Fazl, tomb of—at Âgrā, dated A.H. 1004 68 Lakhaṇadeva, king of Kanauj, pillar inscription of—found at Badāon 252 Lakhaṇapāla, Rāshṭrakūṭa prince of Vodāma-yūtā, undated inscription of—found at Badāon 20 Lakshmīchandra, king of Katyūri dynasty, erected temple at Bagēs-var in A.D. 1450 47 Lakshmī Rāṇī, satī monument of—at Sāhanpūr, dated A.H. 1116 34 Madana, Rājā, copperplate grant of—, said to have been found at Zamāniyā 236 —erected temple and stone pillar at Lāṭiyā 236 —, vercome in fight by Parašu-rāma at Zamāniyā 236 —, king of Kanauj, mentioned in inscription of Samvat 1276 found at Sāhet-Māhet 308 Madanapāla, Rāshṭrakūṭa prince of Vodāma-yūtā 20 —, Rāṭhor king of Kanauj, copper-plate grant of—, dated Samvat 1166, found at Rāhan 332 Madana, Rājā, copperplate grant of—, said to have been found at Zamāniyā 236 —, erected temple and stone pillar at Lāṭiyā 236 —, vercome in fight by Parašu-rāma at Zamāniyā 236 —, king of Kanauj, mentioned in inscription of Samvat 1276 found at Sāhet-Māhet 308 Madanapāla, Rāṣhṭrakūṭa prince of Vodāma-yūtā 252 Madanapāla, Rāṣhṭrakūṭa prince of Vodāma-yūtā 252 Madanapāla, Rāṣhṭrakūṭa prince of Vodāma-yūtā 252 Madanapāla, Rāṣhṭrakūṭa prince of Vodāma-yūtā 252 Madanapāla, Rāṣhṭrakūṭa prince of Vodāma-yūtā 252 Madanapāla, Rāṣhṭrakūṭa prince of Vodāma-yūtā 252 Madanapāla, Rāṣhṭrakūṭa prince of Vodāma-yūtā 252 Madanapāla, Rāṣhṭrakūṭa prince of Vodāma-yūtā 252 Madanapāla, Rāṣhṭrakūṭa prince of Vodāma-yūtā 252 Madanapāla, Rāṣhṭrakūṭa prince of Vodāma-yūtā 252 Madanapāla, Rāṣhṭrakūṭa prince of Vodāma-yūtā 252 Madanapāla, Rāṣhṭrakūṭa prince of Vodāma-yūtā 252 Madanapāla, Rāṣhṭrakūṭa prince of Vodāma-yūtā 252 Madanapāla, Rāṣhṭrakūṭa p		
per-silver seal of— found at Bhitari, 230, 334 Kušāmba, Rājā, traditional founder of Kau- sāmbî 140 Kušanābha, Rājā, traditional founder of Kanauj 78 L. Lâdli Begam, sister of Faizi and Abūl Fazl, tomb of—at Âgrā, dated A.H. 1004 68 Lakhaṇadeva, king of Kanauj, pillar inscription of—found at Badāon 252 Lakhaṇapāla, Rāshtrakūta prince of Vodāma- yūtā, undated inscription of—found at Badāon 20 Lakshmî Rānī, satī menument of—at Sāhanpūr, dated A.H. 1116 34 Madana, Rājā, copperplate grant of—, said to have been found at Zamā- niyā 236 , erected temple and stone pil- lar at Lāṭiyā 236 , overcome in fight by Parašu- rāma at Zamāniyā 236 , performed aēvamedha at Za- mâniyā 236 —, king of Kanauj, mentioned in in- scription of Samvat 1276 found at Sāhet-Māhet 308 Madanapāla, Rāshtrakūta prince of Vodāma- yūtā 20 —, Rāthor king of Kanauj, copper- plate grant of—, dated Sam- vat 1166, found at Rāhan 332 Madana, Rājā, copperplate grant of—, said to have been found at Zamā- niyā 236 —, erected temple and stone pil- lar at Lāṭiyā 236 —, performed aēvamedha at Za- mâniyā 236 ——, king of Kanauj, mentioned in in- scription of Samvat 1276 found at Sāhet-Māhet 308 Madanapāla, Rājā, copperplate grant of—, dated Samvat 1166, found at Rāhan 332 Madanapāla, Rājā, copperplate grant of—, said hiyā 236 ——, verceted temple and stone pil- lar at Lāṭiyā 236 ——, king of Kanauj, mentioned in in- scription of Samvat 1276 found at Sāhet-Māhet 308 Madanapāla, Rājā, copperplate grant of—, said hiyā 236 ——, king of Kanauj, mentioned in in- scription of Samvat 1276 found at Sāhet-Māhet 308 Madana, Rājā, copperplate grant of—, said hiyā 236 ——, king of Kanauj, mentioned in in- scription of Samvat 1276 found at Sāhet-Māhet 308 Madana, Rājā, copperplate grant of—, said hiyā 236 ——, king of Kanauj, mentioned in in- scription of Samvat 1276 found at Sāhet-Māhet 308 Madanapāla, Rāshtrakūta prince of Vodāma- yūtā 252 Madanapāla		
Kušāmba, Rājā, traditional founder of Kau- šāmbî 140 Kušanābha, Rājā, traditional founder of Kanauj 78 L. Lādli Begam, sister of Faizi and Abūl Fazi, tomb of—at Âgrā, dated A.H. 1004 68 Lakhaṇadeva, king of Kanauj, pillar inscription of —, dated Samvat 1253, at Belkhārā 252 Lakhaṇapāla, Rāshṭrakūṭa prince of Vodāma- yūtā, undated inscription of ——found at Badāon 20 Lakshmīchandra, king of Katyūri dynasty, erected temple at Bagēs- var in A.D. 1450 47 Lakshmī Rāṇi, satī monument of—at Sāhanpūr, dated A.H. 1116 34 to have been found at Zamā- niyā 236 —, erected temple and stone pil- lar at Lāṭiyā 236 —, performed aēcamedha at Za- māniyā 236 —, king of Kanauj, mentioned in in- seription of Samvat 1276 found at Sāheṭ-Māheṭ 308 Madanapāla, Rāshṭrakūṭa prince of Vodāma- yūtā 20 ——, Rāṭhor king of Kanauj, copper- plate grant of—, dated Sam- vat 1166, found at Rāhan 332 Madanavarman Dēva, king of Chandella dy- nasty, copperplate grant of—, dated Samvat 1190, found * at Augāsī 145	Value Value	M.
Kušāmba, Rājā, traditional founder of Kau- šāmbî 140 Kušanābha, Rājā, traditional founder of Kanauj 78 L. Lādli Begam, sister of Faizi and Abūl Fazl, tomb of—at Âgrā, dated A.H. 1004 68 Lakhaṇadeva, king of Kanauj, pillar inscription of —found at Badāon 252 Lakhaṇapāla, Rāshṭrakūṭa prince of Vodāma- yūtā, undated inscription of —found at Badāon 20 Lakshmīchandra, king of Katyūri dynasty, erected temple at Bagēs- var in A.D. 1450 47 Lakshmī Rāṇi, satī monument of—at Sāhanpūr, dated A.H. 1116 34 to have been found at Zamā- niyā 236 , erected temple and stone pillar at Iāṭiyā 236 , overcome in fight by Parašu- rāma at Zamāniyā 236 , performed aɛɛamedha at Za- māniyā 236 Madanapāla, Rāshtrakūṭa prince of Vodāma- yūtā 230 Madanapāla, Rāshtrakūṭa prince of Vodāma- yūtā 230 Madanapāla, Rāshtrakūṭa prince of Vodāma- yūtā 232 Madanavarman Dēva, king of Chandella dy- nasty, copperplate grant of—, dated Sainvat 1190, found * at Augāsī 145	found at Bhitari, 230, 334	Madana, Râjâ, copperplate grant of, said
Takhanapâla, Râjâ, traditional founder of Kanauj		to have been found at Zama-
L. Tâdli Begam, sister of Faizî and Abûl Fazl, tomb of—at Âgrâ, dated A.H. 1004 68 Lakhaṇadeva, king of Kanauj, pillar inscription of—, dated Samvat 1253, at Belkhârâ 252 Lakhaṇapâla, Râshtrakûta prince of Vodâmayûtâ, undated inscription of—found at Badâon 20 Lakshmîchandra, king of Katyûri dynasty, erected temple at Bagêsvar in A.D. 1450 47 Lakshmî Rânî, satî menument of—at Sâhanpûr, dated A.H. 1116 34 lar at Lâṭiyâ 236 , performed aévamedha at Zamâniyâ 236 , king of Kanauj, mentioned in inscription of Samvat 1276 found at Sâheț-Mâheț 308 Madanapâla, Râshtrakûta prince of Vodâmayûtâ 20 ——, Râthor king of Kanauj, copperplate grant of—, dated Samvat 1166, found at Râhan 332 Madanavarman Dêva, king of Chandella dynasty, copperplate grant of—, dated Samvat 1190, found at Augâsî 145	śâmbî 140	niyâ 236
Lâdli Begam, sister of Faizî and Abûl Fazl, tomb of—at Âgrâ, dated A.H. 1004	Kusanabha, Raja, traditional founder of	
Lâdli Begam, sister of Faizî and Abûl Fazl, tomb of—at Âgrâ, dated A.H. 1004 68 Lakhaṇadeva, king of Kanauj, pillar inscription of—, dated Samvat 1253, at Belkhârâ 252 Lakhaṇapâla, Râshṭrakûṭa prince of Vodâmayûtâ, undated inscription of —found at Badâon 20 Lakshmîchandra, king of Katyûri dynasty, erected temple at Bagêsyvar in A.D. 1450 47 Lakshmî Rânî, satî menument of—at Sâhanpûr, dated A.H. 1116 34 râma at Zamâniyâ 236 —, king of Kanauj, mentioned in inscription of Samvat 1276 found at Sâheṭ-Mâheṭ 308 Madanapâla, Râshṭrakûṭa prince of Vodâmayûtâ 20 ——, Râṭhor king of Kanauj, copperplate grant of—, dated Samvat 1166, found at Râhan 332 Madanavarman Dêva, king of Chandella dynasty, copperplate grant of—, dated Samvat 1190, found at Augâsî 145	Kanauj 78	CONTROL CONTRO
Lådli Begam, sister of Faizî and Abûl Fazl, tomb of—at Âgrâ, dated A.H. 1004 68 Lakhaṇadeva, king of Kanauj, pillar inscription of—, dated Samvat 1253, at Belkhârâ 252 Lakhaṇapâla, Râshṭrakûṭa prince of Vodâmayûtâ, undated inscription of—found at Badâon 20 Lakshmîchandra, king of Katyûri dynasty, erected temple at Bagêsvar in A.D. 1450 47 Lakshmî Râṇî, satî monument of—at Sâhanpûr, dated A.H. 1116 34 Tama at Zamāniyâ 236 —, performed aévamedha at Zamâniyâ 236 —, king of Kanauj, mentioned in inscription of Samvat 1276 found at Sâheṭ-Mâheṭ 308 Madanapâla, Râshṭrakûṭa prince of Vodâmayûtâ 20 —, Râṭhor king of Kanauj, copperplate grant of—, dated Samvat 1166, found at Râhan 332 Madanavarman Dêva, king of Chandella dynasty, copperplate grant of—, dated Samvat 1190, found at Augâsî 145	L.	
tomb of—at Âgrâ, dated A.H. 1004 68 Lakhaṇadeva, king of Kanauj, pillar inscription of—, dated Samvat 1253, at Belkhârâ 252 Lakhaṇapâla, Râshṭrakûṭa prince of Vodâma- yûtâ, undated inscription of —found at Badâon 20 Lakshmîchandra, king of Katyûri dynasty, erceted temple at Bagês- var in A.D. 1450 47 Lakshmî Râṇî, satî monument of—at Sâhanpûr, dated A.H. 1116 34 mâniyâ 236 —, king of Kanauj, mentioned in in- scription of Samvat 1276 found at Sâhaṭ prince of Vodâma- yûtâ 20 ——, Râṭhor king of Kanauj, copper- plate grant of—, dated Sam- vat 1166, found at Râhan 332 Madanavarman Dêva, king of Chandella dy- nasty, copperplate grant of—, dated Samvat 1190, found * at Augâsî 145		
A.H. 1004 68 Lakhaṇadeva, king of Kanauj, pillar inscription of —, dated Samvat 1253, at Belkhârâ 252 Lakhaṇapâla, Râshṭrakūṭa prince of Vodâmayûtâ, undated inscription of ——found at Badâon 20 Lakshmîchandra, king of Katyūri dynasty, erected temple at Bagêsvar in A.D. 1450 47 Lakshmî Rânî, satî menument of — at Sâhanpûr, dated A.H. 1116 34 A.H. 1004 68 , king of Kanauj, mentioned in inscription of Samvat 1276 found at Sâhatyî prince of Vodâmayûtâ, Râshṭrakūṭa prince of Vodâmayûtâ 20 ———————————————————————————————————		
Lakhaṇadeva, king of Kanauj, pillar inscription of —, dated Samvat 1253, at Belkhârâ 252 Lakhaṇapâla, Râshṭrakûṭa prince of Vodâmayûtâ, undated inscription of ——found at Badâon 20 Lakshmîchandra, king of Katyûri dynasty, erected temple at Bagêsvar in A.D. 1450 47 Lakshmî Rânî, satî monument of—at Sâhanpûr, dated A.H. 1116 34 Sâhanpûr, dated A.H. 1116 34 Samvat 1276 found at Sâheṭ-Mâheṭ 308 Madanapâla, Râshṭrakûṭa prince of Vodâmayûtâ 20 ———, Râṭhor king of Kanauj, copperplate grant of——, dated Samvat 1166, found at Râhan 332 Madanavarman Dêva, king of Chandella dynasty, copperplate grant of——, dated Samvat 1190, found at Augâsî 145	A A	
tion of—, dated Samvat 1253, at Belkhârâ 252 Lakhaṇapâla, Râshṭrakûṭa prince of Vodâma- yûtâ, undated inscription of —found at Badâon 20 Lakshmîchandra, king of Katyûri dynasty, erected temple at Bagês- var in A.D. 1450 47 Lakshmî Râṇî, satî menument of—at Sâhanpûr, dated A.H. 1116 34 at Sâheṭ-Mâheṭ 308 Madanapâla, Râshṭrakûṭa prince of Vodâma- yûtâ 20 ——, Râṭhor king of Kanauj, copper- plate grant of—, dated Sam- vat 1166, found at Râhan 332 Madanavarman Dêva, king of Chandella dy- nasty, copperplate grant of—, dated Samvat 1190, found * at Augâsî 145		
Lakhaṇapâla, Râshṭrakûṭa prince of Vodâma- yûtâ, undated inscription of ——found at Badâon 20 Lakshmîchandra, king of Katyûri dynasty, erected temple at Bagês- var in A.D. 1450 47 Lakshmî Râṇî, satî monument of—at Sâhanpûr, dated A.H. 1116 34 Madanapâla, Râshṭrakûṭa prince of Vodâma- yûtâ 20 ——, Râṭhor king of Kanauj, copper- plate grant of—, dated Saṁ- vat 1166, found at Râhan 332 Madanapâla, Râshṭrakûṭa prince of Vodâma- yûtâ 20 ——, Râṭhor king of Kanauj, copper- plate grant of—, dated Saṁ- vat 1166, found at Râhan 332 Madanapâla, Râshṭrakûṭa prince of Vodâma- yûtâ 20 ——, Râṭhor king of Kanauj, copper- plate grant of—, dated Saṁ- vat 1166, found at Râhan 332 Madanapâla, Râshṭrakûṭa prince of Vodâma- yûtâ 20 ——, Râṭhor king of Kanauj, copper- plate grant of—, dated Saṁ- vat 1166, found at Râhan 332 Madanavarman Dêva, king of Chandella dy- nasty, copperplate grant of—, dated Saṁvat 1190, found * 1116 34	The state of the s	
Lakhaṇapâla, Râshṭrakûṭa prince of Vodāma- yûtâ, undated inscription of ——found at Badâon 20 Lakshmîchandra, king of Katyûri dynasty, erected temple at Bagês- var in A.D. 1450 47 Lakshmî Râṇî, satî monument of—at Sâhanpûr, dated A.H. 1116 34 Lakshmî Rânî, satî monument of—at Sâhanpûr, dated A.H. 1116 34 Lakshmî Rânî, satî monument of—at Sâhanpûr, dated A.H. 1116 34	and the second s	
yûtâ, undated inscription of —found at Badâon 20 Lakshmîchandra, king of Katyûri dynasty, erected temple at Bagês- var in A.D. 1450 47 Lakshmî Rânî, satî menument of—at Sâhanpûr, dated A.H. 1116 34 ——, Râthor king of Kanauj, copper- plate grant of—, dated Sam- vat 1166, found at Râhan 332 Madanavarman Dêva, king of Chandella dy- nasty, copperplate grant of—, dated Samvat 1190, found * at Augâsî 145		
——found at Badâon 20 Lakshmîchandra, king of Katyûri dynasty, erected temple at Bagês- var în A.D. 1450 47 Lakshmî Rânî, satî monument of—at Sâhanpûr, dated A.H. 1116 34 plate grant of—, dated Sam- vat 1166, found at Râhan 332 Madanavarman Dêva, king of Chandella dy- nasty, copperplate grant of—, dated Samvat 1190, found * at Augâsî 145		
Lakshmîchandra, king of Katyûri dynasty, erected temple at Bagês- var in A.D. 1450 47 Lakshmî Rânî, satî monument of—at Sâhanpûr, dated A.H. 1116 34 Nadanavarman Dêva, king of Chandella dynasty, copperplate grant of—, dated Samvat 1190, found * at Augûsî 145	No. of the second secon	
erected temple at Bages- var in A.D. 1450 47 Lakshmî Rânî, satî monument of—at Sâhanpûr, dated A.H. 1116 34 Madanavarman Dêva, king of Chandella dynasty, copperplate grant of—, dated Samvat 1190, found * at Augâsî 145	The state of the s	1100 0 1 100
var în A.D. 1450 47 nasty, copperplate Lakshmî Rânî, satî monument of—at grant of—, dated Sâhanpûr, dated A.H. Samvat 1190, found * 1116 34 at Augâsî 145		
Lakshmî Rânî, satî monument of—at Sâhanpûr, dated A.H. Samvat 1190, found * at Augûsî 145		
Sâhanpûr, dated A.H. Samvat 1190, found * at Augûsî 145	The state of the s	
1116 34 at Augûsî 145		
11 11y	The same of the sa	

Pa	ges.	Pages.
Madanavarman Dêva, traditional founder		Mahmûd, Sultân of Ghaznî, destroyed Kan-
	173	Control of the second of
- , constructed Madan	0,000	
	174	, visited Asi in A.H. 409 89 , conquered Mûnj in A.D.
, undated inscription		7.049
of-found at		, besieged Kålafijar in A.D.
the foot of the		7000
hillock Rôṇi 3	333	, said to have advanced as
Madar Sahib, tomb of-at Kalpi, built in	C. (10.)	
Akbar's time 1	113	far as Banâras 198 Mahmûd Shâh Ghâzî, tomb of—in the cita-
Madar Shah, tomb of-at Makanpur 1	169	del at Kûnch 114
Mådho Singh, Råjå, rebuilt fort of Agorî	313.00	, traditional builder of
Khûs in A H. 1026, 2	252	Jâmi Masjid at Îrichh, 114, 117
Mahâbat Khân, palace of—at Âgrâ	62	Mahmûd Sharqî, Sultân of Jaunpûr, com-
— , bâgh of—at Âgrâ	64	menced building Jami Masjid
Mahabat Shah, faqir, tomb ofat Patan 2	72	nt Tomas Aug 1 at and
Mahaditya, king of Maukhari dynasty, in-		, built IAl Dar-
scription of-found at Ma-		-0
thurd 1	07	Waza masjid at Jaunpūr 183 Mahmūd Taghlaq, Sultūn of Dehlî, inscrip-
Mahakasyapa, chief disciple of Buddha,		tion of —, dated A.H. 815,
halted at Pāwā 2	39	_ 1 T + 1 + 1
Mahasénagupta Devî, queen of Adityavar-		at Irichh 114, 117
dhana, king of		Khwāja-î-Jahân governor of
	89	the Pear D
Mahêndrapâla Dêva, son of king Bhoja Dêva,		Makaradhvaja, Rājā, built temple of Kherā
inscription of,		Devata at Kosî în Samvat
dated Samvat 964,		700
at Sîroņî Khurd 1	24	Makhdûmah Jahân, mother of Sultân Ala-
Mahêndra Singh, Rûjû, built fort of Farîd-		ad-din Alam, tomb of
	38	—at Badáon, dated
Mahi, architect, traditional builder of the		A TI coo
fort at Mîrath]	10	Makhdûm Akhai, Jamshîd Sâhib, tomb of
The state of the		-nt Râjgîr, dated
Barsânâ 9	37	A II OAD
Mahîpa, Chêrû chief, ruled at Dêorî 19	01	Makhdûm Jahâniya Jahângasht, alias Jhâ-
Mahîpâla, Rûjâ of Gauda, inscription of,		maji, tomb of—at Kanauj,
dated Samvat 1083, found at		dated A H QQ1
Sårnåth 215, 33	34	dargâh of
, traditional founder		at Dalmin dated A Tr Took
of Mahôli 28	39	calling tomb of the state of
Mahîpâla Dêva, Tômara, king of Indrapras-		, Chiragh-i-Hind, cave dar-
tha, or ancient Dehli,		Out of The Total
traditional founder of	13	Hasan Ghorî, dargâh of—
Mirath 1		at Nob TLO
, inscription of ,	1	Makhdûm Sa'id Jâfrî, tomb of—at Râi
dated Samvat 1173,		Repolt
found at Ahâr	4	Barelî, erected by Ibrâhîm Shâh
, king of Kanauj, inscription		Shand
of—, dated Samvat 974,	1	Makhdûm Shâh, dargâh of—at Baland-
found at Asni, 158, 160	0	SDADE

Page	8. Pages
Makhdûm Shâh, dargâh of-at Barnâwâ,	Mûn Môr, Nâyak, erected temple at Dibhôr
	0 5 7 1 1001
- dargâh of at Bâzîdpûr,	Mân Singh Dêva, Râjâ of Ambêr, or Jay-
dated A.H 761, 165, 16	
	palaces of—at Âgra, 63
âbâd, dated A.H. 781 18.	
, dargâh ofat Sa'idpûr, 23	
, dargâh ofat Mallawan, 28	The state of the s
, Jûran Ghorî, destroyed an-	, constructed masonry tank,
cient temple of Adinatha	called Manasi Ganga,
at Ayodhyl 29	
Makin Shahid, tomb of-at Kâmpil 78	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2
Makrand Rai, built masjid of the Sunnis at	at Mathurů 108
Barell, about A.D. 1667 28	
, built fort and tomb of Shah-	åras about A.D. 1600 198
dâna at Barelî25, 26	Mansûr Alî Khân, Nawâb, founded Fâîz-
Malâmat Shâh, dargâh of-at Baddû	åbåd 301
Sarāi 263	
Malik Bahri, conquered the Ghazipur dis-	pûr 316
triet 234	
Malik Kûfûr, erected îdgûh at Rûprî in A.H.	båd, now deserted 327
711 95	
Malik Mardan, tomb of-at Sadiabad 234	
Malik Tahir, tomb of-at Man Nathhan-	, built brick fort at
jan 189	manamus 201
Malik Tâj-ad-dîn Ahmad, converted Hindû	Mariam-uz-zamanî, Akbar's supposed Chris-
temple into masjid at	tian wife and mother of
Mahobâ, in A.H. 722 176	Jahangir, palace of-
Malik Tutî, built masjid at Dalvî in A.H.	at Fathpûr Sîkrî 72
718 263	, tomb of—at Sikandrå, 76
Malik-us-Sa'adat Masa'ûd Ghâzî, said to have	Ma'sûm Khân, governor of Jaunpûr in A.H.
founded Ghâzîpûr in A.H. 780 231	978 185
	Mata'mid Khân, treasurer of Jahangir, built
Mallas, nobles of Kusinagara, palace of—, 247 Manadeva, Rathor prince of Kanauj, tradi-	masjid at Agra 67
tional founder of Manapura, the	Mayûradhvaja, king of Ayodhyâ and Śrâ-
	vasti, traditional founder
modern Manikpûr 316 Mandala Rishi, said to have lived at Mân-	of Môrdhaj 33
Control of the Contro	, connected by tradition with
digåon 267 Måndhåtrî, king of Ayodhyâ, traditional	the foundation of Haswi, 161
	, traditional founder of Maura-
founder of Manua 289 Mangalisa, king of Chalukya dynasty, came	wân 273
	Mîna Shah, takia of—at Badaon, dated
Into contact with the Kalachuris, 150 Iangal Khan, built brick fort and residence	А.Н. 896 23
The state of the s	———, tomb of—at Lakhnåů, dated
at Tilhar 43 Iangal Saîn, Rajpat, traditional founder of	A.H. 884 267
	Mir Almas Ali Khan, minister of Asaf-ad-
fort at Manglaur 17 Iânikyachandra, Râthor prince of Kanauj,	daulah, built fort at
traditional founder of	Kudârkôţ 91
THE REAL PROPERTY AND ADDRESS OF THE PARTY AND	, built tank and bâradarî
Māṇikpūr 316	at Korâ 163

Pages.	Pages.
Mir Almas All Khan, built brick fort at	Mubâraq Shâh II, Sa'îd, Sulțân of Dehlî, tomb
Pariâr 273	of-—at Dehlî 179
Mîrân Sadr Jahân, Akbar's chancellor, dar-	, first Sulțân of Jaunpûr 179
gah and masjid of-	, son of Humâyûn, traditional
at Pihânî, built A.H.	founder of Bårî 287
1057—1067 281	Muhammad Adil Shah, Sultan, built masjid
Mîrân Sa'îd Husain, tomb of-at Majhêrâ,	of Haidar Shah at Badaon
dated A.H. 1000 13	in A.H. 957 22
Mîrâ Sâhib, dargâh of—at Banâras 205	Muhammad Afzal, grandson of Shah Kasim
Mîrâ Tîlan, tomb of—at Mahobâ 176	Sulaimāni, tomb of
Mîr Bhâwan, Mâratha lender, repaired fort	at Chunar, dated A.H.
at Garhmuktêsar 9	1028 259
Mîr Hindû Bêg, built Jâmi Masjid at Sam-	, built masjid at Mårhara
bhal in A.H. 983 87	in A.H. 1145 87
Mîr Khân, built masjid at Ayodhyâ in A.H.	Muhammad Ajmal Chaudhari, rebuilt Zamā-
930 297	niyâ about A.D. 1765, 237
Mir Muhammad, governor, built palace at	Muhammad Badr Bakht, Sultan of Dehli,
Aslā in Shāhjahān's time, 213	razed fort at Lonî
Mîr Sâhib Shaikh Saddû, dargâh of—at Jâwarâ 101	about A.D. 1789, 10
	Muhammad Bakhtiyar Khilji, Sultan of Ban-
Mîr Tûfân, tomb of—at Mânikpûr, dated	gâl, received the
A.H. 995 317	two districts of
Mîrzâ Âin-al-mulk, built Mîrzâî Masjid at	Bhagwat and
Barell in A.H. 98725, 26	Bhaili in fief in
Mîrzâ Atâ Bêg, built masjid at Kopâ în A.H.	A.D. 1196 253
Mîrzâ Muhammad Yûsuf, built bâolî at Salî	Muhammad Dâyam, built masjid at Karrâ
in A.H. 977 85	in A.H. 1143 163
Misrî Shahîd, dargâh of—at Sakît, built	Muhammad Gêsû Khân, erected îdgâh at Kôl
in A.H. 1061 88	in A.H. 970 2
Mitra dynasty, coins of-found at Râm-	Muhammad Hâjî, dargâh of-at Bhôjpûr,
nagar27, 29	Murådåbåd district 35
Miyan Bahlal, Khan Bahadur, built masjid	Muhammad Haqîm, grandson of Shâh Kâsim
at Balandshahr in A.H.	Sulaimani, tomb of—at
1006 5	Chunar, dated A.H. 1028 259
Miyan Nûri Shâh, faqîr, built sarâl and mas-	Muhammad Kanaujî, Sa'id, tutor of Aurang-
jid at Yûkûtganj in	zîb, built Rang Mahal
A.H. 1086 84	at Kanauj in A.D.
Miyan Sahib, tomb of-at Sahaswan 24	1685 79
Mohsîn Khân, Nawâb, built masjid at Jaun-	Muhammad Khan N. 60 at Kanauj, 80
pûr in A.H. 975 185	Muhammad Khân, Nawâb, built mud fort at
Môna tribe, built mud forts in pargana Bha-	Farrukhâbâd in A.D.
dohî 255	1714 77
Môriyas, city of the-in the Nyagrodha	, built fort at Fathgarh 78
forest near Barhî 237	, built eastle at Muham-
Mubaraq Shah I, Khilji, Sultan of Dehli,	madåbåd 82
inscription of, dated	, Sa'ld, tomb of at Ma-
A.H. 716, found at Dal-	Muhammad Mt. Add Sant A.H. 982, 13
måå 320	Muhammad Mir Adil, Sa'ld, repaired Jami
built masjid at Bhafff 255	Masjid at Amroha
	in A.H. 981 35

- 1	Pages.		Pages.
Muhammad Murâd, built Âlamgîrî darwâza		Mun'im Khan, built bridge over the Sal at	- "9"
of fort Kalanjar in		Sikrârâ în A.H. 979	185
A.H. 1084	151	Muzaffar Husain, grandson of Ismail Shah	100
Muhammad Râza Shâh, Sa'id, dargâh of-		Sûfî of Persia, built	
at Baisumā	10	Kâli Masjid at Âgrâ	66
, built masjid at Bil-		N.	00
haur in A.H. 1110,	168	Nabî Khân, âmil of Dehlî, traditional	
Muhammad Sålih, built masjid at Ganjahra		founder of Nabinagar, now	
in A.H. 1099	190	The state of the s	212
Muhammad Shah, Sultan of Dehli, built large		Någa tribe, occupied ancient Balandshahr	
bâolî at Sâhanpûr in		Naîn Singh, Gûjar Rajā, repaired and	4
A. H. 1126	34	strengthened fort at Pari-	
, built masjid of Nizâm-ad-		chhatgarh	10
dîn at Badâon in A.H.		Najaf Khân, took fort of Kôl and changed	12
1140	22	name to Aligarh	
, erected masjid at Manohar-	O.F.	Najîb-ad-daula, founder of Najîbâbâd, tomb	3
pûr in A.H. 1158	108	of—, dated A.H. 1180	00
Muhammad Shâh Sharqî, Sultân of Jaunpûr,	200	Najîb Khân, Rohilla, built fort of Ghaus-	33
killed by his brother,		1 / Y 34347 / 3	
Husain Shâh, at Dâlmâû		garh at Jalâlâbâd	13
în A.H. 863	320	, fell in battle against the English	
Muhammad bin Taghlaq, Sultan of Dehli,	0.00	at Bhitaurâ in A.D. 1794	26
restored Jâmi Masjid at Ba-		, built castle at Kîratpûr, Bîjnôr district	
dâon in A.H. 726	21		31
, repaired dargâh of	70	Nakula, Pandava, traditional founder of Na-	- 55
Mîrânjî at Badâon		kûr	17
in A.H. 728	21	Nandivardhana, king of Magadha, inscription	202
, encamped at Kâm-	~~	of —found at Ayodhyâ	298
pil in A.H .745,	78	Nand Râijî, Krishua's foster-father, reputed	
, visited dargah of		home of—at Nandgåon	109
Sâlâr Masa'ûd at Bah-		Nannuka, founder of Chandella dynasty,	
râîch in A.D. 1340	292	mentioned in inscriptions	150
Muhammad Wasit, son of Shah Kasim Sulai-	~0~	Narachandra I, Raja of Kumaon, copper-	
mani, tomb of-at		plates of—, dated Śake	
Chunar, dated A.H. 1028,	259	1219 and 1243, at Chana-	Water
Muhammad Yar, son of Ali Muhammad, tomb	400	yagâon	48
of—at Bareli	25	- II, Râjâ of Kumâon, copper-	
Mujahid Ali Khan, built fort and masjid at	- 22	plate grant of, dated	12.00
Rasûlâbâd in A.H. 1085,	273	Šake 1307, at Gangamān,	48
Mukarrab Khan, Nawab, constructed dar-	2002		
gâh of Bû Alî at Kai-		plate grant of, dated	
rânâ in A.D. 1626	13	Sake 1377, at Ganga-	76
Mumtaz Khan, built masjid at Mumtazna-	200	and the same of th	48
gar in A.H. 1025	302	Narasimhagupta, king of Imperial Gupta	
, built masjid at Biswan in	300	dynasty, mentioned in	
A.H. 1047	287	seal inscription found at Bhîtarî	004
Mun'im Khan, governor of Jaunpar, built		Naravardhana, king of Sthanvisvara, men-	334
palace and great bridge at		tioned in copperplate grant	
Jaunpûr, from A.H. 972		of Samvat 25, found at	
to 975	184	Madhuhan	2.00
	401	Madhuban	189

Pages.	Pages.
Narenu, dependant of king Våsudeva, re-	Pahar Singh, prime minister of Rahmat Khan, 25
paired Manikarnikâ Kund at Banâ-	Pâla dynasty of Vodâmayûtâ, genealogy
ras in Samvat 1680 211	of— 20
Nårå Śańkar, Måratha leader, strengthened	Påndavas, transferred government to Kaus-
fort and founded city of	âmbî (traditionally Ahâr) 3, 4
Jhânsî in A.D. 1744 118	, lived in lac palace at Barnawa 2
Nasir-ad-dîn Mahmûd, Sultan of Dehlî,	Lachhägir, 143
built dargah of Sulţanjî and	, resided during their first exile at
masjid of Dådå Hamid at	Dêoband 14
Badâon in A.H. 648 22	, constructed Dronasagar at Ujjain
, erected the great	near Kâsîpûr 51
mînâr at Kôl in A.H. 652 2	, resided at Bairant 195
Nâsir-ad-dîn, Malik of Ghaznî, defeated Râjâ Śiras Pâl of Sarsâwâ 18	Paramardi Dêva, king of Chandella dynasty,
Siras Pâl of Sarsâwâ 18 ———, son of Sultân Ibrahîm Shâh	inscription of, dated
Sharqî, built fort at Nasîr-	Samvat 1232, at Punian, 172
AV A W	, inscription of , dated
Nasrat Shah, Sultan of Bangal, inscription	Samvat 1240, found at
of—at Kharid, dated A.H.	Mahobâ 175
933 193	, inscription of——, dated Samvat 1552, found at
Naval Raî Kâyath, governor of Audh, altered	The state of the s
Rang Mahal at Kanauj	Bagrari 331, 334 ————, built gate leading to Nîla-
in A.D. 1750 79	kantha's temple at Ka-
Nawab Aliya Begam, queen of Shahjahan,	Indian
mausoleum of-at Ágrâ,	built palace and fort at
dated A.H. 1040 63, 64	Mahobâ 175, 176
Nêkbakht Khân, built masjid at Baland-	, fought battle with Prithvi-
shahr in A.H. 943 5	râjâ of Dehlî at Akorî
Nichakra, prince, makes Kausambi (wrongly	in A.D. 1182. 112 124 175
identified with Kôl) his capital	Parasurama, born at Khairi Dih
after the destruction of Hasti-	, killed Sahasrabâhu near Khairî
napura 1	Dih 194
Nihâl Khân, built mud fort at Nihâlgarh in	, overcame in fight Rājā Madana
A.D. 1715 328	at Zamâniyâ 236
Nirgan Shah, shrine of—at Shahpar 29 Nizam-ad-din, Shaikh, tomb of—at Nizam-	, did penance at Sohanag to re-
4141 7	cover his divinity 251
Nûr Jahân, queen of Jahângîr, erected dar-	, granted arms of Brahmâ to king
gâh of Shâh Pîr at Mîrath	Karna 303
The A To Hann	Parikshit, grandson of Arjuna, traditional
Latte Day Day 1 . C	founder of Paricehatgarh 12
Nûr Muhammad, faqîr, built masjid at	, traditional founder of Padham 95
Karra in A.H. 1065 163	Awank 100
, built Lal Masjid	
at Gångôh in A.H. 1081, 15	Parmal, king of Mahoba, see Paramardi Dêva. ——, Tômara or Pândava chief of Ahâr, tra-
P.	ditional founder of Palant 1
and the second of the second o	Pathans, founded Jalali in tahsil Kol, Ali-
	garn district
sonry tank at Ghâzîpûr in	Patnî Mal, Râjâ of Banâras, built Siva Tâl at
A.D 1580 231	Alathura in A T) tong
	107

Page	Pages
Pîr Faddû, tomb of-—at Râprî 9	TOTAL CONTRACTOR OF THE PARTY O
Pîr Ghâîb, tomb of-at Bhainswâl 1	23 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3 3
Pîr Kashânî, dargâh of-at Muhammad-	1 TO THE TENTH OF THE THE THE THE THE THE THE THE THE THE
åbåd Gohnå 19	
Pir Mardâna, Shahîd, tomb ofin ruined	Josephanou end zore de chianar ill 200
fort of Sarsâwâ 1	, confined in the fort of Khairigarh
Pîr Mubâraq Shâh, dargâh of—at Mahobâ, 17	
Pîr Muhammad, masjid of—at Thâna Bhâ-	1
14 144 2 2 2 2 2	——found at Mahwân
wan, built in A.H. 1114, 14 Pir Sarwani, tomb of—at Orai 114	A CONTRACTOR OF THE PARTY OF TH
Pîr Sarwâr, maqbara of—at Barnâwâ,	0.1
70 1 10 10 1	mentioned in seal inscription
Pîr Tâj Bâj, tomb of—at Tâl Bahat, dated	found at Bhîtarî 334
	Q.
A.H. 874 126 Pîtambar Singh, Râjâ of Âwâ, destroyed	Qanâq Khân, repaired Jâmi Masjid at Am-
	roha in A.H. 965 35
large Buddhist temple at	Qayâm-ad-dîn Khân, built large fort at Dan-
Khera Kundalpur 87	kaur 6
Prabhakaravardhana, king of Sthanvisvara,	Qurban Alf, repaired Jami Masjid at Karra
mentioned in copper-	from A.H. 1012 to 1014 139
plate grant of Samvat	Qutb-ad-dîn Aibaq, governor of Shahâb-ad-
25, found at Madhuban, 189	dîn Muhammad Ghorî, 5
Pradiptavarman, king of Singhapura, men-	, conquered Hindû fort
tioned in stone inscription	at Mîrath in A.D.
at Madha 8	1191 11
Prahlada, according to tradition, thrown by	, built magbara of Sa'id
Hiranyakasipu into the Betwa	Sâlâr Musa'ûd at
at Dêokâlî 118	Mîrath 12
Prajapati Bikshuni, maternal aunt of Bud-	- , captured Kâlpî in A.H.
dha, built vihâra at	593 113
Śrāvasti 309	Qutb-ad-dîn Shâh, king of Bangâl, built fort
Prakataditya, king of Magadha, inscription	at Kathaura in A.D.
of ——found at Sarnath 334	1203 193
Prasênajît, Râjâ of Śrāvastî, palace of	Qutb Âlam, rauzâ of—at Kâch Daryâ
307, 308	Bard, dated A.H. 1116 139
, dethroned by his son Virûdhaka, 220	CONTRACTOR OF THE CONTRACTOR O
Pratapachandra, Raja of Kumaon, copper-	R.
plate grant of-, dated	Rådhå, Krishna's favourite mistress, born at
Sake 1383, at Dâdâgâon 48	Barsânâ 97
Pratâp Singh, Râjâ, founded Pratâpgarh in	Raghunatha, consecrated Panchaganga ghat
A.D. 1618 319	at Banâras in Samvat 1637, 211
Prithvîrājā, Chauhāņa Rājā of Dehlî, inscrip-	Rahilavarman, king of Chandella dynasty,
tion of—at Madanpür, dated	built stone temple at Rahi-
Samvat 1239, recording con-	lyā 177
quest of Parmal and his coun-	Rahmat Khân, Hâfiz-ul-mulk, built Jâmi
try 124	Masjid at Pilibhît in A.H.
, fought battle with Parmal of	1181-82 40
Mahobā at Akorî in A.D.	, built mud fort at Jalâlâbâd,
1182 112, 175	Shâhjâhânpûr district 41
-, captured Mahobâ in A.D. 1182, 175	, tomb of—at Bareli, built
, built fort at Lond 10	in A.H. 1188 25

1000	Pages.		Pages.
Raji Sa'id Nûr, tomb of-at Manikpûr,		Razâ Khân, Mîrzâ Hasan, built Jâmi Masjid	
dated A.H. 965	317	at Bareli	
Rajjab Sålår, confidential slave of Sålår Såhû,		Renukâ, mother of Jamadagni	Des
dargâh of—at Bahrâîch	292	Rizk-ullah Khan, built tomb of Ba Ali at	
Rājā Sa'îd, built shrine of Makhdûm Jahā-		Kairânâ in A.H. 1071,	
niya at Kanauj in A.H. 881,	81	Rôl, Râjâ, traditional founder of Kâgâraul,	
Râjyapâla Dêva I, Râthor king of Kanauj,		Rukmini, daughter of Bhishmaka, carried	
mentioned in copper-		off by Krishna from Ahar,	
plate grant of Samvat	- 3	Balandshahr district	3
1084 found at Jhûsî	138	Rukn-ad-dîn Fîrûz Shâh I, Sulţân of Dehlî,	
- II, son of Govindachandra		built masjid of Ahmad Khan-	
Deva of Kanauj, cop-		dân at Badâon in A.H. 633.	22
perplate grant of,		Rukn-ad-dîn Rukn Âlam, dargâh of-at	
dated Samvat 1199,		Kharid	193
found at Gagahâ	241	Rûmî Begam, Akbar's supposed Turkish	
Râjyavardhana I and II, kings of Sthânvîs-		wife, palace of-at Fath-	
vara	189	pûr Sîkrî	72
Râmachandra, king of Ayodhya, killed the		Rûmî Khân, general of Humâyûn, captured	0.15
demon Karar Bir at Jaun-		Chunâr in A.D. 1536	259
pûr	179	Rûpan Guru, inscription of, dated Sam-	
, halted at Rathaulf and visited	1000	vat 1672, at Akbarpar, Ja-	
sacred tank at Hattia Haran,	280	lâon district	114
, having killed Ravana, bathed	10000	Rup Ram, built Bhanokhar tank at Barsana	
at Dhopap	326	in Samvat 1666	97
, performed dîpadânam cere-		Rustam Khan Dakkhini, built fort and Jami	
mony at Derâ	327	Masjid at Murådåbåd in	
, after performing lamp cere-	0.00	A.H. 1046	37
mony slept at Harsen	327	-, built idgah at Sambhal in	
, Râjâ of Rîwâ, copperplate		A.H. 1066	37
grant of—, dated A.H. 965	****	, repaired Jami Masjid at Sam-	
Râmadeva, Râjâ of Haldî, traditional founder	138	bhal in A.H. 1067	37
of Rhaleand	300	S.	
Râmbhavatî, Râṇî of Mewâr, erected hand-	192	Sabal Khan, Nawab, built Sabalgarh in the	
some chhattri at Brindâban		time of Shahinhan	33
in Samuel 1602	00	Sâbit Khân, Nawâb, alias Jâfar Beg, erected	-
Râm Rât, guru of Udâsi sect, built Sikh	98	dargan of Shah Hah Baksh at	08.
temple at Dêrâ in Samvat 1756,	*	Aol in A.H. 1129	2
Randhîr Singh, Râjâ of Bhâratpûr, cenotaph	7	, built Jâmi Masjid at Kôl from	- 33
of—at Gobardhan	101	A.H. 1137 to 1141	1
Rasûl Khân, built Sarâî Abdur Rasûl at	101	, supposed builder of Moti Mas.	
Sarai Aghat in A.H. 1097,	88	jid at Köl	2
Ratan Nâth, built temple of Pârvatî at Devî-	00	, repaired old Hindû fort at KAI	-
Patan	303	In A.D. 1717	3
Ratan Singh, built brick fort at Khairnagar	81	, commenced building Jâmi Mas-	
Ratnapâla, built stone temple at Garhwâ in	O.L.	Jid at Balandshahr in AD	
Samvat 1199	137	1/60	5
Raushan Ali, built imambara at Gorakhpûr.	242	Sadi, servant of Malik Mardan, traditional	
Raushan Jahan, Bibî, built masjid and well at			234
Raushanabad in A.H. 1149,	83	Sådik Khân, Akbar's spiritual guide, tomb of	-
		at Âgrā	68
			200

Pages	
Sadr Jahan Ajmalî, Jhanjhrî Masjid at Jaun-	2 0900,
pûr built in honor	Salar Masa'ad Ghazî, dargah of—at Bah-
The state of the s	raich, built by Malik
Sådullåh Khan, Rohilla, built masjid at	and the title of the title
21 24 C C C C C C C C C C C C C C C C C C	mad 292
Aonia 25	The state of the s
	, dargâh of—at Satrikh 264
tarchendi 25	The state of the s
Sahab Sultan, mother of Shaikh Muhammad	Sâlât Khân, Nawâb, built Nawalganj at Âgrâ
Fazl, built Masjid Darbar	in the time of Shahjahan 55
Kalân at Kairânâ în A.H.	Salîm Chhishtî, dargah of—at Fathpûr
1051 13	Sîkrî, built by Akbar in
Sahasrabahu, asura, ruined fort of-at Sa-	A.H. 988 71
haswân 24	
, according to tradition, killed by	gâh of Jhajhār Khân at
Parasurāma near Khairā Dih, 194	
, according to tradition, killed by	, the actual founder of the fort
Sålivåhana at Sålôn 325	at Ágra 56
Sa'îd-ad-dîn, Maulavî, built masjid at Thâna	, inscription of , dated
Bhawan in A.H. 1099 14	Samvat 1609, at Azam-
Sa'id Alâ-ad-dîn Alî, dargâh of—at Bân-	301
garmâû, dated A.H.	garh 187 ————, repaired old Hindû fort at
702 269	70.7
Sa'id Khurd, dargah of—at Kheri, dated	
A.H. 970 286	, built large brick fort at
Sa'id Khurram, Nawâb, built brick fort and	Arjunpûr 327
The second secon	Salivahana, Raja, traditional builder of fort
patace at Aurangâbâd 283 Sa'îd Makhan, built masjid at Sambalhêrâ in	at Kôt Sàlbâhan 24
A TT TOTAL	, according to tradition,
Sa'id Muhammad Sughra, tomb of—at Boj-	killed Sahasrabāhu and
har, dated A.H.	founded Sâlôn 325
	Sallakshanasimha, fragmentary inscription
614 278 Sa'îd Muhammad Shujâ'at Khân, Nawâb, tomb	of—found at Jhansi, 333
of—at Jahânâbâd,	Sambhunatha, the third Jina, born at Śra-
Washington and the second seco	vasti 308
	Samghabhadra, stupa and monastery of-
Sa'id Murtază, tomb of—at Zafarâbâd 185	at Mandawar 32
Sa'id Qutb, repaired Jami Masjid at Sam-	Samkaracharya, traditional builder of temple
bhal in A.H. 1030 37	at Rikhikhês 8
Saîf Khan, Sa'id, tomb of—at Majhêra,	-, traditional builder of temple
built in A.H. 972 13	at Adbadrî 44
Sakat Dêva, Râjâ, built fort at Sakît 88	, traditional builder of temple
Sakat Singh, built fort at Saktisgarh 262	at Badrînâth 44
Salabat Khan, treasurer of Shahjahan, tomb	Samudragupta, king of Imperial Gupta dy-
of—at Âgrā 68	nasty, undated inscription
Salar Masa'ad Ghazi, Sa'id, maqbara of——	of-on Asoka's lat at Al-
at Mîrath, built A.H.	lahābād 127—129
1194 12	, mentioned in cave inscriptions
, took fortress of Dêo-	near Chunâr 260
band 14	, mutilated inscription on stone
, killed in battle at Ha-	horse, found at Khairi-
thild non	
292	garh 285

	Pages.	2	Pages.
Samudragupta, mentioned in seal inscription		Shâh Begam, mother of Khusrû Shâh, tomb	0.000
found at Bhîtarî	100000	of—at Allahâbâd, dated	
		А.Н. 1014	700
Sangram Singh, Chauhana Thakur, built mud		Shahdana, tomb of at Barell, built by	
fort at Îtah	-	Makrand Râi	100
Santan Singh, traditional founder of Santan-		Shâh Hisâm-ad-dîn, tomb of-at Mânik-	
nagar, or Sândî	281	pûr, dated A.H. 1008,	
Sâqî Muhammad Sultân, built masjid at Korâ	0.00	Shâh Tlah Baksh, dargâh of—at Kôl	
in A.H. 968	163	Shahjahan, Sultan, built Taj at Agra from	
Sarandaz Khan, built fort, masjid and baradarî		A.H. 1046 to 1057	
at Dâlmâû in A.H. 1049	321	, inscription of—at Saraî Ajit-	00, 01
	442	The state of the s	
in A.H. 1055	320		
Sarat, mythical Râjâ, son of Satyavâna, built	10.00	, inscription of—at Amma	
palace at Sarthal Kherâ	36	Shaganpûr, dated A.H. 1052,	90
C - 24 TO 4 2 12 12 12 12 12	24	, inscription of , dated A.H.	
Sardar Khan, built masjid at Aonla Saromân Dâs, Râî, built large brick fort at	21	1055, in octagonal cupola on	
Saromannagar in A.D.		rocky islet of Sujān Dêo	131
1700	000	, inscription ofat Sakît, dated	
Sarwan Bâbâ, sculptures of—on rock at	283	A.H. 1061	88
	120	, built Masjid Afghanan at Kair-	
	, 153	ânâ in A.H. 1062	13
, killed by Dasaratha at Sarwan,	293	———, built large sarâî at Khâtaulî	13
Saudasa, Buddhist Satrap, coins of found	0.0	, changed name of Akbar's fort	
at Pådham	95	Illâhâbâs to Allahâbâd	127
Sauman, Raja, built fort at Khergarh	94	, tomb of—in Tāj-kā-rauza at	
Sawai Jay Singh, great astronomer, con-		Agra, dated A.H. 1076	64
structed observatory at	12000	Shâh Jalil Bukhârî, Sa'id, tomb of at	
Mathura	108	Marhan	87
Sênavarman, king of Singhapura, mentioned	W. L.	Shah Jhanda, tomb of—at Badaon, dated	
in stone inscription at Madha,	8	A.H. 860	23
Shahab-ad-din Muhammad Ghori, invasion	- 25	Shah Khab Allah, tomb of -at Karra,	~0
of India by	5	dated A H 1061	139
, built dargah of		Shah Pir, dargah of —at Mirath, built by	*30
Makhdâm Shâh	-	Nûr Jahân	11
Wilâyat at Mîrath,	12	Shah Rak-din, alias Pungam, mausoleum	11
, destroyed ancient		of-at Bhagwanpûr, built	
city of Atranjî		from A.H. 1118 to 1190	14.
Khera in A. D.		Shah Rukn, dargah of—at Bisendi, dated	14
1193	85	A H 1041	DOM:
, built large fort at		Shah Safi, dervish, traditional founder of	287
Pațiali	87	Salipur	000
, conquered Banâras	-	Shah Ujalah, maghara of -t D 1	274
in A.D.1194	198	Shahzadi, tomb of—at Badaon, dated A.H.	23
Shah Alf Askikan, founded Sarai Mir in		796	i an
А.Н. 943	190	Shaikh Abdullah, governor of Ghazîpûr,	22
Shah Barkat-ullah, Sa'id, tomb of-at		built - "I	
Marhâra, dated A.H.		built masjid and im-	
1142	87	âmbâra at Ghâzî- pûr	1200
Shah Basit Alf, Sa'id, tomb of-at Damgarh,			231
dated A.H. 1196	143	, constructed brick fort at	
		Jalálábád in A.D. 1734	231

Pages	Pages.
Shaikh Abdullah, built brick fort at Kasim-	Shams-ad-din Iltitmish, undated inscription
âbâd 231	of—in the house of Bun-
Shaikh Afrid, tomb of-at Badaon 2	In the money of Diffe
Shaikh Barhan, died at Kalpi in A.H. 970, 113	The state of the s
- at Zafarâbâd,) water total of Altham
built in A.H. 711 18	Shahîd at Badâon, 22 built tomb of Badr-
Shaikh Chhotê Makhdûm, built masjid at	ad-dîn Badr Âlam
Khairâbâd in A H. 993, 288	
- , dargah of-at	at Dâlmâû 320 Shêo Râo Bhâo, built city wall round Jhânsî
Khairâbâd, dated	from A.D. 1796 to 1814, 118
A.H. 993 and 994, 288	Share Wild No. At a reason of the same
Shaikh Farid, traditional founder of Shaikhû-	Shêr Shâh Sûr, Sultân, built masjid at Sakît
pûr 24	TO A TE MINE
Shaikh Jamal, tomb of-at Sôron 89	
Shaikh Kabîr, alias Bala Pîr, tomb of-at	Charmata
Kanauj, dated A.H. 1009 80	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Shaikh Kabûl Muhammad, built karbalâ at	, built large fort at Shêrgarh, 111
Machhlishahr, 185	Bijaygarh 256
Shaikh Lâm-ad-dîn, dargâh of-at Shâh	, acquires the fort of Chunar
Qulîpûr, dated A.H. 946, 291	The second forms
Shaikh Mahdî, son of Bala Pîr, tomb of	, captured the fort of Kalanjar
at Kanauj 80	in A D 1541
Shaikh Mansûr, built masjid at Amrohâ	Shikhdar Muhammad, built fort at Kôl in
from A.H. 1066 to 1067, 35	A Section of the sect
Shaikh Mînâ, tomb of—at Lakhnâû, dated	A.H. 931 3 Shiù Ghulâm, built mud fort at Mustafâbâd, 94
A.H. 884 267	Shuja'at Khan, dargah of—at Kadirganj,
Shaikh Muhammad, Mangalsî, built îdgâh	built in A.H. 1104 87
at Machhlishahr 185	, built tomb of Barkat-ullah at
, Maulavî, maqbara of	Marhara in A.H. 1142 87
at Thâna Bhawân,	Shûja Shâh, defeated by Aurangzîb at Kha-
dated A.H. 1109 14	juhâ 162
Shaikh Nagah, mausoleum of-at Kanauj,	Siddhitunga, Raja, inscription of at Mar-
dated A.H. 1009 81	phá, dated Samvat 1404 155
Shaikh Samman, faqir, tomb of-at Sa'id-	Sikandar Shah Lodî, Sultan, built masjid of
pûr, dated A.H. 1003 235	Shah Abal Ma'ali at
Shaikh Sultan, rauza of—at Karra, erected	Ambahtâ in A. H.
in A.H. 1061 139	916 14
Shaikh Wall, built masjid at Kalanjar in	, built Jâmi Masjid at
А.Н. 1012 154	Dêoband in A.H. 916, 15
Shaista Khân, destroyed Hindû temple in	, destroyed eastern gate-
middle of Jamna in A.H.	way of Jhanjhri and
1055 131	Jâmi Masjidsat Jaun-
hams-ad-din Iltitmish, Sultan, destroyed	pår 182, 183
Hindû temple and erected	, founded Sikandarpür 194
on its site the Jami Masjid	, baradarî of—at Si-
at Badåon in A.H. 62020, 21	kandrâ 76
, erected Shams-i-id-	, tomb of—at Âgrâ 68
gâh at Badâon 20	Singhavarman, king of Singhapura, men-
, built dargah of Mi-	tioned in stone inscription
rânjî at Badâon 21	at Madhil 8

(1) List of proper names of persons, with dates and places with which they are associated—(continued).

	The second second	
Pages.		Pages.
Sirāj-ad-daulah, built masjid at Bārabauki, 263	Suhriddhvaja, according to tradition the last	-
Siras Pâl, last Râjâ of Sirsâwâ 18	of the Jaina rulers of Sra-	
Šišupāla, Rājā, undated pillar inscription of	vastî	308
—at Pahlådpår 234	The state of the s	77.0
Skandagupta, king of Imperial Gupta dy-	4 69 74	293
nasty, inscription of,	AND THE PROPERTY OF THE PROPER	200
dated Samvat 135, found at	Sair, (Sabara) tribe, traditional founder	020
	of ruined city near Permit,	231
	The state of the s	
, inscription of —, dated Sam-	tunpûr ascribed to	253
vat 139, found at Kauśâmbi, 142	near	
, copperplate grant of,	Bhuili ascribed to	256
dated Samvat 146, found at	Sujan Singh, Raja of Orchha, inscription of	
Indôr 6		
, inscription of-, dated Sam-	and A.H. 1082, at Arjar	112
vat 148, found at Garhwa 136	Sulaimân Shâh, dargâh of—at Jaunpûr,	117
, undated pillar inscription of	Juliannan Shan, dargan of—at Jaunpur,	4127
The state of the s	dated A.H. 867	185
——found at Bhitari 229	, and the state of	
PERSONAL PROPERTY AND ADDRESS OF THE PERSON	of Dehli, buried at Sik-	
Kahâon 244		77
Somadatta, Râjâ, traditional founder of	Sultan Arfin, tomb of-at Badaon	23
Sôron 89		~0
Śrāvasta, king, traditional founder of Śrā-	Simauni in A.H. 988,	154
vastî 307	, built masjid at Augasi in	157
Śrî Mallachandra, Rājā of Kumāon, copper-	A W nen	200
plate grant of ——, dated	A.H. 989	145
Sala 1520 - C 2: 24	Sumatinātha, fifth Tîrthamkara, born at	
Sake 1538, at Gadiudâ 49	Ayodhyâ	297
Sringavira, Rishi, traditional founder of	Suprabuddha, father of Mâyâ Devî, residence	
Singraur 144	of—at Barah Chhetra	217
	Sûrâj Mal, Jât Râjâ of Bhâratpûr, con-	mar
Sirwa 300	structed rock-cut baoli at	
Sthirapûla, mentioned in inscription of Sam-	Jáppár	127
vat 1083 found at Sarnath, 215, 334	constant of a C.1 m	74
Subaktagin, Khair-ad-din, took the fort of	Sûrapâla, Râshtrakûţa prince of Vodâma-	101
Chunar 258	- Vodáma-	
, Nasir-ad-dîn, built dargâh of	Suting W.H. Davis	20
Hazrat Shah Wilayat at Ba-	Sutirana Malla, Râjâ of Kumâon, copper-	
Jones For A TT management	plate grant of, dated	
Sudatta shief minimus #11: 21	Sake 1390, at Dadacton	48
Sudatta, chief minister of king Prasenajit,	Svaini, Raja, inscription of, dated Saria_	-
built stûps at Śrâvastî 308	vat 1390, in the fort of Change	050
, built the great monastery of Jêta-	Svamibhata, inscription of —, dated Sam-	258
vana at Śrâvastî 308	Vat 609, at Dooganh	MANAGEMENT .
Safi Shah, faqir of Akbar's time, tomb of		333
—at Sûfîpûr 74	Ta: . 7 . 7	
Suhriddhvaja, alias Suhal Dêo, Râjâ of Gauda,	Tâj-ad-dîn, faqîr, dargâh of—at Sahâwar,	88
built temple of Asokanatha	And Manan, built fort, Rang Mahal, and	90/
Mahadam a service	masjid at Dilêrganj in A.H.	
traditional founder of N.V.	1021	010
, traditional founder of Naliya	Takshadatta, undated inscription of-	316
and Kargûpûr 304	found of Walants	
, killed Sa'id Sâlâr Masa'ûd in	found at Kudarkôt	92
battle at Hathili 292, 305	Tambôli Begam, tomb of—at Allah-	
5508,0000	åbåd 72,	131

(1) List of proper names of persons, with dates and places with which they are associated-(continued).

Pages. Taghlaq Shâh, see Ghîâs-ad-dîn Taghlaq Shâh. Udhyota Chandra I, Râjâ of Kumâon, copperplate grant of——,	ca.
Shah. perplate grant of—	
per prace grant or	
Thâru tribe, Buddhist ruins in Bastî district dated Sake 1609, at	
accepted to	48
, ruined forts and mounds at, Râjâ of Kumâon, cop-	10
Bhâdapār ascribed to— 239 perplate grant of—,	
TVL condition and the state of	48
Thathera tribe, occupied pargana of Bar- II, copperplate grant of	=
wân 277 —, dated Sake 1691	
	50
and Bilgram, 277, 278, built shrine of Kapi-	
	19
Nîr and pargaṇa of Udit Singh, Bundela Râjâ of Orchhâ, built	
Bângar 280 castle at Barûâ Sâgar 11	14
Pålî, Pihânî, and Umâ, daughter of Daksha, imolated herself	
	6
Te-A-Clat -1.11 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
	1
and the same and t	0
Lâharpûr, Sîtâpûr district, 288 Umar Singh, repaired old temple at Gopê-	3
malaces of at Agris co	*
built temple of Gopinath at Undabhata, general of the kings of Kanauj,	*
Khaira 102 made religious grants to a	
pura in Samvat 1646 211 in Samvat 964 12	4
Tômara clan, traditional founder of ancient Upagupta, Buddhist teacher, site of monas-	
Balandshahr 4 tery of—at Mathurâ 10	6
Tribhuvanapâla, Râshtrakûța prince of Upâli, Buddhist teacher, stûpas of—at	
Vodámayútá 20 Mathurá 10	5
Trilochanapâla Dêva, copperplate grant of Usmân, Sa'îd of Shîrâz, arrived at Jaunpûr	
—, dated Samvat in A.H. 820 181	1
1084, found at Jhûsî, 138	
Tuist Das, poet, born at Majngawan, Banda	
2 to 1	
U. Vajriņîdevî, queen of Naravardhana, king	81
Ûdal, Banâphar chief, dwelling house at of Sthânvisvara 189	
Chillà ascribed to 135 Vaka, asura, traditional founder of Baksar-	
Udayâditya, king of Mâlava, mentioned ghât 268	
in inscription found at Valmiki, celebrated author of the Ramayana.	
Jhansi 333 resided at Balênî 9	
Udâyana, king of Kaušâmbî, made statue of	
Buddha in red sandal-wood 141 ——at Chitrakût 147	
Udayapala Dêva, Raja of Katyari dynasty,	
inscription of—at Baijnath, 47 —at Bithur 168	
Uday Chand Tiwari, built Indargarh at Pûrab Râi 78 in cave near Râmneger 150	
Pûrab Râî 78 in cave near Râmnagar, 156	

(1) List of proper names of persons, with dates and places with which they are associated—(continued).

Page	Page	8.
Vâlmîki, celebrated author of the Râmâyaṇa,	Vigrahapâla Dêva, Râshtrakûţa prince of	
resided at Bâliyâ 19	90 Vodámayútá 2	0
Vasantapâla, mentioned in inscription of Sam-	Vijayachandra Dêva, Râjâ of Kanauj, erected	
vat 1083 found at Sarnath, 215, 3		1
Vasubandhu Bodhisattva, monastery of-	Vijayapāla Dēva, king of Chandella dynasty,	
	43 constructed Vijay Sûgar	
on Tikri mound near Rosam, 1	35 1 1 1	
10 1 7 0 1 7 1 1		*
at Gunîr, Fathpûr district 16	60, king of Kanauj, mentioned	
	in copperplate grant of	
at Bihâr, Unâo district 27	71 Samvat 1084 found at Jhûsî, 13	8
	Vijay Singh, rebuilt Kora during Akbar's	
at Kaûkûr, Râî Barelî district, 32	23 reign 16	2
Vasudéva, father of Krishna 103, 10	07 Vikramåditya, king of Śrâvastî, identified	
, Indo-Skythian king, inscriptions	with Chandragupta II 30	7
	06, king of Ujjayini, according to	
	34 tradition restorer of Ayodhya, 29	0
at Pakhnā Bi-		0
	, traditional	
	82 founder of Bikhâr 32	7
, king of Kanauj, traditional builder	Vimalamitra, Buddhist teacher, stûpa of—	
	13 at Mandâwar 3	1
, Rājā, mentioned in inscription of	Vîradhavala, Râjâ, inscription of—at Da-	
Samvat 1680 at Banāras 21	11 11 11 11 11 11 11 11 11 11 11 11 11	6
Vatsarâjâ, minister of Chandella Râjâ Kîrtti-	Virâța, son of king Vêṇa, traditional founder	
varman, inscription of, dated	A TO STATE OF THE	8
	20	0
Vâyu, Rishi, cursed the hundred daughters		
	of Balmiar-Barkhar 28	3
Vêna, Chakravartti Râjâ, ruined fort of-	A CONTRACTOR OF THE PARTY OF TH	51
THE REPORT OF THE PROPERTY OF	of ancient Sîtâpûr 29	1
The state of the s	15, capital of—said	
, traditional founder of Bij-	to be Hargâm 28	8
	30 Vîravarman Dêva, II, Chandella king, inscrip-	
	26 tion of Samvat 1318	
, built palace at Bernî 8	36 found at Jhansi 33	3
, traditional founder of	Virûdhaka, king of Śrāvastî, attacked Kapi-	-
Garh Kherâ near Dêoriyâ,	20	0
	2 ron for	
of Thânêkâ 4	43 Visākhā, lady of Śrāvastî, built Pūrvārāma	7
Or American	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	
- 0 A + 10 TTL - 0	in honor of Buddha 31	1
of Atranjî Kherâ 8	85 Visala Dêva, Chauhana Raja of Ajmêr, in-	
TO THE RESERVE THE PARTY OF THE	scription of-, dated Sam-	
of Sôrôn 8	88 vat 1220 on Ašoka's "golden	
	lâț" at Dehlî 1	7
of Barheya Khera and	Vriddhavarman, king of Singhapura, men-	8
Jagdîspûr 28	84 tioned in stone inscrip-	
	Alone on Mr. on a	
of Bênnagar near Nim-	W	8
0.2%		
Vidyadhāra, resident of Ajāvrisha, inscrip-	dargan of—	
	at Badâon, erected in A.H.	
tion of —, dated Samvat	391(?) and repaired in A H	
1276, found at Mahet 30	981	1
	212 (#	-

(1) List of proper names of persons, with dates and places with which they are associated—(concluded).

Pages.	Pages.
Wilâyat Shâh, masjid of-at Manglaur,	Yayûti, celebrated monarch of the lunar race,
built in A.H. 683 17	capital of-—at Jājmāū 168
, dargâh ofat Amrohâ,	Yudhishthira, king of Indraprastha, or an-
built in A.H. 783 34	cient Dehlî 10
at Âgrâ, built	Z.
in A.H. 953 66	Zâbita Ķhân, Nawâb, built masjid and well
	1 12 01 44
Y.	Zafar Ali, Nawab, built masjid at Begam-
Yahya, Sa'id of Mashad, tomb of-at Ma-	41.4.3
hâban 104	Zafar Khân, founded Zafarâbâd in A.H. 762, 185
Yajfiavarman, king of Singhapura, men-	- , built dargah of Makhdûm Shâh
tioned in stone inscription	at Zafarâbâd in A.H. 781 185
at Madhâ 8	Zahara, or Zohra, daughter of Sultan Babar, 53, 65
Yakût Khân, alias Khân Bahâdur Khân, built	Zâhid Khân, built masjid at Jaunpûr in A.H.
mud fort, masjids and tombs	1150 185
at Aliganj in A.D. 1747 84	Zâhir Pîr, alias Gûgâ Pîr, born at Sarsâwâ, 18
, built masjids and sarâî at Khudâ-	Zahûr Muhammad, Qâzî, built fort at Târî, 216
ganj 81	Zâîn-ad-dîn, Shaikh, built masjid at Kach-
, tomb of-at Aliganj 84	pūrwā, Āgrā, in A.H. 937 55
Yaqûb, Maulvî, built Jâmi Masjid at Karrâ	Zâîn-al-Abdîn, built bâradarî and tank at
in A.H. 978 139	Korå 163
Yasahpâla, king of Kanauj, stone inscription	, tomb of-inside the fort
of-, dated Samvat 1095, at	of Bijaygarh 256
Karrā 138, 317	Zamân Khân, governor of Jaunpûr in Akbar's
Yasîn Shâh, takiâ of-at Kosî, dated A.H.	time, founded Zamaniya in
1198 102	A.D. 1560 237
Yakodâ, foster-mother of Krishna 103	
Yasomatî, queen of Prabhâkaravardhana,	at Singraur 145
king of Sthanvisvara 189	Zîâ-ad-dîn, Qâzî, built Jâmi Masjid at Îrichh
Yasovarman Dêva, Chandella king, men-	in A.H. 815 117
tioned in temple in-	Zîâ Ahmad, built masjid at Banâras in A.H.
scriptions at Dúdáhí, 123	777 201
Yatima, eunuch of Akbar's time, built Mas-	Zîra, Chêrd Chief, built fort at Zîrâbastî 195
jid Makhan Nishân at Agrâ 67	Zulfikâr, son of Rahmat Khân of Barelî 25

and the latest the lat The state of the s

(2) GENERAL LIST OF PLACES DESCRIBED. (1)

A. Pages,	Pages.

Abahta-Islamnagar, t. in Saharanpür d 14	Ajāvrisha, another name for Śrāvasti, 308
Abhaipûr, old ruined fort in Bândâ d 149	Ajgâon, v. in Unão d 268
Abhapari of Alberani, the modern Aphai	Ajipāra, old name of Ajrārā in Mīrath d 8
in Fathpûr d 157, 158	Ajitmal, v. in Itawah d 87
Achners, v. in Agra d 58	Ajrârâ, v. in Mîrațh d.
Adampûr, v. near Sândî in Hardôî d 282	Formerly called Ajipāra 8
Adbadri, v. in Garhwâl d 44	Ajudhyå, famous pilgrimage place in Faizā-
Adda Motiram, police outpost on the Dêo-	bad d.
rîyâ road in Gôrakhpûr d., 248	Anciently called Ayodhya 295
Adhêsar, hill in Mîrzâpûr d 252	Identified with Hiuen Tsiang's
Adhichhattra, see Ahichhattra.	Pi-so-kia, or Višākhā 299
Afzalgarh, v. in Bîjnôr d 30	Wrongly identified with Hiuen
Agahat, ruined mound near Sankîsâ in Far-	Tsiang's 'O - yu - t' o 299, note
rukhâbâd d84, 88	Also called Baretâ 300
Agôrî Khâs, v. in Mîrzâpûr d 252	Description of antiquities at
Ågrå, tahsil and head-quarters of d.	295-300
Ancient buildings and remains of the	Identification of Buddhist sites
Moghal period at—, 53—69	at 298-300
Ahâr, t. in Balandshahr d.	Akbarâbâd, Musalmân name of Âgrâ 53
Wrongly identified with Kausambi, 3	Akbarpûr, old name of the modern Chau-
Ditto ditto with the capital	muhâ in Mathurâ d 100
of Bhishmaka (Kundinapura) 4	Ditto, v. in Jalaon d 114
Identified with the place of Jana-	Ditto, v. near Bilgûon in Bândâ d 147
meyajaya's snake-sacrifice 3	Ditto, tahsîl in Kûnhpûr d 165
Sculptures of early date found at-, 4	Ditto, tabsil in Faizābād d.
Ahêrîpura, t. in Itâwah d 87	Formerly called Sinjhault or
Ahibaran, ancient name of Balandshahr 4	Sojhâwalgarh 300
Ahichhattra, identified with Ramnagar	Akbarpûr-Aunchhâ, v. in Mâînpurî d 92
in Barêlî d. 26—29	Akbarpûr-Bîrbal, v. in Kânhpûr d 165
Ahîrpûr, ancient kherâ in Balandshahr d.	Akhanda, identified with ruins near Dil-
Extensive block of ruined temple	dârnagar in Ghâzîpûr d., 230, 231
	Akona, v. in Hamîrpûr d 170
Ahivarana, ancient name of Baland-	Ditto, local name for Ikauna in Bahraich d., 294
shahr 4	Akonî, v. in Hamîrpûr d 170
Ahmadnagar, v. in Kherf d 285	Akorhî, v. in Mîrzâpûr d 254
Ahraurâ, t. în Mîrzâpûr d 252	Akorî, small v. in Jalâon d 112
Ahrwâ-Bhavânî, v. near Haidargarh in Bâra	Akrābūd, v. in Alfgarh d 1
Bankî d 264	Alâ-ad-dînpûr, v. near Bângarmâû in Unão d., 271
Ahugî, old v. in Mîrzâpûr d 253, 254	Ålabhi, or Ålabhiya, ancient t. of
Aimah Râjî Muhammad Hayât, v. in Pratâp-	the Jainas.
garh d 316	Identified with Airwa in Itawah d., 87
Âînpûr, v. in Bastî d 222	Ditto with Nawal in Unão d., 271
Airwâ, v. in Itawah d.	Âlamnagar, v. in Hardôî d 277
Identified with the Alavi of the	Alampûr Kôt, v. near Râmnagar in Barêlî d., 27
Bauddhas, and the Alabhi or	Alâpûr, v. în Badâon d 20
Âlabhiya of the Jainas 87	Ditto, v. in Faizābād d 300
Perhaps the A-lo of Fa Hian 87	Alârikhpûr, old name of Pratâpgarh 319
Termina and at a to out a striam of	Section of the sectio

. Pages.	Pages.
Âļavî, ancient town of the Bauddhas.	Anjanî, v. in Mâînpurî d 92
Identified with Airwa in Itawah d., 87	Anjani, v. in Mainpuri d 92 An om å, river of Buddhist legends.
Ditto with Nawal in Unão d 271	Identified with Kûdâwâ Nadî in
Aldemâû, v. in Sultânpûr d 325	
Âlhâpûr, v. in Pratâpgarh d 314	
Alfabâd, t. in Bâra Bankî d 263	5 5 1 La La La La La La La La La La La La La
Alfganj, tahsîl in Îtâh d84, 85	The late of the second
Ditto, v. in Kherî d 284	Ant, v. in Lakhnåû d 267
Ditto w in Dat Donate 1	Anûpshahr, tahsîl in Balandshahr d 4
Alikhard w in Maternast 4	Anyâi Kherâ, ruined mound near Shikârpûr
Allmir w in Mandathan a	in Balandshahr d 7
Allahâbâd, tahsîl and head-quarters of d.	Anyôr, v. near Gobardhan in Mathurâ d 101
Colled Sticket a the Alle	Âonlâ, tahsîl in Barêlî d24, 25
Anciently named Prayaga 127	Aonrîhâr, small v. in Ghâzîpûr d.
Description of antiquities at, 127—131	Identified with Asoka's Vihara
Allahbakshpûr, v. near Taṇḍwâ in Bahrâfeh d. 295	near the capital of the kingdom
Almone constal of Track	of Chen-chu 227
Å-lo, of Fa Hian.	Aphûî, v. in Fathpûr d.
T3 420 7 20 42 44 44	Mentioned by Alberûnî under the
Total and any control of the control	name of Abhapari 157, 158
Amil w near Blacks Till to D at 1	Aptanetravana, of Hiuen Tsiang.
Amilant as man D. I	Identified with the ruins near Ikauna
A - TA TA TA TA TA TA TA TA TA TA TA TA TA	in Bahraich d 294
Ambabat Tulbing at the Control of th	Ārā, or Ārāmnagar, t. in Shāhābād d. of
Ambikanagara, ancient name of Amro-	Bangal,
The Prince of Additional Conference of the Confe	Wrongly identified with Ekacha-
Ambi Kôt, ancient site near Nârâyanpûr in	kra 90
CITA A A 3	Arûî, v. near Safîpûr in Unâo d 273
Amethî, or Garh Amethî, tahsîl in Sultân-	Arâîl, old v. in Allahâbâd.
	Called Jalálábád by Akbar 131
A ALATA TO A A A T T T T T T T T T T T T T T	Aramnagar, see Ârâ.
A CHACTEL A 2	Aranya, of Fa Hian.
Amma Shagannûr v in Itawah d	Identified with an ancient site at
A	Bāhyā 191
Amrapati Kherâ, ancient mound near Âlîpûr	Wrongly identified with ruins
	near Bhâraulî-Gangâtîr in Ghâ-
America America 1977	zipûr d.
Amrohâ, tahsîl in Murâdâbâd d 77	Arel, ruined mound near Basti 218
Anciently named Ambikana-	Argal, name of fort at Kora and of a small
2000	v. in Fathpur d.
Hindû and Musalmân buildings	Arison-Jahanianpur, v. in Azamoarh d
2 P	Ariari, v. in Hardôî d.
Amein w in Printled 3	Aritpur, v. in Muradabad d 26
Andolf w in Gamella A. 3	Aring, t. in Mathuri d.
Aniruddhwâ, v. near Kasîâ in Gôrakhpûr d.	Arjar, v. in Jhansi d.
Ruins near—identified with	Arju, v. in Sultanpûr d.
the palaces of the Malla	Arjunpur, v. in Lakhnaa d 267
	Ditto, v. in Sultanpar d.
	Anciently called Makarakala, 328

Pages.	Pages.
Arôr, old name of Pratâpgarh 319	ACCURACY OF A CONTRACT CONTRAC
Asafgarh, v. near Sabalgarh in Bijnôr d 33	
Asâî Kherâ, small v. in Itâwah d.	
Identified with the Asi of Sul-	
4A- W-1A1 00	
Assessation on the World and I	A COLUMN TO THE REAL PROPERTY OF THE PROPERTY
Appell w in Mathemat J	
Asganwân, v. Faizâbâd d 301	
Ashrafābād, Musalmān name of Sāṇḍī in the	
Handat J con	
Nebrofode w in Dat Double 2 2004	
Ashtabhuja, famous place of pilgrimage	
in Mîrzâpûr d 254	
A si of Sultan Mahmud.	1 11 11 11
Identified with Asaî Kherâ in Ita-	Aurangabad-Nagar, v. in Basti d 225 Aviddhakarna, of Hiuen Tsiang.
wah d 89	Identified with an an-
Identified with Asni in Fathpur 158	The state of the s
Asîwân, t. in Unão d 268	
Askôt Malla, old ruined v. in Kumãon d 47	Wrongly identified with the ruins near Ghâûs-
Aslâ, small v. near Pindrâ in Banâras d 213	A SAN CONTRACTOR AND AND AND AND AND AND AND AND AND AND
Asmanpûr Dîh, ruined site in Gôrakhpûr d., 240	pûr in Ghâzipûr d 231 Âwâ, or Âwûgarh, t. in Îtah d 85
Asnî, v. in Fathpûr d.	
The treasure city of Jayachchhandra	
of Kanauj 158	Ayodhya, ancient name of Ajudhya, 295-300 Ayomukha, see Hayamukha.
Perhaps the Ô-yu-t'o of Hiuen	A com that Anton w in Mitte
Tsiang 158	
Asohâ, v. in Unão d.	Azamgarh, tahsil and head-quarters of d 187
Anciently named Asvattha-	Azampûr, v. in Murâdâbâd d 36
mapura 268	Azmatgarh v. in Azamgarh d 187
Asojpůr, v. in Bastî d 221	В.
Asokpůr, v. in Gondi d 292, 304, 305	Baburî, large v. in Banâras d 195
Asothâr, v. in Fathpûr d.	Bachhraon, v. in Muradabad d 35
Anciently named Asvattha-	Bachhrawan, v. in Rai Bareli d 319
mapura 158	Badanpûr, v. in Hamîrpûr d 171
Âsthân, v. in Pratâpgarh d 318	Baddon, tahsil and head-quarters of d.
Asvatthamapura, identified with Aso-	Anciently named Vodámay ûtâ, 20
hâ in Unâo d 268	Geneology of Pâla dynasty of—, 20
Identified with Aso-	Jâmi Masjid of Iltitmish at 21
thâr in Fathpûr d. 158	Early Musalman buildings at, 22, 23, 249
Atâ, v. in Murâdâbâd d 36	Badarqa Harbans, v. in Unão d 272
Atâ Parasûâ, ancient mound in Pilibhît d 40	Baddû Sarâî, v. in Bâra Bankî d 263
Atehâ, v. in Pratâpgarh d 314	Badnaulf, v. in Mîrath d 12
Atrahat, v. in Bândâ d 145	Badrinath, v. in Garhwal d 44
	Badûghpûr, v. in Faizâbâd d 300
CONTROL OF THE PROPERTY OF THE	Bågësvar, pilgrimage place in Kumaon d.
Hiuen Tsiang 85	Anciently named Vågisvara
Atrârâ, v. in Mîrath d 12	or Vyaghrésvara 47
THE PARTY OF THE P	Båghaunch, v. in Båliyå d 190
100 May 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	=illem: ddistrict

Pages.	Pages.
Bâgpat, or Bâghpat, tahsîl în Mîrath d.	Relat Pastante engine site in Dillete 1 on to
Originally named Vyaghra-	Balaî Pasîâpûr, ancient site in Pilibhît d., 39, 40 Balandshahr, tahsîl and head-quarters of d.
prastha, or Vakyapras-	Anciently and head-quarters of d.
* h o	Anciently named Banchhati,
Bagrârî, v. near Mahobâ in Hamîrpûr d., 331, 334	Baran, or Ahibaran 4
Bagrihât, old deserted t. near Lakhanpûr-	
77.64.2- 77	of the Mahabharata 4
Bagud, identified with Kakapar in Kanh-	Also called Ûnchânagar 4
nord with Kakupur in Kanh-	Occupied by Buddhists from
pår d 169 Båh, tahsil in Âgrå d 69	about A.D. 400 to 800, 4, 331
The last and the state of the last and the l	Occupied by Dôr Râjpûts in
Robbs - in Dat D. etc 1	the 11th century 5
	Baldêo, or Baladêva, t. in Mathurâ d 97
Bâharî Bhîtarî, see Bhîtargâon.	Balênî, old v. in Mîrath d 9
Bahât, v. in Sahâranpûr d.	Balirāj Atāhā, v. in Unão d 274
Indo-Scythic coins and Bauddha	Baliya, or Balar Pasiapar, deserted site in
remains excavated at 14	Pilibhît d 39, 40
Baheriya Dih, ancient deserted site in	Bâliyâ, tahsîl and head-quarters of d.
Basti d 224	Anciently named Vâlmîkîyâ 190
Bahlôlpår, ruined t. near Alamnagar in	Extensive ruined mounds at—, 190, 191
Hardôî d 277	Balmiar-Barkhar, v. in Kherî d.
Bâhmnî, v. in Gôrakhpûr d 241	Also called Bârîkhâr, Bar-
Bahraich, tahsil and head-quarters of d.	iya Kherâ, or Vairâta-
Locally said to be part of the an-	
cient Gandharvavana 292	Balnar v in Dilibited a
Also called Brahmaich 292	Balrampar, t. in Gonda d 40
Dargâh of Sâlar Sa'îd Masa'ûd at, 292, 293	Identified with the ancient
Bahrampur, t. in Bahraich d 293	DA
Bahûâ, v. în Fathpûr d 158	Râm gadha Gauda 302 Bâlôa Sarâî, v. in Banâras d.
Baijnath, or Vaidyanatha, pilgrimage	
place in Kumâon d.	Also called Paschimava-
Anciently named Karttike-	Bambhane w in Strange 196
yapura 47	Banâras, tahsîl and head-quarters of d 288
21b	Anciently and dead-quarters of d.
Bairant, v. in Banaras d.	Anciently named Varanasi 196
Locally identified with Vaira-	Also called Kāšî or Kāšikā 197
ta 195, 196	Called Muhammadâbâd by Aur-
Bairût-kê-dîh, old mounds near Sîtâpûr 290	angzib 198
Bairatnagar, ancient t. in Alwar State of	Extensive Buddhist remains
Râjputânâ 283	at
Bairauna Khas, v. in Gôrakhpûr d. 927	Dranmanical temples at 207_211
TENDED TO BE SEVENDED TO THE TENDE TENDED TO THE TENDED TO THE TENDED TO THE TENDED TO THE TENDED TO THE TENDED TO THE TENDED TO THE TENDED TO THE TENDED TO THE TENDED TO THE TENDED TO THE TENDED TO THE TENDED TO THE TENDED TO	Musalman buildings at
Daisuma, small t. in Mirath d. 10	Danoiragenni, v. in Pratapoarh d
Baitalgarh, ruined site near Gorakhpar d 247	Danchulan, ancient name of Ralandshah.
Bajherâ Kherâ, v. in Jalâon d.	tansii and head-quarters of d
Dakhauli, v. in Faizūbūd d.	Dandhanpur, v. m Faizābād d
	Bangama, v. near Barda Sacar in Thank 3
Daksovehilt w in II. A. 1	Section, L. III United d
Anciently named Vakāšrama, 268	Dangawan, v. near Dariyâbâd in Bâra
(b) Abbreviations: 1 - town	
(*) Abbreviations : +	200

Pages.	Pages.
Baniyâ Kherâ, v. in Murâdâbâd d 36	
Bânjhulâwan, old name of Joharganj in Ghâ-	TO IN THE PARTY AND THE PARTY
zîpûr d 233	The state of the s
Bankata, name of the tappa to the west of	70 4 1 77 411 2
Anāûlā in Görakhpûr d 237	70 7 1 1 1 1 1 1 1 1 1
Bankaulî, v. in Dêrâ Dûn d 8	D. LATE AND DESCRIPTION OF THE PROPERTY OF THE
Banpûr Khâs, large v. in Lalitpûr d., 119, 333	The state of the s
Bânsâ, v. near Mallâwân în Hardôî d 280	Barhalganj, small t. in Görakhpûr d 237 Barhâmpûr, v. in Fathpûr d.
Bânsdîh, tahsîl in Bâliyâ d 191	Mentioned by Alberûnî under the
Bânsgûon, tahsîl in Görakhpûr d 237	W 44 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2
Bânsî, tahsîl in Bastî d 217	The state of the s
Bâr, small v. în Lalitpûr d 119	Barhāpūr, v. in Ghāzīpūr d 227 Barhāpura, v. in Bijnōr d.
Bârd, tahsîl in Allahâbûd d 131	Ruined ancient city in forests
Do., old v. in Ghâzîpûr d 227	The second secon
Barâban, ruined mound at Bânsgâon in	70. 1
Gôrakhpûr d 237	
Båra Banki, tahsil and head-quarters of d.	70 74 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4
Formerly called Jasnaul 263	Barhîapûr, or Bhadar Khas, v. in Gôrakh-
Barâ Dâr, v. in Bastî d 222	-1-1
Barâ Dewâl, or Bar Dewâl, fine temple at	71.1
Barhâ-Kotrâ în Bândâ d. 146, 147	70 1
Barâgâon, deserted high cliff near Kutiyâ in	Bårîkhâr, or Barkhâr, v. in Kherî d. 38, 283
Fathpûr d 164	Bârî Pîhânî, t. in Hardôî d 281
Ditto, v. in Bâliyâ d 192	Bårîthâna, v. in Unâô d 268
Ditto, v. in Banâras d 212	Barkhår, or Bårîkhår, old v. in Kherî d., 38, 283
Ditto, v. near Bilgram in Hardôi d 278	Barkherå, old v. in Pilibhît d 38
Ditto, v. in Sltapar d 287	Bar-kî-bhârî, v. near Tandwâ in Bahrâîch d., 295
Ditto, t. in Faizābād d 302	Barmâyan, old v. in Bâliyâ d 191, 192
Barah Chhetra, deserted ancient site in	Barmdêo, or Brahmadêva, v. in Ku-
Bastf d.	mûon d 47
Anciently named Varahakshetra, 217	Barnawa, v. in Mîrath d.
Identified with the Vyaghrapuri	Identified with Varanavata
of the Puranas and the Koli of the	of the Mahâbhârata 9
Buddhist legends 217, 218	Barode, v. in Lalitpûr d 123.
Barâhî, old v. near Sârnâth in Banâras d.	Barsânâ, small t. in Mathurâ d 97
Anciently named Vajravarahi 214	Barsî Talâo, v. in Hamîrpûr d 174
Baraî, v. in Itah d 85	Barûâ Sûgar, t. in Jhânsî d., 114, 115
Do., v. in Pratapgarh d 316	Barwa, v. near Basti 218
Baráicha, ruined site in Górakhpar d 243	Barwân, v. in Hardôî d 277
Barainî, v. in Mîrzâpûr d 254	Barwar, t. in Kheri d 284
Baraiyapûr-Aphûî, v. in Faṭhpûr d 158	Basaurā, v. in Faizābād d 300
Baran, ancient name of Bulandshahr 4	Båsi, v. in Bijnor d 31
Barûon, v. near Rudrapûr in Gôrakhpûr d 250	Bâsimdhara, ruined fort at Basundra in
Barâ Topra, v. in Ambûla d. of Panjâb.	Îțâh d 85
Identified with the Tobra of	Basnî, v. în Banîras d 212
the Musalman chroniclers 16	Basohrå, ruined site near Nîr in Hardôî d 280
Barâwâ, v. in Bastî d 224	Bastî, tahsîl and head-quarters of d 218
Bar Dewâl, see Barâ Dewâl.	Basundrå, v. in Îtâh d 85

Pages.	Pages.
Batêsar, v. in Âgrâ d.	Bhankargarh, ancient site near Gandwa in
Anciently named Saryapura, 69, 331	II 345 1 000
Bathan, v. in Mathura d 98	Bhânkarî, v. near Bhûîlâ Dîh in Bastî d 218
Bâwân, v. in Hardôî d.	D1 5 - 25 - 2 - C - LiA - A - 3
Anciently named Mahabali-	Bhanwat on Bhamat as in Matanasa a co
pura 277	Rhardigh Kongell in Handat 2 and
Bâwarpāra, v. near Bhūîlā Dîh in Bastî d 218	Bhâratabhârî, the modern Bhârî in
Bazîdpûr, v. in Murâdâbâd d 38	Restt J one
Ditto, v. in Kanhpar d 165, 169	Bharaul w in Mathemat J
Bedå-Bedaunå, v. in Kânhpûr d 167	Rhargult w in Ganalshada 1
Beduwalî, v. near Bâliyâ 191	Ditto, v. formerly in Jhansi d. now in
Begamâbâd, v. in Mîrath d 9	PA ASSA
Begamganj, v. near Jaunpûr 183	Ditto 11 - PRIN N
Begethûâ, v. in Sulţânpûr d 326	Bhârauli-Gangâtîr, v. in Ghâzîpâr d.
Behtâ-Hâjîpûr, v. in Mîrath d 10	Wrongly identified with
Behtî, v. in Partâpgarh d 316	the Aranya of Fa
Bêl, v. in Kherî d 286	
Bêlâ, v. in Iṭâwah d 90	Bhâr Devâl, fine temple at Barhâ-Kotrâ in
Do., head-quarters of the Pratapgarh d 319	Bândâ d., 146, 147
Bêlkhârâ, v. in Mîrzâpûr d 252, 253	Bharêh, v. in Itawah d 90
Bênnagar, old ruined mound near Nimkhâr	Bhârgâon, or Bhârgâîn, or Bhârugâôn, v. in
in Sîtâpûr d 290	Past 3
Benûn, v. in Fathpûr d 165	Bhârgaih, small v. near Gaihwâl in Allahâ-
Bernî, v. in Murâdâbâd d 36	161/3
Besårh, t. in Muzaffarpûr d. of Bangâl.	Bhargavapura, identified with Khaira
Identified with the ancient Vaisali, 239	The state of the s
Bethuriyâ, v. in Faizâbâd d 301	Dih in Baliya d 194 Identified with Bhagal-
Bhadar Khas, v. in Górakhpar d 241	4 . 24
Bhadarsa, v. in Faizabad d 296, 300	Půr in Görakhpûr d., 239 Bhârî, v. in Bastî d.
Bhadaura, v. in Muradabad d 36	Andread 1 may 1 may 1
Bhadohî, ancient t. in Mîrzâpûr d., 254, 255	Distance J . 7041* 4 2
Bhador, ancient khera near Anapshahr in	Photo was Diana Day to The state
Bulandshahr d 4	Bhattapura, old village in Murada-
Bhadri v. in Partapgarh d 316	1.4.1.3
Bhagalanpûrwâ, small v. in Bândâ d 149	Photos - 1 fi
Bhûgalpûr, v. in Gôrakhpûr d.	Bhasana - to da as a s
Anciently named Bhargava-	Rhands Title D. t. As a .
pura 239	Philippen and the Philippen an
Bhâgûpûr, or Ganaur, v. in Sultânpûr d 328	Rhomon at 2 Dat D 14 1
Bhagvanpûr, v. in Saharanpûr d 14	Philippi - 1 Tree 4 2
Bhainsa Pokhara, ancient tank in Basti d 224	Phant Diana A 12 . as
Bhainskhêt v. in Kumâon d 47	Rhiberton months and the state of the state
The state of the s	
Dhaisand, or Dharsand, v. in Baliya d 192	Rhidon w in Editates
Bhander, old t. formerly in Jhansi d. now in	Dill Compose as a life at a s
Gwaliar territory 115	Pinterva w in U
Bhandirban, sacred grove near Mat in Ma-	Bhillagrama the
thurâ d 104	Bhillagrama, the modern Bilgram in Hardol d. 277
	Hardol d 277

Bhim Tal, lake in Kumāon d.,	Pages.	Pages.
Bhīngā, v. in Bahrāchē d	Bhîm Tâl, lake in Kumâon d., 47, 48	Bikaura, v. near Madanpûr in Lalitpûr d 124
Biltât, see Bithât		
Bhlitargåon, or Båharl Bhlitari, v. in Kāṇḥpur d. Formerly known as Phūlpor 165, 166	Bhîtâ, see Bithâ.	A CONTRACTOR OF THE PROPERTY O
pår d. Formerly known as Phål- pår 165, 166 Bhitari, v. in Ghàzipār d., 228—230, 334 Bhitaurā, v. in Barelī d 26 Bhiti, ruined site near Görakhpār 242 Bhōjgā, v. in Faizābād d 302 Bhōjpā, v. in Murādābād d 35 Ditto, v. in Farrukhābād d 35 Bhōnagāon, tahsīl in Māhpurī d 238 Bhōnagāon, tahsīl in Māhpurī d 238 Bhōja, v. in Görakhpār d 238 Bhōjā, v. in Görakhpār d 238 Bhōjā, v. in Görakhpār d 238 Bhōjā, v. in Görakhpār d 238 Bhōjā, v. in Görakhpār d 238 Bhōjā, v. in Görakhpār d 238 Bhōjā, v. in Görakhpār d 218—223 Bhōjā, v. in Kherī d 284 Bhūragarh, ruined fort in Bāndā d 146 Bhūragarh, ruined fort in Bāndā d 146 Bhūragarh, ruined fort in Bāndā d 146 Bhūragarh, v. in Raphār d 258 Bibājār, v. in Raphār d 268 Bibājār, v. in Bāndā d 274 Bibhār, v. in Kherī d 284 Bhūragarh, v. in Kaphpār d 268 Bibhār, v. in Bandā d 274 Bibhār, v. in Kaphpār d 268 Bibhār, v. in Hardōī d 275 Bibhār, t. in Unāo d 276 Bibar, v. in Hardōī d 271 Ldentified with the 'O-yu-t'o of Hiuen Tsiang 271 Do., t. in Pratipgarh d 36 Also called Patan-Bihār 314, 315 Probably the 'O-ye-mu-khi of Hiuen Tsiang 271 Do., see Pakhnā-Bihār 314, 315 Probably the 'O-ye-mu-khi of Hiuen Tsiang 271 Bibhār, v. in Murādābād d 36 Bijaygarh, hīll fort in Mīrzāpār d. 256, 257, 334 Bijgāon, v. in Hardōī d 36 Bijaygarh, till fort in Mīrzāpār d. 256, 257, 334 Bijgāon, v. in Hardōī d 36 Bijaygarh, till fort in Mīrzāpār d. 256, 257, 334 Bijgāon, v. in Hardōī d 36 Bijaygarh, v. in Bandā d 36 Bijaygarh, v. in Bandā d 36 Bijaygarh, v. in Hardōī d 36 Bijaygarh, v. in Bandā d 36 Bijaygarh, v. in Bandā d 36 Bijaygarh, v. in Bandā d 36 Bijaygarh, v. in Bandā d 36 Bijaygarh, v. in Bandā d 36 Bijaygarh, v. in Bandā d 36 Bijayarh, v. in Bandā d 36 Bijayarh, v. in Bandā d 36 Bijayarh, v. in Bandā d 36 Bijayarh, v. in Bandā d 36 Bijayarh,	Bhîtargâon, or Bâharî Bhîtarî, v. in Kânh-	
Formerly known as Phalipara 165, 166	pûr d.	
Bhîtarî, v. in Barelî d. 228-239, 334	Formerly known as Phûl-	Company of the Compan
Bhitarf, v. in Gházþar d., 228—230, 334 Shitarf, v. in Bareli d. 268 242 242 242 242 242 242 242 243 242 243 243 244 245	pûr 165, 166	
Bhitaurâ, v. in Barell d	Bhîtarî, v. in Ghâzîpûr d., 228—230, 334	
Bhôtig, ruined site near Górakhpûr 242 Bhôjgh, v. in Faizábâd d.	Bhitaurâ, v. in Barelî d 26	The transfer of the second sec
Bhôjgh, v. in Fairabhâd d	Bhîtî, ruined site near Gôrakhpûr 242	TOTAL CONTRACTOR OF THE PROPERTY OF THE PROPER
Bhôpar, v. in Muradabad d	Bhôjgî, v. in Faizābād d 302	
Binkaurā-Sakaṇṭhā, v. in Bahrāfeh d.	Bhôjpûr, v. in Murâdâbâd d 35	The second of th
Bibongâon, tahsîl in Mâînpurî d 93 Bibongâon, tahsîl in Mâînpurî d 238 Bhôpâ, v. in Gorakhpûr d 238 Bhôpâ, v. in Gorakhpûr d 238 Bhûllâ Dîh, deserted ancient site in Bastî d.	Ditto, v. in Farrukhâbâd d 77	Bilharîyâ Math, rocky hill in Bândâ d 149
Bhôpā, v. in Gōrakhpūr d	Bhokaurâ-Sakanthâ, v. in Bahrâîch d 293	Bilhaur, tahsîl in Kânhpûr d 168
Bhâilâ Dîh, deserted ancient site in Bastî d. Wrongly identified with Kapi- lavastu 218—223 Bhâilî, ancient v. in Mîrzapûr d. 255, 256 Bhûlî, ancient v. in Mîrzapûr d. 255, 256 Bhûlî, ancient v. in Mîrzapûr d. 255, 256 Bhûr, v. in Kherî d 284 Bhûragarh, ruined fort in Bândâ d 146 Bhûragarh, ruined fort in Bândâ d 146 Bhûragarh, ruined fort in Bândâ d 146 Bhûragarh, v. in Bândâ d 146 Bhûragarh, v. in Bândâ d 146 Bhûragarh, v. in Hardôî d. 278 Bibâhûrâ, tahslî in Itâwah d 278 Bibâhûnâ, tahslî in Itâwah d 90 Bihâr, t. in Unâo d.	Bhongâon, tahsîl in Mâînpurî d 93	Bilkhâr, ruined fort at Yahyâpûr in Pratâp-
Bhûll, ancient v. in Mirzāpūr d. 218—223	Bhôpâ, v. in Gôrakhpâr d 238	garh d 318
Birâm, t. in Îtâh d. 1a va st u 218—223	Bhûîlâ Dîh, deserted ancient site in Bastî d.	Bilkhâwân, v. in Faizâbâd d 301
Bhûll, ancient v. in Mîrzâpûr d. 255, 256 Bhûkharhêrî, v. in Muzaffarnagar d. 12 Bhûr, v. in Kherî d. 284 Bhûragarh, ruimed fort in Bândâ d. 146 Bhûragarh, ruimed fort in Bândâ d. 146 Bhûragarh, ruimed fort in Bândâ d. 146 Bhûragarh, ruimed fort in Bândâ d. 146 Bhûragarh, v. in Bândâ d. 278 Biblâpûr, v. near Bilgrâm in Hardôî d. 278 Bibl Kherâ, v. in Hardôî d. 278 Bibl Kherâ, v. in Hardôî d. 278 Biblahâpûr, v. in Kânhpûr d. 168 Bidhûnâ, tahsîl in Itâwah d. 90 Bihâr, t. in Unâo d. 4 4 4 4 4 4 4 4 4	Wrongly identified with Kapi-	The state of the s
Bhûkharhêrî, v. in Muzaffarnagar d.	lavastu 218-223	Bilsar, or Bilsand, small v. in Îtâh d.
Bhûr, v. in Kherî d	Bhûllî, ancient v. in Mîrzâpûr d. 255, 256	
Bhûragarh, ruined fort in Bândâ d. 146 Binûraliyâ, v. inear Kasiâ in Gôrakhpûr d. 247 Bhûrendî, v. in Bândâ d.	Bhûkharhêrî, v. in Muzaffarnagar d 12	n a of Hiuen Tsiang 86
Bhûrendî, v. in Bândâ d	Bhûr, v. in Kherî d 284	Bilwâî, v. in Sultânpûr d 326
Bibîâpûr, v. near Bilgrâm in Hardôî d 278	Bhûragarh, ruined fort in Bândâ d 146	Binâoliyâ, v. near Kasîâ in Gôrakhpûr d 247
Bibi Kherâ, v. in Hardôi d 279 chala 257	Bhûrendî, v. in Bândâ d 146	Bindhâchal, large v. in Mîrzâpûr d.
Bichhiâpâr, v. in Kânhpâr d 168 Identified with the city of Bidhânâ, tahsîl in Iţâwah d 90 Pampâpura 257 Bihâr, t. in Unâo d. 271 Bindkî, t. in Faṭhpâr d 159 Also called Pâtan-Bihâr 271 Bîrgarh, small fort in Bândâ d 149 Birgarh, small fort in Bândâ d 149 Bîrhar, v. in Faizâbâd d 300 Hiuen Tsiang 271 Bîrpûr, v. near Râsin in Bândâ d 155 Probably the 'O-ye-mu-khi of Hiuen Tsiang 314, 315 Ditto, v. near Bhûllâ Dîh in Bastî d 221 Do., see Pakhnâ-Bihâr. Bisâhî, v. in Itâwah d 90 Bijaurâ, v. in Murâdâbâd d 36 Bijaygarh, hill fort in Mîrzâpâr d., 256, 257, 334 Bisaurâ Buzurg, v. in Bândâ d 147 Bijagâon, v. in Hardôî d 283 Bîjnôr, tahsîl and head-quarters of d. Anciently named Vijayanaga-ram 287 Bijnôr, tahsîl in Sîtâpâr d 287 Bithâ, or Bhîtâ, small v. in Allahâbâd d 287 Bithâ, or Bhîtâ, small v. in Allahâbâd d 287 Bithâ, or Bhîtâ, small v. in Allahâbâd d	Bîbîâpûr, v. near Bilgrâm în Hardôî d 278	Anciently named Vindhya-
Bidhûnâ, tahsîl in Itâwah d. 90 Pampâpura 257 Bihâr, t. in Unâo d. 271 Bindkî, t. in Fathpûr d. 159 Also called Pâtan-Bihâr 271 Bîrgarh, small fort in Bândâ d. 149 Birdhâr, t. in Pathpûr d. 300 Bîrarân, small fort in Bândâ d. 300 Hiuen Tsiang 271 Bîrpûr, v. near Bândâ d. 155 Probably the 'O-ye-mu-khi of Hiuen Tsiang 314, 315 Ditto, v. near Bhûllâ Dîh in Bastî d. 230 Brylarê, v. in Agrâ d. 69 Bisâlpûr, v. in Lîâwah d. Bijaurâ, v. in Murâdâbâ d.	Bîbî Kherâ, v. in Hardôî d 279	chala 257
Bihâr, t. in Unão d. Also called Pâtan-Bihâr 271 Identified with the 'O-yu-t'o of Hiuen Tsiang 271 Do., t. in Pratâpgarh d. 271 Also called Tusârân-Bihâr, Sûâ-Bihâr, or Sûba-Bihâr 314, 315 Probably the 'O-ye-mu-khi of Hiuen Tsiang 315 Do., see Pakhnâ-Bihâr. 315 Bihishtâbâd, another name of Sikandrâ in Âgrâ d. 76 Bijaurâ, v. in Murâdâbâd d. 36 Bijaygarh, hill fort in Mîrzâpâr d., 256, 257, 334 Bisaurâ Buzurg, v. in Bândâ d. 157 Bisaurâ Buzurg, v. in Bândâ d. 287 Bijaygarh, thill fort in Mîrzâpâr d., 256, 257, 334 Bisaurâ Buzurg, v. in Bândâ d. 287 Bijaygarh, thill fort in Mîrzâpâr d., 256, 257, 334 Bisaurâ Buzurg, v. in Bândâ d. 287 Bijpâon, v. in Hardôl d. 283 Bishangarh, v. in Farrukhâbâd d. 287 Bijnôr, tahsîl and head-quarters of d. Anciently named Vijayanaga-ram 30 Bithâ, or Bhîtâ, small v. in Allahâbâd d. Anciently named Bithâbâd d. 287 Bithân, or Bhîtâ, t. in Faṭhpâr d. 30 Birana name 315 Birana name lo sitabâd d. 287 Bisaurâ pâr d. 287 </td <td>Biehhiapar, v. in Kanhpar d 168</td> <td>Identified with the city of</td>	Biehhiapar, v. in Kanhpar d 168	Identified with the city of
Also called Pâtan-Bihâr 271 Identified with the 'O-yu-t'o of Hiuen Tsiang 271 Do., t. in Pratâpgarh d. Also called Tusârân-Bihâr, Sûâ-Bihâr, or Sûba-Bihâr 314, 315 Probably the 'O-ye-mu-khi of Hiuen Tsiang 315 Do., see Pakhnâ-Bihâr. Bihishtâbâd, another name of Sikandrâ in Âgrâ d 76 Bijaurâ, v. in Murâdâbâd d 36 Bijaygarh, hill fort in Mîrzâpûr d., 256, 257, 334 Bijaôn, v. in Hardôl d 283 Bijnôr, tahsîl and head-quarters of d. Anciently named Vijayanaga-ram 30 Ditto, t. in Lakhnâû d 265 Bîtrân, v. in Faizâbâd d 300 Bîrhar, v. in Bândâ d 360 Bîrhar, v. in Bândâ d 360 Bîrhar, v. in Bândâ d 360 Bîrhar, v. in Bândâ d 360 Bîrhar, v. in Bândâ d 360 Bîrhar, v. in Bândâ d 360 Bîrhar, v. in Bândâ d 360 Bîrhâr, v. in Ghâzîpûr d 230 Bîrthalâ, v. in Âgrâ d 360 Bîsâlpûr, tahsîl in Pilibhît d 38 Bisaulî, tahsîl in Badâon d 287 Bishangarh, v. in Farrukhâbâd d 377 Bishangarh, v. in Farrukhâbâd d 378 Bishangarh, v. in Farrukhâbâd d 379 Bishân, or Bhîtâ, small v. in Allahâbâd d 370 Bithâ, or Bhîtâ, small v. in Allahâbâd d 370 Bithâ, or Bhîtâ, small v. in Allahâbâd d 370 Bithâ, or Bhîtâ, small v. in Allahâbâd d 370 Bithâ, or Bhîtâ, small v. in Allahâbâd d 370 Bithâ, or Bhîtâ, small v. in Allahâbâd d 370 Bithân, v. in Farrukhâbâd d 387 Bishangarh, v. in Farrukhâbâd d 387 Bishangarh, v. in Farrukhâbâd d 387 Bithâ, or Bhîtâ, small v. in Allahâbâd d 387 Bithân, or Bhîtâ, small v. in Allahâbâd d 387 Bithân, or Bhîtâ, small v. in Allahâbâd d 387 Bithân, or Bhîtân and Bithâbâd d 388 Bithân, or Bhîtân and Baithâbâd d 387 Bithân and Baithâbâd d 388 Bithân, v. in Faizâbâd d 388 Bishangarh, v. in Faizâbâd d 388 Bishangarh, v. in Faizâbâd d 388 Bishangarh, v. in Faizâbâd d 388 Bithân, v. in Bândâ d 388 Bishangarh, v. in Faizâbâd d 388 Bithân, v. in Bândâd d 388 Bishangarh, v. in Faizâbâd d 388 Bithân another in Bân	Bidhûnâ, tahsîl in Iṭâwah d 90	Pampapura 257
Identified with the 'O-yu-t'o of Hiuen Tsiang		Bindkî, t. in Fathpûr d 159
Hiuen Tsiang .	Also called Pâtan-Bihâr 271	Birgarh, small fort in Bândâ d 149
Do., t. in Pratâpgarh d. Also called Tusârân-Bihâr, Sûâ-Bihâr, or Sûba-Bihâr Bîrpûr, v. near Râsin in Bândâ d.		Bîrhar, v. in Faizâbâd d 300
Also called Tusàrân-Bihâr, Sââ-Bi- hâr, or Sâba-Bihâr 314, 315 Probably the 'O-ye-mu-khi of Hiuen Tsiang 315 Do., see Pakhnâ-Bihâr. Bihishtâbâd, another name of Sikandrâ in Âgrâ d 76 Bijaurâ, v. in Murâdâbâd d 76 Bijaygarh, hill fort in Mîrzâpâr d., 256, 257, 334 Bîjagâon, v. in Hardôl d 283 Bîjaya an hall and head-quarters of d. Anciently named Vijayanaga- ram 30 Ditto, v. near Bhâllâ Dîh in Bastî d 230 Bîrthalâ, v. in Âgrâ d 230 Bîrthalâ, v. in Âgrâ d 99 Bîsâlpâr, tahsîl in Pilibhît d 38 Bisaurâ Buzurg, v. in Bândâ d 23 Bisaurâ Buzurg, v. in Bândâ d 98 Bishangarh, v. in Sîtâpâr d 287 Bishangarh, v. in Farrukhâbâd d 77 Bishân, or Bhîtâ, small v. in Allahâbâd d 287 Bithâ, or Bhîtâ, small v. in Allahâbâd d. Anciently named Bithâbhaya- paṭṭana 131	Hiuen Tsiang 271	Bîriâ, v. in Bândâ d 155
hâr, or Sûba-Bihâr 314,315 Ditto, v. în Ghâzîpûr d. 230 Probably the 'O-ye-mu-khi of Hiuen Tsiang 315 Bîrthalâ, v. în Âgrâ d. 69 Bo, see Pakhnâ-Bihâr. Bisâhî, v. în Itâwah d. 90 Bihishtâbâd, another name of Sikandrâ în Âgrâ d. 56 86 Bijaurâ, v. în Murâdâbâd d. 69 86 Bijaurâ, v. în Murâdâbâd d. 69 86 Bijaygarh, hill fort în Mîrzâpâr d. 76 86 Bijaygarh, hill fort în Mîrzâpâr d. 256, 257, 334 86 86 Bîjaygarh, tahsîl and head-quarters of d. 283 86	Do., t. in Pratapgarh d.	Bîrpûr, v. near Râsin în Bândâ d 157
Probably the 'O-ye-mu-khi of Hiuen Tsiang 315 Bîrthalâ, v. in Âgrâ d. 69 Do., see Pakhuâ-Bihâr. Bihishtâbâd, another name of Sikandrâ in Âgrâ d. Bîsâlpâr, tahsîl in Pilibhît d. 38 Bijaurâ, v. in Murâdâbâd d. 76 Bisaurâ Buzurg, v. in Bândâ d. 147 Bijaygarh, hill fort in Mîrzâpâr d., 256, 257, 334 Bisendî, v. in Sîtâpâr d. 287 Bîjnôr, tahsîl and head-quarters of d. 283 Bishangarh, v. in Farrukhâbâd d. 287 Bijnôr, tahsîl and head-quarters of d. Biswân, tahsîl in Sîtâpûr d. 287 Bithâ, or Bhîtâ, small v. in Allahâbâd d. 287 Bithâ, or Bhîtâ, small v. in Allahâbâd d. 287 Bithâ, or Bhîtâ, small v. in Allahâbâd d. 287 Bithâ, or Bhîtâ, small v. in Allahâbâd d.	Also called Tusårån-Bihår, Såå-Bi-	Ditto, v. near Bhaila Dih in Basti d 221
Hiuen Tsiang 315 Do., see Pakhnâ-Bihâr. Bihishtâbâd, another name of Sikandrâ in	hâr, or Sûba-Bihâr 314, 315	Ditto, v. in Ghâzîpûr d 230
Do., see Pakhnâ-Bihâr. Bihishtâbâd, another name of Sikandrâ in Âgrâ d 76 Bijaurâ, v. in Murâdâbâd d 36 Bijaygarh, hill fort in Mîrzâpâr d., 256, 257, 334 Bijaygarh, v. in Hardôl d 283 Bijayan, v. in Hardôl d 283 Bijayan, v. in Hardôl d 283 Bijayan, v. in Hardôl d 283 Bijayan, v. in Hardôl d 283 Bijayan, v. in Farrukhâbâd d 77 Bijnôr, tahsîl and head-quarters of d. Anciently named Vijayanaga- ram 30 Ditto, t. in Lakhnâû d 265	Probably the 'O-ye-mu-khi of	Bîrthalâ, v. in Âgrâ d 69
Bihishtâbâd, another name of Sikandrâ in Âgrâ d 76 Bijaurâ, v. in Murâdâbâd d 36 Bijaygarh, hill fort in Mîrzâpâr d., 256, 257, 334 Bijagâon, v. in Hardôl d 283 Bîjaôn, v. in Hardôl d 283 Bîjnôr, tahsîl and head-quarters of d. Anciently named Vijayanaga- ram 30 Ditto, t. in Lakhnâû d 265	Hiuen Tsiang 315	Bisâhî, v. in Itawah d 90
Âgrâ d. 76 Bisaurâ Buzurg, v. in Bândâ d. 147 Bijaurâ, v. in Murâdâbâd d. 36 Bisâwar, t. in Mathurâ d. 98 Bijaygarh, hill fort in Mîrzâpûr d., 256, 257, 334 Bisendî, v. in Sîtâpûr d. 287 Bîjnôr, tahsîl and head-quarters of d. 283 Bishangarh, v. in Farrukhâbâd d. 77 Bişwân, tahsîl în Sîtâpûr d. 287 Bithâ, or Bhîtâ, small v. in Allahâbâd d. 287 Bithâ, or Bhîtâ, small v. in Allahâbâd d. paṭṭana 131	Do., see Pakhnâ-Bihâr.	Bîsâlpûr, tahsîl in Pilibhît d 38
Bijaurâ, v. in Murâdâbâd d 36 Bijaygarh, hill fort in Mîrzâpûr d., 256, 257, 334 Bîjgâon, v. in Hardôl d 283 Bîjpâon, v. in Hardôl d 283 Bîjnôr, tahsîl and head-quarters of d. Anciently named Vijayanaga- ram 30 Ditto, t. in Lakhnâû d 265 Bisâwar, t. in Mathurâ d 98 Bisâwar, t. in Mathurâ d 287 Bishangarh, v. in Farrukhâbâd d 287 Bishangarh, v. in Farrukhâbâd d 287 Bishân, tahsîl in Sîtâpûr d 287 Bithâ, or Bhîtâ, small v. in Allahâbâd d 287	Bihishtabad, another name of Sikandra in	Bisaulî, tahsîl in Badâon d 23
Bijaygarh, hill fort in Mîrzâpûr d., 256, 257, 334 Bijagûon, v. in Hardôl d 283 Bijnôr, tahsîl and head-quarters of d. Anciently named Vijayanaga- ram 30 Ditto, t. in Lakhnâû d 265 Bisendî, v. in Sîtâpûr d 287 Bishangarh, v. in Farrukhâbâd d 287 Bishangarh, v. in Farrukhâbâd d 287 Bishangarh, v. in Sîtâpûr d 287	9	Bisaurâ Buzurg, v. in Bândâ d 147
Bîjgâon, v. in Hardôl d 283 Bishangarh, v. in Farrukhâbâd d 77 Bîjnôr, tahsîl and head-quarters of d. Anciently named Vijayanaga- ram 30 Ditto, t. in Lakhnâû d 265 Bishangarh, v. in Farrukhâbâd d 287	Bijaurā, v. in Murādābād d 36	Bisâwar, t. in Mathurâ d 98
Bîjnôr, tahsîl and head-quarters of d. Anciently named Vijayanaga- ram 30 Ditto, t. in Lakhnâû d 265 Biswîn, tahsîl in Sîtâpûr d 287 Bithâ, or Bhîtâ, small v. in Allahâbûd d. Anciently named Bithâbhaya- paṭṭana 131	Bijaygarh, hill fort in Mîrzâpûr d., 256, 257, 334	Bisendî, v. in Sîtâpûr d 287
Anciently named Vijayanaga- ram 30 Ditto, t. in Lakhnaû d 265 Bithâ, or Bhîtâ, small v. in Allahâbâd d. Anciently named Bithâbhaya- paṭṭana 131	Bijgåon, v. in Hardôl d 283	Bishangarh, v. in Farrukhabad d 77
ram 30 Anciently named Bithâbhaya- Ditto, t. in Lakhnâû d 265 paṭṭana 131	Bîjnôr, tahsîl and head-quarters of d.	Biswan, tahsîl in Sîtapar d 287
Ditto, t. in Lakhnaû d 265 pattana 131	Anciently named Vijayanaga-	Bithå, or Bhîtâ, small v. in Allahâbâd d.
	ram 30	Anciently named Bithabhaya-
Bîkar, small v. în Allahâbâd d 134 Ruins of extensive city at— 131—134	Ditto, t. in Lakhnaû d 265	
	Bîkar, small v. în Allahâbâd d 134	Ruins of extensive city at— 131—134

Pa	iges.		Pages
Bithâ, v. in Sultânpûr d	326	Chandes v near Sande in II - 100 2	- Commence
TOTAL A L C TEACH A	168	Chandinar w in Painthat a	755
D. H.	278	Chandrage toheal in Dana A	
TO AA	278	Ditto mined to the Co. I at a	- 11
D 1 401 - 11 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	292	Ditto decented t in Tuliant 3	8 1-2
Brahmadêva, v. in Kumâon d	47	Chandraban, sacred grove near Jaswara in	119
Brahmapura, identified with the ruined		Mathina J	
city near Pânduwâlâ in		Chandrauti, old v. near Banâras.	101
Garhwâl d	46	Anciently - 1 Ct	
Brahmāvarta, sacred spring near Sandi	200	Anciently named Chandra-	
A 120 CO CO CO CO CO CO CO CO CO CO CO CO CO	282	Chandaliana VI	212
Brindaban, or Vrindavana, t. in Mathu-		Chandrésvar Kherâ, ancient mound near	
ra d 98—1	00	Alîpûr in Murûdâbûd d	38
DAA DIII	221	Chandrikapuri, old name of Sahet-	
TV 133 A 17 A T	21	Mahet, or Śra-	
D. H.A.A. F. CHA.L. A.	33	Wastî	308
D		Chandua, v. in Bastî d	226
	48	Chandwâr, ruined city near Firâzâbâd in	
C.		Ågrå d	74
Châchakpûr, suburb of Jaunpûr 1		Changarkha, v. in Kumaon d	49
Chahârdah, see Chardâ.	81	Chaoni Sadr, or Kampū, the new civil station	
	- 1	of Sultanpûr	328
Châh Shikasta, police outpost on the Dêori-	44	Châorâ, v. in Gôrakhpâr d	
yâ road in Gôrakhpûr d 2	48	Charali, v. in Kanhpar d	168
Châtl, v. in Allahâbâd d 1:	34	Charanâdrigadha, the modern Chunâr	4110
Dhakarnagar, v. in Itawah d.		in Mîrzâpûr d., 258-	-260
Identified with Ekachakra		Charda, or Chahardah, v. in Bahraich d	203
of the Mahabharata (90	Charna, v. in Hamîrpûr d	173
Phakésar, v. in Ázamgarh d 18	88	Chotmahhani ald The same	50
Zhakiâ, v. in Mîrzâpûr d 25	57	Chatnehhuinda - I D	213
hak Jangili, v. in Sultanpür d 32	88	Chaukandî, name of the great brick stûpa	210
hak-Pihana, v. near Asnî în Fathpûr d 15	57	at Sårnåth near Banåras	01#
hakra Bhandar, v. near Sahet-Mahet in		Chaukâpârpûr, v. near Mânikpûr in Pratâp-	210
Gonda d 31	11	Chicago III and Chicago III an	W. T. O.
hakratîrtha, sacred pool at Nimkhâr		Chaukî, hamlet near Shâhpûr in Mathurâ d.,	318
in Sîtâpûr d 29	00	Ditto, deserted site near Aphûî in Fath-	111
hampâchal, deserted hill-fort in Kumâon d., 4	17	nûr d	1252
hampânagar, t. in Bhâgalpûr d. of Bangâl.		Chaummuhâ, v. in Mathurâ d.	157
Wrongly identified with the			
city of Malini 30	14	Formerly known as Akbar-	
hampavat, tahsil in Kumaon d 4		Chemiles	100
hampavati, ancient name of Haswa		Chauikā, v. in Fathpûr d	161
in Fathpûr d 16	1	Chayanpûr, v. in Mîrzâpûr d	253
hanayagaon, v. in Kumaon d. 4		Chen-chu, kingdom, mentioned by Hiuen	
handana - i- D. at at a	0	Tsiang.	
handsa - in Det D. 16 1	VI III	Identified with Ghazipûr	231
handanli takali :- D - t 7		Ditto, with Sa'ldpûr in	
handdyan old a in Managaran		CILARA	236
hande - in Det. A. 3		Ditto, with Uddharanpûr	
30)	in Ghâzîpûr d	nna

INDICES. 401

Pages.	Pages.
Chêr, v. in Jalâun d 114	Daryābād, v. in Bāra Banki d 263
Chetiya, ruined mound near Narayanpar in	Dasaulî, v. în Fathpûr d.
Ghâzîpûr d 234	Anciently named Dosahalf 165
Chetiyâon, small v. in Gôrakhpûr d.	Dâûdpûr, v. in Pratâpgarh d 319
Identified with the Pawa of the	Daulêsvar, v. in Îtâh d 86
Buddhist legends 239, 240	Daundia Khera, dilapidated fort in Unão d.
Chhahiri, hamlet near Mat in Mathura d 104	Wrongly identified with the
Chhâtâ, tahsîl in Mathurâ d 100	captital of the kingdom
Ditto, v. in Bâliyâ d 192	of Hayamukha 268
Chhibramaa, tahsal in Farrukhabad d 77	Dêh v. in Kumûon d 49
Chhotî Pihânî, t. in Hardôî d 281	Dêhduâr, v. in Âzamgarh d 189
Chilaulâ, v. in Rât Barelî d 323	Dekaulî, v. in Bahrâich d 293
Chilla, small v. in Allahabad d., 134, 135	Dendâ Sâî, v. in Fathpûr d 159
Chimrawa Dih, deserted ancient site in	Dêoband, tahsîl in Sahâranpûr d.
Bastî d 224	Traditional residence of the Pan-
Chipula, deserted hill fort in Kumaon d 47	dayas during their first exile14, 15
Chirâiyakôt, v. in Âzamgarh d.	Dêodî, v. in Faizâbâd d 302
Formerly called Mubarakpar 187	Dêogâon, tahsîl în Âzamgarh d 188
Chiriyâ Bhawân, v. in Murâdâbâd d 36	Dêogarh, old deserted site in Lalitpûr d.
Chît Fîrûzpûr, v. in Bâliyâ d 192	Anciently named Kirttigiri-
Chitrakûta, celebrated hill in Bândâd.	dûrga 119-121, 333
Also known as Kamada-	Dêokâlî, hill near Îrichh in Jhânsî d 118
giri, 147, 148	Ditto, v. near Kheri 285, 286
Chorhân-kâ-Mâû, old name of Mohanlâlganj	Dêokhan, ruined t. near Nânpâra in Bah-
in Lakhnåû d 267	râîch d 294
Chûâtarîyû, v. in Gôrakhpûr d 241	Dôolâs, v. in Âzamgarh d 190
Chunar, tahsîl and hill-fort in Mîrzâpûr d.	Dêomâî, v. in Fathpûr d 159
Anciently named Charanadri-	Dêorakh, v. in Allahâbâd d 131
gadha 258—260	Dêorakôt, v. in Faizâbâd d 301
D.	Dêorâmghât, old ghât (ferry) in Bastî d.
Dabhā, v. near Bhūflā Dih in Bastī d 218	Anciently named Devarama, 218
Dabhãon, v. in Azamgarh d 188	Dêorî, deserted v. in Bâliyâ d 191
Dedågåon, v. in Kumåon d 48	Dêoriya, v. in Pilibhît d.
Dadhwamanpar-Garrampar, v. in Banda d 148	Anciently named Mayata38, 39
Dåhar, large lake near Såndî in Hardoî d 282	Ditto, small v. in Allahabad d. 131, 132
Dalêlganj, v. near Allahâbâd 130	Ditto, tahsîl in Gôrakhpûr d 241
Dalel Khera, hamlet of Barhat in Fath-	Dêrê, tahsîl and head-quarters of Dêrah
pûr d 160	Dûn d 7
Dâlmâû, tahsîl in Râî Barelî d., 320—322	Do., v. in Sultanpar d.
Dalvî, v. in Bâra Baŭkî d 263	Originally called Dipanagaram, 327
Damgarh, v. in Allahâbâd d 143	Dêrâpûr, tahsîl in Kanhpûr d 168
Danahå, ruined mound in Görakhpår d 240	Dêrî Dhûrâ, or Dêh, v. in Kumâon d 49
Dândûpûr, v. in Banâras d 212	Dêvarâma, the modern Dêorâmghât in
Dankaur, v. in Bulandshahr d 6	Bastî d 218
Danyâlganj v, in Hardôl d 277	Dêvîganj, v. in Pratâpgarh d 316
Dârânagar, v. near Karrâ în Allahâbâd d, 139	Dêvî-Pâṭan, v. in Goṇḍâ d.
Darbhavati, identified with Dibhili in	Identified with the ancient city
Bulandshahr d 6	of Malini 303, 304
2000 PACE 14 (2000 TO 1000 TO	CONTRACTOR CONTRACTOR

Pag	Page
Dêvîpûr, v. in Kumâon d	50 Dôl v in Kumban 3
Dêwâ, t. in Bâra Bankî d 20	33 DAmanoonh mind 2 Gt 1 4
Dêwâl, v. in Pilibhît d 38 :	39 Domardus Dit 24
Dêwâlgarh, v. in Garhwâl d	
Dhamaur, v. in Sultanpûr d 2:	Trusti I Danda d.
Dhamek, name of great stone stone at San	Tath-
nâth near Banâras 213, 21	4 Dronghus par d 16
Dhomes as in Table 1	Dalikhur in
Dhanapûr, v in Ghâzîpûr d 23	John Marian L.
Dhanauraghat, ancient site in Pilibhit d 4	which we in Light DBF (1)
Dhanâwar, ancient ruined site in Ghâzîpûr d.	Indicately named Dugdhakun-
Formerly called Dhanapura, 23	yagrama 995
Discourage we am II 188 1	Ancient Hindû temples at 191 too
Dharmanaki 11 : Day a	Jugaon, ruined t. near Nanpara in Bahraich d
Dharmaôlî, v. in Bâliyâ d 3.	Also called Deokhan 904
Anciently called Dharma-	Dumri, v. in Banaras d.
The same	Dundhgarh, ancient name of Dibbat
Dharmanattana 191	Dungarpur, v. in Bareli d.
Dharmapattana, another name of	Durga Khô, inscribed cave near Changa in
Dhamanan Dili Sravasti 312	Mirzapûr d. ogo
Dharmaranya Pokhara, ancient tank at	Dyaraka mined fort in C 1.4
Bâliyâ 191	326 326
Dhârûpûr, v. in Pratâpgarh d 316	E.
Dhàtâ, v. in Fathpûr d 159	
Dhaurahra, t. in Kheri d 284	Ekachakra, identified with Chakarnagar
Ditto, v. in Faizābād d 301	in Itawah d
Dhikuli, v. in Kumaon d.	Wrongly identified with Ara
Identified with Vairatapatta-	or Arâmnagar in Shâhâ-
na, the capital of Govikana 40	båd d. of Bangal
Dholf Askaran, v. in Faizābād d. 809	EKR, V. III Mainnned d
Dhopap, famous pilgrimage place in Sultan-	93
pûr d.	F.
Anciently named Dhûtapâpa-	
рига 296 907	Faizābād, v. in Sahāranpūr d 17
Dhuriâpâr, v. in Gôrakhpâr d 241	Ditto, tahsil and head-quarters of A one not
Dibhâî, old t. in Bulandshahr d.	Fâjila, or Fâzilnagar, v. in Gôrakh-
Anciently named Darbhamata	pür d.
DDnor, hamlet in Mingenan J	Fakhrpûr, t. in Bahrâseh d.
Othri, v. in Mnradahad d	randnagar, v. in Muradahad d
Oildårnagar, v. in Ghåzîpûr d 36	Pariapur-Kasim, v. in ditto
Anciently named Akhan-	rarrukhabad, t. in Farrukhabad a
4 1 0	Fathâbâd, tahsîl in Âgrâ d 77
Diléronni v in Pratéronal 3	Formerly named Zafa-
Dilwarî, v. near Râmnagar in Barelî d 29	Scene of Appropriate 69
India was Hamban A. A.	Scene of Aurangzîb's victory over Dârâ Shikôh
hindfron - in Manager 170	Fathganj West, v. in Bareli d 26
hindârpûr, v. in Murâdâbâd d 36	Fathgarh, head most 26
îpanagara, ancient name of Dêrâ in	Fathgarh, head-quarters of Farrukhâbâd d., 78 Ditto, ruined citadel 78
Sultanpur d. now	citadel near Pains in
AND PROPERTY AND ADDRESS OF THE PARTY OF THE	Fainnin d
ohrighât, t. in Azamgarh d 188	Fath Karrâ, v. in Kherî d 160

Pages.	Pages.
Fathpûr, tahsîl and head-quarters of d. 159, 160	Garjapatipura, identified with Ghazîpûr, 231
Ditto, tahsil in Bara Banki d. 263, 264	Garwar, v. in Bâliyâ d 192
Fathpûr-Islâmâbâd, Musalmân name of	Gauda, identified with the modern Gonda, 304
Såndî in Hardôî d 281	Gaura, v. in Pratapgarh d., 315, 316
Fathpûr Sîkrî, tahsîl in Âgrâ d. 70-74	Gaurahrî, v. in Hamîrpûr d 171
Fatihan Khera, ruined site near Sandi in	Gaura Khera, v. in Hardôi d 280
Hardôf d 282	Gavidhumat, identified with Kudarkot
Fåzilnagar, v. in Görakhpår d 240	in Itawah d., 91, 331
Firûzâbûd, another name of Dehlî 16	Gehmur, v. in Ghâzîpûr d.
Ditto, tahsîl in Âgrâ d.	Wrongly spelled Gahmur in maps, 227
Ruined city of Chandwar near-, 74	Gerahô, small v. in Jhânsî d 116
Ditto, v. in Kherî d 284	Ghâtampûr, tahsîl in Kânhpûr d 168
Fîrûzpûr, v. near Jhûsî in Allahâbâd d 138	Ghâûsgarh, celebrated fortress near Jalâlâbûd
G.	in Muzaffarnagar d 13
	Ghâûspûr, v. in Ghâzîpûr d.
Gådhipura, old name of Kanauj 308	Wrongly identified with the
Ditto, ancient name of Ghâzîpûr 231	Aviddhakarna of Hiuen
Gadi-uda, v. în Kumaon d 49	Tsiang 231
Gagahâ, small v. in Gôrakhpûr d 241	Ghazanfarâbâd, old name of Kharîd in
Gajapura, ancient name of Ghazîpûr 231	Baliya d 193
Gåjîpûr, name of Ghâzîpûr, as called by	Ghâzîâbâd, or Ghâzî-ad-dîn Nagar, tahsîl in
Hindûs 231	Mîrath d 9
Gajpûr, small v. in Gôrakhpûr d 241	Ghâzîpûr, tahsîl în Faṭhpûr d 160
Ganaur, v. in Sultanpar d 328	Ditto, tahsil and head-quarters of d.
Gandwa, v. in Hardôl d 279	Anciently named Gadhipura,
Ganêsvar, v. in Mathura d 100	or Gajapura 231
Ganganau, v. in Kumaon d 48	Called Gâjîpûr by the Hindûs 231
Gangapûr, v. in Bâliyâ d 193	Identified with the capital of
Gangî Tikar, v. in Görakhpûr d 241	Hiuen Tsiang's Chen-chu,
Gângôh, v. in Sahâranpûr d 15	or Garjapatipura, 231, 232
Gangolî Hât, v. in Kumâon d 49	Ghiswa, tahsil in Jaunpur d 185
Ganjahra, v. in Azamgarh d 190	Ghosî, t. in Âzamgarh d 188
Ganj-Aphûî, v. in Fathpûr d 158	Ghugtîr, v. in Bâra Baukî d 264
Garha, ruined fort at Dhopap in Sultan-	Ghugua, v. near Barua Sagar in Jhansi d., 115
pûr d 327	Ginjâ Hill, isolated mountain in Allahâbâd d. Painted inscription of Indo-Scy-
Garhâ-kâ-kôt, old deserted site near Bhatri	
in Azamgarh d 187 Garh Amethî, tahsîl in Sultânpûr d 326	thic period on— 137 Girwân, tahsîl in Bândâ d 148
Carried and Control of the Control o	Gobardhan, famous place of Hindû pilgrim-
Children 11	age in Mathurâ d., 100, 101
CHAIL MALINIAN IN THE PROPERTY OF THE PROPERTY	Goduria, v. in Kheri d 284
CHILD TO THE PROPERTY OF THE PA	Gohâna Kherâ, large ruined mound in Alî-
Garhî Jâr, v. in Fathpûr d 160 Garh Kherâ, ruined fort near Dêoriya in	garh d.
Pilibhit d 39	Buddhist sculptures exca-
Garh Muktêsvar, v. in Mîrath d 9	vated at— 3
Garhwâ, ruined jangal fort in Allahâhâd d.	Gokul, t. in Mathura d 101
Anciently named Bhattagrama, 135	Gola-Gokarnnath, pilgrimage place in
Description of antiquities at—135—137	Kherî d. 284, 285

Goļā-Rāîpār, v. in Shā		Page		
	hiahannar d		ANAMATA NA TRA	Pages.
	represents the Hi-	La	Hâjîpûr, v. in Faizâbâd d	301
of Fa		100	Haldî, v. in Bâliyâ d	192
Gondâ, v. in Bândâ d.	7.515		The state of the s	261
Do., tahsil and head	anarton of J	148, 149	t -) and mente quarters of d	171
Identified with	the ancient Gaud	- 20	Hamsakshetra, the modern Rudrapar	
Do., v. in Pratapgar	rue ancient Gund		in Gorakhpur d	249
Gopálpůr, v. in Jaláun		319	The state of the s	8
Ditto, v. in Gôrakh		114	Transition of the state of the	
Gopâmâû, t. in Hardôi	E CONTAC III	242	Asamamanganj, v. in Danya d	192
		278, 279	resport tomair in priritin d.	111.7
Gopésvar, v. in Garhwa		44	Anciently named Haranura	10
Gopsahså, v. near Koså			Called Havapura by Ghias-ad-din	10
Gôrakhpûr, tahsîl and h	ead-quarters of d.	242	Tarblan	10
Gorashahgarh, v. in Mu		36	Haradohi ancient name of Hardas	100
Gosaînganj, v. in Lakhr		264, 265	Haradvaratintha	279
Gotávelî, v. in Murâdab		38	350.73	
Gothânî, v. in Mîrzâpûr		252	Chia a	
Govinda-Pachauli, v. in	Kumåon d.	48	Haragrama spirit	290
Govisana, of Hinen	Tsiang.		Haragrâma, ancient name of Hargâm	
Identifie	d with ruins ner	ar	in Sîtâpûr d	288
	lî in Kumâon d	49	Harapura, ancient name of Hapûr in	
Identified			Mîrath d	10
		in	Ditto, old v. near Makanpûr in	
Tarâî d		50-52	Kanhpar d	169
Gudamågalgåon, v. in K	maken d		Harbanspûr, v. near Âzamgarh	187
Gulariyâ, v. near Râmna		49	Harehandpûr, v. in Itâwah d	91
Gulrampar, v. in Banda	d .		Hardîyâ, old v. in Bastî d.	221
Gûm, v. in Kherî d.			Hardôî, tahsîl and head-quarters of d.	
	222 24	1277	Anciently named Haradoh?	279
Gûmchâînî, v. in ditto		. 286	Ditto, v. in Rat Bareli d.	320
Gumthâl Kherû, ancient		-	Hardon Math w in Lalam A	748877
båd d.	***	. 36	Hardvår, famous pilgrimage place in Sahå-	114
Gunîr, v. in Fathpûr d.	***	. 160	ranpûr d.	
Gupta Godâvarî,	small stream near	r	Extensive ruins of ancient city of	
	Chitrakata in	1	MAVOTHER	
	Bândâ d.	. 148	Hargâm, t. in Sîtâpûr d.	16
Jurgãon, ancient v. near 8	Shîûpurî in Barelî d	. 30	Anciently 11 2 T	
Jurônpûr, v. near Sârnât	h in Banaras d	Variable Co.	Anciently called Haragrama,	885
Jursaraî, v. in Jhansî d.	***	220	traditionally the capital of King	
dursârî, v. in Murûdâbâd	a	00	v ikramādītya	288
iwala Prasiddh, ancien	t ruined city in	3	Trainin, v. iii Unao d.	272
	olt 3	11 20/1	area mon, v. in Hardor d.	283
		26	Harnathpür, v. in Banaras d	216
J	H.		Harpur, v. in Faizābād d.	302
Iaidarâbâd, v. in Kherî d		000	Harsen, v. in Sultanpar d	
Iaidargarh, tahsîl in Bâra		100000	Hasanpur, v. in Muzaffarnagar d.	27
Inihaiti Mandin ald	a Danki d		Ditto, tabail in Maradahaa a	13
Iaihaiti Mandir, old tem	pie near Khôh in	The second secon	masanpur-mandhila v in Sultanna 2	36
TIA 24			A THE PART OF THE	CAVA
Bândâ Hâjîpûr, v. in Jalâun d.	d	200	resampur-Dhiphi, v. m Faigabal a	29 01

Pages.	Pages.
Hastigarta, identified with Hathikundat	Hayapura, old name of Haparin Mi-
Bhôilâ Dih in Bastî d., 219, 222	rath d 10
Hastigrama, the modern Hathgaon in	Hêmpûr, v. near Ghâzîpûr 232
Fathpûr d 161	TTAL A 1 250 A A 3 050
Hastinapûr, old v. in Mîrațh d.	Hi-lo, of Fa Hian.
Identified with Hastina-	Identified with Gola-Raipur in
pura of the Mahâbhârata, 10	CHARLES AND A CHARLES
Hastinapura, ancient city of the Pan-	TT: 1 . TO .A . 1 . 1
davas 1, 3, 10, 303	TT:
Hastisandî, v. in Bastî d 223	Hingotar, v. in Ghazipar d 230 Hisâmpâr, v. in Bahrâîch d 293
Haswâ, or Hanswâ, small decayed t. in Fath-	Husainâbâd, v. in Bâliyâ d.
pår d.	Traditionally named Kalasadih, 192
Originally named Champavati, 161	Ditto, Musalman name of Ran Bareli, 324
Hatâo-Sarîfpâr, v. in Mâinpurî d 93	Husainganj, v. in Fathpûr d 161
Hatgauhâ Dîh, extensive mound at the	Husain Jôt, v. near Sâhet-Mâhet in Gondâ d., 311
v. of Shîûpûr in Allahâ-	Husain Jot, V. near Sanet-Manet in Gonda d., 521
båd d 143	I.
Hathâ, v. in Bastî d 224	Ibrāhîmpūr, v. in Murādābād d 36
Hathâna, v. in Mathurâ d 101	Ibrâhîmpûr-Kandâî, v. in Faizâbâd d 301
Håthgåon, t. in Fathpûr d.	Idhona v. in Faizabad d 301
Anciently named Hastigra-	Ikaunå, v. in Bahrålch d.
ma 161	Locally called Akonâ 294
Hâthilî, v. in Gondâ d 292, 304, 305	Identified with the Aptanetra-
Håthisari, or Hastisandi, v. in Basti d 223	vana of Hiuen Tsiang 294
Hâthiyâ Dâh, old tank near Dabhâon in	Ikhtiyârpûr, v. near Râî Barelî d 325
Azamgarh d 188	Ilâhâbâs, or Ilâhâbâd-Dewâl, old v. in Pili-
Hâthiyâ Kuṇḍ, v. in Bahrâlch d 293	bhit d 39, 41
Hâthkânt, v. in Âgrâ d 74	Ditto, name given to Allahabad by Akbar, 127
Hâthras Khâs, tahsîl in Alîgarh d 1	Indargarh, ruined castle in Farrukhåbåd d., 78
Hatovâr, v. in Bândâ d 155	Indôr, large ruined mound in Bulandshahr d.
Hattia Haran, or Hatyaharana, sacred	Anciently named Indrapura 6
tank near Kalyanmal in	Ruined temple of Sûrya at 6, 331
Hardôi d 280	Indpûr-Bhîrâ, v. in Âzamgarh d 190
Also called Panchachhat-	Ingothâ, v. in Hamîrpûr d 171
tra 280	Inhauna, v. in Raî Barelî d 323
Hatyaharana, sacred pond at Begethûâ	Irādatganj, original name of Kopā in Āzam-
in Sultânpûr d 326	garh d 189
Hawalbagh, hamlet in Kumaon d 50	Îrichh, t. in Jhânsî d 117, 118
Hayamukha, or Ayomukha, king-	Îsanagar, v. in Kherî d 284
dom mentioned by Hiuen	Isauli, v. in Sultanpar d 328
Tsiang, capital of-,	Islâmnagar, old name of Mahârâjnagar in
wrongly identified with	Sîtâpûr d 289
Daundin-Khern in Unno d. 268	Islâmpûr, v. in Barelî d 26
Ditto, Identified with Singraur in	Ismâîlpûr, v. near Karrâ in Allahâbâd d 139
Allahûbûd d 269	Ismâîlpûr-Aphûî, v. in Fathpûr d 158
Capital of-, identified	Ismaîlpûr Nur-ad-dîn, v. near Kanauj in
with Tusårån-Bihår in	Farrukhâbâd d 81
Pratâpgarh d., 269, 315	Îțâh, tahsîl and head-quarters of d 86

Hard, v. in Hamirpūr d. 171, 178 Hawah, tahsil and head-quarters of d. 90, 91 Jahiahah, tahsil and head-quarters of d. 90, 91 Jahiahah, tahsil in Agrā d. 243 Jahiahaha, tahsil in Agrā d. 74 Jam ad ag ni pur a, old name of Jaunpūr 179 Jam ad ag ni pur a, old name of Jaunpūr 179 Jam ad ag ni pur a, old name of Jaunpūr 179 Jam ad ag ni pur a, old name of Jaunpūr 179 Jam ad ag ni pur a, old name of Jaunpūr 179 Jam ad ag ni pur a, old name of Jaunpūr 179 Jam ad ag ni pur a, old name of Jaunpūr 179 Jam ad ag ni pur a, old name of Jaunpūr 179 Jam ad ag ni pur a, old name of Jaunpūr 179 Jam ad ag ni pur a, old name of Jaunpūr 179 Jarayyān, v. in Mariahahd d. 290 Jarayyān, v. in Mariahahd d. 293 Jargāon, v. in Muriahahd d. 293 Jargāon, v. in Mariahahd d. 293 Jargāon, v. in Mariahahd d. 294 Jarayah, v. in Bahriāch d. 293 Jaryahahahdad, v. in Bijnōr d. 30 Jargāon, v. in Mariahahd d. 101 Jaryahahahdad, v. in Bijnōr d. 30 Jargāon, v. in Mariahahd d. 101 Jaryahahahdad, v. in Bijnōr d. 30 Jargāon, v. in Mariahahd d. 101 Jaryahahahdad, v. in Bijnōr d. 30 Jargāon, v. in Mariahahd d. 101 Jaryahahahdad, v. in Bahriāch d. 20 Jaryahahahdad, v. in Bahriāch d. 20 Jaryahahahdad, v. in Mariahahani ni na Azamgarh d. 100 Jaryahahahahdad d. 30 Jargāon, v. in Mariahahdad 30 Jargāon, v. in Mariahahdad d. 149 Jaryahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahahdad d. 140 Jaryahahahdad d. 140 Jaryahahahdad d. 140	Pages.	Pages.
Iţhya, hamlet in Görakhpūr d. 243 Jalhhpūr, v. in Banāras d. 212 Jalhkpūr, tahstl in Āgrā d. 243 Jallokhūr, t. in Hamīrpūr d. 172 Jamapūr, tahstl in Āgrā d. 74 Jamapūr, v. in Rāl Barell d. 162 Jagatpūr, v. in Rāl Barell d. 162 Jamapūr, name given to Jaunpūr by Hindūs 179 Jamapūr, name given to Jaunpūr by Hindūs 217 Jamapūr by the Hindūs 290 Jarwal, v. in Rārābād d. 30 Jarwal, v. in Barītāch d. 290 Jasanal, od name of Bāra Banāt 263 Jasanal, od name of Bāra Banāt 263 Jasanal, od name of Bāra Banāt 214 Jasanal, od name of Bāra Banāt 214 Jaurtāt, v. in Rārāt, v. in Rārāt, v. in Rārāt, v. in Rārāt, v. in Rā	Itârâ, v. în Hamîrpûr d 171, 178	Jalékar, tahali in Îtâh d
Thimadpūr, tahsili ni Agrād		
Jamadagnipura, old name of Jaunpūr, 179 Jamaghūr, tahsli in Āgrād		
J. Jaraganj, decayed t. in Fathpûr d. 162 Jagatpûr, v. in Râl Barell d. 162 Huen Tsiang 323 Jagdispûr, v. in Kherl d. 284 Ditto, v. in Sultanpûr d 284 Ditto, v. in Sultanpûr d 328 Jagnår, t. in Ågrå d 340 Ditto, t. in Pilibhit d 39 Ditto, to land nor Man Nathbanjan in Ázamgarh d 190 Ditto, suburb of Râl Barell 39 Jaharpûr, v. near Chhidpâr in Lalitpûr d 193 Jaharpûr, v. near Chhidpâr in Lalitpûr d 193 Jath, t. in Râl Barell d 39 Jath, v. in Mathurâ d 191 Jahmâl, v. in Mathurâ d 191 Jathpûr, t. in Hamirpûr d 117, 171, 172 Ditto, v. near Bhalla Dih in Bastl d. 218 Jajanat, v. in Kaphpûr d 36 Jajinat, v. in Kaphpûr d 36 Jajinat, v. in Kaphpûr d 36 Jajinat, v. in Kaphpûr d 36 Jajinat, v. in Kaphpûr d 36 Jajinat, v. in Kaphpûr d 36 Jalallaba, v. in Kaphpûr d 36 Jahallaba, v. in Muzaffarnagar d 36 Jahallaba, v. in Muzaffarnagar d 36 Jahallaba, v. in Kaphpûr d 37 Jahallaba, v. in Kaphpûr d 38 Jahallaba, v. in Kaphpûr d 39 Jahallaba, v. in Kaphpûr d 39 Jahallaba, v. in Kaphpûr d 39 Jahallaba, v. in Kaphpûr d 39 Jahallaba, v. in Kaphpûr d 39 Jahallaba, v. in Kaphpûr d 39 Jahallaba, v. in Kaphpûr d 39 Jahallaba, v. in Kaphpûr d 39 Jahallaba, v. in Kaphpûr d 39 Jahallaba, v. in Kaphpûr d 39 Jahallaba, v. in Kaphpûr d 39 Jahallaba, v. in Kaphpûr d 39 Jahallaba, v.		
Hindûs 179		
Jarayan, v. in Faizābād d	J.	
Jagatpår, v. in Råt Barell d. Identified with 'O-yu-t'o of Hiuen Tsiang	Jåfarganj, decayed t. in Fathpûr d. 162	
Jagadispūr, v. in Kharld d	The contract of the contract o	To A 2 35 130143 1 00
Hiuen Tsiang		The state of the s
Jagdîspûr, v. in Kherî d		Towns 1 2- 10-1-14-1-3
Ditto, v. in Sulţānpūr d		
Jagnér, t. in Ágrá d		
Jahânâbâd, v. in Bîjnôr d		
Ditto, t. in Pilibhit d	A STATE OF THE PARTY OF THE PAR	
Ditto, old name of Maû Nâtbhanjan in Âzamgarh d 190 Ditto, suburb of Râi Barell 325 Jahâzpār, v. near Chândpār in Lalitpūr d., 119 Jahmāi, v. in Māinpuri d 93 Jāis, t. in Rāi Bareli d 93 Jāis, t. in Rāi Bareli d 323, 324 Jāt, v. in Mathurā d 101 Jaithāl, old v. in Muradābād d 36 Jaitpūr, t. in Hamīrpūr d 117, 171, 172 Ditto, v. near Bhūllā Dīh in Bastī d 218 Jājāo, v. in Āgrā d 75 Jājmāā, v. in Kāahpūr d 175 Jājmāā, v. in Kāahpūr d 175 Jakahī Dīh, deserted site in Gōrakhpūr d 242 Jalālābād, v. in Muzaffarnagar d 13 Ditto, v. in Ghāzpūr d 213 Jaito, v. in Ghāzpūr d 213 Jailpūr, ruined mound near Sarsāwā in Mirath d 12 Jalālpūr, ruined mound near Sarsāwā in Mīrath d 12 Jalālpūr, ruined mound near Sarsāwā in Mīrath d 12 Jalālpūr-Biālsi or Jalālpūr-Sāī, small v. in Jaunpūr d 173 Jalālpūr-Dehf, v. in Rāt Bareli d 232 Jāla n d h a r a , head-quarters of d 174 Jalālpūr-Dehf, v. in Rāt Bareli d 233 Jāla n d ha r a , head-quarters of d 175 Jalālpūr, ruined mound near Sarsāwā in Mīrath d 175 Jalālpūr-Dehf, v. in Rāt Bareli d 232 Jāla n d ha r a , head-quarters of d. in Panjāb 8 Jalāun, tahsīl and formerly head-quarters of d 112 Jwālapūr, v. near Rurki in Sahāranpūr d 233 Jālan, tahsīl and formerly head-quarters of d 112 Jwālapūr, v. near Rurki in Sahāranpūr d 233 Jalāln, t. in Aligarh d 175 Jalālpūr-Dehf, v. in Rāt Bareli d 232 Jalāln, tahsīl and formerly head-quarters of d 112		
Ázamgarh d. 190 Capital of the Sharqî dynasty in the 15th century A.D. 178 Jahâzpâr, v. near Chândpâr in Lalitpûr d. 119 Anciently named Jamadagnipura. 179 Jâts, t. in Rât Barelî d. 93 Called Jamanpûr by the Hindûs. 179 Jait, v. in Mathurâ d. 101 Description of Musalmân antiquites at 178—185 Jaithâl, old v. in Muradâbâd d. 36 Jaitpûr, t. in Hamîrpûr d. 101 Jaitpûr, t. in Hamîrpûr d. 175 Jayasai h hapura, old name of Sitâpûr in Bandâ d. 101 Jajmâd, v. in Kâuhpûr d. 75 Jajimâd, v. in Kâuhpûr d. 124 Jakahî Dîh, deserted site in Görakhpûr d. 242 Jalalâbâd, v. in Muzaffarnagar d. 13 Jhabarbêrâ, v. in Sahâranpûr d. 169 Jhabarbêrâ, v. in Sahâranpûr d. 124 Jalalabâbâd, v. in Muzaffarnagar d. 13 Jhâna, v. in Muzaffarnagar d. 169 Jhabarbêrâ, v. in Sahâranpûr d. 123 Jhâna, t. in Allahâbâd d. <td></td> <td></td>		
Ditto, suburb of Rái Barell		
Jahâzpâr, v. near Chândpâr in Lalitpâr d., 119 Anciently named Jamadagni- pura, or Yavanapura 179 Jâîs, t. in Râî Barelî d. Acciently named Ujâlikanaga- ram 323, 324 Jâît, v. in Mathurâ d. 101 Jaithâl, old v. in Murâdâbâd d. 36 Jaitpâr, t. in Hamîrpâr d. 117, 171, 172 Ditto, v. near Bhâllâ Dîh in Bastî d. 218 Jajêo, v. in Âgrâ d. 75 Jajimât, v. in Kanhpâr d. 169 Jakahî Dîh, deserted site in Gôrakhpâr d. 169 Jakahî Dîh, deserted site in Gôrakhpâr d. 13 Ditto, taheîl in Shâhjahânpûr d. 41, 42 13 Ditto, taheîl in Shâhjahânpûr d. 41, 42 13 Ditto, to, taheîl in Shâhjahânpûr d. 232 Jalâlpûr, ruined mound near Sarsâwâ in Mîrrath d. 12 Ditto, tin Hamîrpâr d. 13 Jalâlpûr, ruined mound near Sarsâwâ in Mîrrath d. 12 Ditto, tin Hamîrpâr d. 12 Ditto, tin Hamîrpâr d.		the 15th century A.D. 178
Jahmāi, v. in Māinpuri d 93 pura, or Yavanapura 179		Anciently named Jamadagni-
Called Jamanpûr by the Hindûs 179		pura, or Yavanapura 179
Description of Musalmân antiquites at————————————————————————————————————		
ram 323, 324 ties at 178—185 Jaîth, v. in Mathurâ d. 101 Jaurâsî, v. near Rurkî in Sahâranpûr d. 18 Jaithâl, old v. in Murâdâbâd d. 36 Jawârâ, t. in Mathurâ d. 101 Jaithâl, old v. in Hamîrpûr d. 175, 171, 172 Jayasin hapura, old name of Sîtâpûr in Bândâ d. 148 Jajmâd, v. in Kâuhpûr d. 75 Jê tavana, name of large Buddhist mo-		
Jâtt, v. in Mathurâ d.		
Jaithâl, old v. in Murâdâbâd d 36 Jaitpûr, t. in Hamîrpûr d 117, 171, 172 Ditto, v. near Bhûlîlâ Dîh in Bastî d 218 Jajão, v. in Âgrâ d 75 Jajîmâû, v. in Kânhpûr d 75 Mentioned by Alberûnî under the name of Jajjmâû 169 Jakahî Dîh, deserted site in Gôrakhpûr d 169 Jakahî Dîh, deserted site in Gôrakhpûr d 13 Ditto, tahsîl in Shâhjahânpûr d. 41, 42 Ditto, old name of Arâlî in Allahâbâd d., 131 Ditto, v. in Ghâzîpûr d 232 Jalâlî, t. in Alîgarh d 12 Jalâlpûr, ruined mound near Sarsâwâ in Mirath d 178 Jalâlpûr-Biâlsî or Jalâlpûr-Sâî, small v. in Jaunpûr d 178 Jalâlpûr-Dehî, v. in Râî Barelî d 178 Jalâlpûr-Dehî, v. in Râî Barelî d 178 Jalâlpûr-Dehî, v. in Râî Barelî d 178 Jalâlpûr-Dehî, v. in Râî Barelî d 178 Jalâlpûr-Dehî, v. in Râî Barelî d 178 Jalâlpûr-Dehî, v. in Râî Barelî d 232 Jalâun, tahsîl and formerly head-quarters of d. in Panjûb 178 Jalâun, tahsîl and formerly head-quarters of d 112 Jwâlapûr, v. near Rurkî in Sahâranpûr d 18	Light in Editor 11/2	
Jaitpûr, t. in Hamîrpûr d 117, 171, 172 Ditto, v. near Bhûllâ Dîh in Bastî d 218 Jajão, v. in Âgrâ d 75 Jajmãû, v. in Kâṇhpûr d 168 Anciently named Siddhapuri, 168 Mentioned by Alberûnî under the name of Jajjmãû 169 Jakahî Dîh, deserted site in Gôrakhpûr d 13 Jalâlbâd, v. in Muzaffarnagar d 13 Ditto, tahsîl in Shâhjahānpûr d. 41, 42 Ditto, v. in Ghâzîpûr d 232 Jalâlî, t. in Alīgarh d 232 Jalâlî, t. in Alīgarh d 232 Jalâlpûr, ruined mound near Sarsûwâ in Mîrath d 172 Jalâlpûr, ruined mound near Sarsûwâ in Mîrath d 172 Jalâlpûr-Biâlsî or Jalâlpûr-Sâî, small v. in Jaunpûr d 172 Jalâlpûr-Dehî, v. in Râî Barelî d. 323 Jâlan dhara, head-quarters of d. in Panjâb 233 Jalâun, tahsîl and formerly head-quarters of d 112 Jalâun, tahsîl and formerly head-quarters of d 112 Jalâun, tahsîl and formerly head-quarters of d. Jwâlapûr, v. near Rurkî in Sahâranpûr d 18		
Ditto, v. near Bhâilâ Dîh in Bastî d 218 Jajão, v. in Ágrâ d		
Jajān, v. in Âgrâ d		
Anciently named Siddhapuri, 168 Anciently named Siddhapuri, 168 Mentioned by Alberûnî under the name of Jajjmâû 169 Jakahî Dîh, deserted site in Gôrakhpûrd 242 Jalâlâbâd, v. in Muzaffarnagar d 13 Ditto, tahsîl in Shâhjahânpûr d. 41, 42 Ditto, old name of Arûlî in Allahâbâd d., 131 Ditto, v. in Ghâzîpûr d 232 Jalâlî, t. in Alîgarh d 232 Jalâlpûr, ruined mound near Sarsâwâ in Mîrath d 12 Jalâlpûr, ruined mound near Sarsâwâ in Mîrath d 172 Jalâlpûr-Biâlsî or Jalâlpûr-Sâî, small v. in Jaunpûr d 178 Jalâlpûr-Dehî, v. in Râî Barelî d 323 Jalâun, tahsîl and formerly head-quarters of d. in Panjâb 180 Jalâun, tahsîl and formerly head-quarters of d 112 Jwâlapûr, v. near Rurkî in Sahâranpûr d 181 Jwâlapûr, v. near Rurkî in Sahâranpûr d 181 Jwâlapûr, v. near Rurkî in Sahâranpûr d 18		
Anciently named Siddhapuri, 168 Mentioned by Alberûnî under the name of Jajjmâû 169 Jakahî Dîh, deserted site in Görakhpûrd 242 Jalâlâbâd, v. in Muzaffarnagar d 13 Ditto, tahsîl in Shâhjahânpûr d. 41, 42 Ditto, v. in Ghâzîpûr d 232 Jalâlî, t. in Alfgarh d 232 Jalâlpûr, ruined mound near Sarsâwâ in Mîrath d 172 Jalâlpûr, ruined mound near Sarsâwâ in Mîrath d 172 Jalâlpûr-Biâlsî or Jalâlpûr-Sâî, small v. in Jaunpûr d 178 Jalâlpûr-Dehî, v. in Râî Barelî d 271 Jalâlpûr-Dehî, v. in Râî Barelî d 232 Jâlan, tahsîl and formerly head-quarters of d. in Panjâb 8 Jalâun, tahsîl and formerly head-quarters of d 112 Jwâlapûr, v. near Rurkî in Sahâranpûr d 18		** *
Mentioned by Alberûnî under the name of Jajjmâû 169 Jakahî Dîh, deserted site in Gêrakhpûrd. 242 Jalâlâbâd, v. in Muzaffarnagar d. 13 Ditto, tahsîl in Shâhjahânpûr d. 41, 42 Ditto, old name of Arâfl în Allahâbâd d., 131 13 Ditto, v. in Ghâzîpûr d. 232 Jalâlî, t. in Aligarh d. 232 Jalâlpûr, ruined mound near Sarsâwâ in Mîrath d. 12 Ditto, t. in Hamîrpûr d. 172 Jalâlpûr-Biâlsî or Jalâlpûr-Sâî, small v. in Jaunpûr d. 178 Jalâlpûr-Dehî, v. in Râî Barelî d. 323 Jâl a n d ha ra, head-quarters of d. in Panjâb 8 Jalâun, tahsîl and formerly head-quarters of d. 112 Jalâun, tahsîl and formerly head-quarters of d. 112 Jalâur, v. in Sahâranpûr d. 128 Jalâur, tahsîl and formerly head-quarters of d. in Panjâb 233 Jalâur, tahsîl and formerly head-quarters of d. in Panjâb 8 Jalâur, tahsîl and formerly head-quarters of d. in Panjâb 8 Jalâur, tahsîl and formerly head-quarters of d. in Panjâb 8 Jalâur, tahsîl and formerly head-quarters of d. in Panjâb 8 Jalâur, tahsîl		
name of Jajjmāû 169 Jakahî Dîh, deserted site in Görakhpûrd 242 Jalâlâbâd, v. in Muzaffarnagar d 13 Ditto, tahsîl in Shâhjahânpûr d. 41, 42 Ditto, old name of Araîl in Allahâbâd d., 131 Ditto, v. in Ghâzîpûr d 232 Jalâlî, t. in Alîgarh d 12 Jalâlpûr, ruined mound near Sarsâwâ in Mîrath d 12 Ditto, t. in Hamîrpûr d 172 Jalâlpûr-Biâlsî or Jalâlpûr-Sâî, small v. in Jaunpûr d 178 Jalâlpûr-Dehî, v. in Râî Barelî d 323 Jâla n d h a r a, head-quarters of d. in Panjâb 8 Jalâun, tahsîl and formerly head-quarters of d 112 Jwâlapûr, v. in Sahâranpûr d 16 Jhalanfara, v. in Muzaffarnagar d 13 Jhanjhâna, v. in Muzaffarnagar d 13 Jh		
Jakahî Dîh, deserted site in Görakhpûr d 242 Jalâlâbâd, v. in Muzaffarnagar d 13 Ditto, tahsîl in Shâhjahânpûr d. 41, 42 Ditto, old name of Araîl in Allahâbâd d., 131 Ditto, v. in Ghâzîpûr d 232 Jalâlî, t. in Alîgarh d 1 Jalâlpûr, ruined mound near Sarsâwâ in Mîrath d 172 Ditto, t. in Hamîrpûr d 172 Jalâlpûr-Biâlsî or Jalâlpûr-Sâî, small v. in Jaunpûr d 178 Jalâlpûr-Dehî, v. in Râî Barelî d 323 Jâla n d h a r a, head-quarters of d. in Panjûb 8 Jalâun, tahsîl and formerly head-quarters of d 112 Jalâpûr, v. near Rurkî in Sahâranpûr d 18		TO TAKE THE PROPERTY OF THE PAR
Jalâlâbâd, v. in Muzaffarnagar d 13 Ditto, tahsîl in Shâhjahânpûr d. 41, 42 Ditto, old name of Arâlî in Allahâbâd d., 131 Ditto, v. in Ghâzîpûr d 232 Jalâlî, t. in Alîgarh d 1 Jalâlpûr, ruined mound near Sarsâwâ in Mîrath d 12 Ditto, t. in Hamîrpûr d 12 Ditto, t. in Hamîrpûr d 172 Jalâlpûr-Biâlsî or Jalâlpûr-Sâî, small v. in Jaunpûr d 178 Jalâlpûr-Dehî, v. in Râî Barelî d 323 Jâlan dhara, head-quarters of d. in Panjâb 8 Jalâun, tahsîl and formerly head-quarters of d 112 Jwâlapûr, v. in ear Rurkî in Sahâranpûr d 18		The last of the state of the st
Ditto, tahsîl in Shâhjahânpûr d. 41, 42 Ditto, old name of Arâlî in Allahâbâd d., 131 Ditto, v. in Ghâzîpûr d 232 Jalâlî, t. in Alîgarh d 1 Jalâlpûr, ruined mound near Sarsâwâ in Mîrath d 12 Ditto, t. in Hamîrpûr d 12 Ditto, t. in Hamîrpûr d 172 Jalâlpûr-Biâlsî or Jalâlpûr-Sâî, small v. in Jaunpûr d 178 Jalâlpûr-Dehî, v. in Râî Barelî d. 323 Jâlan dhara, head-quarters of d. in Panjâb 8 Jalâun, tahsîl and formerly head-quarters of d 112 Jwâlapûr, v. near Rurkî in Sahâranpûr d 18		The man are on
Ditto, old name of Arail in Allahâbâd d., 131 Ditto, v. in Ghâzîpûr d 232 Jalâlî, t. in Alîgarh d 1 Jalâlî, t. in Alîgarh d 1 Jalâlpûr, ruined mound near Sarsâwâ in Mîrath d 12 Ditto, t. in Hamîrpûr d 172 Jalâlpûr-Biâlsî or Jalâlpûr-Sâî, small v. in Jaunpûr d 178 Jalâlpûr-Dehî, v. in Raî Barelî d 323 Jâlan dhara, head-quarters of d. in Panjâb 8 Jalâun, tahsîl and formerly head-quarters of d 112 Jalâlpûr, v. in Garhwâl d 233 Jwâlapûr, v. near Rurkî in Sahâranpûr d 18		The art and are are
Ditto, v. in Ghâzîpûr d 232 Jalâlî, t. in Alîgarh d 1 Jalâlî, t. in Alîgarh d 1 Jalâlpûr, ruined mound near Sarsâwâ in Mîrath d 12 Ditto, t. in Hamîrpûr d 172 Jalâlpûr-Biâlsî or Jalâlpûr-Sâî, small v. in Jaunpûr d 178 Jalâlpûr-Dehî, v. in Râî Barelî d 323 Jâlân d ha ra, head-quarters of d. in Panjâb 8 Jalâun, tahsîl and formerly head-quarters of d 112 Jwâlapûr, v. near Rurkî in Sahâranpûr d 18		Jharmativa, ruined site in Garakhpard
Jalâlî, t. in Alîgarh d		Jhawwaihar, old mound near Aindhua in
Jalâlpûr, ruined mound near Sarsâwâ in Mîrath d		77. J. A1. A.1. 2
rath d		
Jalalpûr-Bialsî or Jalalpûr-Saî, small v. in Jaunpûr d 172 Jalalpûr-Bialsî or Jalalpûr-Saî, small v. in Jaunpûr d 178 Jalalpûr-Dehî, v. in Raî Barelî d 323 Jalalpûr-Dehî, v. in Raî Barelî d 323 Jalalpûr-Dehî, v. in Raî Barelî d 323 Jalalpûr-Dehî, v. in Raî Barelî d 323 Jalalpûr-Dehî, v. in Raî Barelî d 323 Joshîmath, or Jyotirdhâm, pilgrimage place in Garhwâl d 45, 46 Jwâlapûr, v. near Rurkî in Sahâranpûr d 18	The state of the s	
Jalâlpûr-Biâlsî or Jalâlpûr-Sâî, small v. in Jaunpûr d 178 Jalâlpûr-Dehî, v. in Râî Barelî d 323 Jâlandhara, head-quarters of d. in Pan- jâb 8 Jalâun, tahsîl and formerly head-quarters of d 112 Jogîkôt, v. in Unâo d 271 Joharganj, v. in Ghâzîpûr d. Formerly known as Banjhulâ- wan 233 Joshîmath, or Jyotirdhâm, pilgrimage place in Garhwâl d 45, 46 Jwâlapûr, v. near Rurkî in Sahâranpûr d 18	Total	Tilliment or in This all all a
Jaunpûr d 178 Jalâlpûr-Dehî, v. in Râî Barelî d 323 Jâlandhara, head-quarters of d. in Pan- jâb 8 Jalâun, tahsîl and formerly head-quarters of d 112 Joharganj, v. in Ghâzîpûr d. Formerly known as Banjhulâ- wan 233 Joshîmath, or Jyotirdhâm, pilgrimage place in Garhwâl d 45, 46 Jwâlapûr, v. near Rurkî in Sahâranpûr d 18		Toodbat - to TT-1 2
Jalâlpûr-Dehî, v. in Râî Barelî d 323 Jâlandhara, head-quarters of d. in Pan- jâb 8 Jalâun, tahsîl and formerly head-quarters of d 112 Formerly known as Banjhulâ- wan 233 Joshîmath, or Jyotirdhâm, pilgrimage place in Garhwâl d 45, 46 Jwâlapûr, v. near Rurkî in Sahâranpûr d 18	The state of the s	
Jâlandhara, head-quarters of d. in Pan- jâb 8 Jalâun, tahsîl and formerly head-quarters of d 112 Jwâlapûr, v. near Rurkî in Sahâranpûr d 18	T. TAT. A. TO TA. A. MOLLAND.	The suppose of the su
Jalâun, tahsîl and formerly head-quarters of d 112 Jwâlapûr, v. near Rurkî in Sahâranpûr d 18		
Jalâun, tahsîl and formerly head-quarters in Garhwâl d 45, 46 of d 112 Jwâlapûr, v. near Rurkî in Sahâranpûr d 18	441	*** 200
of d 112 Jwâlapûr, v. near Rurkî în Sahâranpûr d 18		in Claut 41 2
(1) Abbreviations: t -town 18		
		18

Pa	ges.	and the second second	Pages.
к.	-	Kalyanmal, v. in Hardôf d.	
Kâbar, ancient t. in Barelf d	26	Anciently named Rathauli	. 280
Kabraiâ, t. in Hamîrpûr d 172,		Kalyûnpûr, v in Banûras d	010
Kachh Darya Bard, v. near Karra in Alla-	110	Kamadagiri, another name of Chitra	
	139	kûta	140
Kachhpûrwâ, v. near Âgrâ	55	Kamalpur, v. in Hardôt d	000
	178	Kâmp, v. near Alîganj în Kherî d.	004
	301	Kâmpil, v. in Farrukhâbâd d.	
Kådirganj, v. in Îtâh d	87	Anciently called Kampilya, th	e
Kågåraul, v. in Ågrå d	75	capital of Pañchûla	MO
Kâhâon, small v. in Gôrakhpâr d.		Kampů, the new civil station of Sultanpůr	. 328
Anciently named Kakubhagra-	- 1	Kâmtâ, v. near Chitrakûț în Bândâ d	710
ma 243,	244	Kanakhala, the modern Kankhal i	n
Kahrâ-Kherâ, v. in Murâdâbâd d	36	Sahâranpûr d	. 16
Kailî Dîh, ancient ruined mound in Bastî d.,	224	Kanakpûr, old v. in Bastî d	. 221
Kaimahrâ, v. in Kherî d	287	Kanapår-Gangåtir, v. in Görakhpür d	. 243
Kaimgarh Dih, deserted site near Kalyanmal		Kanauj, tahsîl in Farrukhâbâd d.	
in Hardôî d	280	Anciently named Kanyakubja	,
Kairânâ, v. in Muzaffarnagar d	13	or Mahodaya 78-	81, 331
Kaithâl, v. in Murâdâbâd d	36	Kanehlîpûr v. in Kânhpûr d	. 168
Kaithauli, v. in Lakhnâû d	265	Kandarâîn, v. în Râî Barelî d	. 324
Kaithî, v. în Banâras d	212	Kanhpar, tahsil and head-quarters of d	. 168
Kakhra, t. in Mîrath d	10	Kanhûpûr, v. in Lakhnâû d	. 265
Kâkorî, t. in Lakhnâû d.		Kankhal, t. in Sahâranpûr d.	
Formerly known as Kâkorgarh	265	Anciently called Kanakhala	, 16
Kakrâla, v. in Badâon d	23	Kankrå, v. in Allahåbåd d	
Kakukhå, small river of Buddhist legends.		Kankûr, v. în RM Barelî d	
Identified with Ghagi river in		Kânt, v. in Shâhjahânpûr d	
AND THE RESERVE OF THE PARTY OF	239	Kaṇṭît, v. in Mîrzâpûr d	
Kâkûpûr, v. in Kâṇhpûr d.	-	Kanyakubja, the modern Kanauj in	
Perhaps Hiuen Tsiang's O'-yu-			78—81
	169	Kapatiya, or Kaptêsvarî, v. near Kanauj i	
	318	Farrukhâbûd d	
Kalanagara, ancient name of Karra in		Kapilavastu, wrongly identified with	
The state of the s	138	Bháila Dih in Bas	
	190	tî d 218—25	
Kalanjar, celebrated hill-fort in Banda d.		Kapili Dih, ancient ruined site in Basti d	
Anciently named Kalanjara-	150	Kapitha, the modern Sankisa-Basantpur	
dri 149—		in Farrukhâbâd d	1000
Kalaparpur, v. in Faizabad d	301	Karahlâ, v. near Chhâta in Mathurâ d	
Kalasadih, old name of Husainābād in Bā-	100	Karâîtî, v. in Pratâpgarh d	. 318
	192	Karanbas, v. in Bulandshahr d.	
Kalhaur, or Kilho, ruined site in Hardol d., 277, 2	46-287-1	Karári, v. in Allahábád d	
	265	Karâûlî, v. in Mâînpurî d	. 94
Kålokhala, old name of Karrâ in Allahâ-	199	Karâwan, v. in Faizâbâd d	
	138	Karawar, v. in Murâdâbâd d	. 35
Kûlpî, tahsîl in Jalâun d 112—1		Karêrû, v. in Hamîrpûr d Karhal, tahsîl in Mâînpurî d	00
Kalû, hamlet near Karwî in Bândâ d	TOT I	Karhal, tahsii in Mainpuri d	. 30

Karimganj, v. in Māhapuri d	Pages.	Pages.
Balandshahr d	Karîmganj, v. in Mâînpurî d93, 94	Kausambi, wrongly identified with Ahar in
Ditto, v. in Bahrâtôn d		T 1 1 1 1 1 1
Kosām Khirāj in Allahā- Karnprayāg, v. in Garhwāld	Dist D.I. As I. I	
Karpayāg, v. in Garkwāl d. 45		
Karrê, t. in Allahâbâd d. Anciently named Kâlan agara 138 Called Kâlok hala in a copperplate grant of A.H. 965 138 Also called Karkotak anagara 138 Description of extensive ruins at 138, 139 Karsotâ, small v. in Mîrzâpâr d. 326 Karthuni, v. in Sultânpâr d. 329 Kârttike yapura, the modern Baijnáth in Kumlon d. 47 Karwî, tahsîl in Bândâd d. 154 Kasanudhân, famous bathing place on the Ganges in Allahâbâd d. 300 Kasshri Buzurg, v. in Bahrâtôd d. 301 Kasâwâ, v. in Faizâbâd d. 302 Kasâwâ, v. in Faizâbâd d. 303 Kasâwâ, v. in Faizâbâd d. 304 Kasâwâ, v. in Gôrakhpûr d. 329 Kâsîhâbâd, v. in Gôrakhpûr d. 329 Kâsîhâbâd, v. in Gôrakhpûr d. 320 Kâsânâ, v. in Gôrakhpûr d. 320 Kâsânâ, v. in Balandshahr d. 36 Kasânâ, v. in Balandshahr d. 36 Kasanudi, v. in Lakhnâû d. 265 Kasanudi, v. in Lakhnâû d. 265 Kasanudi, v. in Bastî d. 202 Katakban or Kata kavana, old name of Katak, amall v. in Allahâbâd d. 102 Kathavâ, v. in Balayâ d. 301 Kadîka kamall v. in Allahâbâd d. 302 Kasahaban or Kata kavana, old name of Katak, amall v. in Allahâbâd d. 303 Kashaban or Kata kavana, old name of Katak, amall v. in Allahâbâd d. 304 Kasahaban or Kata kavana, old name of Katak, amall v. in Allahâbâd d. 305 Katakban or Kata kavana, old name of Katak, amall v. in Allahâbâd d. 308 Kasahaba, v. in Bastī d. 309 Katak, amall v. in Allahâbâd d. 309 Katak, amall v. in Allahâbâd d. 309 Katak, amall v. in Allahâbâd d. 309 Katak, amall v. in Allahâbâd d. 309 Katak, amall v. in Allahâbâd d. 309 Kâsânâ, v. in Bardî d. 309 Kâsânâ, v. in Bardî d. 309 Kâsânâ, v. in Bardî d. 309 Kâsânâ, v. in Bardî d. 309 Kâsânâ, v. in Bardî d. 309	Karnnesvila w in Claubanti J	**************************************
Anciently named Kâlanagara 138 Called Kâlokhala in a copperplate grant of AH. 965. 138 Also called Karkotakanagara, 138 Description of extensive ruins at		77 . 41
Called K & 1 ok h a la in a copperplate grant of A H. 965 138 Also called K ar k ot a k an a gar a, 138 Description of extensive ruins at 138, 139 Karsotd, small v. in Mirzāpār d 261 Karthuni, v. in Sulṭānpār d 261 Karthuni, v. in Sulṭānpār d 261 Karthuni, v. in Sulṭānpār d 261 Karthuni, v. in Sulṭānpār d 261 Karwi, tahsil in Bāndā d 154 Ka a a p ur a, of Huen Tsiang. Identified with Sulṭānpār 329 Kasault, v. in Murādābād d 380 Kasaundhān, famous bathing place on the Ganges in Allahābād d 380 Kasabā, v. in Fairābād d 380 Kasabri Buzurg, v. in Bahrātch d 381 Kasaya, v. in faḥ d 87 Kā st, or Kā si kā , ancient name of Banāras 197 Kasāpār, tahsil in Tarāt d 232 Kasamadl Kaha, v. in Bastī d 265 Kāsana, v. in Bastī d 265 Kāsana, v. in Bastī d 265 Kāsana, v. in Bastī d 265 Kāsanadu, v. in Šgrā d 75 Katahāba, v. in Bastī d 265 Kātahaban or K at a ka va na a, old name of Kofā in Mathurā d 102 Kathaurā, v. in Bāliyā d 103 Khairā Dih, deserted site near Turtipār in Bāliyā d 87 Kāsīja, v. in Fairābād d 380 Khairāgarh, tahsil in Āgrā d 283 Khairāgarh, v. in Karpā d 283 Khairāgarh, v. in Fairhābād d 285 Khairabāda, v. in Görakhpūr d 285 Katahban or K at a ka va na a, old name of Korā in Mathurā d 102 Kathaurā, v. in Bastī d 223 Katakban or K at a ka va na a, old name of Korā in Mathurā d 102 Kathaurā, v. in Bastī d 223 Katakban or K at a ka va na a, old name of Korā in Mathurā d 102 Kathaurā, v. in Bāliyā d 103 Katka, small V. in Allahābād d 103 Katka, small V. in Allahābād d 103 Katka, small V. in Mlahābād d 103 Katka, v. in Karpā d 103 Kathaurā, v. in Karpā d 223 Katahban or K at a ka va na a, old name of Korā in Mathurā d 102 Khairād, v. in Garahpār d 102 Khairād, v. in Mathurā d 102 Khairād, v. in Mathurā d 102 Khairād, v. in Mathurā d 102 Khairād, v. in Mathurā d 102 Khairād, v. in Mathur		Keddrahhami idanigal alit G 1 at
Plate grant of A.H. 965	Called K Alokhala in a copper-	Kedaynath femons towals : C. 1 all
Also called Karkotakanagara, 138 Description of extensive ruins at —	TO BE AND THE PARTY OF THE PART	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Description of extensive ruins at		Kosziczek old nem of V. A. D. 7 222
138, 139	Description of extensive ruins	K hadinanananananananananananananananananan
Karsotā, small v. in Mīrzāpār d		1 15 3 4 3
Karthunf, v. in Sultânpûr d	/FF 146 147 14	Whateh - to Mr. of A. a.
Kârttike yapura, the modern Baijnáth in Kumãon d		Khaira, v. in Mathura d 102
Karwi, tahśli in Bāndā d		
Ka ša pura, of Hiuen Tsiang. Jdentified with Sulţānpūr 329 Kasault, v. in Murādābād d. 38 Kasaundhān, famous bathing place on the Ganges in Allahābād d. 143 Kasāwā, v. in Murādābād d. 38 Kasbē, v. in Faizābād d. 38 Kasbē, v. in Faizābād d. 300 Kasehrī Buzurg, v. in Bahrāch d. 293 Kāsganj, v. in ftāh d. 87 Kāsī, v. in Gôrakhpūr d. 197 Kasiā, v. in Gôrakhpūr d. 197 Kasimābād, v. in Gôrakhpūr d. 232 Kāsīpūt, tahsīl in Tarāt d. 232 Khairnagar, v. in Fathpūr d. 285 Kāsīna ra . 50-52 Kasmandī Kalān, v. in Lakhnāū d. 265 Kāsnā, v. in Bulandshahr d. 6 6 Kassaundī, v. in Bāliyā d. 223 Kataban or K at a k av an a, old name of Kôtā in Mathurā d. 223 Kathaurā, v. in Bāliyā d. 102 Kathaurā, v. in Bāliyā d. 223 Kathaurā, v. in Allahābād d. 265 Kathaurā, v. in Bāliyā d. 102 Kathaurā, v. in Allahābād d. 102 Kathaurā, v. in Allahābād d. 103 Sculptured obe		Anciently called Masachitra, 288
Anciently named Bhârgava- Lientified with Sultanpar 329	Wound takes in Danda 3	Anaira Din, deserted site near Turtîpâr in
Identified with Sulfanpûr		A STATE OF THE PARTY OF THE PAR
Kasault, v. in Murâdâbâd d. 38 Khasaundhân, famous bathing place on the Ganges in Allahâbâd d. 143 Kasâwâ, v. in Murâdâbâd d. 143 Kasbû, v. in Faizâbâd d. 300 Kasehrî Buzurg, v. in Bahrâîch d. 293 Kasanj, v. in Îtâh d. 87 Kasî, v. in Gôrakhpûr d. 197 Kasiâ, v. in Gôrakhpûr d. 232 Kasîpûr, tahsîl in Tarâî d. 232 Extensive ruins near—, identified with the ancient city of Govisan a. 50-52 Kasmandî Kalân, v. in Lakhnâû d. 265 Kâsnâ, v. in Bulandshahr d. 6 Kasasaundî, v. in Âgrâ d. 223 Katahbâ, v. in Bastî d. 203 Katahaban or Ka ta ka va na, old name of Kataha, small v. in Allahâbâd d. 102 Kathava, v. in Baliyâ d. 193 Kathavâ, small v. in Allahâbâd d. 102 Kathawâ, w. in Baliyâ d. 102 Kathawân, v. in Baliyâ d. 102 Kathawân, v. in Baliyâ d. 102 Kathawân or Ka ta ka va na, old name of Kataka, small v. in Allahâbâd d. 102 Kathawân, w. in Samgarh d. 103 Kauriâ, v. in Âzamga		Anciently named Bhargava-
Ditto, v. in Maînpurî d		pura 194, 239
Ganges in Allahābād d		Khairagarh, tahsil in Agra d 75
Kasāwā, v. in Murādābād d. 38 Kasbā, v. in Faizābād d. 300 Kasehrī Buzung, v. in Bahrāfeh d. 293 Kāsganj, v. in fitāh d. 87 Kāsī, or Kāsikā, ancient name of Banāras 197 Kasiā, v. in Gôrakhpūr d. 197 Identified with Kušinagaram, 244—247 Kasīmābād, v. in Gōrakhpūr d. 232 Kāsīpūr, tahsīl in Tarāi d. Extensive ruins near—, identified with the ancient city of Goviana a. 50—52 Kasmandī Kalān, v. in Lakhnāū d. 265 Kāsnā, v. in Bulandshahr d. 6 Kassaundī, v. in Āgrā d. 75 Katakhan or Katakavana, old name of Kōtā in Mathurā d. 102 Kathaurā, v. in Bāliyā d. 193 Katkak, small v. in Allahābād d. 193 Sculptured obelisk of Gupta period at— 139, 140 Kauriā, v. in Āzamgarh d. 188 Kauriā, v. in Algarh d. 188 Kauriā, v. in Algarh d. 188 Khālaft Kherā, v. in Murādābād d. 247 Sculptured obelisk of Gupta period at— 188 Khairāli in Dêrah Dūn d. 180 Khālaft Kherā, v. in Faizābād d.	Assaundnan, ramous bathing place on the	Ditto, v. in Mainpuri d 94
Kasbå, v. in Muradabad d	Tr A a c or investa	Ditto, old ruined fort in Allahâbâd d., 140
Kased, v. in Fazabād d.	The second secon	Ditto, deserted site near Turtîpâr in
Kåsganj, v. in Îṭāh d. 87 Kåsî, or Kåsikâ, ancient name of Banāras 197 Kasiâ, v. in Gôrakhpûr d. 197 Kasîmābād, v. in Gôrakhpûr d. 232 Kāsîpûr, tahsîl in Tarâî d. 232 Extensive ruins near—, identified with the ancient city of Govisan a. 50-52 Kasmandî Kalân, v. in Lakhnâû d. 265 Kasmandî, v. in Bulandshahr d. 6 Kassaundî, v. in Bastî d. 223 Katahlâ, v. in Bastî d. 223 Katahla, v. in Baliyâ d. 102 Kathaura, v. in Bâliyâ d. 103 Katkâ, small v. in Allahâbâd d. 103 Sculptured obelisk of Gupta period at— 139, 140 Kauriâ, v. in Âzamgarh d. 188 Kauriâ, v. in Âzamgarh d. 188 Kausâmbî, wrongly identified with Köl in Aligarh d. 188 Kausâmbî, wrongly identified with Köl in Aligarh d. 188 Khâlgarh d. 188 Khândâusâ, v. in Faizābād d. 26 Khâlgarh d. 188 Khâlgarh d. 188 Khâlgarh d. 188 Khâlgarh d.		
Nasaganj, v. in Aland d. 194, 239	Trans	Anciently named Bhargava-
Kasi, v. in Gôrakhpûr d. 197 Kasiâ, v. in Gôrakhpûr d. 289 Kasîmabâd, v. in Gôrakhpûr d. 285 Kasîmabâd, v. in Gôrakhpûr d. 282 Kâsîpûr, tahsîl in Tarâî d. 282 Extensive ruins near—, identified with the ancient city of Govisan a. 50-52 Kasmandî Kalân, v. in Lakhnâû d. 265 Kâsnâ, v. in Bulandshahr d. 6 Kassaundî, v. in Âgrâ d. 223 Katahlâ, v. in Bastî d. 223 Katahlâ, v. in Baliyâ d. 102 Kathaurâ, v. in Bâliyâ d. 193 Katkâ, small v. in Allahâbâd d. 193 Kauriâ, v. in Âzamgarh d. 188 Kauriâ, v. in Fathpûr d. 247 Khâlîsî, tahsîl in Fathpûr d. 162 Khakhurdû, v. in Gôrakhpûr d. 247, 248 Identified with the town of Hiuen Tsiang's hospitable Brâhmana 247 Khâlîp		pura 194 939
Kasiâ, v. in Gôrakhpūr d. Identified with Ku sinagaram, 244—247 Kasîmābād, v. in Gôrakhpūr d. Extensive ruins near—, identified with the ancient city of Govisana 50—52 Kasmandî Kalân, v. in Lakhnāū d. Kasna, v. in Bulandshahr d. Kasaundî, v. in Âgrā d. Kasaundî, v. in Bastî d. Katahlî, v. in Bastî d. Sculptured obelisk of Gupta period at— 139, 140 Kauriâ, v. in Āzamgarh d. Kausāmbî, wrongly identified with Kôl in Aligarh d. Identified with Ku sinagaram, 244—247 Khairangar, v. in Kherî d. Scene of Aurangzīb's victory over Shūja Shūh Khaijūrgāon, v. in Rāl Barelī d. Scene of Aurangzīb's victory over Shūja Shūh Khaijūrgāon, v. in Rāl Barelī d. Scene of Aurangzīb's victory over Shūja Shūh Aligarh d. Scene of Aurangzīb's victory over Shūja Shūh Khāilārangar, v. in Faitabūd d. Scene of Aurangzīb's victory over Shūja Shūh Khāilārangar, v. in Sitāpa d. Skāipa Shūh Khāilārangar, v. in Sitāpa d. Skāipa Shūh Khāilā		Khairai, v. in Fathpur d 169
Kasimābād, v. in Görakhpūr d 232 Kāsīpūr, tahsīl in Tarāi d 232 Kāsīpūr, tahsīl in Tarāi d 50—52 Kasmandī Kalān, v. in Lakhnāū d 265 Kāsanā, v. in Bulandshahr d 6 Kassaundī, v. in Āgrā d 255 Katahlā, v. in Bastī d 265 Katahlā, v. in Bastī d 265 Katahlā, v. in Bastī d 223 Katakban or Katakavana, old name of Kōṭā in Mathurā d 102 Kathaurā, v. in Bāliyā d 193 Katkā, small v. in Allahābād d 193 Katkā, small v. in Allahābād d 193 Katurā, v. in Āzamgarh d 188 Kausāmbī, wrongly identified with Kōl in Alīgarh d 188 Kausāmbī, wrongly identified with Kōl in Alīgarh d 11	*** ***	Khairandêsnagar, v. in Sîtâpûr d. 280
Kasîmâbâd, v. in Görakhpâr d 232 Kâsîpûr, tahsîl in Tarâi d. Extensive ruins near—, identified with the ancient city of Govisana 50—52 Kasmandî Kalân, v. in Lakhnâû d 265 Kâsnâ, v. in Bulandshahr d 6 Kassaundî, v. in Bastî d 223 Katakban or Katakavana, old name of Kôtû in Mathurâ d 102 Kathaurâ, v. in Baliyû d 103 Katkâ, small v. in Allahâbâd d. Sculptured obelisk of Gupta period at—— 139, 140 Kauriâ, v. in Âzamgarh d 188 Kausâmbî, wrongly identified with Kôl in Aligarh d 1		Khairianni 4 in Wt. A 1
Kāsimaoad, V. in Gorakhpūr d 232 Kāsipūr, tahsīl in Tarāi d. Scene of Aurangzīb's victory over Shūja Shāh 162 Kasmandī Kalān, v. in Lakhnāū d 265 Kāsnā, v. in Bulandshahr d 6 Kassaundī, v. in Agrā d 75 Katahlā, v. in Bastī d 223 Katakban or Katakavana, old name of Kōtā in Mathurā d 102 Kathaurā, v. in Bāliyā d 193 Katkā, small v. in Allahābūd d. Sculptured obelisk of Gupta period at 139, 140 Kauriā, v. in Āzamgarh d 188 Kausāmbī, wrongly identified with Kōl in Alīgarh d 1188 Kausāmbī, wrongly identified with Kōl in Alīgarh d 1188 Khālādāusā, v. in Faṭhpūr d. Scene of Aurangzīb's victory over Shūja Shāh 162 Khajūrgāon, v. in Rāt Barelī d 323 Khakhuratā in Faṭhpūr d 162 Khajūrgāon, v. in Gōrakhpūr d 162 Khakhundū. v. in Gōrakhpūr d 162 Khakhundū. v. in Gōrakhpūr d 247, 248 Identified with the town of Hiuen Tsiang's hospitable Brāhmaṇa 247 Khākī Kherā, v. in Murādābād d 36 Khākukhūrī, deserted site in Gōrakhpūr d. 243 Khālpūr, v. in Barelī d 26 Khālsī, ṭahsīl in Dērah Dūn d. Rock inscribed with edicts of Ašoka at 7, 8 Khāndāusā, v. in Faizābād d 7, 8	Identified with Kusinagaram, 244-247	Khairmanan w in U. Tlavas
Extensive ruins near—, identified with the ancient city of Govisana 50—52 Kasmandî Kalân, v. in Lakhnâû d 265 Kâsnâ, v. in Bulandshahr d 6 Kassaundî, v. in Agrâ d 75 Katahlâ, v. in Bastî d 223 Katakban or Katakavana, old name of Kôtâ in Mathurâ d 102 Kathaurâ, v. in Bâliyâ d 193 Katkâ, small v. in Allahâbâd d. Sculptured obelisk of Gupta period at— 139, 140 Kauriâ, v. in Âzamgarh d 188 Kausâmbî, wrongly identified with Kôl in Aligarh d 1 Khândâusâ, v. in Faizâbâd d 7, 8 Khândâusâ, v. in Faizâbâd d 7, 8 Khândâusâ, v. in Faizâbâd d 7, 8 Khândâusâ, v. in Faizâbâd d 7, 8	A STATE OF THE STA	Khajuha, t. in Fathray d
with the ancient city of Govisanna 50—52 Kasmandî Kalân, v. in Lakhnâû d 265 Kâsnâ, v. in Bulandshahr d 6 Kassaundî, v. in Âgrâ d 75 Katahlâ, v. in Bastî d 223 Katakban or Katakavana, old name of Kôţâ in Mathurâ d 102 Kathaurâ, v. in Bâliyâ d 193 Katkâ, small v. in Allahâbâd d. Sculptured obelisk of Gupta period at— 139, 140 Kauriâ, v. in Âzamgarh d 188 Kausâmbî, wrongly identified with Kôl in Alîgarh d 1		Scene of Aurangzib's victory over
Kasmandî Kalân, v. in Lakhnâû d 265 Kâsnâ, v. in Bulandshahr d 6 Kassaundî, v. in Agrâ d 75 Katahlâ, v. in Bastî d 223 Katakban or Katakavana, old name of Kôtâ in Mathurâ d 102 Kathaurâ, v. in Bâliyâ d 193 Katkâ, small v. in Allahâbâd d. Sculptured obelisk of Gupta period at— 139, 140 Kauriâ, v. in Âzamgarh d 188 Kausâmbî, wrongly identified with Kôl in Aligarh d 1 Khajûrgâon, v. in Râi Barelî d 323 Khakhrerû, tahsîl in Faṭhpûr d 162 Khakhundû. v. in Gôrakhpûr d 247, 248 Identified with the town of Hiuen Tsiang's hospitable Brâhmana 247 Khâkî Kherâ, v. in Murâdâbâd d 36 Khâkukhûrî, deserted site in Gôrakhpûr d 26 Khâlpûr, v. in Barelî d 26 Khâlpûr, v. in Barelî d 26 Khâlpûr, v. in Barelî d 26 Khâlpûr, v. in Barelî d 26 Khâlpûr, v. in Faizâbâd d 7, 8 Khândâusâ, v. in Faizâbâd d 7, 8		Share SLAT
Kasmandî Kalân, v. in Lakhnâû d 265 Kâsnâ, v. in Bulandshahr d 6 Kassaundî, v. in Âgrâ d 75 Katahlâ, v. in Bastî d 223 Katakban or Katakavana, old name of Kôţâ in Mathurâ d 102 Kathaurâ, v. in Bâliyâ d 193 Katkâ, small v. in Allahâbâd d. Sculptured obelisk of Gupta period at— 139, 140 Kauriâ, v. in Âzamgarh d 188 Kausâmbî, wrongly identified with Kôl in Aligarh d 1 Khândâusâ, v. in Faizâbâd d 7, 8 Khândâusâ, v. in Faizâbâd d 7, 8 Khândâusâ, v. in Faizâbâd d 7, 8	with the ancient city of Govi-	Khaidradan w in DALD 14 1
Kâsnâ, v. în Bulandshahr d 6 Kassaundî, v. în Agrâ d 75 Katahlâ, v. în Bastî d 223 Katakban or Katakavana, old name of Kôtâ în Mathurâ d 102 Kathaurâ, v. în Bâliyâ d 193 Katkâ, small v. în Allahâbâd d. Sculptured obelisk of Gupta period at— 139, 140 Kauriâ, v. în Âzamgarh d 188 Kauriâ, v. în Âzamgarh d 188 Kauriâ, v. în Âzamgarh d 188 Kausâmbî, wrongly identified with Kôl în Alîgarh d 1 Khândâusâ, v. în Faizâbâd d 7, 8 Khândâusâ, v. în Faizâbâd d 7, 8	00 04	Khakhaara tahati in Ti di a
Kassaundî, v. in Âgrâ d 6 Katahlâ, v. in Bastî d		Khakhundû, v. in Gûrakhpûn d
Katahlâ, v. in Bastî d 223 Katakban or Katakavana, old name of Kôţâ in Mathurâ d 102 Kathaurâ, v. in Bâliyâ d 193 Katkâ, small v. in Allahâbâd d. Sculptured obelisk of Gupta period at— 139, 140 Kauriâ, v. in Âzamgarh d 188 Kauriâ, wrongly identified with Kôl in Alîgarh d 1 Khândâusâ, v. in Faizābâd d 7, 8 Khândâusâ, v. in Faizābâd d 7, 8		Anciently named W: 11:
Katahan, v. in Bash d 223 Katakban or Katakavana, old name of Kôtâ in Mathurâ d 102 Kathaurâ, v. in Bâliyâ d 193 Katkâ, small v. in Allahâbâd d 193 Katkâ, small v. in Allahâbâd d. Sculptured obelisk of Gupta period at 139, 140 Kauriâ, v. in Âzamgarh d 188 Kauriâ, wrongly identified with Kôl in Alîgarh d 188 Khândâusâ, v. in Faizābâd d 7, 8 Khândâusâ, v. in Faizābâd d 7, 8	Kassaundî, v. in Âgrâ d 75	of the second of
Kathaurâ, v. in Bâliyâ d 193 Katkâ, small v. in Allahâbâd d. Sculptured obelisk of Gupta period at— 139, 140 Kauriâ, v. in Âzamgarh d 188 Kausâmbî, wrongly identified with Kôl in Alîgarh d 1 Hiuen Tsiang's hospitable Brâhmaṇa 247 Khâkî Kherâ, v. in Murâdâbâd d 36 Khâkukhûrî, deserted site in Gôrakhpûr d., 243 Khâlpûr, v. in Barelî d 26 Khâlsî, tahsîl in Dêrah Dûn d. Rock înscribed with edicts of Asoka at— 7, 8 Khândâusâ, v. in Faizâbâd d 7, 8	220	
Kathaurâ, v. in Bâliyâ d 102 Kathaurâ, v. in Bâliyâ d 193 Katkâ, small v. in Allahâbâd d. Sculptured obelisk of Gupta period at— 139, 140 Kauriâ, v. in Âzamgarh d 188 Kausâmbî, wrongly identified with Kôl in Alîgarh d 1 Khândâusâ, v. in Faizābâd d 7, 8 Khândâusâ, v. in Faizābâd d 7, 8	Katakban or Katakavana, old name of	Hippon m: the town of
Kathaurâ, v. in Bâliyâ d 193 Katkâ, small v. in Allahâbâd d. Sculptured obelisk of Gupta period at 139, 140 Kauriâ, v. in Âzamgarh d 188 Kausâmbî, wrongly identified with Kôl in Alîgarh d 1 Khâkî Kherâ, v. in Murâdâbâd d 36 Khâkukhûrî, deserted site in Gôrakhpûr d., 243 Khâlpûr, v. in Barelî d 26 Khâlsî, tahsîl in Dêrah Dûn d. Rock inscribed with edicts of Asoka at 7, 8	TO A A	P.A. Islang's hospitable
Katkâ, small v. in Allahâbâd d. Sculptured obelisk of Gupta period at— 139, 140 Kauriâ, v. in Âzamgarh d. Kausâmbî, wrongly identified with Kôl in Alîgarh d. Alîgarh d. Sculptured obelisk of Gupta period at— 139, 140 Khâlsî, tahsîl in Dêrah Dûn d. Rock inscribed with edicts of Asoka at— 7, 8 Khândâusâ, v. in Faizâbâd d. Khândâusâ, v. in Faizâbâd d. 36 Khâkukhûrî, deserted site in Gôrakhpûr d., 243 Khâlsî, tahsîl in Dêrah Dûn d. Rock inscribed with edicts of Asoka at— 7, 8	Washington C. Dalling 1	Khaki Khara 247
At 139, 140 Kauriâ, v. in Âzamgarh d 188 Kausâmbî, wrongly identified with Kôl in Alîgarh d 1 Khândâusâ, v. in Faizābâd d 26 Khândâusâ, v. in Faizābâd d 7, 8	Katkå, small v. in Allahåbåd d.	Khākukhā 2 36
Kauriâ, v. in Âzamgarh d 139, 140 Kausâmbî, wrongly identified with Kôl in Alfgarh d 1 Khâlsî, tahsîl in Dêrah Dûn d. Rock înscribed with edicts of Asoka at— 7, 8 Khândâusâ, v. in Faizâbâd d 7, 8	Sculptured obelisk of Gupta period	Dilling war Range 3
Kauriâ, v. in Azamgarh d 188 Kausâmbî, wrongly identified with Kôl in Alfgarh d 1 Khândâusâ, v. in Faizâbâd d 7, 8		Khalet takett in Da 1 Da 26
Kausâmbî, wrongly identified with Kôl in Alîgarh d 1 Khândâusâ, v. in Faizâbâd d 7, 8	To an extend on the state of th	Post in Deran Dan d.
Alfgarh d 1 Khândâusâ, v. in Faizābād d 7, 8		
A Faizabad d 201	A female d	7.0
		301

Fages.	Pages.
Khandant, deserted site near Jalalpar in	Khudaganj, v. in Shahjahanpur d 42
Hamîrpûr d 179	Ditto as in Day 13 61 63 3
Khandeh, v. in Bândâ d 154	
Khânpûr-Pilâî, v. in Faizâbâd d 302	110000000000000000000000000000000000000
Khaptiha, v. in Banda d 154	Whent takethin Dalandatalan
Khârâ, v. in Allahâbâd d 140	Whintin La South 2 - 4
Kharaila, t. in Hamirpar d 178	The state of the s
Khargpûr, v. in Tarâl d 52	The state of the s
Khargûpûr, v. in Gondâ d 304	The state of the s
Kharîd, small v. in Bâliyâ d.	Identified with Sul-
Formerly named Ghazanfarabad, 193, 194	10-4- 000
Khâspûr, v. in Faizâbâd d 302	The state of the s
Khataull, v. in Muzaffarnagar d 13	
Khawaspur, v. near Âgra 53	TA . A . That A 1
Khûz, old v. in Pilibhît d 40	1771-8A10 2 2 A A A
Khekara, or Khekora, t. in Mîrath d 10	
Khemrâjpûr, old v. in Bastî d.	Dêogarh in Lalit-
Anciently called Kshemâ-	pûr d 120
vatî 221	
Kherå, small v. in Ågrå d 75	
Kherâ Bajherâ, deserted town in Aligarh d., 1	
Ditto, old v. in Shâhjahânpûr d., 42	
Khera Basundra, ruined fort in Îtâh d 85	part at a series of the series
Khera Khas, old v. in Muradabad d 36	
Khera Kundalpûr, v. near Nûh Khera in	
Îtâh d 87	
Kherâ Mangraur, pargana in Mîrzâpûr d 261	Kôh Inâm, ruined v. in Allahâbâd d 140
Khergarh, or Khairagarh, v. in Maîn-	Kohnrår, or Kohrår, v. in Allahåbåd d 140 Kokilaban, sacred wood near Bathan in
D. C. Commission of the Commis	37.43 4.3
The A. A. S. Wheeld I con	111
271 . 1 3V . 2701.0.2.2	
White-indu small or in Booth d pop	The state of the s
Trans. in Day Parell J. Book	Wrongly identified with Kausambi, 1-3
The state of the s	Köli, identified with Barah Chhetra in
The second secon	Bastî d 217
	Kopâ, v. in Azamgarh d.
Khîwâr, v. in Faizâbâd d 300	Also called Irâdatganj 189
Khizrâbâd, t. in Sahâranpûr d.	Do., v. near Maghar in Bastî d 225
Ašoka's lâţ removed by Fîrûz	Korâ, tahsîl in Faṭhpûr d.
Shah to Dehli from—, 16, 331	Anciently called Mahakaya 162
Khôh, v. near Karwî in Bândâ d 154	Mentioned by Alberûnî under the
Khopoù Dih, old ruined site in Basti d.	name of Kuraha 163
Identified with Sobhavati-	Also called Argal 163
nngaram 221	Kora Dih, small v. in Mîrzapûr d 261
Khôr, old ruined t. near Shamsâbâd in	Koráwán, v. in Faizábád d 301
Farrukhåbåd d 84	Koron, or Korâwâ, v. in Bastî d.
Khôr Kâlî, ruined mound near Sarsâwâ in	Anciently named Sobhama-
Mirath d 12	ninagaram 226
Khudådåd, old name of Neotini in Unio d., 272	Kosahrå, v. near Bhûilâ Dîh in Bastî d 220

Pages,	Pages.
Kosâm Inâm and Kosâm Khirâj, two small	Kundilpûr, or Kundanpûr, v. near Khairi-
v. in Allahâbâd d.	garh in Kherî d.
Identified with Kausambi, 140-143	Locally identified with the capi-
Kôsî, tahsîl in Mathurâ d.	tal of Bhishmaka 286
Anciently named Kusasthali 102	Kundinapura, wrongly identified with
Kôt, v. in Fathpûr d 163	Ahâr in Bulandshahr d., 4
Do., v. near Bhûîla Dîh in Bastî d 220	Kurdå, v. in Bastî d 221
Kôtā, v. in Kumāon d 50	Kurh, v. in Sultanpar d 330
Do., small v. in Mathura d.	Kûrmaganj, v. in Pratâpgarh d 318
Anciently called Katakavana 102	Kursanda, t. in Mathura d 102
Kôṭalgarh, old fort in Kumâon d 49,50	Kursat, v. in Unão d.
Kôtban, sacred grove near Kôsî in Mathu-	Formerly named Qudsat 272
râ d 102	Kurselî, v. in Hardôî d 283
Kôtdîh, v. in Faizâbâd d 301	Kursî, t. in Bâra Baûkî d.
Kôtêśra, v. in Muzaffarnagar d 13	Formerly called Kesrigarh 264
Kôthot, or Kôt-ut, ruined fort at Jurapattî	Kusabhavanapura, or Kusapura,
in Sultânpûr d 329	the modern Sul-
Kôt Sâlbâhan, v. in Badâon d 23	tânpûr, 326, 328, 329
Kột Sarâwân, v. in Faizâbâd d 302	Kusinagara, ancient name of Kasia in
Kôṭwā, small v. in Allahâbâd d 143	Gôrakhpûr d 239
Ditto, v. near Bhûlla Dih in Bastî d 219	Kutilâ, v. in Fathpûr d 163
Ditto, v. near Nârâyanpûr in Ghâzîpûr d., 233	Kutiyâ, v. in Faṭhpûr d.
Ditto, v. near Gagahâ in Gôrakhpûr d 241	Perhaps the 'O-yu-t'o of Hiuen
Ditto, v. in Sultanpar d 329	Tsiang 163
Kôtwân, v. in Mathurâ d 102	T. T. T. T. T. T. T. T. T. T. T. T. T. T
Krelulendrapura, identified with Ma-	L.
sâon Dih in Ghâzî-	Lachhagir, famous bathing-place on the
pûr d 233	Ganges in Allahâbâd d. 148
Kshemâvatî, the modern Khemrâjpûr in Bastî d. 221	Laharpür, t. in Sîtâpûr d.
7744 7 4 4 4 4 4 4 4 4 4	Formerly called Taghlaqpûr 288
Kua-ka-chaur, hill in Kumaon d 49 Kudarkôt, v. in Itawah d.	Birthplace of Raja Todaramalla 288
Supposed to be the ancient	Lakhanpür, deserted site in Hamirpür d 178
	Lakhanpur-Köt, deserted hill-fort in Ku-
Gavîdhumat, 91, 92, 331 Kûdawâ Nadî, river in Bastî d.	maion d 47
· Identified with the Anoma river	Lakhanû, or Lakhnô, deserted v. site in
0.73 (3.31.7.4.1.4.1.4.1.4.1.4.1.4.1.4.1.4.1.4.1.	Aligarh d.
Kukkurpattî, v. în Gôrakhpûr d 240	Buddhist sculptures excavated
Kukrâ, v. in Kherî d 286	at— o
Kukuttha, small river of Buddhist	Daknimpur, tahsil and head-quarters of
legends.	Table 286
Identified with the Ghagi	Lakhnâû, capital of Audh.
river in Gôrakhpûr d 239	Anciently named Lakshmana-
Kulpahâr, tahsîl in Hamîrpûr d 173	vatî 265
Kûnch, tahsîl in Jalâun d 114	Palaces of kings of Audh at, 265267
Kundanpür, deserted t. site in Bulandshahr d., 6	mannaura, v. near Basti
Kundarkhi, v. in Murådåbåd d.	Lakhnésar Dih, deserted v. in Báliyâ d 193
Kundilpûr, or Kunarê, v. in Gôrakhpûr d., 248	Lakrāpūr, old mound near Akbarpūr in
	Kanhpar d 165

Pages.	Pages.
Lakshman avati, ancient name of Lakh-	Madhuban, v. in Azamgarh d 189
nâû 265	Madiyâ, or Mandiyâ, v. in Bîjnôr d 31
Lakshmanpûr, v. in Basti d 224	Maghar, t. in Basti d 224
Lakshmîpûr, v. in Bâliyâ d 194	Magôrâ, v. in Mathurâ d.
Lalauli, v. in Fathpûr d 165	Formerly named Mangodala 108
Lâldhang, v. in Bîjnôr d.	Mâh, small v. in Allahâbâd d 143
Ruins in the Panduwala Sot	Mahabalipura, the modern Bawan in
near— 31	Hardôî d 277
Lalitpûr, tahsîl and head-quarters of d 123	Mahâban, tahsîl in Mathurâ d.
Lalpur, v. in Bijnor d.	Remains of ancient Hindû temple
Site of Gunaprabha's and Samgha-	at— 103, 104
bhadra's monasteries at31, 32	Mahadeva, old v. in Basti d 223
Landhaura, v. in Saharanpar d 17	Ditto, v. in Gondâ d 305
Lâr, v. in Gôrakhpâr d 248	Mahaff, v. in Pilibhit d 40
Latifpür, ruined stone fort in Mîrzâpür 252	Mahakaya, the modern Kora in Fath-
Lâțiyâ, small v. in Ghâzîpâr d. 232, 236	pûr d 163
Lauri, or Lokhri, v. in Banda d 154	Māhal, tahsīl in Āzamgarh d 189
Lauta Shahr, another name of Bangarman	Mahârâjnagar, large v. in Sîtâpûr d.
and Nawal in Unão d 270	Formerly called Islâmnagar, 289
Lohâban, small v. in Mathurâ d. 102, 103	Mahasthan Dih, ruined ancient site near
Lohrâmâu, v. in Sultânpûr d 329	Maghar in Bastî d 224
Loni, old v. in Mîrath d 10	Mahêspûr, v. in Jalâun d 114
Ludhiya Ghat, v. in Gonda d 305	Mahidant-ka-khera, traditional name of Mi-
M. M.	rath 10
M.	rath 10 Mahirashtra, ancient name of Mirath, 10
Machhligaon, v. in Gonda d 305	
Machhligaon, v. in Gonda d 305 Machhlishahr, tahsal in Jaunpur d 185	Mahirashtra, ancient name of Mirath, 10
Machhligâon, v. in Goṇḍâ d 305 Machhlishahr, tahsîl in Jaunpûr d 185 Machhrehtâ, v. in Sîtâpûr d 289	Mahirâshtra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278
Machhligâon, v. in Gondâ d 305 Machhlishahr, tahsîl in Jaunpûr d 185 Machhrehtâ, v. in Sîtâpûr d 289 Madana-Banâras, old name of Zamâniyâ in	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôi d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14
Machhligâon, v. in Goṇḍâ d 305 Machhlishahr, tahsîl in Jaunpûr d 185 Machhrehtâ, v. in Sîtâpûr d 289 Madana-Banâras, old name of Zamâniyâ in Ghâzîpûr d 236	Mahirâshtra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sultânpûr d 329
Machhligaon, v. in Gonda d 305 Machhlishahr, tahsal in Jaunpar d 185 Machhrehta, v. in Satapar d 289 Madana-Banaras, old name of Zamaniya in Ghazapar d 236 Madanapura, the modern Madanpar in	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174
Machhligaon, v. in Gonda d 305 Machhlishahr, tahsal in Jaunpur d 185 Machhrehta, v. in Sitapur d 289 Madana-Banaras, old name of Zamaniya in Ghazipur d 236 Madanapura, the modern Madanpur in Lalitpur d. 123, 124	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period
Machhligaon, v. in Gonda d 305 Machhligaon, v. in Gonda d 185 Machhlishahr, tahsal in Jaunpar d 289 Machhrehta, v. in Satapar d 289 Madana-Banaras, old name of Zamaniya in Ghazapar d 236 Madanapura, the modern Madanpar in Lalitpar d. 123, 124 Ditto, ruined city near Sahet-	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at 174—177
Machhligaon, v. in Gonda d 305 Machhlishahr, tahsil in Jaunpur d 185 Machhrehta, v. in Sitapur d 289 Madana-Banaras, old name of Zamaniya in Ghazipur d 236 Madanapura, the modern Madanpur in Lalitpur d. 123, 124 Ditto, ruined city near Sahet- Mahet in Hamirpur d., 173	Mahirashtra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgram in Hardôi d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sultanpûr d 329 Mahoba, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at— 174—177 Mahodaya, ancient name of Kanauj in
Machhligaon, v. in Gonda d 305 Machhlishahr, tahsil in Jaunpür d 185 Machhrehta, v. in Sitapür d 289 Madana-Banaras, old name of Zamaniya in Ghazipür d 236 Madana pura, the modern Madanpür in Lalitpür d. 123, 124 Ditto, ruined city near Sähet- Mähet in Hamirpür d., 173 Madanpür, small v. in Lalitpür d.	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at— 174—177 Mahodayâ, ancient name of Kanauj in Farrukhâbâd d 331
Machhligaon, v. in Gonda d 305 Machhligaon, v. in Gonda d 185 Machhlighahr, tahsal in Jaunpar d 289 Machhrehta, v. in Sitapar d 289 Madana-Banaras, old name of Zamaniya in Ghazapar d 236 Madanapar a, the modern Madanpar in Lalitpar d. 123, 124 Ditto, ruined city near Sahet- Mahet in Hamarpar d., 173 Madanpar, small v. in Lalitpar d. Formerly named Madana-	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at— 174—177 Mahodayâ, ancient name of Kanauj in Farrukhâbâd d 331 Mahôlî, v. in Bastî d.
Machhligaon, v. in Gonda d 305 Machhlishahr, tahsal in Jaunpar d 185 Machhrehta, v. in Sitapar d 289 Madana-Banaras, old name of Zamaniya in Ghazipar d 236 Madanapura, the modern Madanpar in Lalitpar d. 123, 124 Ditto, ruined city near Sahet- Mahet in Hamarpar d., 173 Madanpar, small v. in Lalitpar d. Formerly named Madana- pura 123	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at— 174—177 Mahodayâ, ancient name of Kanauj in Farrukhâbâd d 331 Mahôlî, v. in Bastî d. Anciently named Mâhuliyâ 225
Machhligaon, v. in Gonda d 305 Machhlishahr, tahsil in Jaunpür d 185 Machhrehta, v. in Sitapür d 289 Madana-Banaras, old name of Zamaniya in Ghazipür d 236 Madana pura, the modern Madanpür in Lalitpür d. 123, 124 Ditto, ruined city near Sähet- Mähet in Hamirpür d., 173 Madanpür, small v. in Lalitpür d. Formerly named Madana- pura 123 Chandella temples and inscrip-	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at— 174—177 Mahodayâ, ancient name of Kanauj in Farrukhâbâd d 331 Mahôlî, v. in Bastî d. Anciently named Mâhuliyâ 225 Ditto, large v. in Sîtâpûr d 289
Machhligaon, v. in Gonda d 305 Machhlishahr, tahsal in Jaunpar d 185 Machhrehta, v. in Satapar d 289 Madana-Banaras, old name of Zamaniya in Ghazapar d 236 Madanapara, the modern Madanpar in Lalitpar d. 123, 124 Ditto, ruined city near Sahet- Mahet in Hamarpar d., 173 Madanpar, small v. in Lalitpar d. Formerly named Madana- pura 123 Chandella temples and inscriptions at— 123, 124	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at— 174—177 Mahodayâ, ancient name of Kanauj in Farrukhâbâd d 331 Mahôlî, v. in Bastî d. Anciently named Mâhuliyâ 225 Ditto, large v. in Sîtâpûr d 289 Ditto, v. in Faizâbâd d 301
Machhligaon, v. in Gonda d 305 Machhlishahr, tahsal in Jaunpar d 185 Machhlishahr, tahsal in Jaunpar d 289 Machhrehta, v. in Sitapar d 289 Madana-Banaras, old name of Zamaniya in Ghazipar d 236 Madana pura, the modern Madanpar in Lalitpar d. 123, 124 Ditto, ruined city near Sahet- Mahet in Hamarpar d., 173 Madanpar, small v. in Lalitpar d. Formerly named Madana- pura 123 Chandella temples and inscriptions at— 123, 124 Madarpar, v. in Faizabad d 302	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at— 174—177 Mahodayâ, ancient name of Kanauj in Farrukhâbâd d 331 Mahôlî, v. in Bastî d. Anciently named Mâhuliyâ 225 Ditto, large v. in Sîtâpûr d 289 Ditto, v. in Faizâbâd d 301 Mahôlî-Shamshêrganj, v. in Mâînpurî d 94
Machhligaon, v. in Gonda d 305 Machhlishahr, tahsil in Jaunpür d 185 Machhrehta, v. in Sitapür d 289 Madana-Banaras, old name of Zamaniya in Ghazipür d 236 Madana pura, the modern Madanpür in Lalitpür d. 123, 124 Ditto, ruined city near Sähet- Mahet in Hamirpür d., 173 Madanpür, small v. in Lalitpür d. Formerly named Madana- pura 123 Chandella temples and inscriptions at— 123, 124 Madarpür, v. in Faizābād d 302 Madha, v. in Dērah Dūn d.	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at— 174—177 Mahodayâ, ancient name of Kanauj in Farrukhâbâd d 331 Mahôlî, v. in Bastî d. Anciently named Mâhuliyâ 225 Ditto, large v. in Sîtâpûr d 289 Ditto, v. in Faizâbâd d 301 Mahôlî-Shamshêrganj, v. in Mâînpurî d 94 Mahonâ, v. in Lakhnâû d 267
Machhligaon, v. in Gonda d 305 Machhlishahr, tahsal in Jaunpar d 185 Machhlishahr, tahsal in Jaunpar d 289 Machhrehta, v. in Satapar d 289 Madana-Banaras, old name of Zamaniya in Ghazapar d 236 Madanapar mach madanpar in Lalitpar d. 123, 124 Ditto, ruined city near Sahet- Mahet in Hamarpar d., 173 Madanpar, small v. in Lalitpar d. Formerly named Madana- pura 123 Chandella temples and inscriptions at— 123, 124 Madarpar, v. in Faizabad d 302 Madha, v. in Derah Dan d. Two inscriptions of 6th century A.D.	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at— 174—177 Mahodayâ, ancient name of Kanauj in Farrukhâbâd d 331 Mahôlî, v. in Bastî d. Anciently named Mâhuliyâ 225 Ditto, large v. in Sîtâpûr d 289 Ditto, v. in Faizâbâd d 301 Mahôlî-Shamshêrganj, v. in Mâînpurî d 94 Mahonâ, v. in Lakhnâû d 267 Mahsand, v. in Bâra Baûkî d 264
Machhligaon, v. in Gonda d 305 Machhligaon, v. in Sitapar d 185 Machhligaon, v. in Sitapar d 289 Madana-Banaras, old name of Zamaniya in Ghazipar d 236 Madana pura, the modern Madanpar in Lalitpar d. 123, 124 Ditto, ruined city near Sahet- Mahet in Hamarpar d., 173 Madanpar, small v. in Lalitpar d. Formerly named Madana- pura 123 Chandella temples and inscriptions at— 123, 124 Madarpar, v. in Faizabad d 302 Madha, v. in Derah Dan d. Two inscriptions of 6th century A.D. at— 8, 331	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at— 174—177 Mahodayâ, ancient name of Kanauj in Farrukhâbâd d 331 Mahôlî, v. in Bastî d. Anciently named Mâhuliyâ 225 Ditto, large v. in Sîtâpûr d 289 Ditto, v. in Faizâbâd d 301 Mahôlî-Shamshêrganj, v. in Mâînpurî d 94 Mahonâ, v. in Lakhnâû d 267 Mahsand, v. in Bâra Baûkî d 264 Mahûâ Dûbar, v. near Bhûllâ Dîh in Bastî d., 219
Machhligaon, v. in Gonda d 305 Machhlishahr, tahsal in Jaunpar d 185 Machhlishahr, tahsal in Jaunpar d 289 Machhrehta, v. in Satapar d 289 Madana-Banaras, old name of Zamaniya in Ghazapar d 236 Madana pura, the modern Madanpar in Lalitpar d. 123, 124 Ditto, ruined city near Sahet- Mahet in Hamarpar d., 173 Madanpar, small v. in Lalitpar d. Formerly named Madana- pura 123 Chandella temples and inscriptions at— 123, 124 Madarpar, v. in Faizabad d 302 Madha, v. in Derah Dan d. Two inscriptions of 6th century A.D. at— 8, 331 Madharpa, ancient name of Marpha in	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at— 174—177 Mahodayâ, ancient name of Kanauj in Farrukhâbâd d 331 Mahôlî, v. in Bastî d. Anciently named Mâhuliyâ 225 Ditto, large v. in Sîtâpûr d 289 Ditto, v. in Faizâbâd d 301 Mahôli-Shamshêrganj, v. in Mâînpurî d 94 Mahonâ, v. in Lakhnâû d 267 Mahsand, v. in Bâra Baûkî d 264 Mahûâ Dûbar, v. near Bhûîlâ Dîh in Bastî d., 219 Mâhuliyâ, ancient name of Mahôlî in
Machhligaon, v. in Gonda d 305 Machhligaon, v. in Sitapar d 185 Machhligaon, v. in Sitapar d 289 Madana-Banaras, old name of Zamaniya in Ghazipar d 236 Madana pura, the modern Madanpar in Lalitpar d. 123, 124 Ditto, ruined city near Sahet- Mahet in Hamirpar d., 173 Madanpar, small v. in Lalitpar d. Formerly named Madana- pura 123 Chandella temples and inscriptions at— 123, 124 Madarpar, v. in Faizabad d 302 Madha, v. in Dêrah Dûn d. Two inscriptions of 6th century A.D. at— 8, 331 Madharpa, ancient name of Marpha in Bânda d 154, 155	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at— 174—177 Mahodayâ, ancient name of Kanauj in Farrukhâbâd d 331 Mahôlî, v. in Bastî d. Anciently named Mâhuliyâ 225 Ditto, large v. in Sîtâpûr d 289 Ditto, v. in Faizâbâd d 301 Mahôlî-Shamshêrganj, v. in Mâînpurî d 94 Mahonâ, v. in Lakhnâû d 267 Mahsand, v. in Bâra Baûkî d 264 Mahûâ Dâbar, v. near Bhûllâ Dîh in Bastî d., 219 Mâhuliyâ, ancient name of Mahôlî in Bastî d 225
Machhligaon, v. in Gonda d 305 Machhligaon, v. in Sitapar d 289 Machhrehta, v. in Sitapar d 289 Madana-Banaras, old name of Zamaniya in Ghazipar d 236 Madana pura, the modern Madanpar in Lalitpar d. 123, 124 Ditto, ruined city near Sahet- Mahet in Hamirpar d., 173 Madanpar, small v. in Lalitpar d. Formerly named Madana- pura 123 Chandella temples and inscriptions at— 123, 124 Madarpar, v. in Faizabad d 302 Madha, v. in Derah Dan d. Two inscriptions of 6th century A.D. at— 8, 331 Madhagarh, tahail in Jalaun d 114	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at— 174—177 Mahodayâ, ancient name of Kanauj in Farrukhâbâd d 331 Mahôlî, v. in Bastî d. Anciently named Mâhuliyâ 225 Ditto, large v. in Sîtâpûr d 289 Ditto, v. in Faizâbâd d 301 Mahôlî-Shamshêrganj, v. in Mâînpurî d 94 Mahonâ, v. in Lakhnâû d 267 Mahsand, v. in Bâra Baûkî d 264 Mahûâ Dûbar, v. near Bhûîlâ Dîh in Bastî d., 219 Mâhuliyâ, ancient name of Mahôlî in Bastî d 225 Mahwân, small v. in Mathurâ d 104
Machhligaon, v. in Gonda d 305 Machhligaon, v. in Sitapar d 185 Machhligaon, v. in Sitapar d 289 Madana-Banaras, old name of Zamaniya in Ghazipar d 236 Madana pura, the modern Madanpar in Lalitpar d. 123, 124 Ditto, ruined city near Sahet- Mahet in Hamirpar d., 173 Madanpar, small v. in Lalitpar d. Formerly named Madana- pura 123 Chandella temples and inscriptions at— 123, 124 Madarpar, v. in Faizabad d 302 Madha, v. in Dêrah Dûn d. Two inscriptions of 6th century A.D. at— 8, 331 Madharpa, ancient name of Marpha in Bânda d 154, 155	Mahirâshţra, ancient name of Mîrath, 10 Mahmûdnagar, v. near Bilgrâm in Hardôî d., 278 Mahmûdpûr, v. in Muzaffarnagar d 14 Ditto, v. near Sulţânpûr d 329 Mahobâ, tahsîl in Hamîrpûr d. Anciently named Mahotsava- nagaram 174 Extensive ruins of Chandella period at— 174—177 Mahodayâ, ancient name of Kanauj in Farrukhâbâd d 331 Mahôlî, v. in Bastî d. Anciently named Mâhuliyâ 225 Ditto, large v. in Sîtâpûr d 289 Ditto, v. in Faizâbâd d 301 Mahôlî-Shamshêrganj, v. in Mâînpurî d 94 Mahonâ, v. in Lakhnâû d 267 Mahsand, v. in Bâra Baûkî d 264 Mahûâ Dâbar, v. near Bhûllâ Dîh in Bastî d., 219 Mâhuliyâ, ancient name of Mahôlî in Bastî d 225

Pages	
The state of the s	I light
Mainpuri, tahsil and head-quarters of d 9	0 /
Majhaulî, v. in Görakhpûr d 24	O The state of the
Majhaura, v. in Faizabad d 301	Control of the Contro
Majhawan, v. in Basti d.	Manhan, v. in Bastl d 218
Identified with the Moksha-	Manîar, v. in Bâliyâ d 193
vana of Buddhist legends 222	Mâṇikpûr, small t. in Pratapgarh d.
Majhêrâ, v. in Muzaffarnagar d 18	Traditionally named Manapura,
Majhgaon, v. in Kherî d 287	later changed to Manikya-
Majhgâwan, t. in Bândâ d 154	pura 316
Majhîtâ, v. in Rái Bareli d 323	Description of extension with
Makanpûr, v. in Kânhpûr d 169, 170	pt pt pt pt pt pt pt pt pt pt pt pt pt p
Makârbâî, small v. in Hamîrpûr d., 173, 174	Manipura, t. of the Mahabharata.
Makarikund, sacred pond at Begethûa in	Traditionally believed to be
Sulţânpûr d 326	AF AAA MALAYA A
Makkhanpûr, v. near Dâlmâû în Râî Bare-	Manufacture and the second second
lî d 320	Mannan w in Duly 1.1.1.1
Makrandnagar, suburb of Kanauj in Far-	Ditto w in Manadalad 3
rukhâbâd d81, 82	Ditto, v. in Muradabad d 36
Mål, v. in Lakhnåå d 267	Manpar-Mustafabad, old name of Manaa in
Malâkâh, v. in Allahâbâd d 143	Manage at W. J. Situpur d 289
Mâlâwân, v. in Îtâh d 87	Mansar, or Mahsand, v. in Bara Bankî d 264
Målini, river of Sanskrit writers.	Mansûrnagar, v. near Pihânî in Hardôî d 281
Identified with a small affluent of	Manûâ, v. in Sîtâpûr d.
the Ghaghra near Ajudhiya in	Locally identified with Manipura
Foiethal 2	of the Mahabharata 289
Malîpar, v. near Sikandra în Allaha-	Probably the ancient Manava-
TALL TALL	pura 289
Waliphhid takell - T 11 44 1	Called Manpar-Mustafabad in the
Wallawan + in Hamlet 2	last century 289
	Måola Köl, deserted site in Görakhpür d. 949
Malwa, v. in Fathpur d 164	Marauri, v. in Pilibhit d 38
Mânapura, traditional name of Mânikpâr in	Marha, v. near Man in Jhanel d tto
Pratapgarh d 316	Mårharå, v. in Îtâh d.
Manavapura, ancient name of Manûa în	Mariahû, tahaîl in Jaunpûr d. 195
Sîtâpûr d 289	Marjadpattî, v. near Bhadohî in Mîrzâ-
lândâ, v. în Allahâbûd d 143	pûr d 255
dandalpûr, v. in Ambâlâ d. of Panjâb.	Markhaman at in all-12121
Identified with the ancient city	Markhera, v. near Madanpar in Lalit-
of Srughna 19	nord Laur-
I and apapura, ancient name of Mandu	pûr d 124, 333 Marṇā, v. in Faizābād d 300
in Malwa 120	Maron v near Dil Tr
Jandawar, or Madawar, v. in Bîjnôr d.	Marpha spined bill fact in Dr. 278
Anciently called Matinura	Marphâ, ruined hill-fort in Bândâ d.
Extensive Buddhist rains at 01 oc	Anciently named Madharpa, 154, 155
mandan, rumed city in Garbwal d	Marwar, v. m Banda d.
taningaon, or Mariaon, v. near Lakhnaa	Måsachitra, ancient name of Khairabad
tandiya, v. in Bîjnôr d.	in Sîtâpûr d 288
Lânêyanagara, ancient name of Mên-	Masaon Dih, deserted site in Ghazipur d.
hîyâ in Bastî d 226	Anciently named Krelulen-
	drapura 227, 233

Pages.	Pages.
Masa'ûdpûr, v. in Faizâbâd d 300	Menhiya, v. near Tama in Basti d.
Maskara, or Mashkara, tahsil in Hamir-	Identified with Maeyanagara
pûr d 177	of Buddhist legends 226
Masorâ, v. in Faizâbâd d 302	Mêopûr Khâs, v. in Sultânpûr d 326
Mastâlîpûr, v. in Murâdâbâd d 38	Mîrâ Dîh, ancient site near Barmâyan in
Mât, tahsîl in Mathurâ d 104	Bâliyâ d 192
Mathiya, v. near Narayanpur in Ghazîpur d., 233	Mîrânpûr, tahsîl in Faizâbâd d.
Mathurâ, tahsîl and head-quarters of d.	Anciently called Sinjhault, or
Great Buddhist and Jaina cen-	Sojháwalgarh 301
tre , 104—108	Mîrânpûr Katra, t. in Shâhjahânpûr d 43
Bråhmanical temples at-, 106, 107	Mîrân Sarâî, v. near Kanauj in Farrukhâbâd d., 79
Extensive excavations carried on	Mîrath, tahsîl and head-quarters of d. and
nt 105, 106, 333	division.
Ditto, v. in Goṇḍâ d 305	Originally called Mahirashtra, 10
Måti, ancient ruined site in Shahjahanpûr d.	Traditionally called Mahidanta-ka-
Anciently named Matripura, 42,285	Kherâ 10
Do., v. in Lakhnâû d 255	Ediet pillar of Asoka brought by
Mâtihaniyâ, deserted site near Gôrakhpâr 243	Fîrûz Shâh from—, 11, 331
Matipura, the modern Mandawar in	Conquered by Dôr Râjpûts in the
Bijnôr d 31	11th century A.D 11
Matkopå, deserted site in Görakhpår d 243	Ruined fort and Musalman remains
Matripura, the modern Mati in Shahja-	at11, 12
hânpûr d 42	Mîr Bihâr, v. in Gôrakhpûr d 240
Mâû, tahsîl in Jhânsî d 118, 119	Mîrzapûr, tahsîl and head-quarters of d 262
Do., tahsil in Banda d 155	Ditto, v. in Hamîrpûr d 178
Maudhâ, tahsîl in Hamîrpûr d 177	Misrikh, tahsil in Sîtâpûr d 289
Mââ Natbhanjan, t. in Azamgarh d.	Mithabêl, v. in Gôrakhpûr d 238
Formerly called Jahana-	Mithanpar-Paja, v. in Muradabad d 36
båd 189, 190	Mithauli, v. in Kheri d 287
Maurawan, v. in Unao d 273	Moghal Saraî, or Moghal Chauk, v. in Ba-
Mawâî, v. in Unão d 272 Mawânâ, tahsîl in Mîraṭh d.	nāras d 212
	Mohân, v. în Kumâon d 49
APPROXICATION OF THE PROPERTY	Do., tahsil in Unio d 272
Mawwa Sarai, or Mawwa Chachar, ancient	Mohânlûlganj, tahsîl in Lakhnâû d.
site near Gopamâû in Har-	Formerly called Chorhân-kâ-
dôt d 279	Mad 267
Mâ yâ, ancient name of Mâi în Jaunpûr d., 185	Mohârî, v. in Hamîrpûr d 173
Mayaradhvaja, ancient name of Môr-	Mohrî, v. in Bahrûîch d 293 Môrâ, or Morâmêyî, small v. in Mathurâ d.
dhaj in Bîjnôr d., 32, 33	Inscription of son of Satrap Rajubul
Mayata, the modern Déoriya and Deval in	at— 108, 109
Pilibhît d 38, 39, 41	Mordhaj, or Munawwar Jar, ruined fort in
Mednîganj, v. in Pratâpgarh d 319	Bijnôr d.
Meharaulî, v. in Ghâzîpûr d 227	Anciently named Mayaradh-
Mekhala, kingdom of Buddhist legends.	vaja32, 33
Kshemavati, capital city	Ruins of large stûpa at 32
of-, identified with Khem-	Morêr Dîh, ancient ruined site near Bhûîla
râjpûr in Bastî d 221	Dih in Basti d 220

Pages	Pages
Moriyanagara, of the Buddhist legends.	Mustafábád, small t. in Faizábád d 30
Identified with Updha-	Ditto, v. in Pratâpgarh d 31
oliyâ and Râjdhâni in	Ditto, v. in Råi Bareli d 32
Gôrakhpûr d., 237, 238	Muzaffarnagar-Sainî, v. in Mîrath d.
Mornah, v. in Muzaffarnagar d 14	
Mosâlm, v. in Kherî d 285	A TANAL TO A TO A TO A TO A TO A TO A TO A TO
Motirâm-kû-Addâ, police outpost on the Dê-	W. C. A. C. Ser of Hastimpura, 11
oriyâ road în Görakh-	Muzamarpūr, v. in Mîrzāpūr d 261
pûr d 248	A STATE OF THE PARTY OF THE PAR
Mrakshavarana, river of Buddhist le-	Tradingar, our name of Mandarpar in Ba-
gends.	nâras d 215
Identified with the Ma-	Nagar, old name of Mansûrnagar in Hardôl d., 281
jhara Nadî in Bastî d., 221	Någar Khås, old v. in Basti d., 221, 222, 225
Mrigadava, of Buddhist legends.	Nagariya Khera, deserted t. in Aligarh d.,
Identified with Sarnath in	Naghiāwān, v. in Faizābād d 301
Banâras d 214	Nagînâ, tahsîl in Bîjnôr d 33
Mubarakpûr, old name of Chiraiyakot in	Nagpura, v. in Bâliyâ d 193
Azamgarh d 187	Nagrâm, v. in Lakhnâû d.
Muhamdi, tahsil in Kheri d 287	Anciently named Nalagrama, 268
Muhammadábád, v. in Facrukhábád d 82	Nagraura, v. near Bilgram in Hardôi d 278
Ditto, Musalman name of Banaras, 198	Naimisharanya, or Naimishasa-
Ditto, ruined fort near Haidara-	ras, the modern
båd in Kheri d 285	Nimkhâr or Nim-
Muhammadâbâd-Gohnā, tahsîl in Âzam-	sâr în Sîtâpûr d 290
garh d 190	Nâîn, v. în Râî Barelî d 325
Muhammadnagar Qasbah, v. in Murådåbåd d., 36	Najafgarh, dismantled fort near Najibâbâd in
Muhammadpûr, v. near Bâliyâ 191	Bijnôr d 33
Mumana, ancient name of Mawana in	Najîbûbûd, tahsîl in Bîjnôr d 33
Mîrath d 10	Najûrkêt, deserted hill-fort in Kumaon d 47
Mumtåznagar, v. in Faizābād d 302	Nakula, the modern Nakûr în Saharan-
Munawwar Jâr, see Môrdhaj.	pûr d 17
Mundivâ, v. in Kumâon d	Nakûr, tahaîl in Sahâranpûr d 17
dundiva Khera, v. in Muradahad d	Nalagrama, the modern Nagram in
Mûnj, v. in Itâwah d 92	Lakhnáů d 268
Munrâ-Munrî, v. in Kherî d 287	Naliya, v. in Gonda d 304
furådåbåd, tahsil and head-quarters of d.	Nanāmāu, v. in Sultānpūr d 327
Anciently named Chaupâla36, 37	Nandakini, river in Garhwal d.
Iurassapûr, or Nawâbganj, v. in Pratâp-	Temple of Nandadevî near
cont d	source of 46
furtazābād, old name of Sarāi Mir in Âzam-	Nandganj, v. in Ghâzîpûr d 227
Control of	Nandgâon, v. near Chhâtâ in Mathurâ d., 100, 109
Jusafirkhana tabell in Sulstand	Nandwa, ruined site in Gôrakhpûr d. 240
Iûsânagar, t. in Kânhpûr d	Nåndyaprayåg, pilgrimage place in Garh-
Insharifa, old v in Roust a	wâl d 48
luskahad v nane Banana	Nanpārā, tahsil in Bahrāich d. 204
Instafâbûd old desented 209	Nanyaura, v. in Hamîrpûr d 177
Mueddahad a	Na-po-ti-po-ku-lo, of Hiuen Tsiang.
Ditto, tahsil in Mainmet d	Identified with Bangarman and
94	Nawul in Unão d., 269-271

Pag	jes.	Pages.
Narauli, v. in Murâdâbâd d	37	Nihâlgarh, v. in Sultânpûr d 328
	155	Nihtone w in Rtinas J
Nåråyanpår, small v. in Båliyå d.		Nilauti, ruined Hindû t. near Jalâli in
Site of temple of Narayana Dêva,	315	Aligarh d 1
visited by Hiuen Tsiang,		Nimkhâr, or Nimsâr, v. in Sîtâpûr d.
	193	Identified with Naimi-
Ditto, v. in Ghâzîpûr d.		sharanya or Nai-
Wrongly identified with the		mishasaras 290
	233	Nîr, v. near Hardôl 280
	330	Nizâmâbâd, t. in Âzamgarh d 190
Narkataha Dîh, deserted site near Gôrakhpûr, 2	243	Nizâmpûr, t. in Hardôî d 281
	114	Nôh Jhîl, small t. in Mathurâ d 109
Nasîrâbâd, v. in Sîtâpûr d 2	289	Nonairă, large v. in Măinpuri d., 94, 95
Ditto, v. in Råi Barell d 3	324	Nûh Kherâ, v. în Îtâh d 87
Nasratganj, v. near Ramnagar in Barelf d.,	27	Nûr Kherâ, v. in Murâdâbâd d 37
Nasratnagar, v. near Bilgram in Hardôl d., 2	78	Nyagrodhå, v. in Bastî d 222
Nathawan, great ruined fort near Bijnôr in		Nyagrodha, forest of Hiuen Tsiang.
Lakhnāŭ d 20	65	Identified with the dense
Nåthmalpûr, v. in Faizâbâd d 3	01	forest near Mithabêl in
Nåthnagar, great ruined fort near Rudrapûr	U.	Gôrakhpûr d 238
*	49	Nyurâî, v. in Îṭâh d 87
	64	
Naubatpûr, v. in Banâras d.		0.
	12	Ochhâwân, v. in Faizâbâd d 301
THE RESERVE OF THE PARTY OF THE	78	Onôl, v. in Dêrah Dûn d 8
Naushahr, hamlet in Mâînpuri d.		Oraî, tahsîl and head-quarters of Jalaun d., 114
The state of the s	94	Orajhar, or Oradih, old mound near Nimkhar
A STATE OF THE PROPERTY OF THE	36	în Sîtâpûr d 290
Navadêvakula, of Hiuen Tsiang.	V.	Ditto, old mound near Ajudhyâ
Identified with Nawal		in Faizābād d 298
and Bangarmaa in		Ditto, old mound near Sahet-
Unão d., 269—27		Mâhet in Goṇḍâ d., 308, 311
Nawabganj, another name of Bara Banki 26	375 111	Oran, v. in Båndå d 155
Ditto, v. in Pratapgarh d 31	18	'O-ye-mu-khi, of Hiuen Tsiang.
Nawal, v. near Bângarmâû in Unâô d.		Capital of—, identified
Identified with Navadêvakula		with Daundiâ Kherâ in
of Hiuen Tsiang 269, 27	11	Unão d 268
Identified with the A-lo of Fa-		Perhaps Singraur in Alla-
Hian 27	965	hâbâd d 269
Locally called Lautâ Shahr 27		Identified with Tusaran-
Nêorîyâ-Husainpûr, v. in Pilibhît d 4	10	Bihâr in Pratâp-
Nêotînî, v. near Mohân in Unão d.	2	garh d 269, 315
Formerly known as Kudådåd 27:		O-yu-t'o, of Hiuen Tsiang.
Newada, v. in Pratapgarh d 31 Nichlawal, ancient v. in Görakhpar d 24	200	Perhaps Asnl in Fathpurd 158
	56	Do. Kutiyâ in do 163 Do. Kûkûpûr in Kûnh-
TT 14 1 1 11 1 TT 1 1 1 1 1 1 1 1 1 1 1	_	4.1
Nighāsan, tahsti in Kheri d 28. Nigohān, tahsti in Lakhnāū d 268		Do. Pâtan-Bihârin Unâo d., 271
Angelian, tonor in parameter in 200	A 1	200 FROM SHARIN CHIEVRY SIT

Pages.	Pages.
'O-yu-t'o, wrongly identified with Aju-	Pållåtpår, see Pahlådpår.
dhyā in Faizābād d., 299, note.	Pampapara, the modern Bindhachal in
Identified with Jagatpûr in	Mirzāpūr d 257
Râi Bareli d 323	Dondask ald as to Williams 1
P.	Pañchabhûmi, the modern Pachômî in
	Bareli d 26
Pabhôsā, small v. in Allahābād d.	Panchachhattra old name of second
Anciently named Prabhasa 143	tank Hattiâ Haran
Inscribed rock-cave of the 2nd cen-	at Kaluannal in
tury B.C. at— 143, 144	Hardôî d 280
Pachkhaurå, small v. in Hamîrpûr d 171	Pancharanya, the modern Pachran in
Pachnehî, v. in Bândâ d 155	Gondâ d., 305, 306
Pachômî, v. in Barelî d.	Pańchmuha, or Pańchamukha, small v.
Identified with the ancient Pan-	2- 0.31-1.41-1.3
ehabhûmi 26	Dandal-Manager 11 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Pachran, v. in Gonda d.	District Control of the Control of t
Anciently named Pancha-	Pânduwâlâ, ancient ruined city in Garhwâl d 324
ranya 305, 306	Probably represents the capital
Padarauna, or Parauna, tahsil in Gorakhpur d.	of Dan L
Anciently named Pa-	Powher w That 3
daravana 249	Panward t in Hamtendard 273
Identified with Pawa, or Parban. 249	Panwârî, t. in Hamîrpûr d 177 Pâor Kheriyâ, small v. near Sankîsâ in Far-
Pådham, or Pårham, v. in Måinpuri d 85	
Paharnagar-Tikurîya, v. in Lakhnaa d 267	Partichart or in II.
Pahladpûr, or Pallappûr, v. in Ghazîpûr d., 232, 234	Parûs Dîh v pear Phátia Det : D
Pahra, v. in Hamirpur d 174	Parâs Dîh, v. near Bhâilâ Dîh in Bastî d 218
Pailání Khás, tahsil in Bándá d 155	Parasnath, ruined ancient city near Burha-
Paina, v. in Fathpar d 180	pura in Bijnôr d 30
Paindhat, or Pendhat, v. in Mainpuri d 95	Parashakot, ancient mound in Pilibhit d 40
Pair, v. in Basti d 991	Parasurampur, v. in Pratapgarh d., 318, 319
Paithana Dih, ancient mound near Maghar	Parâulî, v. in Kânhpûr d 167 Parban, see Pâwâ.
in Basti d 295	Pariár, v. in Unão d.
Pakhnâ-Bihâr, v. in Farrukhâbûd d.	
Site of great Buddhist monas-	Anciently named Parihara, 272, 273
tery at	Parichhatgarh, v. in Mìrath d 12
Pakhráůlí, v. near Dálmáu in Rái Bareli d 200	Parihara, the modern Pariar in
Pakkā Kôt, ancient site near Barāgâon in	Unão d 272, 273
Baliya d 100	Parkham, old v. in Mathura d.
Pakrêlâ, v. in Faizâbâd d 300	Colossal inscribed statue of 1st
Pali, v. near Pabhasa in Allahataa a	century B.C. at—, 109, 110, 333
Do., t. in Hardôl d 980 901	Farna, v. in Agra d.
Do. v neer Munagalla.	Parnanandpati-urf-Dahwa, v. in Faizahad d 201
pûr d 200	Larsa, v. near Bhalla Dih in Basti d
Palikhand, v. in Itawah d 92	Parsandan, v. in Unão d.
Pali Khera, hamlet in Mathura d.	Farwar Parab, v. in Lakhnaa d
Bacchanalian group excavated	Paschimavâhimî, old name of Balûâ
nt—	Sardi in Bandras A 100
Palind, v. near Saffpår in United	ringawan, v. in Kherl d.
273	Pâțalî, the modern Pariâlî in Îtâh d. 87, 331

	Pages.	1000	Pages.
Pâtan-Bihâr, t. in Unão d.		Pindarå, v. in Pilibhît d	. 40
Identified with the 'O-yu-t'	0	Pindari Dih, ancient ruined site near Bhill	
a team that is	71, 272	Ditt in Donat 2	. 220
Patarů, deserted site near Gôrakhpûr	10.40	****	12, 213
Pataunjû, v. in Sîtâpûr d	000	Dinnith w in Kumban d	20
Pathâ-Sigaulî, v. in Jhânsî d	. 118	Direct or in Daniel I	man
Patiall, v. in Îţâh d.		Pîrân Kalhar, v. near Rurkî in Sahâran	
Anciently named Patali, 8	37, 333	nAn J	10
Th. 1814	262	Pîrnagar, v. în Sîtâpûr d	004
Patkârî, v. in Hamîrpûr d		Ditto, v. in Faizābād d	000
Patnā, v. in Sulţānpûr d	ERRE	Pi-so-kia, of Hiuen Tsiang.	. 000
Patthargarh, dismantled castle near Najiba-		Identified with Ajudhya is	1
bâd in Bîjnôr d	no.	Total And 3	non
Pattî, tahsîl în Pratâpgarh d		Polyhorbhátá w in Polyhatad a	DOT
Pâû, v. in Kumâon d	10	Political as in Paris 3	mak
Pauriyâ, v. în Bastî d	0.00	Downston in the name of 3	400
Påwå, or Parban, t. of Buddhist legends.		Prabhasa, ancient name of Pabhosa in	
Identified with ruins near Chetiyaon	N.	Allahâbâd d.	10 PH
in Gôrakhpûr d 23		Denothing to Denote 1 2	044
Identified with Padarauna in Gorakh-		Pratapgarh, tahsîl in Pratapgarh d	OLT
pûr d	0.10	Anciently named Alarikhpûr	
Permit, v. near Ghâzîpûr	200	A. A.	0
Phaphund, tahsîl in Itawah d	200	Pratishthanapura, the modern Jhus	
Phatera, small v. near Baran Sagar in Jhan-	100	in Allahabad d.	
sî d	115	D. A. C. CRITALIS	
Phûlârâ, v. in Kumâon d	48	DAnah - i- Danah	***
Phůliyà Kherů, deserted site near Shaikhû-		Donida a in Handanda 2	-
pûr in Badêon d	24	DAN m in Mindada 2	0.00
Phůlpůr, old name of Bhîtargåon in Kûnh-		Dard hamlet were Hatanda to Day 14 3	
	165	Danah Dat	
Phůlwaria, old ruined v. near Azamgarh	187	Páronnán tuhati in Dilikkis a	78
Pihânî, v. in Kânhpûr d	168	Purom v in Robettah d	40
Ditto, t. in Hardôl d	281	Purênî, ruined t. near Hisâmpûr in Bah-	293
Pîkhî, v. near Safîpûr in Unão d	273	m10.3. J	009
Pilibhit, tahsil and head-quarters of d	40	Pûrnagiri, famous temple of Pûrvatî	293
Pilkhāna, v. in Alīgarh d	3	near Barmdêo in Ku-	
Ditto, v. in Farrukhâbûd d.	-	miles d	1499
Probably represents the Pi-lo-		Daniel takell to Trate 2	47
shan-na of Hiuen Tsiang	82	Pushpavati, identified with Path in	273
Pi-lo-shan-na, of Hiuen Tsiang.	-	Minush J	10
Identified with Pilkhana		Pûth, v. in Mîrath d	12
in Farrukhâbâd d	82		10
Identified with Bilsar in	80	Anciently named Pushpavati	12
Îtâh d	86	Q.	
Perhaps to be identified	-		
with Atranjî Kherâ in		Qasbah Bâbarpûr, v. near Ajitmal in	-
Îtâh d	85	Onebah Ninda - i 6	89
Pinahāt, small t. in Âgrā d	96	Qasbah Nigûn, v. in Azamgarh d	189
(I) Althoughtons a	00	Qâzîpûr, v. near Safîpûr in Unão d	274

Pages.	Pages.
Qila Nawâ, old brick fort at Tambaur in	
C144-A-3 201	Râmgarh, v. in Azamgarh d 188 Ditto, v. in Banâras d 196
Qudsat, old name of Kursat in Unão d 272 R.	Ditto, ruined site near Gôrakhpûr 242
	Râmiyâ-Bihâr, v. in Kherî d 284
Rachhpâl, v. in Faizâbâd d 301	Rāmkôt, v. in Sîtâpâr d 291
Rådhåkund, small t. in Mathurå d.	Râmnagar, v. in Barelî d.
Occasionally called Srikund 110	Anciently named Ahichhat-
Raghupar Dih, ruined mound near Bhaila Dih in Basti d 219	tra, or Adhichhat- tra 26-29
	The 1 74 11 2
THE THE PARTY OF T	
DALT - 1- T 1- T 1	*******
Raho, local name of the ruined t. Bahlôl-	The A is a constant of
mAn in Hamilat J	Râmpûr, t. in Sahâranpûr d 18
Råî Bareli, tahsil and head-quarters of d.	Ditto, v. near Bháilá Díh in Bastí d 220
Formerly called Bharauli and	Ditto, v. in Hardôî d 283
4. 1	Ditto, v. in Pratapgarh d 316
Details with Vander 1	Râmpura, v. in Jalâun d 114
Râîgâôn, v. în Kumâon d 49	Růmpůr-Aphůî, v. in Fathpůr d 158
Rấtpûr, v. in Faizābâd d 301	Râmpûr-Dêoriyâ, v. in Bastî d.
Ditto, v. in Sultânpûr d 326	Identified with the Ra-
Râiwân, v. in Sîtâpûr d 288	magrāma of Fa Hian
Rájá Bárí, deserted site in Gôrakhpûr d 242	and Hiuen Tsiang, 225, 226
Râjâ Karan-kâ-kherâ, ruined site near Mus-	Râmpûr-Gôkul, v. in Kherî d 286
tafâbâd in Mîrațh d., 12	Râmpâr-Thariaon, v. in Fathpâr d 164
Râjâpûr, t. in Bândâ d 154	Ranchula, old fort near Baijnath in Ku-
Râjâ-Satôn-kâ-kherâ, ruined mound in Mur-	mâon d 47
âdâbâd d 36	Rângî, v. in Pratâpgarh d 314
Rajavasini, ancient name of Rasin in	Rangilnagar, v. in Kheri d 286
Bândâ d 156	Rânîghât, v. in Gôrakhpûr d 249
Råjbhår-kå-kôt, old deserted site near Bhatri	Rânîpûr, small t. in Jhânsî d 119
in Azamgarh d 187	Raņūāpāra, v. in Sîtāpūr d 289
Râjdhânî, v. near Barhî in Gôrakhpûr d.	Rão Karna, v. near Unão 276
Identified with Moriyanaga-	Râprî, v. in Mâînpurî d 95, 96
ram 237, 238	Kar, v. in Kanhpûr d 167
Râjgîr Hâr, v. near Kanauj in Farrukhâ-	Rasema, v. in Mainpuri d 94
båd d 79, 81	Râsin, old v. in Bândâ d.
Râjthâl, v. in Murâdâbâd d 36	Anciently named Rajavasini, 156, 157
Râjûpur, v. in Sahâranpûr d 18	masra, tanshi in Baliya d 194
Râjwarêo, v. near Âgrâ 67	Rasulabad, tahsil in Kanhpur d. 170
Râktôe, large lake near Khairâ Dîh in	Ditto, t. in Unão d.
Bâliyâ d 194	Rasulpur, v. in Mîrzapûr d 959
Râl, small t. in Mathurâ d 110	Ditto, v. in Faizābād d 901
Ramagadha Gauda, the modern Bal-	Rain, tahail in Hamirpur d 177 170
rîmpûr in Goņ-	Råthauli, old name of Kalyanmal in Har-
Râmagrâma of Fa Hierard Him. 702	doi d 999
Râmagrâma, of Fa Hian and Hiuen Tsiang.	Rauli, v. near Gonda in Banda d. 149
Identified with Rûmpûr-	Raushanâbâd, v. in Farrukhâbâd d.
Dêoriyâ in Bastî d 220	Rawatpur, v. in Hamirpur d
(1) Abbreviations: t,=town	

Pages.	Pages.
Râyâ, v. in Mathurâ d 110	Såhêgarh, or Sâîgarh Kherâ, deserted t. in
Rên, v. in Fathpûr d 164, 165	Aligarh d 1
Rikhiân, caves near Barhâ-Kotrâ in Bândâ d., 147	Såhet-Måhet, small v. in Hamîrpûr d.
Rithora, small hamlet near Maa in Banda d., 155	Extensive ruins of Madana-
Ronahî, v. în Faizâbâd d 301	pûra at 173
Ronî, hillock near Mâû in Jhânsî d., 119, 333	Ditto, ruined ancient site in Gonda d.
Rorâ, v. in Hamîrpûr d 178	Identified with the Shi-lo-
Rudault, v. in Jalaun d 114	fu-shi-ti of Hiuen
Ditto, t. in Bara Bauki d 264	Tsiang 223, 306
Rudhâî, v. in Faizâbâd d 301	Identified with Śrâvastî
Rudrapûr, t. in Gôrakhpûr d.	or Savatthi, Sewet
Anciently named Hamsa-	and She-wei, 293, 294, 306
kshetra 249	Identified with Chandrika-
Identified with the t. of Hiuen	puri 308
Tsiang's hospitable Brahmana, 249	Called Ajavrisha in stone
Great fort of Såhankôt, or Nåth-	inscription of 13th cen-
nagar at 249, 250	tury A.D 308
Rûhî, v, in Hardôî d, 283	Named also Dharmapatta-
Rukhârâ, v. in Lakhnâû d 267	na 312
Rûpnagar, v. in Bastî d 216	Description of extensive ruins
Rurkî or Lurkî, tahsîl in Sahûranpûr d 18	at— 306—313
S.	Identification of sites
The state of the s	at 309-312
Sa'idatnagar, v. in Hardôi d 283	Sâhiyâ, v. in Gôrakhpâr d 239
Sabalgarh, ruined castle in Bijnôr d 33	Sâhpââ, v. in Mathurâ d 110
Sabûwâ, v. in Ghâzîpûr d 227	Sâîa, v. near Bilgram in Hardôî d 278
Sa'dâbâd, tahsîl in Mathurâ d 110	Sa'id Bhûrâ, v. near Sabalgarh in Bijnôr d., 33
Sådîåbåd, v. in Ghâzîpûr d 234	Sa'îdpûr, tahsîl in Ghâzîpûr d.
Safîpûr, or Sâîpûr, tahsîl in Unâo d., 273, 274	Wrongly identified with the capi-
Sagaichâ, v. in Faizābād d 301	tal of the Chen-chu, 234—236
Såh, v. in Fathpår d 165	Sa'idpûr-Sirwadih, v. in Faizâbâd d 301
Såhankôt, ancient ruined site near Barhî in	Sa'idrājā, v. in Banāras d 216
Gôrakhpûr d 238	Såigarh Kherû, deserted t. in Aligarh d 1
Ditto, great ruined fort near Rudrapûr in Gôrakhpûr d 249	Såîpûr, or Safîpûr, tahsîl in Unâo d., 273, 274 Sakaldîhâ, t. in Banâras d.
	Anciently named Śuklapura, 213
Sâhanpûr, v. in Bîjnôr d 34 Sahansrâ, pass in Sahâranpûr d.	Sakarâ, v. in Hamîrpûr d 174
Ruins of old temple near 19	Sakardâha, v. in Pratâpgarh d 316
Sahar, small t. in Mathura d 110	Sakargâon, v. in Farrukhâbâd d 83
Saharapûr, tahsîl and head-quarters of d., 18	Såketam, or Sha-chi, of Hiuen Tsiang.
Sahaspûr, v. in Bîjnôr d 34	Identified with Sanchankot in
Sahasrabahunagara, ancient name of	Unão d 274, 275, 304
Sahaswan in	Sakhân, v. near Safîpûr in Unão d 273
Badâon d 24	Sakhûî, deserted site in Gôrakhpûr d 242
Sahaswân, tahsîl in Badâon d.	Sakît, t. in Îtâh d 88
Anciently called Sahasraba-	Sakráî, v. in Farrukhâbâd d 83
hunagarm 24	Sakrar, v. in Jhansî d 117
Sahāwar, v. in Îṭâh d 88	Sakraudā, v. in Sahāranpūr d 14
Summing to be special to the second	A STATE OF THE PARTY OF THE PAR

Pages	· Pages.
Sakrāwā, v. in Farrukhābād d 8	Sankîsa-Basantpûr, v. in Farrukhâbâd d.
Śaktîsgarh, small v. in Mîrzâpûr d 263	
Salî, v. near Alîganj în Îtâh d 86	The state of the s
Salîmpûr, v. in Badâon d 24	and July of Hapi-
Ditto, v. in Kherî d 286	00,001
Sâlôn, v. în Jhânsî d 119	7,00,01
Do., tahsîl in Râî Barelî d 325	Co. 30 2. TT. 100 1
Samādābād, v. near Mānikpūr in Pratāp-	Shed - in Wandald a con-
garh d 318	
Samaría-Ghôsa, v. in Pilibhit d 40	Saråî Aghat, small t. in Îṭâh d 88
Samathâl, ruined mound in Murâdâbâd d 36	Sarat Atitmal w in Teamsh J
Samaur, v. in Faizābād d 301	Quedo Aliberates . The Process
Sambalhêrâ, v. in Muzaffarnagar d 14	C At TAIL SILL AND DAILE II. 200
Sambhal, tahsîl in Murûdâbâd d.	Cause Trans.
Anciently named Sambhala-	Sarai Ikdii, v. in Itawah d 92 Sarai Mîr, t. in Âzamgarh d.
pura 37, 38	77 1 11 12 12 12 12 12 12 12 12 12 12 12 1
Sambhar, v. in Sultanpar d 330	Sarâl Nûrî, old name of Yakûtganj in Far-
Sâmdîh, v. in Faizâbâd d 301	24 22 4 4
Samgrampur, v. in Ghazîpur d 237	Śarakûpa, of Buddhist legends 84
Ditto, v. in Unão d 268	Identified with Sarkuhiya in
Samkasya, the modern Sankisa-Basant-	Routt A cox
pår in Farrukhåbåd d., 83, 331	D5
Samôgar, v. near Rudrapûr in Gôrakhpûr d., 250	Sarauli, v. in Barell d. no.
Samonghar, v. near Fathâbâd în Âgrâ d.	Ditto v in Gosakhada d
Scene of Aurangzib's victory	Sarawa v in Miroth d
over Dárá Shikôh 70	Saravat v in Rootl d
Samradh, v. in Mîrzâpûr d 255	Sardamagar v in Manadahad d
Sanaulf, deserted v. site in Bastf d 223	Q-314-4 (1 a) - 35
Sanchankôt, or Sujankôt old v. in Unão d.	Control of the first of the fir
Wrongly named Râmkôt 274	Contact Tall - 2 C - 14 3
Identified with the capital of	Quality A 15 1 Trail 1
the Sha-chi, or Saket-	Santan - in Allanda a
am 274, 275, 304	Soulden Who ar areas a
Såndå, v. in Sitapår d 288	Sarkuhîyâ, v. in Bastî d 38
Såndî, t. în Hardôî d.	Identified with Sarakupa of
Formerly called Santannagar, or	Ruddhint lane 1
Såntankherå 281	Sârnâth, ancient Buddhist aite near Ban-
Called Fathpur-Islamabad, or Ashraf-	Arms Old oto on
åbåd by Musalmans 281, 282	Aras 213—216, 334 Saromannagar, v. in Hardôl d 283
Såndî Kherû, ruined site near Pâlî in Har-	Saraagoni w in Mathemat 7
dôî d 281	Sarsawa, or Sirsawa, v. in Saharanpur d 96
Sandîlâ, tahsîl in Hardôî d 282	Anciently named 6:
Sandwa Chandika, v. in Pratapgarh d 319	Anciently named Siraspatta- na, or Sirasawa 18
Sanichra, v. in Sultanpur d 330	Birtherland of Park 1 To a 18
Saukara, extensive ancient site in Alf-	Birth-place of Bachhal Rani, the
garh d 3	mother of Gaga Chauhana,
Sankarpûr, hamlet near Jugatpûr in RM	Sarsawan, v in Lubbanka 2 18
Barelf d 323	Sarthal Khora decented to 35 trans-
(') Abbreviations: t,=town	t verillers de district

Pages,	Pages.
Sarthrå, v. in Båra Baŭkî d 263	Shahr Anwar, old name of Zafarabad in
Sarwan, v. near Pûrwâ în Unão d 273	Jaunpûr d 185
Sarwârî, v. in Faizābād d 301	Shâhzâdpûr, v. near Karrâ în Allahâbâd d., 139
Såsnî, v. in Alîgarh d 3	Shaikhanpar, v. in Ghazîpar d 236
Sâtan, v. in Unão d 275	Shaikhûpûr, v. in Badâon d 24
Såtgato, v. in Lalitpår d 125	Shâkumrî, pass in Sahâranpûr d.
Såthan, v. in Sultanpur d 328	Ruins of old stone fort in 19
Såthanpûr, v. in Rål Barell d 323	Shakûrâbâd, v. in Murâdâbâd d 36
Satmâs, v. in Âgrâ d 75	Shamsabad, t. in Farrukhâbâd d.
Satôl, v. in Garhwâl d 46	Extensive ruins of old t. of
Satongarh, old deserted site in Murådå-	Khôr near 84
bâd d 36	Shërgarh, ancient t. in Barell d 26
Satrikh, old t. in Bâra Bankî d 264	Ditto, v. in Mathurâ d 111
Sauj, v. in Mâînpurî d 97	Ditto, ruined fort at Dhopap in Sultan-
Saural, large v. in Lalitpar d 124	pûr d 327
Saurîkh, v. in Farrukhâbâd d 84	She-wei, identified with Sahet-Mahet in
Savatthi, identified with Sahet-Mahet in	Gondâ d 306-313
Gonda d 306-313	Shiampur, or Syampur, v. near Bilgram in
Sayar, v. in Hamîrpûr d 178	Hardôl d 278
Semrå, small t. in Ågrå d 76	Shikârpûr, v. in Bulandshahr d 7
Sênthâl, v. in Barell d 29	Shikôhâbâd, tahsîl in Maînpurî d 97
Sentûå, v. near Bhûîla Dîh in Bastî d 220	Shi-lo-fu-shi-ti, of Hiuen Tsiang.
Sêopûr, v. in Mîrzâpûr d 257	Identified with Sahet-
Séosará, v. in Basti d 227	Mahet in the Gop-
Scota, v. in Sîtâpûr d 290	₫â d 306—313
Sêt Barâh, or Sveta Varâha, celebrated	Shîshgarh, t. in Bareli d 29
shrine of Vishnu at Kôtwâ în	Shîûpûr, v. near Malâkâh in Allahâbâd d 143
Suljānpūr d 329	Shîûpurî, v. in Barelî d 30
Sewet, identified with Sahet-Mahet in	Shiarajpar, v. in Fathpar d 165
GondA d 306-313	Ditto, tahsil in Kanhpur d 170
Sha-chi, of Fa Hian.	Siâthû, v. în Kherî d 285
Identified with Sanchankôt in	Siddhapura, the modern Siddhaur in
Unão d 274, 275	Bâra Baûkî d 264
Shâhâbâd, tahsîl in Hardôî d 283	Siddhapuri, ancient name of Jajmaa in
Ditto, ruined city near Paparghat in	Kāṇhpār d 168
Sulianpar d 327	Siddhaur, v. in Bâra Baakî d.
Shahâb-ad-dînâbâd, v. near Mâṇikpûr in	Anciently named Siddha-
Pratâpgarh d 317	pura 264
Shahgarh, ruined fortress in Pilibhit d 41	Sihonda, t. in Banda d 157
Ditto, v. in Sultanpûr d 326	Sijhårî, v. in Hamîrpûr d 177
Shahi, v. in Barell d 29	Sikandarpûr, v. in Mîrzâpûr d 261
Shahjahanpar, tahsil and head-quarters of d., 43	Ditto, v. in Bâliyâ d 194
Shahpar, v. near Sarauli in Bareli d 29	Sikandrâ, v. în Âgrâ d.
Ditto, v. in Mathura d 110	Also called Bihishtabad 76
Ditto, v. in Kherî d 284, 285	Buildings of Moghal period
Ditto, v. in Pratapgarh d 316	at—76, 77
Shahpar Kalan, v. in Muradabad d 36	Ditto, v. in Allahābād d 144
Shâh Qulîpûr, v. in Sîtûpûr d 291	Ditto, t. in Kanhpard 170

Pages	Pages,
Sikhirî, v. near Bhûîla Dîh in Bastî d 220	THE RESERVE OF THE PROPERTY OF
	A CONTRACTOR OF THE CONTRACTOR
	and the second s
	The state of the s
Simauni, v. in Banda d 157	2 0 1 1
Simaurgarh, v. in Hardôî d 281	
Simbhûâ, v. in Kânhpûr d 167	The state of the s
Simrâ-Râmpura, v. in Barelî d 26	110 200
Simrî, v. in Unâo d 268	100
Sindhan Kalân, v. în Bândâ d 157	Sônkh, v. in Mathurâ d 111
Singha Parasî, v. in Bahrâîch d 292	Soraon, tahsil in Allahabad d 145
Singhapura, of Hiuen Tsiang.	Sôron, t. in Îţâh d.
Perhaps Madha in Dêrah	Anciently named Sukarakshe-
Dûn d8, 331	
Singraur, v. in Allahâbâd d.	Śravāsti, identified with Sahet-Mahet in
Anciently named Śringavira-	Gonda d 306-313
pura 144	Śrikund, small t. in Mathurâ d 110
Scene of defeat of Khân Zamân 145	Śrînagar, v. in Garhwâl d.
Identified with the capital of	Temples and ruined palaces of the
Hayamukha 269	Chan't I am a f
Śirasāwā, old name of Sirsāwā in Sahāran-	Ditto, traditional name of Bilgram in
pûr d 18	TE AAA 3
Śiraspattana, ancient name of Sirsawa	Ditto win Hamington 1
2 0 1 2 1	Ditto, v. in Hamîrpûr d 178
CULT. TI CALAT T	Srughna, identified with Sugh in Am-
Fit A A T AT AT A	bala d 18
Sîrîs, v. m Lakhnâû d 267 Sîrônî Khurd, v. in Lalitpûr d.	Súa-Bihar, another name for Bihar in Pra-
Market Market Control of the Control	tåpgarh d 314
Anciently called Siyadoni, 124 Long inscription of Samvat	Sûâ-Kôt, ruined fort in Pilibhît d., 40, 41
	Såba-Bihâr, Musalmân name of Bihâr in
964 at— 124, 125 Sirsâ Jujhâr, v. in Murâdâbûd d 36	Pratûpgarh d 315
	Subehâ, v. in Bâra Bankî d 264
Sirsår, v. in Mirath d 9	Subhamaninagara, the modern Koron
Sirsfråð, v. in Bastf d 224	in Bastî d 226
Sirsawa, see Sursawa.	Subhanpur, v. in Kanhpurd 188
Sirsend, v. in Faizâbâd d 301	Sûfîpûr, v. near Fîrûzâbâd in Âgrâ d. 74
Sirwâbaran, cluster of 12 villages near Gur-	Sugh, v. in Ambâlâ d. of Panjâb.
sarâî in Jhânsî d., 116, 117	Identified with the ancient Srugh-
Sirwâ-Pâlî, or Sarâî Dâla, v. in Faizâbâd d., 300	na 19
Sitâban, v. în Kumâon d 50	Sûî Bisung, v. in Kumâon d.
Sîtâpûr, small t. near Chitrakût in Bândâ d.	Sûîrî-kâ-Râj, deserted t, near Permit in Ghâ-
Formerly called Jayasimha-	Zipûr d
pura 148	Sujân Dêo, rocky islet în Jamna near Dêo-
Ditto, tabsil and head-quarters of d 291	riva in Allahahad a
Sivapûr, v. in Banâras d 216	Sujânkôt, see Sanchânkôt 131
Ditto, v. in Bastî d 222	Sukarakshetra, the modern Sôron in
Sîyadonî, the modern Sîrônî Khurd in	Teal 1
Lalitpûr d 124, 125	Iţâh d., 88, 89 Sukhâwân, v. in Faizâbâd d 301
Sobhavatinagara, identified with Kho-	Śuklapura angiesta 301
poâ Dîh in Bastî d., 221	Suklapura, ancient name of Sukaldiha in
(') Abbreviations: t.=to	Banáras d y 213

Pages.	Pages.
Sultannagar, v. in Sîtâpûr d 289	Telî Pahârî, v. in Hamîrpûr d 173
Sultanpür, v. in Muradabad d 38	Tendûâpûr, v. near Bilgrâm in Hardôf d 278
Ditto, v. near Âgra 53	Tewah, v. in Hamirpar d 173
Ditto, tahsil and head-quarters of d 328	Thakura, v. in Mainpuri d 94
Anciently named Kusapura,	Thâkurdvâra, tahsîl in Murâdâbâd d.
or Kušabhavanapura 328	Ancient mounds in pargana
Identified with Kin-shi-po-	of— 38
lo, or Kasapura, of Hiuen	Thânâ, v. near Unão 276
Tsiang 328, 329	Thânâ Bhâwân, t. in Muzaffarnagar d 14
Sumêrpûr, t, Hamîrpûr d 178	Thânâ Dâryâoganj, v. in Îṭâh d 89
Sunawardeh-Aphûî, v. in Fathpûr d 158	Thânêkâ, v. in Shâhjahânpûr d 43
Sungrâ, v. in Hamîrpûr d 178	Thânûpûr, v. in Faizâbâd d 302
Sûpå, v. in Hamîrpûr d 178	Tharerû, v. in Faizâbâd d 301
Surahar, or Surar, old t. in Lalitpûr d 158	Thâtrâ, small t. in Farrukhâbâd d 84
Surhârpûr, small t. in Faizâbûd d 302	Thawâi, v. in Fathpûr d 165
Suriānwān, v. in Mîrzāpār d 255	Thûlendî, v. in Râî Barelî d 319
Surîr, small t. in Mathurâ d 111	Tikôr, v. near Chunâr în Mîrzâpûr d 259
Sûrya Bhîtâ, deserted site near Singraur in	Tikrî, large mound near Kosâm in Allahâ-
Allahâbâd d 145	båd d 142
Suryapûra, the modern Batêsar in	Do., v. in Faizābād d 300
Âgrâ d 69	Do., v. in Sultanpar d 326
T.	Tiksariya, v. in Fathpar d 158
	Tikuṇṭhî Mankûâ Maksarpûr, v. in Murâdâ-
Taghlaqpûr, old name of Lâharpûr in Sîtâ-	bâd d 38
pûr d 289	Tilbegampûr, v. in Bulandshahr d 7
Tăjpûr, v. in Faizâbâd d 302	Tilchûân, v. in Bastî d 222
Takht Pahlwan, v. near Âgra 64	Tilhår, tahsîl in Shahjahanpar d 43
Takrârâ Daulat, small v. in Mâînpurî d 97	Tindulf, v. in Fathpûr d 159
Takshaprayâg, pilgrimage place in Garhwâl d., 46	Tîp, ancient v. in Bîjnôr d 34
Tâl Bahat, or Beht, t. in Lalitpûr d., 125, 126	Tirwa, tahsîl in Farrukhabad d 84
Tålgråm, t. in Farrukhåbåd d 84	Tobra, v. mentioned by Musalman chroni-
Talpat Någari, deserted t. near Shikarpur in	clers.
Bulandshahr d 7	Identified with Bara Topra in Am-
Tama, small v. in Bastî d.	bâlâ d. of Panjâb 17
Identified with the Maneyagra-	Ţoḍarpûr, v. in Hardôi d 283
m a of Buddhist legends 226	Tolâpati-urf-Jaitpûr, v. in Faizâbûd d 301
Tambaur, v. in Sitāpūr d 291	To-wai, of Fa Hian.
Tâṇdâ, tahsîl in Faizâbâd d 302	Identified with Tandwa in Bah-
Do., v. in Råi Bareli d 325	râlch d 294, 295, 309
Taṇḍwâ, old v. in Bahraleh d.	Tuksan, ancient khera in Aligarh d 3
Identified with To-wai, the birth-	Tumaulâ, v. în Mathurâ d 111
place of Kâsyapa Buddha, 294, 295, 309	Tundapura, v. in Bîjnôr d 30
Tapnipāl, v. in Kumāon d 49	Turtîpâr, v. in Bâliyâ d 194
Tappal, v. in Allgarh d 3	Tusârân-Bihâr, t. in Pratâpgarh d.
Tarahwan, t. in Banda d 154	Originally named Tush a-
Târakulwâ, large v. in Gôrakhpâr d 251	rārāma 314
Tawakkulpur, v. in Bahraich d 293	Probably the 'O-ye-mu-
Tekriya, v. in Gôrakhpûr d 243	khi of Hiuen Tsiang 315


(2) General List of Places described (1)-(continued).

Pages.	Pages.
Tyarkuda, v. in Kumaon d 48	Vairatapattana, identified with ruins
Tyârsâû, v. in ditto 49	near Kâsîpûr in
U.	Tarâî d., 50—52
Udharanpûr, small v. in Ghâzîpûr d.	Locally identified with
Perhaps the Chen-chu, or	Bairant in Bana-
Yuddharanapura, of	ras d 195
Hiuen Tsiang 236	Vaisali, the modern Besarh in Muzaffar-
Ûgû, v. near Safîpûr în Unão d 274	pår d. of Bangål 239
Ujaîn, or U j ja y i n î, old fort near Kasîpûr	Vajravarāhi, the modern Barāhi near
in Garhwâl d.	Sårnåth in Banåras d 214
Identified with the capital of Govi-	Vakarma, v. near Safîpûr in Unão d 274
ŝana 51, 52	Vakāšrama, the modern Baksar Ghāt in
Ujálikanagara, old name of Jáis in Rái	Unão d 268
Bareli d 323	Våkyaprastha, ancient name of Bågpat
Ujår, v. in Kherî d 286	in Mîrath d 9
Ujhānî, v. in Badaon d 24	Vålmikiya, the modern Baliya, 190, 191
Ujhārî, v. in Murādābād d 38	Varahakshetra, identified with Barah
Umargarh, old fort near Mûsânagar in Kânh-	Chhetra in Basti d., 217
pûr d 170	Varanasi, ancient name of Banaras 196
Umêdâ, v. in Faizâbâd d 302	Varanavata, might be identified with
Umran, v. in ditto 302	Bulandshahr 4
Umrî, v. în Jalâun d 114	Might be identified with
Unão, tahsîl and head-quarters of d., 275, 276	Barnawa in Mîrath d 9
Unâsiâ, v. in Sîtâpûr d 288	Vazîrapûr, v. near Bâliyâ 191
Unchagaon, v. near Azamgarh 187	Vijayanagara, ancient name of Bîinôr. 20
Ditto, v. in Kherî d 284, 286	Vindhyachala, the modern Bindhachal
Unchanagar, ancient name of Bulandshahr, 4	in Mirzâpûr d. 955
Unchâtîlâ, ruined fort near Sândî in Har-	Virasana, the Pi-lo-shan-na of
dôf d 282	Hiuen Tsiang. 89 95 00
Updhāoliyā, v. near Barhî in Görakhpūr d.	visukna, identined with Ajudhva in
Identified with Moriyana-	Faizābād d 299 304
garam 237, 238	visanuprayag, pilgrimage place in Garh-
Urwara, v. in Hamîrpûr d 177	wâl d 46
Utrauliä, tahsil in Gonda d 313	vodamayata, ancient name of Badaon, 20
Uttar, v. in Hardôî d 283	Vyaghraprastha, ancient name of Bag-
V.	pat in Mirath d o
	Vyaghrapuri, identified with Barah
Vågisvara, the modern Bågësar in Ku-	Chhetra in Basti d 217 210
mion d 47	, yagaresvara, the modern Bagesvar
Vågud, identified with Kakapar in Kanh-	in Kumaon d 47
pûr d 169	W.
Vaidyanath, pilgrimage place in Kumaon d., 47	Wahidpûr-Pachômî, v. in Barelî d.
Vaidyapûr, ancient kherû in Bulandshahr d., 6	Identified with Pan-
Vairātakherā, v. in Kherī d 283	chabhami oc
Vairatapattana, ancient capital of	wama, v. m Bahya d.
Govisana.	waira-Qazi, v. in Bahraich d.
Identified with Dhiku-	Wairi Dih, deserted site near Kalyanmal in
li in Kumaon d 49	Hardôf d 280

(2) General List of Places described (1)-(concluded).

Page	Pages.
Warâi, small v. in Bastî d 22	out hame of the modern Paina-
Yahyâpâr, v. in Pratâpgarh d 31	8 Zahir Dîwân, v. near Sabalgarh in Bîj-
Yakûtganj, v. in Farrukhâbâd d. Originally called Sarâî Nûrî 8	nôr d 33 4 Zahûrganj, v. in Ghûzîpûr d 235
Yasingarh, v. in Faizabad d 30 Yavanapura, perhaps the modern Jaun-	2 Zamānîyā, tahsîl in Ghāzîpūr d.
pûr 17	v 1310 231 AUU
Yuddharan pura, the modern Udharan- pûr in Ghâzîpûr d., 230	Called Jamaniya by modern Hin- dûs 237
Z.	Later called Madana-Banaras 236
Zafarâbâd, v. în Jaunpûr d. Formerly known as Shahr Anwâr, 185, 186	

(*) Abbreviations: t.=town; v.=village; d.=district.



[ADVERTISEMENTS.]

ARCHÆOLOGICAL SURVEY OF INDIA.

NEW SERIES, VOLUME I.

THE SHARQI ARCHITECTURE OF JAUNPUR.

WITH

NOTES ON ZAFARABAD, SAHET-MAHET AND OTHER PLACES IN THE N.-W. P. & OUDH:

By DR. A. FÜHRER, PH.D., and EDMUND W. SMITH, ARCHITECT.

Edited by JAS. BURGESS, LL.D., C.LE.,

Director-General of the Archeological Survey of India.

Illustrated by 74 Plates of the Sharqi Architecture of Jaunpur, &c. Super-royal 4to. Price Rs. 16.
CALCUTTA: -SUPERINTENDENT OF GOVERNMENT PRINTING, INDIA.

"The Government may properly be urged and expected to continue this Survey in the North-Western Provinces, and to utilize the Architectural Members of the Survey, moreover, in advising and controlling a reasonable conservation of Historical Monuments in the Indian Empire,"—R. Institute British Architects' Journal, 19th June 1890.

"The first volume of Dr. Burgess' New Series is a scholarly and exhaustive Monograph on a special and well-defined Architectural period. It is published in the form of a handsome quarto . . . supplying a valuable and interesting record of the History and Architecture of Jaunpur, a city which for nearly a century vied with Imperial Dehli both in power and splendour.

"Unlike the majority of the volumes in the former Series, the Report is one of which the Government has no reason to be ashamed, and it may be safely recommended to any one interested, either specially in Jaunpur, or generally in Indian Architecture, as an adequate and trustworthy source of information."—The Pioneer.

VOLUME II.

Royal 4to, Rs. 10.

THE MONUMENTAL ANTIQUITIES AND INSCRIPTIONS IN THE N.-W. PROVINCES AND OUDH:

DESCRIBED AND ARRANGED By Dr. A. FÜHRER, Ph.D.,

Archaelogical Surevy, N.-W. Provinces and Oudh.

ALLAHABAD :-- GOVERNMENT PRESS.

VOLUME III.

Super-royal 4to. Rs. 6.

SOUTH-INDIAN INSCRIPTIONS:

COLLECTED, EDITED AND TRANSLATED By E. HULTZSCH, Ph.D.,

Government Epigraphist.

MADRAS: -- GOVERNMENT PRESS, AND HIGGINBOTHAM & Co.

CALCUTTA:-THACKER, SPINK & Co.

BOMBAY:-THACKER & Co. (Limited).

LONDON:-KEGAN PAUL, TRENCH, TRUBNER & Co., AND W. H. ALLEN & Co.

CORPUS INSCRIPTIONUM INDICARUM.

Vol. III.—INSCRIPTIONS OF THE EARLY GUPTA KINGS AND THEIR SUCCESSORS:

By JOHN FAITHFULL FLEET, C.LE., BO. C.S.

With 45 Plates, Rs. 25: without Plates, Rs. 15.

CALCUTTA: SUPERINTENDENT OF GOVERNMENT PRINTING, INDIA.

THE ANTIQUITIES OF DABHOI IN GUJARAT:

By J. BURGESS, LL.D., C.LE.,

Director-General of the Archaelogical Survey of India.

and

H. COUSENS, M.R.A.S.,

Archieological Survey, Western India.

Illustrated by 22 Plates. Large Folio, 17×14 inches. One Guines.

EDINBURGH :- GRORGE WATERSTON & SONS.

This handsome Volume, illustrative of the Antiquities of the ancient City of Dabhoi, with its splendid Gateways and Temples, has been prepared and published at the expense of His Highness the Maharaja of Baroda, in whose territory Dabhoi is,

The Illustrations—more especially the Drawings—will be found to be of permanent importance to all interested in Architecture and Art, as reproducing accurately and to scale very important typical examples of the elaborately scalptured Architecture of India in the Thirteenth Century of our Era. The Drawings are supplemented by collotype reproductions of large Photographs, and the whole is described in detail in the letter-press of the volume.

ARCHÆOLOGICAL SURVEY OF SOUTHERN INDIA.

THE BUDDHIST STUPAS OF AMARÂVATÎ AND JAGGAYYAPETA:

DESCRIBED AND ILLUSTRATED

By J. BURGESS, LLD., C.I.E., &c.

With Transcripts and Translations of the Asoka Edicts at Dhauli and Jaugada:

By PROFESSOR G. BUHLER, PH.D., LL.D., C.LE., Vienna.

With 69 Plates of Sculptures and Inscriptions, mostly Autotypes, and 32 Wood-cuts.

Super-royal 4to., half-bound, gilt top, 1887. 3 Guineas.

"Mr. Burgess has recently issued an admirable Monograph on the Buddhist Stispus at Amarivati and Jaggayyapeta, supplementary to the late Mr. Fergusson's 'Tree and Serpent Worship,' and has thus, to some extent, wiped away the reproach of the Southern Presidency,—Quarterly Review, July 1889.

GUIDE TO BIJAPUR:

By HENRY COUSENS, M.R.A.S.,

Archaological Survey of Western India.

A FULL ACCOUNT OF THE PRINCIPAL BUILDINGS IN AND ABOUND THE CITY, WITH AN OUTLINE OF THE HISTORY OF THE ADIL SHAHI KINGS OF BIJAPUR.

144 pages, Cloth: Maps of the City and Environs. Price Rs. 2.

[Published with the sanction of the Government of Bombay.]

HOMBAY:-THOS. COOK & SONS; THACKER & Co. (Limited).

Published by order of Her Majesty's Secretary of State for India.

ARCHÆOLOGICAL SURVEY OF WESTERN INDIA.

THE CAVE TEMPLES OF INDIA:

By J. FERGUSSON, D.C.L., C.I.E., F.R.S., V.P.R.A.S.; and JAS. BURGESS, LL.D., C.I.E., F.R.G.S., M.R.A.S., &C., Super-royal Sec., half morocco, gilt top, pp. XX and 536, with Map, 90 Plates and 76 Wood-cuts. #2.

REPORTS:

By JAS. BURGESS, LL.D., C.LE, &C. Super-royal 4to., half morocco, gilt tops.

Vol. I.—Report of the First Season's Operations in the Belgaum & Kaladgi Districts.

With 56 Photographs and Lithographic Plates, and 6 Wood-cuts. £2 2s.

Vol. II.—Report on the Antiquities of Kathiawad and Kachh.

With 74 Photographs and Lithographic Plates, 242 pages. £3 3s.

Vol. III.—Report on the Antiquities of the Bidar and Aurangabad Districts.

With 66 Photographs and Lithographic Plates, and 9 Wood-cuts. £2 2s.

LONDON: -W. H. ALLEN & Co., Waterloo Place.
TRUBNEE & Co., Ludgate Hill.

CALCUTTA: -THACKER, SPINK & Co. BOMBAY: -THACKER & Co. (Limited).

VOLUMES IV & V.

IV .- The Buddhist Caves and their Inscriptions.

With 60 Plates and 25 Wood-cuts.

V.—The Caves of Elura and the other Brahmanical and Jaina Caves in Western India.

With 51 Autotype and other Plates, and 18 Wood-cuts.

The two Volumes: Price £6 6s.

LONDON :- TRUBNER & Co.

MISCELLANEOUS PUBLICATIONS OF THE ARCHÆOLOGICAL SURVEY OF WESTERN INDIA.

4to. Demy.

- No. 1.—Memorandum on the Buddhist Caves of Junnar; by J. Burgers, LL.D.; and Translations of three Inscriptions from Badami, Pattadkal and Aiholi, by J. F. Flerer, Bo. C.s., 1874.
- No. 2.—Memorandum on the Antiquities at Dabhol, Ahmedaabad, Than, Junagadh, Girnar, and Dhank, with Appendix of Inscriptions and 10 Plates of Facsimiles: by J. BURGESS, LL.D., 1875.
- No. 3.—Memorandum on the Remains at Gumli, Gop, and in Kachh, &c.; by the same, 1875.
- No. 4.—Provisional Lists of Architectural and other Archieclogical Remains in Western India: by the same, 1875.
- No. 5.—Translations of Inscriptions from Belgaum and Kaladgi Districts: by J. F. FLEET, Bo. C.S.; and of Inscriptions from Kathlawad and Kachh, by HARI VAMAN LIMAYA, R.A., 1876.
- No. 6.—Notes on the Antiquities of the Talukas of Parner, Sangamner, Ankols, and Kopargaum, in Ahmadnagar: by W. F. SINGLAIR, Bo. C.S.; with revised Lists of Remains in the Ahmaduagar, Nasik, Puna, Thana, and Kaladgi Zillas, by J. Burgess, LL.D., 1877.
- No. 7.—Architectural and Archmological Remains in Khandesh: by W. H. PROPERT, Bo. c.s., Collector, 1877.
- No. 8.—Reports regarding the Archeological Remains in Sindh, with Plans of Tombs: by District Officers, 1879.

- No. 9.—Notes on the Banddha Rock-Temples of Ajanta, their Paintings and Sculptures; and on the Paintings of the Bagh Caves, Modern Banddha Mythology and the Sanskrit Inscription at Cintra, with 31 Plates: by J. Burgess, Lt.D., 1879.
- No. 10.—Inscriptions from the Cave-Temples of Western India, with Descriptive Notes, a Siláhára grant of Márasimha, and three Sanskrit Inscriptions in possession of the American Oriental Society, with 52 Plates: by J. Burgess, Ll.D., and Beagwanlar, INDRAJI PANDIT, PH.D., 1881.
- No. 11.—Lists of the Antiquarian Remains in the Bombay Presidency, Sindh, and Berar, with an Appendix of Inscriptions from Gujarat, pp. 340; by J. Burgess, LL.D., C.L.E., 1885. Rs. 6.
- No. 12.—The Caves at Nadsur and Karsambla, with 7 Piates: by HENRY COUSENS, M.R.A.S., Archeological Surveyor of Western India.
- Report on the Architectural and Archmological Remains in the Province of Kachh, with Inscriptions and 10 Native Drawings: by DALPATRAM PRANJIVAN KHAKAR; with five papers by the late SIR ALEX, BURNES: edited by J. BURGESS, LLD, 8VO., pp. 120. (Selections from the Records of Bambay Government, No. 152, 1879).
- Notes on Bijapur and Satrunjaya, with two Maps, published as a Government Selection: by HENRY COUSENS, M.R.A.S. Price annas 12.

BOMBAY :- GOVERNMENT CENTRAL PRESS.

THE INDIAN ANTIQUARY:

A JOURNAL OF ORIENTAL RESEARCH IN ARCHÆOLOGY, HISTORY, LITERATURE, LANGUAGES, FOLKLORE, &c., &c.

(FIRST SERIES, 1872-1884.)

Edited by JAS. BURGESS, LL.D., C.I.E.

One complete Set only-Vols. I to XIII, bound in Cloth, with numerous Facsimiles of Inscriptions and other Illustrations.

4to. Demy. Rs. 310 (or £27) cash nett, and carriage extra.

Volumes II to XIII together, a very few sets of these 12 volumes. Rs. 245 (£21) nett, and carriage extra.

Volumes IV to XIII together. Rs. 170 (£15) nett, and carriage extra.


Volumes V to XIII may be had separately, bound in cloth, at Rs. 16 each, cash; or the nine volumes together for Rs. 140 (£11 I6s.) nett, and carriage extra.


Volumes I, II, III, and IV are not sold separately.


BOMBAY:-THE MANAGER, EDUCATION SOCIETY'S PRESS.

∞0€000









Archaeological Library

21558

Call No. R913.012 IIDA/TA

Author— A. Fakses

Title—The monumental ontograte of the parties and in scriptions in the parties of the parties of the parties of the parties of the parties of the parties of Archaeology

NEW DELHI.

Please help us to keep the book clean and moving.